APRIL 1987 VOL. 5 NO. 4 $3.95

FOR THE IBM SYSTEMS PROFESSIONAL

PC TECH JOURNAL®

dBASE DIALECTS

Three compilers support a de facto standard

ALR'S ACCESS 386

UTION: CLASSIC

NEW

Eureka: The Solver™

Anyone and everyone who routinely works with equations needs Eureka: The Solver

It solves the most complex equations in seconds. Whether you're a scientist, engineer, financial analyst, student, teacher, or some other professional, you need Eureka: The Solver!

Any problem that can be expressed as a linear or non-linear equation can be solved with Eureka. Algebra, Trigonometry and Calculus problems are a snap.

Eureka: The Solver also handles maximization and minimization problems, does plot functions, generates reports, and saves you an incredible amount of time.

X+exp(X) = 10 solved instantly instead of eventually!

Imagine you have to "solve for X," where X + exp(X) = 10, and you don't have Eureka: The Solver. What you do have is a problem, because it's going to take a lot of time guessing at "X." Maybe your guesses get closer and closer to the right answer, but it's also getting closer and closer to midnight and you're doing it the hard way.

With Eureka: The Solver, there's no guessing, no dancing in the dark—you get the right answer, right now. (PS: X = 2.0705799, and Eureka solved that one in .4 of a second!)

How to use Eureka: The Solver

It's easy.

1. *Enter your equation into the full-screen editor*
2. *Select the "Solve" command*
3. *Look at the answer*
4. *You're done*

You can then tell Eureka to

- *Evaluate your solution*
- *Plot a graph*
- *Generate a report, then send the output to your printer, disk file or screen*
- *Or all of the above*

Eureka: The Solver includes

- ☑ *A full-screen editor*
- ☑ *Pull-down menus*
- ☑ *Context-sensitive Help*
- ☑ *On-screen calculator*
- ☑ *Automatic 8087 math co-processor chip support*
- ☑ *Powerful financial functions*
- ☑ *Built-in and user-defined math and financial functions*
- ☑ *Ability to generate reports complete with plots and lists*
- ☑ *Polynomial finder*
- ☑ *Inequality solutions*

*Introductory price—good through July 1, 1987

Some of Eureka's key features

You can key in:

- ☑ *A formula or formulas*
- ☑ *A series of equations—and solve for all variables*
- ☑ *Constraints (like X has to be < or = 2)*
- ☑ *A function to plot*
- ☑ *Unit conversions*
- ☑ *Maximization and minimization problems*
- ☑ *Interest Rate/Present Value calculations*
- ☑ *Variables we call "What happens?," like "What happens if I change this variable to 21 and that variable to 27?"*

All this power for only $99.95!

Equation-solving used to be a mainframe problem, but we've solved that problem.

Eureka: The Solver is all you need—and it's yours for only $99.95!

That kind of savings you can calculate with your fingers!

System requirements

IBM PC, AT, XT, Portable, 3270 or true compatibles. PC-DOS (MS-DOS) 2.0 and later. 384K.



BORLAND INTERNATIONAL

Vive la différence

4585 SCOTTS VALLEY DRIVE
SCOTTS VALLEY, CA 95066
(408) 438-8400 TELEX: 172373

GF6

For the dealer nearest you or to order by phone call

(800)255-8008

in CA (800) 742-1133 in Canada (800) 237-1136

BI-1103

Turbo Prolog™

> "If you're at all interested in artificial intelligence, databases, expert systems, or new ways of thinking about programming, by all means plunk down your $100 and buy a copy of Turbo Prolog."
> **Bruce Webster, BYTE**

Only $99.95!



Turbo Prolog, the natural language of Artificial Intelligence, is the most popular AI package in the world with more than 100,000 users. It's the 5th-generation computer programming language that brings supercomputer power to your IBM PC and compatibles. You can join the AI revolution with Turbo Prolog for only $99.95. Step-by-step tutorials, demo programs and source code included.

New! Turbo Prolog Toolbox

NEW

Our new Turbo Prolog Toolbox™ enhances Turbo Prolog—with more than 80 tools and over 8,000 lines of source code that can easily be incorporated into your programs. It includes about 40 example programs that show you how to use and incorporate your new tools.

New Turbo Prolog Toolbox features include:

- ☑ *Business graphic generation*
- ☑ *Complete communications package*
- ☑ *File transfers from Reflex, dBASE III, 1-2-3, Symphony*
- ☑ *A unique parser generator*
- ☑ *Sophisticated user-interface design tools*

System requirements

Turbo Prolog: IBM PC, XT, AT or true compatibles. PC-DOS (MS-DOS) 2.0 or later. 384K. Turbo Prolog Toolbox requires Turbo Prolog 1.10 or higher. Dual-floppy disk drive or hard disk. 512K.

It's the complete developer's toolbox and a major addition to Turbo Prolog. You get a wide variety of menus—pull-down, pop-up, line, tree and box—so you can choose the one that suits your application best. You'll quickly and easily learn how to produce graphics; set up communications with remote devices; read information from Reflex,® dBASE III,® Lotus 1-2-3® and Symphony® files; generate parsers and design user interfaces. All of this for only $99.95.

Only $99.95!



MACINTOSH™ VERSION ALSO AVAILABLE

Turbo Pascal®

The power and high performance of Turbo Pascal is already in the hands of more than half-a-million people. The technically superior Turbo Pascal is the de facto worldwide standard and the clear leader.

The Turbo Pascal family includes:

- *Turbo Pascal® 3.0*
- *Turbo Tutor® 2.0*
- *Turbo Database Toolbox®*
- *Turbo Editor Toolbox®*
- *Turbo Graphix Toolbox®*
- *Turbo GameWorks®*
- *Turbo Pascal Numerical Methods Toolbox™*

Turbo Pascal, the worldwide standard in high-speed compilers, and family.

> "The language deal of the century."
> **Jeff Duntemann, PC Magazine**

New! Turbo Pascal Numerical Methods Toolbox

NEW



Only $99.95!

What our new Numerical Methods Toolbox will do for you now:

- ☑ *Find solutions to equations*
- ☑ *Interpolations*
- ☑ *Calculus: numerical derivatives and integrals*
- ☑ *Differential equations*
- ☑ *Matrix operations: inversions, determinants and eigenvalues*
- ☑ *Least squares approximations*
- ☑ *Fourier transforms*

As well as a free demo FFT program, you also get Least Squares Fit in 5 different forms:

1. *Power*
2. *Exponential*
3. *Logarithm*
4. *5-term Fourier*
5. *5-term Polynomial*

They're all ready to compile and run.

All this for only $99.95!

System requirements

IBM PC, XT, AT or true compatibles. PC-DOS (MS-DOS) 2.0 or later. Turbo Pascal 2.0 or later. Graphics module requires graphics monitor with IBM CGA, IBM EGA, or Hercules compatible adapter card, and requires Turbo Graphix Toolbox. 8087 or 80287 numeric co-processor not required, but recommended for optimal performance. 256K.

Turbo Pascal 3.0.
Includes 8087 & BCD features for 16-bit MS-DOS and CP/M-86 systems. CP/M-80 version minimum memory: 48K; 8087 and BCD features not available. 128K.

BI-1103

NEW

Turbo Basic®

Introducing Turbo Basic, the high-speed BASIC you'd expect from Borland!

It's the BASIC compiler you've been waiting for. And it's so fast that you'll never have to wait again.

Turbo Basic is a complete development environment; it includes a lightning-fast compiler, an interactive editor, and a trace debugging system.

Because Turbo Basic is compatible with BASICA, chances are that you already know how to use Turbo Basic.

With Turbo Basic your only speed is "Full Speed Ahead"!

You probably already know us for both Turbo Pascal® and Turbo Prolog.™ Well, we've done it again!

We created Turbo Basic, because BASIC doesn't have to be slow.

In fact, building fast compilers is a Borland specialty; both our Turbo Pascal and our Turbo Prolog outperform all their rivals by factors, and with Turbo Basic, we're proud to introduce the first high-speed BASIC compiler for the IBM®PC. If BASIC taught you how to walk, Turbo Basic will teach you how to run!

The Critics' Choice

"Borland has succeeded in stretching the language without weighing us down with unnecessary details . . . Turbo Basic is the answer to my wish for a simple yet blindingly fast recreational utility language . . . The one language you can't forget how to use, Turbo Basic is a computer language for the missus, the masters, the masses, and me.

Steve Gibson, InfoWorld

Borland's Turbo Basic has advantages over the Microsoft product, including support of the high-speed 8087 math chip.

John C. Dvorak"

Turbo Basic ends the basic confusion

There's now one standard: Turbo Basic.

It's fast, BASICA-compatible, and because Turbo Basic is a Borland product, the price is right, the quality is there, and the power is at your fingertips. You see, Turbo Basic's part of the fast-growing Borland family of programming languages—we call it the "Turbo Family." Hundreds of thousands of users are already using Borland's languages, so you can't go wrong. So join a whole new generation of smart IBM PC users—get your copy of Turbo Basic today. You get an easy-to-read 300+ page manual, two disks, and a free MicroCalc spreadsheet—and an instant start in the fast new world of Turbo Basic. All of this for only $99.95—Order your copy of Turbo Basic today!

Free spreadsheet included, complete with source code!

Yes, we've included MicroCalc, our sample spreadsheet, complete with source code, so that you can get started right away with a "real program." You can compile and run it "as is," or modify it.

A technical look at Turbo Basic

- ☑ *Full recursion supported*
- ☑ *Standard IEEE floating-point format*
- ☑ *Floating-point support, with full 8087 (math co-processor) integration. Software emulation if no 8087 present*
- ☑ *Program size limited only by available memory (no 64K limitation)*
- ☑ *EGA and CGA support*
- ☑ *Access to local, static, and global variables*
- ☑ *Full integration of the compiler, editor, and executable program, with separate windows for editing, messages, tracing, and execution*
- ☑ *Compile, run-time, and I/O errors place you in the source code where error occurred*
- ☑ *New long integer (32-bit) data type*
- ☑ *Full 80-bit precision*
- ☑ *Pull-down menus*
- ☑ *Full window management*

System requirements

IBM PC, XT, AT and true compatibles, PC-DOS (MS-DOS) 2.0 or later. One floppy drive, 256K.

Only $99.95!

BI-1103

NEW

Turbo C®

Turbo C: The fastest, most efficient and easy-to-use C compiler at any price

Compilation speed is more than 7000 lines a minute, which makes anything less than Turbo C an exercise in slow motion. Expect what only Borland delivers: Quality, Speed, Power and Price.

Turbo C: The C compiler for amateurs and professionals

If you're just beginning and you've "kinda wanted to learn C," now's your chance to do it the easy way. Like Turbo Pascal, Turbo C's got everything to get you going.

If you're already programming in C, switching to Turbo C will considerably increase your productivity and help make your programs both smaller and faster. Actually, writing in Turbo C is a highly productive and effective method—and we speak from experience. Eureka: The Solver and our new generation of software have been developed using Turbo C.

Turbo C: a complete interactive development environment

Free MicroCalc spreadsheet with source code

Like Turbo Pascal and Turbo Prolog, Turbo C comes with an interactive editor that will show you syntax errors right in your source code. Developing, debugging, and running a Turbo C program is a snap.

Turbo C: The C compiler everybody's been waiting for. Everybody but the competition

Borland's "Quality, Speed, Power and Price" commitment isn't idle corporate chatter. The $99.95 price tag on Turbo C isn't a "typo," it's real. So if you'd like to learn C in a hurry, pick up the phone. If you're already using C, switch to Turbo C and see the difference for yourself.

System requirements

IBM PC, XT, AT and true compatibles. PC-DOS (MS-DOS) 2.0 or later. One floppy drive. 320K.

Technical Specifications

- ☑ *Compiler: One-pass compiler generating linkable object modules and inline assembler. Included is Borland's high performance "Turbo Linker." The object module is compatible with the PC-DOS linker. Supports tiny, small, compact, medium, large, and huge memory model libraries. Can mix models with near and far pointers. Includes floating point emulator (utilizes 8087/80287 if installed).*
- ☑ *Interactive Editor: The system includes a powerful, interactive full-screen text editor. If the compiler detects an error, the editor automatically positions the cursor appropriately in the source code.*
- ☑ *Development Environment: A powerful "Make" is included so that managing Turbo C program development is highly efficient. Also includes pull-down menus and windows.*
- ☑ *Links with relocatable object modules created using Borland's Turbo Prolog into a single program.*
- ☑ *ANSI C compatible.*
- ☑ *Start-up routine source code included.*
- ☑ *Both command line and integrated environment versions included.*

*Introductory price—good through July 1, 1987

Sieve benchmark (25 iterations)

	Turbo C	Microsoft® C	Lattice C
Compile time	**3.89**	16.37	13.90
Compile and link time	**9.94**	29.06	27.79
Execution time	**5.77**	9.51	13.79
Object code size	**274**	297	301
Price	**$99.95**	$450.00	$500.00

Benchmark run on a 6 Mhz IBM AT using Turbo C version 1.0 and the Turbo Linker version 1.0; Microsoft C version 4.0 and the MS overlay linker version 3.51; Lattice C version 3.1 and the MS object linker version 3.05.

All Borland products are trademarks or registered trademarks of Borland International, Inc. or Borland/Analytica, Inc. Other brand and product names are trademarks or registered trademarks of their respective holders. Copyright 1987 Borland International BI-1103

Only $99.95!*



For the dealer nearest you, or to order by phone

call (800) 255-8008

CA (800) 742-1133

Canada (800) 237-1136

CIRCLE NO. 254 ON READER SERVICE CARD

If lightning still scares you, you're using the wrong file manager.

Be sure. Btrieve.®

Lightning may strike. But it doesn't have to destroy your database.

Btrieve® file management offers automatic file recovery after a system crash. So accidents and power failures don't turn into database disasters. Your Btrieve-based applications will come up when the lights come back on.

Fast. Btrieve is lightning fast, too. Its b-tree file structure automatically balances—you never waste time reorganizing the index. And Btrieve is written in Assembly language especially for the IBM PC. The result: electrifying speed on file maintenance routines. Applications that run fast. Users who don't waste time waiting.

The standard for networking. When your application requires multi-user file sharing, Btrieve (network version) sets the standard for the industry's most popular LANs: Novell, IBM, and 3COM, to name a few. Btrieve offers *safe* multi-user file management that coordinates simultaneous updates and protects against lost data.

Fully-relational data management. Using SoftCraft's entire family of products gives you a complete, fully-relational database management system. Xtrieve® speeds users through database queries with interactive, on-screen menus—no command language or special syntax. And you can add our report writer to Xtrieve to generate the reports you need.

For professional programmers. Btrieve is the fast, reliable answer for all your application development. In any development language—BASIC, Pascal, Cobol, C, Fortran and APL. With multikey access to records. Unlimited records per file. Duplicate, modifiable, and segmented keys. Variable length records.

With Btrieve, you can develop better applications faster. And know they'll be safe if lightning strikes.

NO ROYALTIES

Suggested single/multi-user prices:
Btrieve: $245/$595
Xtrieve: $245/$595
Reporter: $145/$345
Requires PC-DOS or MS-DOS 2.X or 3.X.

Btrieve and Xtrieve are registered trademarks of SoftCraft, Inc.

SoftCraft Inc.
P.O. Box 9802 #917
Austin, Texas 78766
(512) 346-8380 Telex 358 200

CIRCLE NO. 201 ON READER SERVICE CARD

PC TECH JOURNAL

APRIL 1987 VOLUME 5, NUMBER 4



A CADD Workstation 150



A Multiuser Solution 78



DOS Exception Handling 130

DIALECTS OF dBASE / TED MIRECKI
An enduring and esteemed name among data managers, Ashton-Tate's dBASE III is on its way to earning its pedigree among programming languages as well. Three compilers are now available to enhance the dBASE III language. 46

SPEED INFUSION, PART 2 / TED MIRECKI
Accelerator boards that increase the PC's clock speed can go only so far toward improving performance. The next step is to replace the microprocessor with a faster variety. Four accelerators that substitute an 8086 for an 8088 are reviewed. 66

A MULTIUSER SOLUTION / STUART BLAIR
Classic Technology borrows from the timesharing technology of minicomputers and from the architecture of networks to deliver a hybrid multiuser system that achieves some advantages of networking without cost and performance penalties. 78

Compatibility and Performance: **POISED FOR TOMORROW** / MICHAEL ABRASH and DAN ILLOWSKY
Advanced Logic Research opens an affordable door to the 80386-based environments and applications of the future with the Access 386, a high-performance AT compatible, comparable to its competitors in functionality—at a significantly lower price. 104

DOS EXCEPTION HANDLING / DAN ROLLINS
Often overlooked, Ctrl-Break handling and critical device errors are fundamental to an application's smooth user interface. DOS methods for handling errors and exceptions can help prevent a program from being compromised by user actions. 130

A CADD WORKSTATION / VICTOR E. WRIGHT
CADD vendors are beginning to realize the potential of the microcomputer market. Computervision is testing the waters with Personal Designer, which provides a substantial subset of a minicomputer CADD system in a microcomputer environment. 150

Programming Practices: **A RESIDENT EXCEPTION MANAGER** / TED MIRECKI
Custom interrupt-handling routines can improve the Break key and error handling ability of any application program. A sample program presented here demonstrates how to install a resident interrupt handler for DOS interrupts 22H and 23H. 170

9 DIRECTIONS
IS UNIX Important?

17 LETTERS

30 TECH RELEASES

41 TECH NOTEBOOK
DOS Moves on the 80386

179 PRODUCT WATCH
Tom Rettig's Library
R-Card
MEGA

185 EXPERT CONSULTANT: *COMPUTER LAW*
Liability and Expert Systems

189 BOOK REVIEWS
Clarifying MS-DOS

191 TECH MART

197 TECH MARKETPLACE

208 CALENDAR

209 READER SERVICE CARD

Cover computer graphic · Dov Jacobson

Software Tools

For Programmers & Non-Programmers

Get 'State of the Art' performance and save valuable time with these high quality utilities!

Opt-Tech Sort™

Opt-Tech Sort is a high performance Sort/Merge/Select utility. It can read, sort and write a file faster than most programs can even read the data. Example: 1,000 records of 80 bytes can be read, sorted and a new file written in less than 10 seconds (IBM XT). Opt-Tech Sort can be used as a stand-alone program or called as a subroutine to over 25 different programming languages.

All the sorting, record selection and reformatting facilities you need are included. A partial list of features includes: The ability to process files of any size. Numerous filetypes are supported including Sequential, Random, Delimited, Btrieve, dBASE II & III and many others. Up to 10 key fields can be specified (ascending or descending order). Over 16 different types of data supported. Powerful record selection capability allows you to specify which records are to be included on your output. Record reformatting allows you to change the structure of your output record and to output special fields such as record numbers for use as indexes.

MS-DOS $149. ★ NEW ★ Xenix $249.

★ NEW ★ VERSION On-Line Help™ ★ NEW ★ VERSION

On-Line Help allows you to easily add "Help Windows" to all your programs. On-Line Help is actually two help packages in one. You get BOTH Resident (pop-up) and Callable Help Systems.

The resident version allows you to add help to any system. Your Help System is activated when the "Hot Keys" that you specify are pressed. You can then chain between help windows in any manner you desire.

The callable version allows you to easily display help windows from your programs. A simple call to the help system makes the window appear. The original screen is automatically restored when the help window is cleared. On-Line Help is callable from over 20 different languages.

You have full control over the help window content, size, color and location.

MS-DOS $149. **Demo $10.** (apply toward purchase).

Scroll & Recall™

Scroll & Recall is a resident screen and keyboard enhancement. It allows you to conveniently scroll back through data that has gone off the top of your display screen. Up to 27 screens of data can be recalled or written to a disk file (great for documenting systems operations). Also allows you to easily recall and edit your previously entered DOS commands without retyping.

Scroll & Recall is very easy to use. It's a resident utility that's always there when you need it. MS-DOS $69.

Visa, M/C, AMEX, Check, Money Order, COD or Purchase Orders accepted.

To order or to receive additional information just call and receive immediate highly qualified attention!

Opt-Tech Data Processing

P.O. Box 678 — Zephyr Cove, NV 89448

(702) 588-3737

CIRCLE NO. 222 ON READER SERVICE CARD

PC TECH JOURNAL®

VOL. 5, NO. 4

PUBLISHER: *Newton Barrett*
EDITOR: *Will Fastie*

EDITORIAL
MANAGING EDITOR: *Marjory Spraycar*
EXECUTIVE EDITOR: *Julie Anderson*
SENIOR TECHNICAL EDITOR: *Jim Shields*
TECHNICAL EDITORS: *Caroline Halliday, David Methvin, Ted Mirecki*
CHIEF COPY EDITOR: *Susan Holly*
SENIOR COPY EDITOR: *Gail Shaffer*
COPY EDITOR: *Bruce Ansley*
PROOFREADER: *Elizabeth Wardlaw*
NEW PRODUCTS EDITOR: *Carole L. Eyring*
OFFICE MANAGER: *Trish Ledbetter*
EDITORIAL SECRETARY: *Valerie Rose*
RECEPTIONIST: *Debbie Lintner*
CONTRIBUTING EDITORS: *Steven Armbrust, Dave Browning, Michael Covington, Richard M. Foard, Ted Forgeron, Augie Hansen, Thomas V. Hoffmann, Henry F. Ledgard, Max Stul Oppenheimer, Richard Schwartz, Robert Shostak*

ART & PRODUCTION
ART DIRECTOR: *Paula Jaworski*
ASSOCIATE ART DIRECTOR: *Sharon Reuter*
ART ASSISTANT: *Maria Sese*
PRODUCTION MANAGER: *Alison Regan Mrohs*
CONTRIBUTING ARTISTS: *Maciek Albrecht, David Povilaitis*

ADVERTISING SALES
NATIONAL SALES MANAGER: *Rita Burke*
ADVERTISING MANAGER/WEST COAST: *Phyllis Egan*
MARKETING DIRECTOR: *Gayl Sorota*
ADVERTISING COORDINATOR: *Mary Martin*
MARKETING COORDINATOR: *Kimberly Schroeder*
SALES SECRETARY: *JeanMarie Donlin*
DISTRICT MANAGERS: *Rosemarie Caruso—New England; Arlene Braithwaite—Southeast; John Blake—Mid-Atlantic; Bill Barney—Midwest; Bill Bush, Deborah Gisonni, Nan Hanna—West Coast*
ACCOUNT REPRESENTATIVES: *Nanette Vilushis—Mid-Atlantic/Midwest; Carey Clarke, Steve Moorman—West Coast; John Blake—National Accounts, Mail Order; Classified advertising director—Kathryn Cumberlander*

CIRCULATION
CIRCULATION MANAGER: *Charles Mast*
CIRCULATION SALES DEVELOPMENT: *Daniel Rosensweig*
MEDIA MANAGER: *Melinda Kendall*
RETAIL SALES MANAGER: *Carol Benedetto*

ZIFF-DAVIS PUBLISHING COMPANY, *a division of Ziff Communications Co.*
PRESIDENT: *Kenneth H. Koppel*
SENIOR VICE PRESIDENT, Marketing: *Paul Chook*
VICE PRESIDENT, Operations: *Baird Davis*
VICE PRESIDENT, Controller: *John Vlachos*
VICE PRESIDENT, Creative Services: *Herbert Stern*
VICE PRESIDENT, Circulation: *Alicia Marie Ivans*
VICE PRESIDENT, Circulation Services: *James Ramaley*
VICE PRESIDENT, Marketing Services: *Ann Pollak Adelman*
VICE PRESIDENT, Development: *Seth Alpert*
VICE PRESIDENT: *Hugh Tietjen*
BUSINESS MANAGER: *Gary A. Gustafson*
PRODUCTION DIRECTOR: *Walter J. Terlecki*

ZIFF COMMUNICATIONS COMPANY
CHAIRMAN: *Philip B. Korsant;* PRESIDENT: *Kenneth H. Koppel;* SENIOR VICE PRESIDENT: *Philip Sine;* VICE PRESIDENTS: *Laurence Usdin, William L. Phillips, J. Malcolm Morris, Steven C. Feinman;* TREASURER: *Selwyn I. Taubman;* SECRETARY: *Bertram A. Abrams*

EDITORIAL OFFICE
PC Tech Journal, Suite 800, 10480 Little Patuxent Parkway, Columbia, MD 21044. 301/740-8300. FAX (group 3): 301/740-8809. MCIMail: PCTECH. PCTECHline: 301/740-8383. Telex: 6502565932 MCI.

ADVERTISING OFFICES
(East Coast/Midwest) Suite 800, 10480 Little Patuxent Parkway, Columbia, MD 21044. 301/740-8300. (Mid-Atlantic) 118 Palisade Avenue, Suite 5C, Cliffside Park, NJ 07010. 201/945-8833. (New England) 90 Everett Street, Arlington, MA 02174. 617/868-4611. (West Coast) 3460 Wilshire Blvd., Los Angeles, CA 90010. 213/387-2100; 11 Davis Drive, Belmont, CA 94002. 415/598-2290.

SUBSCRIPTION INQUIRIES
PC Tech Journal, P.O. Box 2968, Boulder, CO 80321. Subscription service: 800/525-0643, 303/447-9330. Back issues: send $7/copy ($8 outside U.S.) to Ziff-Davis Publishing, One Park Avenue, 4th floor, New York, NY 10016.

PC Tech Journal (ISSN 0738-0194) is published by Ziff-Davis Publishing Co., a division of Ziff Communications Co., One Park Ave., New York, NY 10016. Published monthly except semi-monthly in December. Subscription rate is $34.97 for one year (13 issues). Additional postage for Canada and Foreign is $.60/copy or $8.00/year. Second-class postage paid at New York, NY, and at additional mailing offices. POSTMASTER: Send address changes to PC Tech Journal, P.O. Box 2968, Boulder, CO 80321.

PC TECH JOURNAL is an independent journal, not affiliated in any way with International Business Machines Corporation. IBM is a registered trademark of International Business Machines Corp. Entire contents Copyright © 1987 Ziff-Davis Publishing Company, a division of Ziff Communications Company. All rights reserved; reproduction in whole or in part without permission is prohibited. Direct written requests to Jean Lamensdorf, Licensing Manager, Reprints/Rights & Permissions, One Park Avenue, New York, NY 10016.

BPA

1985 AWARD FOR BEST COMPUTER MAGAZINE Computer Press Association

NEW MODEL III!

The Periscope™ Difference

You'll need it sooner or later if you're doing serious software development

When you're writing large and/or complex programs, it's inevitable that you'll have to deal with some tough debugging problems. Your debugger should help you find and solve those problems quickly. The more solid, dependable, and efficient your debugger is, the better able it is to help you out in those difficult situations. The big difference between Periscope™ and other debuggers is this: Periscope enables you to debug programs other debuggers can't handle AND to debug in situations in which other debuggers won't work!

"We have been buying Periscope for about two years now, and have always been more than satisfied with the hardware, the software, and the responsiveness of the company. We have used Periscope in a great many difficult situations, where our only other alternative was a very expensive ICE (in circuit emulator). Periscope has performed most admirably," writes Dr. William Ash, Technical Director, FEL Computing.

The Periscope Promise. Continued product enhancement and user support.

"Not only is your Periscope (Model I) software the greatest thing since K & R, but your support has won over even the heart of this hardened programmer," writes Periscope user Mark Kumler of US Maintenance. *"I had decided long ago that no one in the industry cared about their customers after the check was cashed. You have definitely changed my opinion on that subject!"*

- User ideas are often implemented
- Your first software update is free; later updates are just $20
- You get free technical support and advice
- You can trade up for $10 plus the difference in price
- You get a 30-Day, Money-Back Guarantee

To Order or Receive Free Information, Call Toll-Free:

800/722-7006

Periscope Quality. The reason for Product of the Month.

"Periscope was chosen as the January (1986) Product of the Month because it represents what we felt was an excellent balance between power and cost and it has an extraordinarily clean and innovative design. . . the overall aura of quality was too strong to ignore," writes Jeff Duntemann, Technical Editor, PC Tech Journal, 7/86.

The Periscope Solution. A full line of debugging products that keep getting better.

"I have used Periscope daily for the past few months for testing and debugging my assembly code and I am still convinced this is the finest hardware or software debugger available at any price," writes long-time Periscope user Wynn Bailey.

There's a model of Periscope to meet your needs and budget. The enhanced Version 3.0 gives you more value than ever before! Call for details.

Periscope I has break-out switch & board with 56K of protected RAM . . . . . $345.

Periscope II has break-out switch . . . . . $175.

Periscope II-X (software-only model) . . . . . $145.

Periscope III has break-out switch & board with hardware breakpoints, a real-time trace buffer, and 64K of protected RAM . . . . $995.

The PERISCOPE Company, Inc.

14 Bonnie Lane, Atlanta, GA 30328 404-256-3860

CIRCLE NO. 215 ON READER SERVICE CARD

Critics Go Hog Wild

Over AutoSwitch™ EGA.

Here's an EGA card to get really excited about.

Autoswitch. "The most versatile EGA board on the market today," that "even the klutziest novice should have up and running in less than 10 minutes." **(PC World 9/86)** That's partly because it has "the best documentation we've seen for such cards." **(Infoworld 7/86)**

But "what really sets Autoswitch apart is its ability to automatically select appropriate video modes from its extensive built-in assortments." **(PC World 9/86)**

In other words, we've "consolidated the best features of other EGA clones into one board, and added an automatic (software) switching feature," **(Infoworld 7/86)** that "work(s) flawlessly." **(Byte 1/87)**

"No board has been more successful at improving IBM's® original idea" **(PC World 9/86),** and "none simplifies the mechanics and widens the choices as much as Paradise's™ Autoswitch EGA card." **(Personal Computing 9/86)**

And that was before we introduced the **Autoswitch EGA 480 Card** with **132 column mode, 480 vertical line resolution,** and extended our already **unbeatable range of software applications support.**

For the name of your local dealer, call (415) 871-4939.

PARADISE™

CIRCLE NO. 230 ON READER SERVICE CARD

AutoSwitch is a trademark of Paradise Systems, Inc.
IBM is a registered trademark of International Business Machines Corporation.

$9450 FOR A 20-MHZ 68020 EMULATOR? HELLOOOOOOO ATRON BUGBUSTERS!

For those of you who don't like to read, here's the bottom line: We're the Atron *Bugbusters,* and we've come to take over our rightful position as the leaders in the 68020 in-circuit emulator market, with the fastest and least expensive silicon wizardry our thunderstruck competition has ever seen. It's called 68020 PROBE.™ When we say *fastest,* we mean real-time, no-wait-state, 20-mhz emulation. When we say *least expensive,* we mean $9450, assuming you already own a PC/AT.

SO WHO'S ATRON?

Today, Atron is the number-one supplier of hardware-assisted software debuggers for 8088-based PCs and 80286-based ATs. Nine of the top ten PC and AT software packages were written by Atron customers. Everybody from AST to Borland to Oracle to Zenith. This time next year, we plan to make the same claims about the 68020 marketplace.

20-MHZ REAL-TIME EMULATION: SOONER OR LATER, YOU KNOW YOU'LL NEED IT.

Why invest in a slower emulator (especially one that costs more)? Some bugs only occur in real time, and you *know* your next design will be 20 mhz. Before Atron's state-of-the-art design, there was no such thing as a 20-mhz emulator. There still isn't another one anywhere near $9450.

PROBE CAN TRACE IT THROUGH THE PIPELINE, SO YOU WON'T LOSE YOUR MIND.

The 68020 has an on-board pre-fetch pipeline. Without Atron's 68020 PROBE, your best software engineer will spend a lot of time figuring out which instructions actually execute, and then, which bus cycles go with those instructions. The 68020 PROBE eliminates all these tedious mental translations and displays what the processor really did. The technology, called pipeline dequeueing, is only available from Atron. Because the Atron bugbusters are the only ones anywhere who've figured out how to do it. And it took us 100,000 lines of code. Consider it our contribution to your sanity. (It was a dirty job, but somebody had to do it.)

FROM SOURCE-LEVEL DEBUGGING TO PERFORMANCE ANALYSIS

Just so you'll know we've covered all the bases, the 68020 PROBE supports source-level debugging in C, Pascal and assembler. And when the job of bugbusting is done, you can use the 68020 PROBE as a timing analyzer, with Atron's software version or the *SoftAnalyst* from Northwest Instruments. So you can engineer both reliability and performance. So you can send only the best system into the field.

68020 PROBE SPECIFICATIONS

Clock speed	20 mhz
Execution	Transparent
Trace	2048 cycles by 96 bits
	Qualified trace region
	Dequeued trace data
	Pre and center triggered
	Includes symbols and source
	Dynamic cache control
Breakpoints	8 hardware on execute
	Read, write, fetch, logic
	Single or range addresses
	16 software breakpoints
	Sequential triggers - 4 terms
	Real-time pass counter
	Guarded access on memory
	Output lines for cross trigger
	Input lines for external logic
Mapped RAM	512K or 1 megabyte
Source debug	Yes for C, Pascal, Assembler
Symbolic debug	S, Tek, Coff formats
Symbol table	Limited only by AT disk size
User interface	Multiple windows and menus
Macros	Yes, and conditional execution
Download	To target system at 375k baud

HOW CAN ATRON DO ALL THIS FOR ONLY $9450?

The 68020 PROBE uses a PC/AT (or compatible) as its instrumentation chassis - the least expensive solution we could offer. Code generation can be done on the AT, a VAX or engineering workstation. And you don't have to tie up the latter two just for debugging. Smart, eh?

TO WAIT, OR TO WAIT STATE? THAT IS THE QUESTION.

Your choice, now, is a simple one. You can call Atron today. Or you can wait and call Atron tomorrow. And risk losing a production slot to one of *your competitors* who didn't want to wait, or who didn't want the wait-state technology of *our competitors*. So don't wait at all. Call 408/741-5900 today.

atron

BUGBUSTERS
A division of Northwest Instruments.
20665 Fourth Street • Saratoga, CA 95070
408/741-5900

Copyright © 1986 by Atron. 68020 PROBE is a trademark of Atron. The other companies mentioned own numerous trademarks. Adv. by TRBA.

Is UNIX Important?

Recent moves by IBM, Microsoft, Interactive, and AT&T provide food for thought.

ILLUSTRATION • MACIEK ALBRECHT

Something very important happened to UNIX recently. An improbable group of companies seems to have come to an agreement about it.

Fact 1: Microsoft and Interactive Systems have signed a mutual pact.

Fact 2: Interactive Systems is responsible in large part for several of the UNIX implementations supplied by IBM, including AIX for the RT PC.

Fact 3: Vittorio Cassoni, the head of AT&T Data Systems Group, speaking at the 1987 Personal Computer Forum in February, said that the 80386 would have one binary standard, and he also took some credit on behalf of AT&T for the Microsoft/Interactive deal.

Fact 4: At the recent announcement of enhancements to the RT PC, an IBM spokesman said that AIX would form the basis for UNIX offerings on its entire computer line.

Given the history of UNIX, this is an incredible set of facts and represents a significant, positive step forward. Although IBM and Interactive have worked together for years, AT&T has been touting its own hardware solutions for UNIX and not paying too much attention to the rest of the market (outside of collecting license fees), and Microsoft has been pushing its own XENIX and talking about bridges from MS-DOS. Now these four companies seem poised to nail UNIX's shoes to the floor, to hold it in place long enough to let things stick to it.

This is at once commendable and confusing. It is commendable that four important UNIX companies can be working, if not in perfect harmony, at least toward the common goal of a more secure standard for UNIX; that Microsoft, without abandoning its own identity, is working toward compatibility with IBM's UNIX versions; that IBM is focusing on AIX, perhaps the most commercially viable UNIX port to date; and that AT&T is recognizing the significance of other hardware.

But why this sudden cooperation? What makes working toward a common, standard UNIX a more important goal now than it was, say, a year ago? Have the issues changed? If so, what is the driving force?

A NEW WORLD

AT&T's Cassoni gave us the answer. The driving force is the 80386.

UNIX never achieved much of a foothold in the PC market. Most PCs are not up to the demands of such a large operating system—one that needs both high processor performance and above average disk performance. AT-class machines do not measure up, either. Although the 80286 does have built-in hardware memory management, it lacks other architectural features beneficial to a complex operating environment. Even its memory management is less than a contemporary operating system implementer would prefer. As a result, UNIX imposes considerable overhead when used on both the first and second generations of 86-family processors.

The 80386 changes all that. It is the first processor with all the architectural features required to run a "real" operating system. Most significant is the demand-paged, virtual memory management system that is, like its counterpart on the 80286, built into the processor. It has the performance, especially when coupled with high-speed mass storage. Better yet, it is a de facto part of the IBM PC standard, which means that a host of companies is working on 386-based, AT-compatible systems.

That is a most important fact. The number of UNIX installations, rumored to have doubled last year, has not yet reached a commercial critical mass. The current market is being fed by a plethora of companies with proprietary hardware architectures (everyone from Sun to Data General and dozens of others). Portability is not as good as the UNIX community would have us believe, however, because a significant share of the UNIX market falls in the workstation category, where exploiting the underlying hardware is often important. What an AT-compatible 386 machine (or even a new IBM standard machine) promises to do is reduce the number of variables that an application vendor needs to worry about. That is the essence of MS-DOS on the current IBM standard.

A computer's memory management unit is a key to stabilizing the hardware. This was the argument for XENIX 286 put forth by Microsoft's Bill Gates, and it applies equally to the 386. The point: *every* 386 system installed has precisely the same, built-in memory unit. A manufacturer can provide a more advanced,

external subsystem, but the memory architecture of the 386 is more than satisfactory; a vendor with such a strategy would be taking a major risk.

In short, the 80386 represents a stable, standard, hardware platform, and there are going to be a lot of 386 machines within the next two years.

WHO CARES?

For starters, IBM, AT&T, Microsoft, and Interactive Systems care. Second, all the manufacturers of UNIX-based software who would like to see improvement in their growth curve and jumps in their profitability care. Oh, I almost forgot: Apple cares.

Apple may be the catalyst that has companies on the other side of the architectural fence running so scared that they would resort to a very close working arrangement. Why? Because right now the workstation market is focused on machines using the 68000 processor family. Apple, by the time you read this, will have announced the Open Mac. I suspect that UNIX will have been announced for the machine; if not, expect it shortly if for no other reason than Apple President and CEO John Sculley's statement at the PC Forum that Apple is committed to UNIX.

The details of Open Mac are fuzzy, but clearly it will be an excellent platform for workstation products. Perhaps more important, the Mac interface has more in common with the dedicated workstation products than does the IBM PC interface, so buyers in that market will naturally gravitate toward such a machine. Sculley is not exactly immodest about Apple's future, but he may be too modest about prospects in the workstation segment.

That leaves those of us on this side of the fence with a big problem. I am sure that IBM and AT&T would like a piece of the workstation pie. Microsoft and Interactive undoubtedly would like a more significant revenue stream from 86-family UNIX software products. Certainly the application vendors want their potential market (that is, the total number of UNIX-capable machines installed) to grow, grow, grow.

This is the reason for the sudden and serious cooperation. The right hardware is here today and more is just around the corner. If the vendors committed to the 86 architecture do not act quickly, every workstation in sight will probably sport that little Apple logo.

DO WE CARE?

It is probably safe to say that the majority of *PC Tech Journal* readers are not involved in the workstation market. Then, why am I making such a fuss?

We may not be looking for workstations, but we do need 386-class machines applied to other tasks. One particularly important area is the network server. Eventually, it would be nice if servers ran the same operating system found on the network's nodes, meaning MS-DOS. The rumor mill to the contrary, it will be some time before we see a version of DOS for the 386. (In fact, it may be some time before we see one for the 286.) In the meantime, LAN is headed for critical mass.

In order for LANs to be effective in a general-purpose environment, servers need to become smarter. They need to be able to execute code in support of the network applications (and not just electronic mail). Data servers will need data manager stubs to process queries. Printer servers will need page description language translators and drivers (if they are not built into the printer). Transaction systems will need local intelligence in gateways.

When a vendor delivers a network server with proprietary operating software, adding intelligence to the server is not possible because the vendors of products such as data managers are not going to build their network stubs for all the different operating systems. Because this need is beginning to become apparent, UNIX-based servers represent a strong alternative to what is bound to be the long-awaited 386 DOS.

A 386 machine, even in the AT class, is a very good platform for dedicated applications, the type that are traditionally supported by timesharing, multiuser systems with dumb terminals. Enormous opportunity exists for systems of this type, especially in small businesses where the cost per node of a LAN solution is prohibitive and the flexibility delivered by networked PCs is simply not required.

The foothold that UNIX can gain in the PC marketplace remains uncertain. Increased competition, the availability of a suitable hardware platform, and just plain pride on the part of the participating companies may drive UNIX toward its own critical mass in a market that has traditionally shunned it.

INSPIRING CONFIDENCE

One problem in the computer industry is that so many companies fail to understand just how long their development efforts will take. Provoked by fierce competition for the dollars of customers and the attentions of journalists, companies tend to announce a product too soon and then are not able to meet their own deadlines.

Such behavior hardly builds confidence. At least two companies, however, have impressed me with how well they have kept to their plans (even if their schedule slipped a bit) and maintained their focus.

The first is Gold Hill Computing, manufacturer of Golden Common LISP, a developer's toolkit, and the soon-to-be-released GoldWorks (formerly Acorn), an expert-system tool. A year ago Gold Hill CEO Carl Wolfe candidly laid out his long-range plan; he was so frank that I almost dismissed what he was saying as braggadocio. Late last year Wolfe outlined the same plan, with milestones reached and others clearly in sight.

This is especially impressive because the Gold Hill products are complex, requiring the efforts of not only LISP programmers but also those knowledgeable in expert systems and artificial intelligence. The higher complexity of the software increases the likelihood of scheduling errors. Gold Hill seems to have avoided the pitfalls, and the important side effect is that people will listen to Wolfe's posturing about the future much more carefully.

The second company to impress me with its planning is Compaq. Although *PC Tech Journal* was not privy to a year's-eye view, we were given a few advance hints, which, combined with a growing respect for Compaq's serious and thoughtful managers, convinces us that, indeed, the firm is planning very carefully.

Compaq also is able to focus, an ability sorely lacking in so many companies. Its portable model has been successively refined with smaller, lighter, faster, and better machines. Even though Compaq now makes desktop models, it promotes its own mystique by producing better versions of the machine that fueled its extraordinary business success.

Gold Hill and Compaq merit special recognition for delivering the goods. They also should stand as models for other firms that, perhaps, are struggling too much.

—WF

Never Lose Work in Progress Again!

Automatically marks your place so you can resume where you left off.

- BOOKMARK is a memory-resident utility that automatically backs up work in progress to the hard disk at user-definable intervals.
- Work in progress can be resumed within seconds after system crash, power failure, accidental reset or power down.
- Use it like a BOOKMARK for your computer to bring you back where you left off so you can stop wasting time navigating through menus . . . or teaching novices.
- Easy to use. You choose how often work is saved, by number of keystrokes or length of time.
- Operates concurrently and transparently with most software.
- Costly battery backup systems are no longer needed when work in progress is already saved to the point of the previous BOOKMARK placement.
- Password protection is provided as an option to prevent unwanted viewing of resumed work by others.
- Exiting programs can be as simple as placing a BOOKMARK and powering down, reloading as simple as powering up & pressing "y" to resume.

Call or write for the name of the dealer or distributor nearest you.

INTELLISOFT™

INTERNATIONAL

Call Toll Free (800) 544-MARK • In California Call Toll Free (800) 543-MARK
70 Digital Drive • P.O. Box 5055 • Novato, California 94948 • (415) 883-1188

Requirements:
IBM PC/XT/AT or 100% Compatible • 256k to 640k • IBM DOS 2.1 or Higher. 1 Floppy Drive • Hard Disk Drive (10 Megabytes Minimum) • Video Display Adapter IBM (Monochrome, Color, Enhanced Color), Hercules, AST (BOOKMARK occupies an equivalent space on hard disk as in system RAM plus video RAM)

BOOKMARK™ is a trademark of INTELLISOFT International. Copyright © 1986 by INTELLISOFT International. All rights reserved. Patent Pending. IBM PC/XT/AT are registered trademarks of International Business Machines Corporation. Hercules is a trademark of Hercules Computer Technology. AST is registered trademark of AST Research, Inc.

CIRCLE NO. 114 ON READER SERVICE CARD

COMPATIBLE DESIGN. INCOMPARABLE PERFORMANCE. INCREDIBLE VALUES.

In three years, PC's Limited has revolutionized the way America buys personal computers by manufacturing demonstrably better systems and then selling them directly to end users at remarkably low prices. That's why we've shipped tens of thousands of computers to date.

It's also why the trade press has praised our machines with comments like "a perfect tool" and "an incredible value." And it's no wonder. Because PC's Limited gives you more speed with 8 and 12 MHz machines. Plus a megabyte of high-speed RAM. We provide SmartVu™, an exclusive alphanumeric display that gives you real-time diagnostics. And you even get your choice of chassis sizes, plus a wide selection of drives, monitors, and add-on boards.

What's more, we back what we sell with industry-leading free 800-line technical support, an unconditional 30-Day Money-Back Guarantee, and a full One-Year Limited Warranty.

Right now, you can select from a wide variety of fully configured systems at dramatically reduced prices. If you are just getting acquainted with us, there's never been a better time to find out what you've been missing. Because with PC's Limited, everyone can afford to be a power user.

PC'S LIMITED TURBO PC™

Monochrome Systems

- Intel 16-Bit 8088-2 System Unit running at 4.77 MHz and 8.0 MHz
- 640K on Motherboard
- AT™-Style 84-Key Keyboard
- 130 Watt Power Supply
- Hercules Compatible Graphics Adapter with one Parallel Port
- PC's Limited Mono-IIA Flat Screen Monochrome Monitor with Tilt and Swivel Base

with two 360K Floppy Disk Drives—**$859**

with one 360K Floppy Disk Drive and one 20 Meg, 65 MS Hard Disk Drive—**$1199**

EGAds! Color Systems

- Intel 16-Bit 8088-2 System Unit running at 4.77 MHz and 8.0 MHz
- 640K on Motherboard
- AT™-Style 84-Key Keyboard
- 130 Watt Power Supply
- PC's Limited EGAds! Card
- PC's Limited EGAds! Monitor

with two 360K Floppy Disk Drives—**$1229**

with one 360K Floppy Disk Drive and one 20 Meg, 65 MS Hard Disk Drive—**$1589**

PC'S LIMITED 286[8]

Monochrome Systems

- Intel 80286 running at 8 MHz
- 1024K on Motherboard
- 1.2 Meg Floppy Disk Drive
- Combined Floppy and Hard Disk Controller
- AT™-Style 84-Key Keyboard
- 192 Watt Power Supply
- Clock/Calendar with Battery Backup
- Hercules Compatible Monochrome Graphics Card
- 2 Serials and 2 Parallel Ports
- PC's Limited Mono-IIA Flat Screen Monochrome Monitor with Tilt and Swivel Base
- SmartVu™ (Real Time Diagnostic Display)

with 20 Meg, 65 MS Hard Disk Drive, Space Saving Chassis—**$1795**

with 30 Meg, 40 MS Hard Disk Drive, AT™ Standard Chassis—**$2195**

EGAds! Color Systems

- Intel 80286 running at 8 MHz
- 1024K on Motherboard
- 1.2 Meg Floppy Disk Drive
- Combined Floppy and Hard Disk Controller
- AT™-Style 84-Key Keyboard
- 192 Watt Power Supply
- Clock/Calendar with Battery Backup
- PC's Limited EGAds! Card
- 2 Serials and 1 Parallel Port
- PC's Limited EGAds! Monitor
- SmartVu™ (Real Time Diagnostic Display)

with 20 Meg, 65 MS Hard Disk Drive, Space Saving Chassis—**$2195**

with 30 Meg, 40 MS Hard Disk Drive, AT™ Standard Chassis—**$2595**

PC'S LIMITED 286[12]

Monochrome Systems

- Intel 80286 running at 12 MHz
- 1024K on Motherboard
- 1.2 Megabyte Floppy Disk Drive
- Combined Floppy and Hard Disk Controller
- AT™-Style 84-Key Keyboard
- 192 Watt Power Supply
- Clock/Calendar with Battery Backup
- Hercules Compatible Monochrome Graphics Card
- 2 Serials and 2 Parallel Ports
- PC's Limited Mono-IIA Flat Screen Monochrome Monitor with Tilt and Swivel Base
- AT™-Standard Chassis
- SmartVu™ (Real Time Diagnostic Display)

with 30 Meg, 28 MS Hard Disk Drive—**$3095**

with 40 Meg, 28 MS Hard Disk Drive—**$3295**

EGAds! Color Systems

- Intel 80286 running at 12 MHz
- 1024K on Motherboard
- 1.2 Megabyte Floppy Disk Drive
- Combined Floppy and Hard Disk Controller
- AT™-Style 84-Key Keyboard
- 192 Watt Power Supply
- Clock/Calendar with Battery Backup
- PC's Limited EGAds! Card
- 2 Serials and 1 Parallel Port
- PC's Limited EGAds! Monitor
- AT™-Standard Chassis
- SmartVu™ (Real Time Diagnostic Display)

with one 30 Meg, 28 MS Hard Disk Drive—**$3495**

with one 40 Meg, 28 MS Hard Disk Drive—**$3695**

A GUARANTEE THAT STANDS UP.

PC's Limited has established itself as the leader in PC technology. And the guarantee and warranty programs we offer put us ahead of the pack, too. Here are our terms in plain English.

30-Day Total Satisfaction Guarantee—Any item bought from PC's Limited may be returned within 30 days from the date it was shipped for a full refund of your purchase price. Returned items must be as-new, not modified or damaged, with all warranty cards, manuals, and packaging intact. Returned items must be shipped prepaid and insured, and must bear a PC's Limited Credit Return Authorization (CRA) on the shipping label.

One Year Limited Warranty—PC's Limited warrants the products it manufactures to be free from defects in materials and workmanship for one year following the date of shipment from PC's Limited. During the one year warranty period, PC's Limited will repair or replace, at its option, any defective products or parts at no additional charge, provided that the product is returned, shipping prepaid, to PC's Limited.

PC'S LIMITED

To buy PC's Limited computers, call us directly at . . . 1-800-426-5150

Calls inside Texas, 1-800-252-8336.

Sales lines open 7 a.m. until 7 p.m. Monday–Friday, 10 a.m. until 3 p.m. Saturday, Central Standard Time

1611 Headway Circle, Building 3, Austin, Texas 78754

Sales Calls from anywhere in the country, (512) 339-6962, Technical Support Calls, 1-800-624-9896 or PC's Limited BBS (512) 339-4127

Customer Service Calls, 1-800-624-9897 or MCI MAIL: PC's Limited, Telex No. 9103808386 PC LTD FAX (512) 339-6721

CIRCLE NO. 150 ON READER SERVICE CARD

Seal of Approval

Lotus certifies ATI's Graphics Solution

ATI's **"Small Wonder" Graphics Solution** has never been slow to pick up compliments, particularly in the area of multi-mode flexibility. Much of the credit for this is due to ATI's use of advanced technology. Therefore it's not very surprising that Lotus – the world's leader in software – has certified the "Graphics Solution" for 132 x 44 monochrome spreadsheets and 640 x 200 7 color graphics so you can see more spreadsheet and sharper, more colorful graphs on 1-2-3 (2.0) and Symphony (1.1).

At ATI, we think we've developed a better graphics card. It just might surprise you how much better. Call us at **(416) 477-8804** for more information.



LOTUS CERTIFIED 132 x 44 MONOCHROME SPREADSHEETS

COLOR SOFTWARE ON MONOCHROME MONITOR IN 16 SHADES



LOTUS CERTIFIED 640 x 200 HIGH RESOLUTION COLOR/GRAPHICS

FEATURES

- **Hercules Compatible Monochrome Graphics**
- **Runs Color/Graphics Software on Monochrome Monitor in 16 Shades Without Pre-Boot Drivers**
- **High Resolution Color/Graphics — 320 x 200 16 Colors**
  Plantronics compatible — 640 x 200 4 Colors
  — 640 x 200 16 Colors
- **IBM Compatible Color/Graphics**
- **132 Columns in Either Color or Monochrome**
- **Lotus Certified Drivers for 132 Columns and 640 x 200 High Resolution Color/Graphics**
- **Drivers for 640 x 200 High Resolution 16 Colors on Framework II**
- **Drivers for 640 x 200 16 color Autocad available**
- **Parallel Port and Serial Port Optional**
- **2 Year Warranty**
- **$299 Suggested Retail**

NOW! ATI ALSO HAS **DRIVERS** FOR ASHTON-TATE® **FRAMEWORK II**

Small Wonder From

ATI Technologies Inc.
450 Esna Park Dr.
Markham, Ontario, Canada L3R 1H5
TELEX 06-966640 (CMC - MKHM)

ATI TECHNOLOGIES INC.

Technology you can Trust.

* *Trademarks: Lotus 1-2-3, Symphony, — Lotus Development Corporation; Framework II — Ashton-Tate Inc.; PC Paintbrush + — Z-Soft Inc.; IBM — International Business Machines Inc.; Hercules — Hercules Computer Technology Inc.; Plantronics — Plantronics Enhanced Graphics Corp. Autocad — Autodesk Inc.

CIRCLE NO. 207 ON READER SERVICE CARD

***This Lotus logo is used by permission of Lotus Development Corporation.**

The Graphics Solution has successfully passed compatibility testing with 1-2-3 (2.0) and Symphony (1.1) on an IBM PC-XT with PC-DOS 3.1. The Graphics Solution must be installed.

EGAWONDER™

Any Software. Any Monitor. Any Time.[1]



Any Software on an EGA Monitor

Any Software on a TTL Monochrome Monitor



Any Software on an RGB Color Monitor[3]

Upgrade to EGA without an EGA Monitor
The unique **ATI EGA WONDER** allows upgrade to the new EGA graphics standard without the purchase of an expensive EGA monitor. **EGA WONDER** runs EGA, CGA, MDA, Hercules and 132 column software on EGA Color, RGB Color, TTL Monochrome and Composite monitors. Extremely flexible, **EGA WONDER** maintains downward compatibility to both existing software and existing monitors. On the internal monitor of a Compaq PC Portable, **EGA WONDER** displays EGA, CGA, MDA and Hercules software via an optional expansion module.[2] For EGA monitor users, the **ATI EGA WONDER** improves the display of CGA software by producing high resolution 8×14 text and double scanned graphics. Old CGA software is now displayed with EGA quality. Completely compatible to IBM's EGA, **ATI's EGA WONDER** performs smooth scrolling, pixel panning and windowing. No memory modules are required because 256K of video memory is a standard feature. **EGA WONDER** is the only card able to display EGA software on the internal monitor of both the IBM PC Portable and the Compaq PC Portable. **EGA WONDER** provides an NTSC Composite signal for interface to a Polaroid Palette.

SoftSense Automatic Mode Switching
User friendly and easy to use, the **ATI EGA WONDER** has built-in SoftSense Automatic Mode Switching. It is actually able to sense and automatically switch between EGA and CGA color modes or between EGA, MDA and Hercules monochrome modes. The **ATI EGA WONDER** is compatible at the hardware level to the IBM Enhanced Graphics Adapter, the IBM Color/Graphics Adapter, the IBM Monochrome Display Adapter and the Hercules Graphics Card to minimize software incompatibilities.



$399 Suggested list price

EGA WONDER is now available from all major computer stores, call us today at **(416) 477-8804** for more information.

CIRCLE NO. 206 ON READER SERVICE CARD

ATI® TECHNOLOGIES INC.

Technology you can Trust.

ATI Technologies Inc., 450 Esna Park Dr.,
Markham, Ontario, Canada L3R 1H5. TLX. 06-966640.

Trademarks IBM PC Portable – EGA CGA MDA – International Business Machines – Compaq – Compaq Computer Corporation – Hercules – Hercules Computer Technology – Polaroid Palette – Polaroid Corporation. Graphics courtesy Rix Softworks Inc.

1. Any Software, Any Monitor, Any Time applies to IBM graphics, standards, monitors, software.
2. Optional Compaq Expansion Module, (available for internal portable dual-mode monitor no 132 Columns) Suggested list price $99.
3. EGA, MDA, Hercules software displayed via interlacing. Flickering effect of interlacing reduced with purchase of anti-glare screen filter.

USERS SAY BRIEF™ is BEST

84% of BRIEF users were more productive with BRIEF than with any other editor. 72% were performing normal operations in 2 hours or less.*

The Program Editor with the BEST Features

Since its introduction, BRIEF has been sweeping programmers off their feet. Why? Because BRIEF offers the features **MOST ASKED FOR** by professional programmers. In fact, BRIEF has just about every feature you've ever seen or imagined, including the ability to configure windows, keyboard assignments, and commands to **YOUR** preference. One reviewer (David Irwin, DATA BASED ADVISOR) put it most aptly, "(BRIEF)...is quite simply the best code editor I have seen."

*500 users were surveyed 111 responded.

REGULAR EXPRESSION SEARCH

Regular expression searching is one of BRIEF's most powerful features. A regular expression is a series of "wildcards" that match pieces of your text. BRIEF supports a full set of regular expression characters similar to those found in UNIX including: beginning an end of line, groups, and the "closure" and "or" operators.

As Steve McMahon explained in Byte, "Not only does BRIEF make use of this marvelously general regular expression notation in its search facility, but its pattern recognition extends to its replacement (or translation) facility." "The usefulness of this facility for programmers who deal constantly with the regular expressions of formal languages is obvious . . ."

Every Feature You Can Imagine

Compare these features with your editor (or any other for that matter).

- FAST
- Full UNDO (N Times)
- Edit Multiple Large Files
- Compiler-specific support, like auto indent, syntax check, compile within BRIEF, and template editing
- Exit to DOS inside BRIEF
- Uses all Available Memory
- Tutorial
- Repeat Keystroke Sequences
- 15 Minute Learning Time
- Windows (Tiled and Pop-up)
- Unlimited File Size –(even 2 Meg!)
- Reconfigurable Keyboard
- Context Sensitive Help
- Search for "regular expressions"
- Mnemonic Key Assignments
- Horizontal Scrolling
- Comprehensive Error Recovery
- A Complete Compiled Programmable and Readable Macro Language
- EGA and Large Display Support
- Adjustable line length up to 512

Program Editing YOUR Way

A typical program editor requires you to adjust your style of programming to its particular requirements – NOT SO WITH BRIEF. You can easily customize BRIEF to your way of doing things, making it a natural extension of your mind. For example, you can create ANY command and assign it to ANY key – even basic function keys such as cursor-control keys or the return key.

The Experts Agree

Reviewers at BYTE, INFOWORLD, DATA BASED ADVISOR, and DR. DOBB'S JOURNAL all came to the same conclusion – BRIEF IS BEST!

Further, of 20 top industry experts who were given BRIEF to test, 15 were so impressed they scrapped their existing editors!

NOT COPY PROTECTED

Solution Systems™

MONEY-BACK GUARANTEE
Try BRIEF ($195) for 30 days – If not satisfied get a full refund.
TO ORDER CALL (800-821-2492)

SOLUTION SYSTEMS, 335-P WASHINGTON ST., NORWELL, MA 02061, 617-659-1571

BRIEF is a trademark of UnderWare

CIRCLE NO. 130 ON READER SERVICE CARD





MOUSETRAP

I agree wholeheartedly with Jeff Duntemann's favorable review of the Logitech Logimouse C7 (Product Watch, December 1986, p. 185). I recently bought one for use on my own personal PC/XT-compatible system, and I much prefer it to the Microsoft Mouse that I use at work. The fact that the Logimouse is such a good value is icing on the cake.

However, I have one caveat for prospective buyers: I ordered my Logimouse from a distributor (Programmer's Connection) and was pleased to receive it in less than a week. Upon opening the package, though, I was puzzled to find a very different mouse than the one I expected. Instead of three large flat buttons, I found three sets of "ribs" poking through slots where the buttons should have been. For my money, the feel of these ersatz buttons wasn't anywhere near as good as those of the conventional Logimouse that I had tried earlier.

When I called about this, the distributor's salesperson seemed completely unaware of any question regarding the Logimouse buttons. She thought all mice that are available from Logitech had the same buttons (the "fancy" kind) and suggested that I call Logitech's customer service number.

The Logitech customer service representative knew all about the new buttons—she referred to the two different button styles as the "conventional" button and the "fluted" button. It seems both styles are current, and both are being shipped more or less at random. Mine was evidently not the first complaint, because even before I asked, she said that I could return my fluted-button mouse for replacement with a conventional-button mouse. I did.

In sum, I would advise users to specify the button style when ordering a Logitech Logimouse. The salesperson may not be aware of the distinction between the two styles, and I have never seen this difference mentioned in the company's advertisements or even in the user's manual.

Richard M. Kruse
Prairie Physics
Wichita, KS

Mr. Kruse is not alone. When PC Tech Journal *first received a Logimouse C7 for review, it too had the fluted-button design. Worse, when the center button was pressed, a slight misalignment of the case caused it to stay down, and the screws holding the case together had to be loosened to get the button to release. According to Logitech, the fluted design is popular in Europe, but it was never intended for the U.S. retail channel. A few have appeared in U.S. distribution, however, and Logitech has promised to replace any fluted-style mouse with a conventional mouse at no charge. The packaging is identical, so the distributor has no way of knowing which mouse is on the shelf without breaking the shrink wrap and looking inside.*

—Jeff Duntemann

ALL BOTTLED UP

Once again I find myself amused by complaints about graphics processors ("Display Adapter Bottleneck," Michael Abrash, January 1987, p. 104). Mr. Abrash starts off with a noble mission since many programmers do not seem to understand the implications of wait states in accessing display memory. However, I think the article really misses the point by suggesting that awareness of the problem is the best solution. It is time we admit that this "state of the art" graphics board—the IBM Enhanced Graphics Adapter (EGA)—is simply inadequate. The insertion of multiple wait states is just one example of the EGA's weakness. Even more alarming is the complex interface that makes the EGA the most nonportable graphics device around and does little to enhance performance.

If the user really wants to make a fast display buffer, it would be very easy to beat the EGA. Here are three rather obvious techniques: First, tighten up the memory cycle timing to make good use of the memory bandwidth instead of minimizing the complexity of the control logic. Given the overall complexity of the EGA chip set, the additional logic required to do this is insignificant.

Second, buffer display RAM write operations. By this I mean to latch the address and data to be written, letting the CPU go on to the next instruction without any wait states. The sequencer then would perform the write cycle in the next available slot. Wait states would be inserted only when the CPU tried to perform another access to the display RAM (or GDC control registers) before the first operation was completed.

Third, use video RAMs (dual-ported RAM devices designed specifically for display buffers). This can reduce display refresh cycles to less than 5 percent and vastly simplify the complexity of the control circuitry. To be fair, video RAMs were not available at a reasonable price at the time the EGA was designed. Until quite recently they were available from only one manufacturer (in the 256KB density) and so the price was artificially high. But today there is very little reason not to use them.

So what are end users to do? Build their own graphics boards? Suffer CGA (IBM Color Graphics Adapter) graphics until something better comes out? I think anyone interested in high quality, speedy graphics should look at the various (IBM Professional Graphics Controller) PGC-compatible products on the market. Unlike most graphics boards around, these boards present a simple, generic interface and a native graphics command set that eliminates a large part of the effort involved in writing a graphics application. PGC-compatible boards have been implemented with a variety of architectures and characteris-

tics. EGA clone manufacturers, on the other hand, must practically copy the IBM design, gate for gate (including numerous design errors).

PGC compatibles have resolutions ranging from 640-by-480 to 1,280-by-1,024 pixels, and list prices ranging from under $1,000 to more than $4,000. Yet, they all behave the same from the view of an application program or the user (except for various enhancements beyond IBM's original specification). The biggest problem with these boards is that some software developers seem to resent that a hardware product now performs tasks that used to be their job. Some popular graphics toolkit products on the market today are rendered totally obsolete by the PGC. And with the excitement over new graphics controllers, such as Texas Instruments' 34010, everyone seems to be saying that is the way it should be.

Greg Marshall
Fremont, CA

I certainly agree that the EGA is a low-performance display adapter with a quirky architecture (although this relates only tangentially to the topic of the article). I do not agree that the EGA is inadequate, however, and I am not sure it makes a difference to state that claim in any case. At least half a million EGAs are now installed, and they continue to sell briskly; developers have no choice but to support the EGA, warts and all. Inadequacy is judged by the marketplace; in that sense, the PCjr was inadequate, but the EGA is not. Railing against the deficiencies of the EGA is somewhat like complaining about the inferiority of the 8088 relative to the 68000: it may or may not be true, but given that the largest installed base of computers in history is built around the 8088, it is not particularly relevant.

Mr. Marshall suggests three ways in which EGA performance might be improved. Frankly, given the architecture of the EGA, I doubt that the display adapter bottleneck can be significantly eased, and a review of Mr. Marshall's suggestions reinforces this point.

The first suggestion is tighter memory timing. This has been implemented already by several chip manufacturers, including Chips and Technologies and Tseng Labs, and does indeed improve the performance of bit-mapped interfaces perceptibly. However, the EGA is still an 8-bit device (and because of pin counts will likely remain so); therefore EGA performance in the PC/AT is improved by a ratio of only about 2:1, at best. Performance on 80386-based computers is similarly limited.

The second suggestion is the buffering of display RAM writes. This would be of little help in the case of multiple successive accesses, which is where the bottleneck matters most. This case includes block copies to EGA memory and block copies with EGA memory as both source and destination, which are used heavily in window-oriented and animated EGA programs. In particular, virtually no speed improvement would result in the case of block copies involving EGA memory on ATs and 80386-based computers, because these computers request successive accesses much faster than the EGA perform them.

The third suggestion is the use of video RAM. Given the EGA's design, it would be difficult to use video RAM, most notably because the fonts, which are stored in video memory, must be accessed randomly, and because of the virtual screen width capability.

In short, a fully compatible, higher-performance version of the IBM EGA is unlikely to appear. Moreover, the price/performance ratio of the EGA seems to be more than acceptable to the PC market right now; thus, the EGA will likely remain the standard for some time.

—Michael Abrash

CIRCLE NO. 101 ON READER SERVICE CARD

CODE READ

In Tech Notebook 71 ("Reading Locked Files," December 1986, p. 51), Arsen Darnay provides a complicated and potentially dangerous method of handling read-only files with Turbo Pascal. Unlocking a read-only file creates the possibility of accidentally erasing the file if the program fails or is interrupted before it relocks the file. Suppose the program ROREADER, using this method with the read-only file SAMPLE.TXT, is invoked from the file:

```
ROREADER.COM
REM        Next erase all .TXT files
ERASE *.TXT
```

If ROREADER fails before relocking SAMPLE.TXT, the file would be erased.

Additionally, the global variable F_Attr *must* be safely maintained in order for the Restore_Attr procedure to correctly restore the original file attributes. A simple programming error might alter the value of F_Attr, thus causing Restore_Attr to change the file attributes to something different.

To top it off, many applications running in a network environment *require* that a file be set to read-only in



PC MAGAZINE EDITOR'S CHOICE

*...one package stands out as the best support available for Turbo Pascal programmers: **Blaise Computing's Turbo Power Tools.** This definitive set of prewritten Pascal functions and procedures will make the life of any programmer—from the beginner to the hard-core professional—easier and more productive.*

Power Tools Plus™

Window Routines. Memory Resident Routines. Routinely.

ANOTHER PLUS FROM BLAISE COMPUTING

The best just got better! Turbo POWER TOOLS, acclaimed as the best programmer support package for Turbo Pascal, now has even more functions, more detailed documentation and more sample programs.

NO SECRETS

Turbo POWER TOOLS PLUS is crafted so that the source is efficient, readable and easy to modify. We don't keep secrets! We tell you exactly how windows are managed, how interrupt service routines can be written in Turbo Pascal, and how to write memory resident programs that can even access the disk. Maybe you've heard of some undocumented DOS features that resident programs use to weave their magic. Turbo POWER TOOLS PLUS documents these features and lets you make your own magic!

Here's just part of the PLUS in Turbo POWER TOOLS PLUS:

- **WINDOWS** that are stackable, removable, with optional borders and a cursor memory.
- **FAST DIRECT VIDEO ACCESS** for efficiency.
- **SCREEN HANDLING** including multiple monitor and EGA 43-line support.
- **POP-UP MENUS** which are flexible, efficient and easy to use, giving your applications that polished look.
- **INTERRUPT SERVICE ROUTINES** that can be written in Turbo Pascal without the need for assembly language or inline code.
- **INTERVENTION CODE** lets you develop memory resident applications that can take full advantage of DOS capabilities. With simple procedure calls, you can "schedule" a Turbo Pascal procedure to execute either when a "hot key" is pressed, or at a specified time.
- **PROGRAM CONTROL ROUTINES** allow you to run other programs from Turbo Pascal, and even execute DOS commands.
- **MEMORY MANAGEMENT** allows you to monitor, allocate and free DOS-controlled memory.
- **DIRECTORY AND FILE HANDLING** support to let you take advantage of the newer features of DOS including networking.
- **STRING** procedures allowing powerful translation and conversion capabilities.
- **FULL SOURCE CODE** for all included routines, sample programs and utilities.
- **DOCUMENTATION, TECHNICAL SUPPORT** and attention to detail that have distinguished Blaise Computing over the years.

Turbo POWER TOOLS PLUS** supports Turbo Pascal Version 2.0 and later and is just **$99.95.

*Another quality product from Blaise Computing: **Turbo ASYNCH PLUS™***

A new package which provides the crucial core of hardware interrupt support needed to build applications that communicate. ASYNCH PLUS offers simultaneous buffered input and output to both COM ports at speeds up to 9600 baud. The XON/XOFF protocol is supported. Now it also includes the "XMODEM" file-transfer protocol and support for Hayes compatible modems.

The underlying functions of Turbo ASYNCH PLUS are carefully crafted in assembler for efficiency and drive the UART and programmable interrupt controller chips directly. These functions, installed as a runtime resident system, require just 3.2K bytes. The high level function are all written in Turbo Pascal in the same style and format as Turbo POWER TOOLS PLUS. All source code is included for just $99.95.

BLAISE COMPUTING INC.
2560 Ninth Street, Suite 316 Berkeley, CA 94710 (415) 540-5441

ORDER TOLL-FREE 800-227-8087
Calif. residents call (415) 540-5441

YES, send me the PLUS I need! Enclosed is $_____ for ☐ Turbo POWER TOOLS PLUS ☐ Turbo ASYNCH PLUS ☐ OTHER _____. (CA residents add 6½% Sales Tax. All domestic orders add $10.00 for Federal Express shipping.)

Name: _____ Phone: (____) _____

Shipping Address: _____

City: _____ State: _____ Zip: _____

VISA or MC #: _____ Exp. Date: _____

CIRCLE NO. 104 ON READER SERVICE CARD

Reprinted from PC Magazine, June 10, 1986 Copyright © 1986 Ziff-Davis Publishing Company

The Answer to your Debugging Problems

ICD286

Announcing New Features

- ***Supports EMS***
- ***Supports Microsoft windows***

At last! An 80286 emulator which is affordable, compact and easy to use. IDEAL for development, debugging, testing and field service.

FAST—Full speed, real-time emulation up to 10 Mhz.

AFFORDABLE—From $2400 to $5600, depending on options.

EASY TO USE—On-line HELP with a screen oriented display.

KEY FEATURES:

- Hardware/software breakpoints
- 2048 bus cycles of real-time trace
- 64K of emulation memory
- Symbol and line number support
- Source-level debugging
- Real and virtual (protected) mode support
- Symbolic assembly/disassembly
- Macros with parameters
- Installs in an IBM-PC/XT/AT* or compatible
- Supports EMS (New Features)
- Supports Microsoft Windows (New Option)

For further information, please contact:

Answer Software
Corporation

20863 Stevens Creek Boulevard
Cupertino, CA 95014
(408) 253-7515

*IBM-PC/XT/AT are registered trademarks of International Business Machines Corporation.

CIRCLE NO. 214 ON READER SERVICE CARD

order that multiple users may access it simultaneously. As soon as the procedure Clear_Attr cleared the file's read-only attribute other users on the network might not be able to access it.

Because Turbo Pascal (version 3.x) uses the DOS function call 3DH to open a file, a much safer way to open read-only files is to temporarily change the mode byte that Turbo Pascal passes to DOS to a zero (for read-only access). In the regular version of Turbo Pascal, this byte is located in the code segment at offset 24FCH. In the 8087 version, it is at offset 1FABH, and in the binary-coded-decimal (BCD) version, it is at 2402H. A sample program demonstrating this method is as follows:

```
Program Open_RO;

Var
  InFile     : Text;
  Tmp_Mode   : Byte;
  Mode_Byte  : Byte Absolute CSeg:$24FC;

  { Note: use CSeg:$1FAB for 8087 version,
          CSeg:$2402 for BCD version  }

Begin
  Tmp_Mode   := Mode_Byte   { save mode }
  Mode_Byte  := 0;          { read only }
  Assign(InFile,  'Sample.Txt');
  Reset(InFile);
  Mode_Byte := Tmp_Mode;    { restore mode }

  { now read and use the file normally }

  Close(InFile);
End.
```

This far safer method also works when reading normal files.

Ernest G. Allen
Tri-Cities, WA

I was delighted to see this elegant solution offered by Mr. Allen. The Tech Notebook reported my solution to a particular problem that I had devised on short notice, without benefit of disassembling the Turbo Pascal code.

My approach arose in an environment where files are locked daily and kept locked. The files are edited using WordStar—which has no difficulty reading locked files. Upon saving the file, it renames the old file by replacing (or adding) the .BAK suffix and then creating a new and unlocked file under the old name. DOS 3.1 permits renaming a locked file. A number of Turbo Pascal utilities are used on these files as well; they both read and write data. Hence, there is a need to lock and unlock the files. Nevertheless, Mr. Allen's cautions are well worth heeding.

—Arsen Darnay

The method recommended by Mr. Allen works as he has described, and with far less programming effort than Mr. Darnay's solution. However, because code patches can cause unexpected side effects and the correct patch location can vary depending upon the version of software, any type of modification to Turbo Pascal's library can be risky. If a patch is used, new versions of Turbo Pascal must be checked to make sure the patch is still valid. Building a self-check into the code (before the patch is made) is a good idea. For example, Mode_Byte is actually part of the instruction MOV AX,3D02H where 3DH is the DOS open-file function and 02H is the original value of the mode byte. The program can make sure it is modifying the correct location with the code that immediately follows.

—DM

```
Var  Patch_check : Word Absolute CSeg:$24FB;

If Patch_check <> $3D02 then
   writeln('Wrong version of Turbo Pascal!');
```

BASIC CONSIDERATION

With regard to "Reconsidering BASIC" (Marty Franz, December 1986, p. 142), I do not see how *any* BASIC compiler can be considered even satisfactory if it does not support the 8087/80287. For some of us, the whole purpose of computers is to compute. The numeric coprocessor not only speeds calculations, it performs them with more accuracy. Professional BASIC from Morgan Software is precompiled, has excellent trouble-shooting aids, and has always supported the numeric coprocessor.

Russ Roberts
La Habra, CA

It is true that users who perform a large volume of floating-point computations generally require 8087 support. The compiler review that Mr. Roberts mentions notes that both Pecan BASIC and Softaid MTBASIC offer support for the 8087. Professional BASIC was reviewed as an interpreter in "Six New Shapes of BASIC" (Ted Mirecki, June 1986, p. 52); it supports the 8087, as do some other interpreters reviewed—BetterBASIC from Summit Software, True BASIC from True Basic, Inc., and WATCOM BASIC from Waterloo Computing.

—JS

I just purchased Microsoft's QuickBASIC 2.0 after reading your review of BASIC compilers. I am confused by one thing. Table 1 of the article (on page 144) in-

MICROSOFT LANGUAGES NEWSLETTER VOL. 2, NO. 4

News about the Microsoft Language Family

New FORTRAN Compiler Uses Microsoft® C Code Emitter and Optimizer

Microsoft FORTRAN Optimizing Compiler Version 4.0 was redesigned to take advantage of the innovative optimizer and code generator technology of Microsoft C Compiler Version 4.0. We have taken the C optimizer and added loop optimizations. These enhancements result in the fastest execution and smallest, most efficient code size for MS-DOS® FORTRAN programs. The compiled code generated by Version 4.0 is 17% faster on the Sieve benchmark and 220% faster on the Lookup benchmark than our nearest competitor.

Compile-time switches let you choose the level of optimization. The compiler can optimize for execution speed or for code size. Optimization can be turned off altogether in the early development stages to speed up compilation.

The new compiler supports a wide range of math libraries. You can produce in-line 8087/80287 instructions for fast execution or emulate the math co-processor if it is not present. On non-8087/80287 systems, the alternate math package is provided for more speed but less accuracy (64 bit) than the IEEE math standard (80 bit).

By default, the FORTRAN compiler uses the instruction set for the 8086/8088 processor. Programs can take advantage of the more powerful instruction sets of 80186/80188/80286 processors by turning on a switch option when compiling.

New Microsoft FORTRAN Optimizing Compiler Gains GSA Certification at Highest Level

Now, Microsoft FORTRAN Optimizing Compiler Version 4.0 is Full ANSI FORTRAN 77. The General Services Administration (GSA) has certified it at the highest level without any errors. We have gone beyond ANSI FORTRAN 77 by adding IBM® VS and DEC® VAX® FORTRAN extensions to simplify porting to and from these environments.

Medium and huge memory models have been added to the existing large memory model support. The medium memory model allows programs with up to 1 megabyte code to access 64K of data. The huge model lets you write programs with up to 1 megabyte each for code and data and arrays larger than 64K. You may mix memory models in your programs by the use of NEAR, FAR and HUGE keywords to make the most efficient use of memory. For example, you could create a medium model program and declare a huge array.

Microsoft CodeView™ Debugger Included Free with the New Microsoft FORTRAN Opitimizing Compiler

The innovative windowing debugger that was included in Microsoft C Compiler has been added to our new FORTRAN package. Now, Microsoft CodeView lets you debug using your FORTRAN source or disassembled code or both intermingled. You can watch and change the values of your local and COMMON variables as you debug. You may set the conditional breakpoints on variables, expressions, or memory. Trace and single step through the execution of your FORTRAN application. Watch and change registers and flags as you execute. Program and CodeView screen I/O are kept separate so you can easily debug graphics programs. You may view the program output on two separate monitors or through screen swapping on a single monitor.

In addition to CodeView, Microsoft FORTRAN Optimizing Compiler Version 4.0 includes a number of other utilities, such as the new program maintenance utility (MAKE) that rebuilds your applications after your source files have changed, a faster overlay linker, a library manager, an EXE file compression utility, an EXE file header utility, and an MS-DOS environment setting utility.

Version 4.0 has the most complete set of diagnostic error messages available on a FORTRAN compiler for the MS-DOS operating system (almost twice as many as our competitors). The comprehensive documentation, separated into three manuals, is brand new with non-ANSI extensions highlighted in blue to stand out from the rest of the text.

For more information on the products and features discussed in the Newsletter,
write to: Microsoft Languages Newsletter
16011 NE 36th Way, Box 97017, Redmond, WA 98073-9717.
Or phone:
(800) 426-9400. In Washington State and Alaska,
call (206) 882-8088. In Canada, call (416) 673-7638.

Latest DOS Versions:	
Microsoft C Compiler	4.00
Microsoft COBOL	2.10
Microsoft FORTRAN	4.00
Microsoft Macro Assembler	4.00
Microsoft Pascal	3.32
Microsoft QuickBASIC	2.01

Microsoft, the Microsoft logo and MS-DOS are registered trademarks and CodeView is a trademark of Microsoft Corporation.
IBM is a registered trademark of IBM Corporation. DEC and VAX are registered trademarks of Digital Equipment Corporation.

Microsoft®

Look for the Microsoft Languages Newsletter every month in this publication.

dicates that QuickBASIC supports BCD math. After searching the manual, I called Microsoft, only to be told that QuickBASIC does not support BCD math. Could you please publish a correction so that others are not misled.

Dwight Carter
Augusta, KS

Microsoft verifies that QuickBASIC does not support BCD math. PC Tech Journal *regrets the error.*

—CE

UP THE WRONG TREE

I am writing to correct several inaccuracies in Marshall Brain's Programming Practices column in the December 1986 issue ("Jump Searching Linked Lists," p. 177). It appears that Mr. Brain does not know the difference between binary trees and B-trees. These data structures are both *trees*, but that is where any similarity ends between the two.

The B-tree concept is a relatively new one, attributed to R. Bayer and E. McCreight in 1970. A B-tree is a dynamically self-balancing tree. It is constructed from the bottom upward. This type of tree cannot become unbalanced by any sequence of additions or deletions, and it never needs to be rebuilt or rebalanced for any reason. Depending on the order of the B-tree, each record may have any number of sons. Using a B-tree of order 21 (a reasonable order), any record that is within a file containing 4,084,100 records is accessible with a maximum of five disk accesses. Jump searching simply cannot achieve this level of performance.

A binary tree is defined recursively as either being empty or as a node with either zero, one, or two binary trees attached. Each node can branch in no more than two ways. It is constructed from the top downward. It can become unbalanced if the keys of records being added are not in random order, but rather in ascending or descending sequence. However, regarding deletions, Knuth volume 3 (*The Art of Computer Programming*, D. E. Knuth, Addison-Wesley, 1973) states that if a random element is deleted from a random binary tree, the resulting tree is still random. Finally, concerning rebuild times, Knuth contains a very good algorithm that rebuilds an N-record tree in an order of *N* steps.

Michael E. Wengler
Computer Related Services, Inc.
Virginia Beach, VA

I thank Mr. Wengler for taking the time to comment on my article. I would like to respond to two of his points.

First of all, jump searching is a simple technique that can be added quickly on top of an existing linked-list structure without the need for fundamental code modification. It provides search times that are significantly faster than linear search times. As stated in the article, jump searching is not a replacement for a tree of any kind, because trees are inherently faster. A specific example in the article demonstrates that jump searching is approximately 50 times faster than a linear search of 10,000 elements, but it is about 7 times slower than a binary tree search. Because jump searching is much easier to implement than is a binary or B-tree structure, it is, as I suggested, a technique "worthy of consideration."

Second, Mr. Wengler is correct to point out that binary trees and B-trees are different structures. The article was written to compare jump searching to binary trees only, not B-trees. In the process of being published, "binary

THE ATRON BUGBUSTERS BRING HARDWARE BREAKPOINTS TO MICROSOFT'S CODEVIEW

You already have MicroSoft's CodeView.™ And you've seen our ads for the Atron hardware-assisted software debuggers. Right? You know, the Atron *Bugbusters*? We make the debugging tools used by 9 of the top 10 software developers in the PC market. Now, with our new MiniProbe™ shortcard, you can use your familiar *watchpoints* and *tracepoints* in real time. Without learning new debugging technology.

device. This solves the most common debugging problem: Out-of-range pointers which overwrite the program code or data. Often, the overwrite is different after each new compile of the program.

The MiniProbe can also set a hardware breakpoint over a range of memory locations, helping to trap uninitialized pointers. And MiniProbe has a crash-recovery switch box, which lets you regain control of a frozen system.

Only $395 puts you into world-class debugging.

With real-time watchpoints and tracepoints, a one-minute program will run in one minute. Not 50 hours (the difference between software-only debuggers and hardware-assisted debuggers is a 3000-to-1 increase in efficiency). And if the program bug you're trying to find has anything to do with interrupt activity, it might *never* occur when you're debugging with CodeView alone.

But with the Atron MiniProbe, you can trap events like reading and writing to memory or an IO

So now that you don't have to learn a new debugger, the only thing keeping you from debugging like the pros is $395. And our phone number: 408/741-5900. Call today. Bust bugs, and records, tomorrow.

Atron
THE DEBUGGER COMPANY
20665 Fourth Street • Saratoga, CA 95070

© 1986 by Atron. MiniProbe™ Atron. CodeView™ MicroSoft. Atron is a division of Northwest Instruments. TRBA

CIRCLE NO. 249 ON READER SERVICE CARD

WINDOWS FOR DATA™

The first choice of professional C programmers

"Windows for Data is the best programming tool I've ever used.
It's the most flexible I've seen.
Whenever I've wanted to do something,
I've been able to find a way."

Steven Weiss,
Stratford Systems

Professionals choose our tools because they are designed, crafted, and supported for professionals. Here at Vermont Creative Software, we understand that performance and pleasure in programming derive from more than a long list of functions. **Windows for Data** provides:

PROFESSIONAL FLEXIBILITY: Our customers repeatedly tell us how they've used WFD in ways we never imagined - but which we anticipated by designing WFD for unprecedented adaptability. Virtually every capability and feature can be modified to meet special needs. You will be amazed at what you can do with WFD.

PROFESSIONAL PERFORMANCE: Screen output is crisp and fast. Windows, menus, and data-entry forms snap up and down from the screen. WFD is built upon and includes **Windows for C, the windowing system rated #1 in speed and overall quality** in PC Tech Journal (William Hunt, July 1985).

PROFESSIONAL RELIABILITY: An unreliable tool is worse than no tool at all. VCS products are known in the industry for their exceptional reliability. Ask anyone who owns one.

PROFESSIONAL DOCUMENTATION: Over 600 pages of documentation provide step-by-step explanations for each major application, a reference page for each function, listings of functions alphabetically and by usage, and a fully cross-referenced index. Extensive tutorials and demonstration programs assist learning.

PROFESSIONAL TECHNICAL SUPPORT: The same expert programmers that develop our products provide prompt, knowledgeable technical support.

PROFESSIONAL PORTABILITY: High-performance versions of VCS products are available for XENIX, UNIX, and VMS, as well as DOS. No royalties on end-user applications.

OUR CHALLENGE AND GUARANTEE

If you have an application where no other tool can do the job, try **Windows for Data.** If it doesn't help you solve your problem, RETURN FOR A FULL REFUND. YOU MUST BE SATISFIED.

Ask for **FREE DEMO DISKETTE**

Vermont Creative Software

21 Elm Ave.
Richford, VT 05476
Telex: 510-601-4160 VCSOFT
Tel.: 802-848-7738

Prices: PCDOS* $395; XENIX, VMS, UNIX Call.
*PCDOS specify C compiler.

WINDOWS FOR DATA

for DOS, UNIX, VMS ...

The complete windowing data entry, menu, and help system that does the hard job others can't — we **guarantee** it!

Pop-up data entry windows; field types for all C data types, plus decimals, dates, and times; auto conversion to and from strings for all field types; system and user supplied validation functions; range checking; required, must-fill, and protected fields; free-form movement; multiple-choice field entry; scrollable sub-forms. Branch and nest windows, forms, and menus.

Complete context-sentitive help system with pop-up windows and scrollable text.

Pop-up, pull-down, scrollable, and Lotus-style menus.

NEW FOR DEBUGGING: Exclusive **VCS Error Traceback System** automatically identifies the location and cause of program errors. Eliminates the need to code error checks on all function calls! **VCS Memory Integrity Checking** helps catch those hard-to-detect, memory-corruption errors.

NEW FOR ERROR HANDLING: Install your own error handler to be called whenever a function detects an error.

NEW FORM LAYOUT UTILITY simplifies form design.

CIRCLE NO. 115 ON READER SERVICE CARD

trees" was mistakenly abbreviated in the article to B-trees. B-trees have some problems of their own, such as added complexity and space consumption.

—Marshall Brain

STANDARD ISSUE

Will Fastie may have identified a legitimate problem in "The Printer Standards Gulf" (Directions, January 1987, p. 9), but he omits any mention of the standards that already exist in this area. The problem is due to the failure to observe existing standards as well as the failure to establish new ones. By "standard" I mean a document that is adopted as such by the American National Standards Institute (ANSI).

In the original standard code for information interchange (ASCII, X3.4-1967, revised 1977), provision for code extension was made by its inclusion of two shift characters. The first one, SO, is intended to select an alternate code subset; the second, SI, is intended to restore the base subset.

The code extension standard (X3.41-1974) defines mechanisms by which multiple extended code subsets may be invoked. These are known as G1 sets if they are alternate graphic (that is, not control) character sets, such as italics on Epson printers and the line-drawing graphics on IBM printers. X3.41 allows 126 G1 sets.

While it would be better if one of the principal printer definitions could be chosen as the base for a standard, both the Epson and IBM implementations conflict with the existing standards, such as in the use of SO and SI, which are fundamental to the standard code extension mechanism. A standard extended printer code can accommodate all of the graphic symbols in common use today, but it cannot do so in a manner that is upwardly compatible with any existing printer.

The situation is identical to that experienced by video display users a few years ago. While a few implementations dominated, innumerable variants were available. None of these was sufficiently general to form a base for a standard, hence a new implementation was defined along the lines prescribed by X3.41. This was adopted as X3.64. Conforming terminals are now known as ANSI-compatible terminals. Nonconforming terminals are still supported on many systems by enumeration or by virtual terminal definitions.

Printer standardization will likely follow a similar course. Any serious proposal for a standard must first take the existing standards into account and then build on them. I would recommend to any persons who wish to contribute to the solution of this problem that they first read the standards cited in their original form.

Gary A. Hill
St. Paul, MN

COMMENT AT WILL

All letters to the editor should be directed to Editor, *PC Tech Journal*, Suite 800, 10480 Little Patuxent Parkway, Columbia, MD 21044. Correspondence also can be submitted over MCI Mail to PCTECH.

Although *PC Tech Journal* cannot publish every letter received, every effort is made to answer as many as possible. Please keep letters brief and to the point, and include name, mailing address, and telephone number; when a letter is lengthy, a diskette is appreciated.

PolyShell

Now MS-DOS Can Be A True Programmer's Operating System

Now you can break through the barriers of MS-DOS and work faster with more flexibility & power than ever. The reason: PolyShell has literally redefined MS-DOS as an operating system for programmers. PolyShell consists of two major components: ***a)*** The PolyShell Command Interpreter is a UNIX-like command environment that runs under MS-DOS. It can be used instead of, or in conjunction with, the standard MS-DOS command interpreter. You will use this command interpreter both for command entry and for batch files, yet you can use MS-DOS commands at any time and run MS-DOS batch files. ***b)*** The PolyShell Utility Set gives you the power of 50 UNIX-like tools to perform tasks that are either not possible or are more limited under MS-DOS. Includes grep, tr, diff, sed, and over 50 more tools. Shell scripts are portable between the UNIX Bourne Shell and PolyShell. PolyShell also contains the best features of the C-Shell and Korn Shell. Prior experience with UNIX is NOT neccessary. Requires NO modifications to any other software. PolyShell is not UNIX, and a UNIX license is not included or required. Requires DOS 2.0 or higher. Compatible with the IBM PC, XT, AT and other MS-DOS PCs. For complete details write for the POLYTRON Programmer's Catalog. **$149**

"After one evening's exposure, I've already concluded that PolyShell is a terrific product! As a command interface it gives me the best of both UNIX and MS-DOS, and a tremendous number of utilities and enhancements for only $149. I especially like the ability to use all MS-DOS command and application programs while gaining the wide range of programmer's aids in UNIX. I hope that other MS-DOS users will give PolyShell a try — I've had only slight exposure to UNIX before, and now I realize what I've been missing!"

Dan Fylstra
Palo Alto, CA

TO ORDER: VISA/MC **1-800-547-4000**, Dept. No. 310; Oregon/Outside US, 503-684-3000
Send Checks/POs To: **POLYTRON Corp.** 1815 NW 169th Pl., #2110, Dept. No. 310, Beaverton, OR 97006

POLYTRON
High Quality Software Since 1982

CIRCLE NO. 164 ON READER SERVICE CARD

WE'RE LOOKING FOR A LASTING RELATIONSHIP.

When we founded Programmer's Connection in 1984, we dedicated ourselves to providing our customers with personal service, low prices and the highest level of support possible. Our goal was to make *every* customer a lifelong customer.

And we're close to our goal. According to the results of our customer service questionnaire, 99% of those responding said they would buy from us again.

Last October, we began including our questionnaire in every outgoing package. It asks our customers to rate each area of service and invites them to tell us what we need to improve as well as what we're doing right.

Since then, we received almost a thousand responses with many valuable comments and suggestions. And we're quite pleased that so many of them were highly favorable.

So call Programmer's Connection today and find the lasting relationship you've always been looking for. You'll be glad you did!

Here are some comments offered by people responding to our customer service questionnaire:

"If only all the companies I used were as good as Programmer's Connection!"

"The best service for professional users in the country."

"As a dealer specializing in programming, I've found that you are my best source."

"Thank you for all your courteous assistance."

"Programmer's Connection is really outstanding. Good prices, prompt shipment, no extra fees. Wonderful 30day trial."

"There is a lot of competition in your field, but Programmer's Connection is the best!"

"It's a pleasure to deal with a company that understands the needs of the computer professional. Thanks."

"You're the best in the business! Keep it up!"

"Your service and prices are outstanding. I'm glad I found you."

"Keep up the good work. I like the way you stay up to date."

"I appreciate your courteous, reliable service."

"This method of purchasing software allows good selection and convenience."

"Good products and great prices!"

"It's unusual to find a company that offers the best price and the best service. Programmer's Connection does — keep up the good work!"

"You have the best prices."

"I particularly like your pricing policy — lower than anyone else and no extras for shipping, credit cards, etc. Keep up the good work!"

"With the service I have received from you, I am sure to look at Programmer's Connection next time I buy."

"I appreciate your professional attitude. It's refreshing."

"Class "A" performance!"

"Very pleasant, helpful order taker. I'm impressed."

"You are the FIRST place I go for professional software products. Thanks! (Especially for your 30-day trial service)."

"Product was out of stock, but shipped exactly as I was told it would be. Good Job!"

"You provide a great service to me as a professional programmer. You are #1 on my list. Keep up the excellent work!"

"Your company is a pleasure to do business with."

"Thanks for providing prompt, reliable service and delivery."

"I'm extremely happy — just placed my 6th order."

"Anything you carry, I buy from you. You can teach your competition a lesson!"

"You have great service! You have the best prices!"

"An oasis in the mail-order desert. Keep up the excellent work!"

"Amazing — no problems — I'll be back."

"Probably the best service of any well advertised company."

"I always recommend you when asked where to buy software."

"I have not found any mail order company with such competitive prices whose people are as helpful and knowledgeable as yours. I truly appreciate it and will order more from you. Keep up the good job."

"You have both lowest prices and best service — a great combination! Keep up the good work."

"You guys are SUPER."

"Technical staff very helpful."

"Once again, it was a pleasure dealing with you."

"I'm extremely satisfied with all aspects of your operation with which I am familiar."

"Excellent service. I most definitely will be purchasing from you in the near future. Keep up the good work."

"Impressive service and pricing. I'll recommend you to my friends."

"Your prices are the best! It's great that you pick up the shipping charges and charge no sales tax (for me anyway). The price I see advertised is the price I pay, period."

"GOOD JOB!"

"I referred you to two others because they could not get current versions from other vendors."

"Your service is unusual for purchasing software."

"The person who took my phone order seemed to be genuinely eager to help me, not just get an order. Thanks."

"I like having no surcharge on credit cards and no shipping charge. There is no hidden cost."

"Good products + good service + good prices = happy customers. Keep it up."

"Fastest I've ever received by mail order. Good job. You have my patronage."

"Good service at very good prices. I plan to make all purchases from you."

"You sell up-to-date products at reasonable prices and good support."

Turn the page for our latest advertised price list.

ai - arity products

Arity Combination Package	1095	979
Expert System Development Pkg	295	229
File Interchange Toolkit	50	44
PRDLOG Compiler & Interpreter	650	569
Screen Design Toolkit	50	44
SQL Development Package	295	229
Arity PROLOG Interpreter	295	229
Arity Standard Prolog	95	77

ai - expert systems

1st-CLASS *by Programs in Motion*	495	399
AutoIntelligence *by IntelligenceWare*	990	749
ExpertEDGE Advanced *by Human Edge*	2500	CALL
ExpertEDGE Professional *by Human Edge*	5000	CALL
Experteach II *by IntelligenceWare*	475	349
EXSYS *Development Software by EXSYS*	395	309
EXSYS Runtime System	600	469
Insight 1 *by Level Five Research*	95	75
Insight 2+ *by Level Five Research*	485	379
Intelligence/Compiler *IntelligenceWare*	990	749
Logic-Line Series 1 *by Thunderstone*	90	85
Logic-Line Series 2 *by Thunderstone*	125	115
Logic-Line Series 3 *by Thunderstone*	150	139

ai - lisp language

GCLISP *Golden Common LISP by Gold Hill*	495	CALL
GCLISP 286 Developer *by Gold Hill*	1190	CALL
IQCLISP *by Integral Quality* *New*	300	CALL
IQLISP *by Integral Quality* *New*	270	CALL
Microsoft LISP *Common LISP*	250	149
QNIAL *Combines LISP & APL by NIAL Systems*	375	349
TransLISP *from Solution Systems*	95	CALL
TransLISP PLUS *from Solution Systems* *New*	195	CALL

ai - prolog language

APT *Active Prolog Tutor from Solution Systems*	65	CALL
LPA microPRDLOG *All Varieties*	CALL	CALL
MPROLOG Language Primer *LOGICWARE*	50	45
MPRDLDG P500 *by LOGICWARE*	495	395
MPROLOG P550 *by LOGICWARE*	220	175
Prolog-86 *from Solution Systems*	125	CALL
Prolog-86 Plus *from Solution Systems*	250	CALL
Turbo PRDLDG *by Borland Intl* *New Version*	100	63
Turbo PRDLDG Toolbox *by Borland Intl* *New*	100	64

ai - smalltalk language

Smalltalk/V *by Digitalk*	99	84
EGA Color Option *New*	49	45
Goodies Diskette *New*	49	45
Smalltalk/Comm	49	42

ai - texas instruments

PC Scheme *Lisp*	95	84
Personal Consultant Easy	495	435
Personal Consultant Plus	2950	2589
Personal Consultant Runtime	95	84

apl language

APL*PLUS/PC *by STSC*	595	429
APL*PLUS/PC Spreadsheet Mgr *by STSC*	195	139
APL*PLUS/PC Tools Vol 1 *by STSC*	295	199
APL*PLUS/PC Tools Vol 2 *by STSC*	85	58
Financial/Statistical Library *by STSC*	275	189
Pocket APL *by STSC*	95	69
STATGRAPHICS *by STSC*	795	579

assembly language

386 ASM/LINK *Cross Asm by Phar Lap*	495	389
8088 Assembler *w/Z-80 Translator by 2500 AD*	100	89
ASMLIB *Function Library by BC Assoc*	149	129
asmTREE *B-Tree Dev System by BC Assoc*	395	339
Cross Assemblers *Various by 2500 AD*	CALL	CALL
Microsoft Macro Assembler	150	93
Norton Utilities *by Peter Norton*	100	59
screenplay *by Flexus*	100	79
Turbo EDITASM *by Speedware*	99	84
Uniware Cross Assemblers *Various by SDS*	295	249
Visible Computer: 8088 *Software Masters*	80	64

basic language

87 QB Pak *by Hauppauge*	69	59
87 Software Pak *by Hauppauge* *New*	180	149
BetterBASIC *by Summit* *Final Clearance*	200	119
EXIM Services Toolkit *by EXIM*	50	45
Finally *by Komputerwerks*	99	85
Inside Track *from Micro Help*	65	51
MACH 2 *by Micro Help*	75	58
MACH 2 *for Turbo BASIC by Micro Help* *New*	69	CALL
Microsoft QuickBASIC Compiler	99	63
Peeks 'n Pokes *from MicroHelp*	45	37
Professional BASIC *by Morgan*	99	68
8087 Math Support	50	42
QuickPak *by Crescent Software* *New*	69	59
Scientific Subroutine Library *by Peerless*	125	99
Stay-Res *by MicroHelp*	95	73
True Basic *w/Run-time* *New Version*	245	179
True Basic *New Version*	150	97
Run-time Module	150	97
Various Utilities	50	41
Turbo BASIC Compiler *by Borland Intl* *New*	100	64

blaise products

AS"NCH MANAGER *Specify C or Pascal*	175	119
C TOOLS PLUS	175	119
EXEC *Program Chainer*	95	73
LIGHT TOOLS *for Datalight C*	100	78
PASCAL TOOLS	125	94
PASCAL TOOLS 2	100	74
PASCAL TOOLS & TOOLS 2	175	119
RUNOFF *Text Formatter*	50	43
TURBO ASYNCH PLUS	100	78
TURBO PDWER TOOLS PLUS	100	78
VIEW MANAGER *Specify C or Pascal*	275	179

borland products

EUREKA *Equation Solver*	100	64
Reflex & Reflex Workshop	200	128
Reflex *Data Base System*	150	89
Reflex Workshop	70	45
Sidekick & Traveling Sidekick	125	85
Sidekick	85	57
Traveling Sidekick	70	45
Superkey	70	45
Turbo BASIC Compiler *New*	100	64
Turbo C Compiler *New*	100	64
Turbo Database Toolbox	70	41
Turbo Editor Toolbox	70	41
Turbo Gameworks Toolbox	70	41
Turbo Graphix Toolbox	70	41
Turbo Lightning	100	64
Turbo PASCAL Numerical Methods Toolbox	100	64
Turbo PASCAL and Tutor	125	85
Turbo PASCAL	100	64
Turbo Tutor	40	24
Turbo PRDLDG Compiler *New Version*	100	63
Turbo PRDLDG Toolbox *New*	100	64
Word Wizard	70	47
Word Wizard and Turbo Lightning	150	94

c++

C++ *by Guidelines w/version 1.1 kernel*	195	172
PforCe++ *Function Library by Phoenix* *New*	395	225

c compilers

68000/10/20 Cross Compiler *by SDS*	595	CALL
C86PLUS *by Computer Innovations*	497	CALL
Datalight C Compiler *Small Model*	60	43
Datalight Developer Kit	99	74
Datalight Optimum-C	139	109
DeSmet C *w/Debugger & Large Case*	209	184
DeSmet C *w/Debugger Only*	159	138
Eco-C *Development System by Ecosoft*	125	83
Lattice C Compiler *from Lattice*	500	269
Mark Williams Let's C Combo Pack	125	99
Let's C *Compiler*	75	54
csd *Source Level Debugger*	75	54
Mark Williams MWC-86	495	286
Microsoft C *with CodeView*	450	269
Turbo C Compiler *by Borland Intl* *New*	100	64
Wizard C Combo *by Wizard Systems*	750	529
Wizard C Compiler	450	299
ROM Development Pkg	350	259

c interpreters

C-terp *by Gimpel Software compiler*	300	219
C Trainer *with Book by Catalytix*	122	87
Instant C *by Rational Systems*	500	369
Introducing C *by Computer Innovations*	125	CALL
Run/C *by Age of Reason*	150	88
Run/C Professional *by Age of Reason*	250	157

c utilities

C to dBase *by Computer Innovations*	150	CALL
c-tree & r-tree Combo *by FairCom*	650	519
c-tree *ISAM File Manager*	395	315
r-tree *Report Generator*	295	239
C Windows *by Syscom*	100	85
C Wings *by Syscom*	50	43
CI RDMPac *by Computer Innovations*	195	CALL
dBx *dBase to C Translator by Desktop AI*	350	299
with Library Source Code	550	469
Various Support Utilities	CALL	CALL
Flash-up Windows *by Software Bottling*	90	79
GraphiC *Color version by Sci Endeavors*	350	282
GraphiC *Mono version by Sci Endeavors*	280	209
GRAFLIB *by Sutrasoft*	175	159
HALO *Graphics by Media Cybernetics*	300	205
HALD Development Pkg *for Microsoft*	595	389
The HAMMER *by OES Systems*	195	129
MetaWINOOWS *No Royalties*	185	109
MetaFDNTS	80	58
MetaWINODWS/Plus *by Metagraphics*	235	185
MetaFDNTS/Plus	235	185
PANEL *by Roundhill Computer Systems*	295	215
PC Lint *by Gimpel Software*	139	99
PLDTHI *by Sutrasoft*	175	159
PLDTHP *by Sutrasoft*	175	159
Professional C Windows *by Washburn* *New*	CALL	CALL
Scientific Subroutine Library *by Peerless*	175	128
screenplay *for C by Flexus*	175	129
Vitamin C *by Creative Programming*	225	158
VC Screen *Forms Designer*	100	79
Zview *by Data Management Consultants*	245	169

cobol language

EASY SCREEN *by Retail Mgmt Systems* *New*	225	199
Micro Focus COBOL Workbench	4000	CALL
Micro Focus Level II COBDL	1500	CALL
CDGRAPHICS	250	CALL
COMATH	200	CALL
FDRMS-2	300	CALL
Level II Animator	900	CALL
Level II SDURCEWRITER	2000	CALL
Micro Focus Level II COBOL *for Novell*	2000	CALL
Micro Focus Professional COBOL	3000	CALL
Multi-user Runtime *for PC Network*	500	CALL
Microsoft COBOL *See Microsoft Section*		
Realia COBOL	995	783
REALCICS *New*	995	783
REALMENU *New*	150	119
RM/COBOL *by Ryan-McFarland*	950	CALL
RM/CDBOL 85 *by Ryan-McFarland*	1250	CALL
screenplay *for COBOL by Flexus*	175	129

debuggers & profilers

386 OEBUG *Cross Debugger by Phar Lap*	195	129
Advanced Trace-86 *by Morgan Computing*	175	115
CI Probe *by Computer Innovations*	225	CALL
Codesifter *Profiler by David Smith*	119	85
Codesmith-86 *by Visual Age*	145	98
OSO86 *by Soft Advances*	70	61
OSO87 *by Soft Advances*	100	79
MiniProbe *by Atron*	395	CALL
Periscope I *with Board by Periscope*	345	289
Periscope II *with NMI Breakout Switch*	175	139
Periscope II-X *Software only*	145	105
The PROFILER *with Source Code by DWB*	125	89
The WATCHER *Profiler by Stony Brook*	60	51

dos utilities

Command Plus *by ESP Software* *New*	80	69
FANSI-CDNSOLE *by Hersey Micro*	75	62
MKS Toolkit *with vi Editor by MKS*	139	99
Norton Commander *by Peter Norton*	75	55
Scroll & Recall *by Opt-Tech Data*	69	59
Taskview *by Sunny Hill Software*	80	56

entelekon products

C Dynamo *New*	250	209
C Dynamo Screen Painter *New*	130	109
C Function Library	130	109
Dyanamo Data Entry *New*	130	109
Power Windows	130	109
Superfonts for C	50	43
Screen Painter & Data Entry *New*	180	150

essential products

C Essentials *by Essential Software*	100	75
C Utility Library	185	119
Essential Comm Library *with Debugger*	250	189
Essential Comm Library *Software Only*	185	125
Breakout Debugger *Any language*	125	89
Essential Graphics	250	183

forth language

CFORTH *Native Code Compiler by LMI*	300	229
Forth/83 Metacompiler *Specify Target*	750	599
PC/Forth *by Laboratory Microsystems*	150	109
PC/Forth+ *by Laboratory Microsystems*	250	199
Advanced Color Graphics Support	100	74
Enhanced Graphics Support	200	148
Intel 8087 Support	100	74
Interactive Symbolic Debugger	100	74
Native Code Optimizer	200	148
Software Floating Point	100	74
UR/Forth *by LMI*	350	279
Object Module Libraries	500	395
Source Code License	1500	995

fortran language

50 MORE: FORTRAN *by Peerless Engr*	125	95
ACS Time Series *Alpha Computer Service*	495	389
Essential Graphics *by Essential Software*	250	183
For-Winds *Alpha Computer Service*	90	69
Forlib-Plus *Alpha Computer Service*	70	44
FORTLIB *by Sutrasoft*	95	85
FORTRAN Addendum *by Impulse Engr*	95	85
FORTRAN Addenda *by Impulse Engr*	165	138
GRAFLIB *by Sutrasoft*	175	159
HALO *by Media Cybernetics*	300	205
I/D PRO *by MEF Environmental*	149	129
Microcompatibles Combo Package	240	215
Grafmatic	135	117
Plotmatic	135	117
Microsoft FORTRAN *w/CodeView* *New Version*	450	269
No Limit *by MEF Environmental*	129	115
Numerical Analyst *by MAGUS* *New*	295	CALL
PANEL *Screen Designer by Roundhill*	295	215
PLOTHI *by Sutrasoft*	175	159
PLOTHP *by Sutrasoft*	175	159
RM/FORTRAN *Ryan-McFarland*	595	CALL
RTC PLUS *Fortran to C by Cobalt Blue* *New*	325	CALL
Scientific Subroutine Lib *by Peerless*	175	128
Statistician *Alpha Computer Service*	295	245
Statlib.GL: *by PSI/Systems* *New*	295	239
Statlib.TSF: *by PSI/Systems* *New*	295	239
Strings & Things *Alpha Computer Service*	70	51

greenleaf products

Greenleaf Comm Library	185	125
Greenleaf Data Windows	225	157
with Source Code	450	289
Greenleaf Functions	185	125

help utilities

HELP/Control *by MDS*	125	99
On-line Help *from Opt-Tech* *New Version*	149	99
SoftScreen/HELP *by Dialectic Systems*	195	149

lattice products

Lattice C Compiler *from Lattice*	500	269
with Library Source Code	900	495
C Cross Reference Generator	50	37
with Source Code	200	139
C-Food Smorgasbord *Function Library*	150	95
with Source Code	300	179
C-Sprite *Source Level Debugger*	175	129
Curses *Screen Manager*	125	89
with Source Code	250	174
dBC II *Specify dBC II or dBC III*	250	169
with Source Code	500	356
dBC III Plus *New*	750	CALL
with Source Code *New*	1500	CALL
LMK *Make Facility*	195	138
RPG II Combo *All three items below*	1100	875
RPG II Compiler *No Royalties*	750	625
RPG II SEU *Screen Entry Utility*	250	199
RPG II Sort/Merge	250	199
RPG II Screen Design Aid Utility	350	309
SecretDisk *File Encryption Utility*	120	89
SideTalk *Resident Communications*	120	89
SSP/PC *Scientific Subroutine Library*	350	269
Text Management Utilities	120	89
TopView Toolbasket *Function Library*	250	178
with Source Code	500	356

microport products

System V/AT *by Microport Systems*	499	429
Runtime System *(Operating System)*	199	189
Software Development System	199	189
Text Preparation System	199	189
User Upgrade *3 to Unlimited Users*	CALL	CALL

microsoft products

Microsoft BASIC Interpreter *for XENIX*	350	209
Microsoft C *with CodeView*	450	269
Microsoft COBOL Compiler	700	429
for XENIX	995	609
Microsoft COBOL Tools *with Debugger*	350	194
for XENIX	450	289
Microsoft FORTRAN *w/CodeView ... New Version*	450	269
for XENIX	695	419
Microsoft Learning DOS	50	36
Microsoft LISP *Common LISP*	250	149
Microsoft MACH 10 *w/Mouse & Windows*	549	369
Microsoft MACH 10 *Board only*	399	279
Microsoft Macro Assembler	150	93
Microsoft Mouse *Bus Version*	175	114
Microsoft Mouse *Serial Version*	195	124
Microsoft muMath *Includes muSIMP*	300	179
Microsoft Pascal Compiler	300	179
for XENIX	695	419
Microsoft QuickBASIC Compiler	99	63
Microsoft Sort	195	125
Microsoft Windows	99	63
Microsoft Windows Development Kit	500	299

modula-2 products

IOTools *by Rhodes Associates ... New*	80	69
with Source Code ... New	950	CALL
MODULA-2 Apprentice Pkg by LOGITECH ... New	99	79
MODULA-2 Magic Pkg by LOGITECH ... New	99	79
MODULA-2 ROM Pkg & Cross RT Debugger New	299	239
MODULA-2 Window Pkg by LOGITECH ... New	49	39
MODULA-2 Wizard's Pkg by LOGITECH ... New	199	159
REPERTOIRE *for MODULA-2 by PMI*	89	79
Object Code Only	19	15

mouse products

LOGIMOUSE BUS *with PLUS Pkg by LOGITECH ...*	139	115
with PLUS & PC Paintbrush	189	149
with PLUS & CAD Software	209	175
with PLUS & CAD & Paint	239	195
LOGIMOUSE C7 *Specify Connector*	99	83
with PLUS Package	119	98
with PLUS & PC Paintbrush	169	134
with PLUS & CAD Software	189	153
with PLUS & CAD & Paint	219	179

other languages

CCS MUMPS *Single-User by MGlobal*	60	51
CCS MUMPS *Single-User/Multi-Tasking*	150	129
CCS MUMPS *Multi-User*	450	359
Janus/ADA C Pak *by R&R Software*	95	84
Janus/ADA D Pak *by R&R Software*	900	769
Janus/ADA ED Pak *by R&R Software ... New*	395	CALL
Marshal Pascal *by Marshal Language Systems New*	189	155
Personal REXX *by Mansfield Software*	125	99
SNOBOL4+ *by Catspaw*	95	80

other products

Dan Bricklin's Demo Pgm *Software Garden*	75	57
Disk Optimizer *by Softlogic Systems ... New*	60	55
FASTBACK *by 5th Generation Systems*	179	133
Instant Replay *by Nostradamus*	90	79
Net-Tools *by BC Associates ... New*	149	129
OPT-Tech Sort *by Opt-Tech Data Proc*	149	99
VTEK *Term Emulator by Sci Endeavors*	150	129

phoenix products

Pasm86 *Macro Assembler Version 2.0*	195	108
Pdisk *Hard Disk & Backup Utility*	145	89
Pfantasy Pac *Phoenix Combo ... Sale*	1295	799
Pfinish *Execution Profiler ... Sale*	395	209
Pfix86plus *Symbolic Debugger ... Sale*	395	209
PforCe *Comprehensive C Library ... Sale*	395	209
PforCe++ *Library for Guidelines C++ ... Sale*	395	209
Plink86plus *Overlay Linker ... Sale*	495	279
Pmaker *Make Utility*	125	78
Pmate *Macro Text Editor*	195	108
Pre-C *Lint Utility*	295	154
Ptel *Binary File Transfer Program*	195	108

polytron products

PolyBoost *The Software Accelerator*	80	64
PolyLibrarian *Library Manager*	99	73
PolyLibrarian II *Library Manager*	149	109
PolyMake *UNIX-like Make Facility*	149	109
PolyShell	149	109
Polytron C Beautifier	50	42
Polytron C Library I	99	72
Polytron PowerCom *Communications*	139	105
PolyWindows Products *All Varieties*	CALL	CALL
PolyXREF *Complete Cross Ref Utility*	219	169
PolyXREF *One language only*	129	99
PVCS Corporate *Version Control System ... New*	395	309
PVCS Personal *New*	149	109

program mgmt utilities

Compact Source Print *by Aldebaran*	55	44
Interactive EASYFLOW *by Haventree*	150	125
PrintQ *by Software Directions*	89	84
Quilt Computing Combo Package	199	159
QMake *Program Rebuild Utility*	99	79
SRMS *Software Revision Mgmt Sys*	125	109
Source Print *by Aldebaran Labs*	75	59
TLIB *by Burton Systems Software*	100	89
Tree Diagrammer *by Aldebaran Labs*	55	49

raima products

dbQUERY *Single-User Query Utility*	195	129
Single-User with Source Code	495	389
Multi-User	495	389
Multi-User with Source Code	990	799
dbVISTA *Single-User DBMS*	195	129
Single-User with Source Code	495	389
Multi-User	495	389
Multi-User with Source Code	990	799

sco products

Complete XENIX System V *by SCO*	1295	999
Development System	595	499
Operating System *Specify XT or AT*	595	499
Text Processing Package	195	144
Networks for XENIX *by SCO*	595	495
SCO Professional *Lotus clone for XENIX*	795	595

softcraft products

Btrieve *ISAM Mgr with No Royalties*	245	184
Xtrieve *Query Utility*	245	184
Report Option *for Xtrieve*	145	99
Btrieve/N *for Networks*	595	454
Xtrieve/N	595	454
Report Option/N *for Xtrieve/N*	345	269

solution systems products

APT *Active Prolog Tutor*	65	CALL
Brief & dBrief Combo	250	CALL
Brief *Programmer's Text Editor*	195	CALL
dBrief *Customizes Brief for dBase III*	95	CALL
C Screen Editor	75	CALL
C ToolSet	95	CALL
Faster C	95	CALL
Prolog-86	125	CALL
Prolog-86 Plus	250	CALL
Security Library	125	CALL
with Source Code	250	CALL
TransLISP	95	CALL
TransLISP PLUS *New*	195	CALL
ZAP *Communications*	95	CALL

text editors

Brief *from Solution Systems*	195	CALL
Epsilon *Emacs-like editor by Lugaru*	195	147
KEDIT *by Mansfield Software*	125	98
Micro/SPF *by Phaser Systems ... New*	175	139
PC/VI *by Custom Software Systems*	149	99
SPF/PC *by Command Technology Corp New Version*	245	175
Vedit *by CompuView*	150	98
Vedit Plus *by CompuView*	185	128

turbo pascal utilities

ALICE *Interpreter by Software Channels*	95	66
DOS/BIOS & Mouse Tools *by Quinn-Curtis ... New*	75	67
Flash-up Windows *by Software Bottling*	90	79
MetraByte D/A Tools *by Quinn-Curtis ... New*	100	89
Science & Engrg Tools *by Quinn-Curtis ... New*	75	67
Screen Sculptor *by Software Bottling*	125	91
screenplay *for Turbo Pascal by Flexus*	100	79
Speed Screen *by Software Bottling ... New*	125	91
System Builder *by Royal American*	100	CALL
IMPEX *Query Utility ... New*	75	CALL
Report Builder	75	CALL
TOebugPLUS *by TurboPower Software*	60	49
Turbo EXTENDER *by TurboPower Software*	85	64
Turbo Professional *by Sunny Hill*	70	45
TurboHALO *from IMSI*	129	98
TurboPower Utilities *by TurboPower*	95	78
TurboRef *by Gracon Services*	50	45
TURBOsmith *Debugger by Visual Age*	69	45
TurboWINDOW *Graphics/Windows by MetaGraphics*	80	58

wendin products

Operating System Toolbox	99	75
PCNX *Operating system*	99	75
PCVMS *Similar to VAX/VMS*	99	75
XTC *Text Editor with Pascal source*	99	75

xenix/unix products

Btrieve *ISAM File Mgr by SoftCraft*	595	454
C-terp *by Gimpel, Specify compiler*	498	379
c-tree *ISAM Mgr by FairCom*	395	315
dbVISTA *See Raima Section*		
dBx *with Library Source by Desktop AI*	550	489
DOSIX *Console Version by Data Basics*	399	CALL
OOSIX *User Version by Data Basics*	199	CALL
Micro Focus Level II Compact COBOL	1000	CALL
Forms-2	400	CALL
Level II ANIMATOR	600	CALL
Microport Products *See Microport Section*		
Microsoft Products *See Microsoft Section*		
PANEL *Screen Designer by Roundhill*	625	535
REAL-TOOLS *Binary Version by PCT*	149	89
Library Source Version	399	289
Complete Source Version	499	369
RM/COBOL *by Ryan-McFarland*	1250	CALL
RM/COBOL '85 *by Ryan-McFarland*	CALL	CALL
RM/FORTRAN *by Ryan-McFarland*	750	CALL
SCO Products *See SCO Section*		

LOWEST PRICES

Since this ad is prepared in advance of publication, some of our current prices may be lower than what's advertised here. Call for latest pricing.

FREE SHIPPING

Orders within the USA (including Alaska & Hawaii) are shipped FREE via UPS. Express shipping is available at the shipping carrier's standard rate with no rush fees or handling charges. To avoid delays when ordering by mail, please call first to determine the exact cost of express shipping.

CREDIT CARDS

VISA and MasterCard are accepted at no extra cost. Your card is charged when your order is shipped. Mail orders please include credit card expiration date and telephone number.

CODs AND POs

CODs and Purchase Orders are accepted at no extra cost. POs with net 30-day terms are available to qualified US accounts only.

FOREIGN ORDERS

Shipping charges for foreign and Canadian orders are based on the shipping carrier's standard rate. Since rates vary between carriers, please call or write for the exact cost. Foreign orders (except Canada), please include an additional $10 for customs form preparation. All payments must be made with US funds drawn on a US bank. Please include your telephone number when ordering by mail. Due to government regulations, we cannot ship to all countries.

VOLUME ORDERS

Call for special pricing.

SOUND ADVICE

Our knowledgeable technical staff can assist in comparing products, answer technical questions and send you detailed product information tailored to your needs.

30-DAY GUARANTEE

Most of our products come with a 30-day documentation evaluation period or 30-day return guarantee. Please note that some manufacturers restrict us from offering guarantees on their products. Call for more information.

© 1987, Programmer's Connection, Inc.

CALL TOLL-FREE

CIRCLE NO. 175 ON READER SERVICE CARD

U S	**800-336-1166**
CANADA	**800-225-1166**
OHIO & ALASKA (Call Collect)	**216-877-3781**
FOREIGN CUSTOMER SERVICE	**216-877-3781 216-877-1110**

Hours: Weekdays 8:30 AM to 8:00 PM EST.

Ohio customers please add 6% state sales tax.

Prices are subject to change without notice.

Call or write for our FREE comprehensive price guide.

136 SUNNYSIDE STREET HARTVILLE, OHIO 44632

programmer's connection

ZIM DEFINES THE WORDS

1) Productivity
2) Portability

ZIM®, the definitive 4GL/DBMS for the serious application developer, brings new meaning to words like "productivity," "portability," "power" and "performance." That's because in four short years **ZIM** has established a *new* standard of database design, the Entity-Relationship (E-R) model, and in doing so, has created new standards by which all other 4GLs are measured.

Productivity **ZIM** delivers productivity improvements over the entire development lifecycle, from requirements all the way through maintenance. Although other products demonstrate a 10:1 productivity gain in the coding phase of systems development, **ZIM** outperforms them in all stages, as shown below.



ZIM productivity across the development lifecycle

At the core of **ZIM** users' gains is the E-R model, a graphically-oriented data model that eclipses traditional Relational models because it recognizes relationships *between* tables of data as well as those within. **ZIM**'s pre-defined relationships permit the implementation of many-to-many relationships, outer joins, and relationship consistency with an ease not found in any other product.

Intrinsic to **ZIM**'s E-R orientation is the code-reducing **ZIM** language. Since **ZIM** code is a generation ahead of 3GLs (like COBOL) and much tighter than other 4GLs, your development time is slashed accordingly.

```
SQL:
SELECT *
FROM WORKONTAB, PROJECTS, EMPLOYEES-
WHERE WORKTONTAB.ENUM = EMPLOYEES.ENUM-
AND WORKONTAB.PNUM = PROJECTS.PNUM-
AND PROJNAME = 'ALPHA'

ZIM:
List all employees workon projects where
projname = 'Alpha'
```

A typical SQL command and the ZIM equivalent.

ZIM is a true 4GL that integrates all necessary facilities (forms, data dictionary, update, query, report writer, debugging) into one package using common concepts. **ZIM**'s code efficiency, combined with its 4GL conciseness, make it a system that will not only significantly reduce your development time, but maintenance programming as well.

ZIM/DA (**ZIM**'s development assistant companion product) brings new depth to the concept of "productivity." **ZIM/DA** is comprised of an application generator, menu generator, interactive data dictionary, context-sensitive help and an on-line training module. **ZIM/DA** permits remarkably fast transition from prototype to finished application; a **ZIM/DA** user can generate a simple prototype in 5–10 minutes that is the equivalent of *2–4,000* lines of "C" code!

Portability Tools and applications written in any version of **ZIM** (single-user MS-DOS®, MS-DOS networks, Novell networks, QNX®, UNIX™, XENIX®, VAX®/VMS®, VM/CMS®) are uniquely 100 percent portable to and from any other supported environment. For example, a multi-user VAX application can be developed under single-user MS-DOS, since **ZIM** ports require *no code alteration.*

CIRCLE NO. 236 ON READER SERVICE CARD

FOUR BIGGEST IN A 4GL:

3) Power
4) Performance



100 percent portability

Power ZIM is rich in powerful features and functions, for example:

- AI-based access strategy analyzer
- Unsurpassed computational abilities, including case expression, which handles with ease the "step" function found in real-world business applications
- Natural multi-user features, including roll-back, audit trails and roll-forward
- Complete code-data independence
- Active data dictionary
- Exceptional text-handling capabilities
- Unlimited forms manipulation and report-writing capabilities
- Multi-lingual applications (French, German, etc.)

Performance **ZIM** was designed to be an optimally-performing development platform in each machine environment. As a result, it is an exceptionally speedy, compact system; for example, **ZIM** on UNIX typically requires 280K for development and 175K for application runtime, with 30–35K per user of data space. A **ZIM** application will typically run as fast as the same written in "C," and with regard to competing 4GLs, the fact that **ZIM**'s memory use is *less than half* by comparison permits faster performance **and** up to three times as many users on the same system.

In addition to **ZIM/DA,** several other companion products are available to enhance your development application process. An integrated **ZIM Compiler** will ensure highest performance of your finished application, while a **Program Language Interface** permits "C" access to **ZIM** databases. **Runtime** and **Query Runtime** systems are available, too.

More Big Words Zanthe Information believes in backing up excellent products with superior Service and Support, at a price that makes you as happy with Zanthe as you will be with **ZIM.**

Zanthe's Priority Support program includes first-rate telephone technical support, free updates and new versions, and periodic technical bulletins. New users are entitled to 90 days of free Priority Support, while **Code Review** and **Training** services are available for all **ZIM** users, experienced or novice.

Finally, there's our price. All versions of **ZIM** are priced to deliver exceptional value, starting at $795 for single-user MS-DOS **ZIM.** Zanthe's attractive site license program is an option, too.

In searching for the highest quality solution to your application development needs, Zanthe doesn't just say big words about product, support and price. We **mean** time—so give us a call, today!

ZIM™

Zanthe Information Inc.
1200-38 Antares Drive
Nepean, Ontario K2E 7V2

U.S. 800-267-9972
Canada 613-727-1397

ZIM is a registered trademark of Zanthe Information Inc. VAX and VMS are registered trademarks of Digital Equipment Corp. UNIX is a trademark of AT&T Bell Laboratories. XENIX and MS-DOS are registered trademarks of Microsoft Corp. QNX is a registered trademark of Quantum Software Systems Ltd. VM/CMS is a registered of IBM Corp. © 1987 Zanthe Information Inc.

Hardware, software, and other developments for the IBM PC family



DT2821-G data acquisition board from Data Translation



Quadram Corporation's Quad386 XT, shown with daughterboard (front)

FROM IBM

A 1MB to 6MB **Memory Expansion Adapter**, along with the 1MB **Memory Module Kit** (composed of two 512KB memory modules that snap onto the adapter), has been announced by **IBM Corporation**. These products increase the memory on the PC/AT or XT-286 up to 6MB on one adapter. The memory modules are more densely packed, which allows a larger amount of memory per module, and thus conserves expansions slots for other functions. Memory expansion is possible without a piggyback adapter arrangement or add-on adapters. Other features include split memory addressing capability, which allows adding both conventional and extended memory to the system; a parallel printer port; and an asynchronous serial communications port. Memory Expansion Adapter with 1MB memory, $749; 1MB Memory Module Kit, $349.
IBM Corporation, 100 Summit Avenue, Montvale, NJ 07645; 800/426-2468
CIRCLE 301 ON READER SERVICE CARD

IBM has lowered the price on two models of the PC/XT and one model of the PC/AT. The price of the **XT-286** has been reduced to $3,395 (from $3,995). The XT-286 comes standard with 640KB memory, a 1.2MB 5¼-inch diskette drive, a 20MB hard-disk drive, a serial/parallel adapter, and an IBM enhanced PC keyboard. The **PC/XT Model 089**, with 640KB memory, a 360KB diskette drive, an asynchronous communications adapter, and an enhanced PC keyboard has been lowered to $2,660 (from $2,895). The **PC/AT Model 068**, with 256KB memory, a 1.2MB diskette drive, and the AT keyboard is priced at $3,395, down from $3,995.
IBM Corporation, Information Systems Group, 900 King Street, Rye Brook, NY 10573, 800/426-2468
CIRCLE 302 ON READER SERVICE CARD

HARDWARE

Able to acquire data at a rate of 250 KHz, the **DT2821-G** from **Data Translation, Inc.** is a single-board data acquisition system with 12-bit resolution for 16 single-ended or 8 differential analog inputs; programmable gain; two 12-bit, D/A (digital-to-analog) converters; a channel-gain list; a programmable clock; and support for interrupts and DMA (direct memory access) transfers. The 250-KHz throughput rate is only available with the Compaq Deskpro 386; on the PC/AT, the throughput rate varies between 180 and 235 KHz, depending on clock speed. A/D (analog-to-digital) sampling is controlled by channel-gain list RAM. The 16-location RAM allows users to sample input channels in any sequence and at any gain. Analog output is provided by two 12-bit independent D/A converters with a throughput of 130 KHz each. The DT2821-G is supported by the **ATLAB** software package. ATLAB is a library of subroutines and supports continuous performance to memory or to disk. DT2821-G, $2,995; ATLAB, $149.
Data Translation, Inc. 100 Locke Drive, Marlboro, MA 01752; 617/481-3700
CIRCLE 310 ON READER SERVICE CARD

An 18-MHz, 80386-based microcomputer is being shipped by **Computer Dynamics**. The computer, called the **Micro System 386** (MS-386), consists of an Intel Corporation manufactured motherboard, a 1.2MB diskette drive, diskette/hard-disk controller, 512KB RAM, 220-watt power supply, and keyboard. The serial, parallel, and clock ports are incorporated on the motherboard, which leaves eight expansion slots available. Two expansion slots are 8-bit, four are 16-bit, and two are 32-bit slots that can be used for memory expansion or 32-bit I/O boards. Computer Dynamics offers a 32-bit memory expansion board with 2MB of 120-nanosecond DRAM. Available options are 40MB, 60MB, and 130MB hard disks with average access times under 28 milliseconds, an 80287-10, an enhanced graphics board and display, a monochrome graphics adapter, a 360KB diskette drive, 60MB and 120MB internal tape backups, and a second serial port. $3,295.
Computer Dynamics, One Technology Center, 2201 Donley, Suite 365, Austin, TX 78758; 512/535-3637
CIRCLE 305 ON READER SERVICE CARD

A board that delivers all the power and functionality of the 80386 to the PC/XT and compatibles is now available from **Quadram Corporation**. The **Quad386 XT** board occupies a single slot in the XT and features a 16-MHz 80386 and 1MB of true 32-bit memory using 256KB dynamic RAM (DRAM). It features 80287 support, 96KB of image memory, 32KB of direct cache memory, and disk-caching software (bundled with the board). A 2MB memory upgrade on a daughterboard is optional. Quad386 XT, $1,495.
Quadram Corporation, One Quad Way, Norcross, GA 30093-2919; 404/923-6666
CIRCLE 303 ON READER SERVICE CARD

Immediate availability has been announced by **Intel Corporation** of its **ICE-386** in-circuit emulator, which provides hardware/software integration and debugging capabilities for 80386 application development. ICE-386 comes in two versions: a DOS version for the PC/AT and compatibles running DOS 3.1 or later, and a XENIX version that runs on Intel 286/310 systems. Intel's emulator supports realtime, transparent emulation of the 80386 at speeds up to 16 MHz. Other key features include 128KB of emulation memory that can be mapped in 4KB increments, full support of Intel's symbolic debugging, user-defined breakpoints of task switching, external inputs, trace buffer full, instruction execution address and data access, storage

Intel Corporation's ICE-386 in-circuit emulator

of more than 2,000 frames of program execution history with time tags for analyzing execution time of user code, support for realtime debugging of numeric coprocessors, and emulator, electrical, and timing characteristics that match those of the 80386 component. $15,000.
Intel Corporation, Literature Department, W342, 3065 Bowers Avenue, Santa Clara, CA 95051; 800/548-4725; in California, 408/987-8080

CIRCLE 304 ON READER SERVICE CARD

An 80286-to-80386 adapter board that converts an 80286-based PC/AT or XT-286 into functional 80386 ATs with a 16-bit bus has been introduced by **Cheetah International, Inc**. The **Cheetah Adaptor/386** is a 3½-inch by 3½-inch translator board that mounts on the motherboard above the 80286 socket. When installed with the Cheetah Combo/70 zero-wait-state memory board, 80286 and 80386 programs run 10 percent faster. With the Cheetah Adaptor/386 and Quarterdeck Office Systems' DESQview 1.3 and Expanded Memory Manager 386 installed in an AT, users can run as many as nine separate programs concurrently. $495.
Cheetah International, Inc., 107 Community Boulevard, Suite 5, Longview, TX 75602; 800/243-3824; in Texas, 214/757-3001

CIRCLE 306 ON READER SERVICE CARD



The Cheetah Adaptor/386 from Cheetah International

Two enhanced graphic adapters have been released by **SCOA Systems**. Both the **STAR EGA** and **STAR EGA PLUS** are compatible with the IBM EGA, CGA, monochrome display adapter, and Hercules Graphics Card. The STAR EGA displays graphics via 640-by-350 pixel resolution in 16 colors from a palette of 64. Other features include 256KB on-board DRAM, a RAM loadable character set, light pen interface, flicker-free panning and scrolling, windowing via 1-million-pixel memory, selectable 4.77- , 6- , 8- , or 10-MHz clock speed, feature connector, and an RCA video jack. The STAR EGA PLUS offers optional parallel and RS-232 serial ports. STAR EGA, under $500; STAR EGA PLUS, under $600.
SCOA Systems, 2100 Golf Road, Suite 100, Rolling Meadows, IL 60008; 312/640-8782

CIRCLE 315 ON READER SERVICE CARD

A mass storage controller chip has been announced by **Adaptec, Inc.** The **AIC-610** replaces approximately 10 logic components, including a programmable storage controller, a dual-port buffer controller, and buffer addressing logic. It is compatible with any standard interface used by Winchester disks, diskettes, and tape drives, and also can be programmed to support an SCSI (small computer system interface), IBM PC bus, or a proprietary bus. With a data transfer speed as fast as 15 MHz and a bus transfer rate as high as 1.5MB per second, the AIC-610 is intended for embedded controller applications in high-performance 3½-inch and 5¼-inch drives. The chip has fully programmable, 48-bit error checking and correction (ECC), which corrects errors up to 19 bits long. In addition, the AIC-610 offers 16-bit cyclical redundancy checking (CRC). Available in OEM quantities only. 10-MHz version, $23.00; 15-MHz, $34.50.
Adaptec, Inc., 580 Cottonwood Drive, Milpitas, CA 95035; 408/432-8600

CIRCLE 308 ON READER SERVICE CARD

Local Data, Inc. has made available **DataLynx/3174**, a 16-port cluster controller (based on the Intel 16-bit, 10-MHz 80186) that connects asynchronous networks, PCs, terminals, and printers to IBM System/370-type mainframes. DataLynx/3174 emulates IBM SNA 3174, 3274, and 3276 control units. Offering up to 16 asynchronous ports, it recognizes as many as 32 logical units, which allows users to transfer and control 32 simultaneous data streams through its 16 physical asynchronous ports. The standard 4-port controller can be expanded in 4-port modular increments up to a maximum of 16 ports.

As an intelligent interface, upgrades are recognized when the unit is powered on without additional set-up. DCE and DTE signals are automatically recognized and selected, which allows the same cables to be used for DCE and DTE on modem and terminal ports. Users can mix and match IBM and asynchronous terminals throughout a network. DataLynx/3174 supports more than 150 asynchronous terminal types including native support for TV910, TV925, VT52, VT100, ADM3A, VT220, and Wyse 50 Plus. Operators can configure as many as six additional unique terminal drivers that are stored in nonvolatile memory (EEPROM). Both 3270 terminal emulation and file transfer are provided by TruLynx/3270 PC software. The DataLynx/3174 is a powerful protocol converter built around the same 80186. It offers dual-host support through two synchronous channels that are RS-232/V.24 compatible. 4-port version, $3,000; 16-port version, $6,500; TruLynx/3270 PC software, $195.
Local Data, Inc., 2771 Toledo Street, Torrance, CA 90503; 213/320-7126

CIRCLE 309 ON READER SERVICE CARD

A 9600-bps (bits per second), synchronous modem with a multiprotocol automatic dialer and a 25-millisecond (ms) fast training time, has been introduced



The CM 201 CD ROM drive from Laser Magnetic Storage International



Emulex Corporation's DCP-286 communications coprocessor

by **Racal-Vadic**. The **9650PA** provides four integral automatic dialers, full front-panel control, and V.29 and V.27 ter compatibility. It is targeted at twisted-pair, dial-up applications, such as micro-to-mainframe SNA and bisynchronous data transmissions, RJE (remote job entry) batch processing, and database uploads. The 9650PA operates at 9600, 7200, and 4800 bps; its integral automatic dialer supports 801-type parallel automatic calling and 3270 SDLC, HDLC, and 3780-bisynchronous serial dialing protocols. The dialing and serial command protocol is modeled around the CCITT V.25 bis recommendation for synchronous automatic dialing. $1,675.
Racal-Vadic, 1525 McCarthy Blvd., Milpitas, CA 95035; 408/946-2227
CIRCLE 311 ON READER SERVICE CARD

Incorporating the Texas Instruments (TI) 34010 graphics processor, the **Genesis 1024**, from **National Design, Inc.** is a single-slot board for fast, high-resolution graphics (1,024 by 800 pixels) with a palette of 4,096 colors. It can be used as a parallel processor and has up to 1.5MB of RAM on the card. It can run simultaneously with the IBM EGA using Genesis' EGA pass-through capability. The Genesis 1024 uses both CGI standards and GSS interface and is compatible with TI's SDB board. The TI 34010 is a 32-bit graphics processor capable of 6 million instructions per second running at 50 MHz. $1,700.
National Design, Inc., 12885 Research Blvd., Suite 105, Austin, TX 78750; 512/335-1550
CIRCLE 316 ON READER SERVICE CARD

PASSION-286 is an 8-MHz, 80286-based accelerator board from **Earth Computers**. Designed to fit in the short slot of the PC/XT, it uses a proprietary custom VLSI (very large scale integration) chip to implement a memory cache system. The PASSION-286 also provides a socket for an 80287. The board contains two switches: the first is for toggling between the 80286 and 8088, the second allows the cache to be disabled for reading copy-protected disks. $395.
Earth Computers, P.O. Box 8067, Fountain Valley, CA 92728; 714/964-5784
CIRCLE 319 ON READER SERVICE CARD

A family of half-height, 5¼-inch CD ROM drives, the **CM 200 Series** has been introduced by **Laser Magnetic Storage International**. The units are designed to access up to 600MB of digitally encoded data on standard 120-millimeter (4.72-inch) compact disks. The average access time is less than 500 milliseconds (ms), and the error-correction system provides high data integrity, with errors in data retrieval occurring less than once for every 10^{16} bits read. The drives have an MTBF (mean time between failure) rate of 16,000 hours at a 25-percent duty cycle. An audio support board that allows the unit to play audio compact disks is optional. The series includes the CM 210, a model with an embedded small computer system interface (SCSI) controller, and the CM 201, with a proprietary interface for the IBM PC. Both models are available in OEM quantities of 1,000 units. CM 210 (drive only), $500; CM 201 (drive only), $400.
Laser Magnetic Storage International, 200 Park Avenue, Suite 5501, New York, NY 10166; 212/578-9400
CIRCLE 313 ON READER SERVICE CARD

The **Everex Professional Graphics Adapter** (EPGA) is now available from **Everex Systems, Inc.** The EPGA emulates the IBM CGA, monochrome display adapter, and Hercules Graphics Card as well as the IBM PGC. Occupying one full-length slot, the EPGA is equipped with an on-board 80286 with 512KB of fast video RAM. It is an intelligent graphics controller that accepts high-function graphics commands and transforms them into colorful two- or three-dimensional images on a PGD monitor. Modeling, viewing transformations, command lists, color manipulation, and programmable text fonts are standard features. A text or graphics resolution of 640 by 480 pixels is available in 256 programmable colors from a palette of 4,096. Two- or four-color graphics of up to 640-by-200 pixel resolution can be displayed in CGA mode. High-resolution Hercules graphics are available in the monochrome mode. Both the monochrome and CGA modes include text displays of 40 characters by 25 lines or 80 characters by 25 lines. $999.
Everex Systems, Inc., 48431 Milmont Drive, Fremont, CA 94538; 415/498-1111
CIRCLE 314 ON READER SERVICE CARD

A high-performance, four-line, front-end communications coprocessor board designed for applications requiring high-speed, multiline communications, and multiprocessing capability has been announced by the Persyst division of **Emulex Corporation**. The single-slot **DCP-286** board increases data communications throughput by coupling DMA technology with an on-board, 6-MHz (or optional 8-MHz) 80286. It can support multiprotocol communications in excess of 300,000 bps via its RS-232 and optional RS-422/RS-485 interfaces. Configured for an open architecture, future boards that provide additional memory and I/O capability may be connected to and controlled by the DCP-286. The 512KB of dual-ported, parity-checked RAM (or shared memory) on the board allows the PC to directly access the DCP-286 memory. Other features include an on-board interval timer supporting three 16-bit counters, and a configurable 16KB-to-1MB shared memory window for installing multiple DCP-286 boards in a single system. $1,595.
Persyst Division of Emulex Corporation, 3545 Harbor Blvd., P.O. Box 6725, Costa Mesa, CA 92626; 714/662-5600
CIRCLE 320 ON READER SERVICE CARD

CIRCLE READER SERVICE NO. 200 FOR FACING AD

TEKTRONIX NEW ADVANCED PC GRAPHICS STANDS ALONE.

BECAUSE IT WORKS TOGETHER.

Introducing Tek Advanced PC Graphics: a fully integrated system of high-performance graphics, easy system connectivity, and unparalleled application software for your PC. Tek Advanced PC Graphics starts with a flexible multiple-rate color graphics monitor that provides 640x480 Tektronix-style graphics as well as EGA and CGA software compatibility.

Driving your monitor to a whole new level of graphics speed is Tek's PC4100 graphics coprocessor board. It features Texas Instruments® powerful TMS 34010 32-bit





Graphics System Processor for ultra-fast throughput of your design applications. Add to that Tek's PC-05 or PC-07 terminal emulation software, and you're ready for stand-alone computing or access to a world of mainframe graphics.

To bring those applications to life, you can connect a Tek color ink-jet printer. And start producing high-resolution, vibrant hardcopy output on either paper or transparencies.

Couple all that with Tektronix worldwide support and service, and your PC can gain the same productive advantages that host-based systems in scientific and engineering environments have had for close to two decades.

Tek's PC4100 graphics coprocessor board delivers serious graphics on a stand-alone basis. Built around the Texas Instruments Graphics System Processor(GSP),™ the graphics coprocessor board achieves a combination of sophisticated graphics and fast throughput your PC just couldn't deliver before. The GSP assumes the complete graphics processing workload, freeing your PC processor for other requirements.



New companion monitor brings together fine detail and maximum flexibility. You'll view your applications on Tek's new multiple-rate monitor. In true Tek tradition, it provides ideally balanced, 640x480 addressability and a 60 Hz non-interlaced refresh rate. So you can use advanced packages like AutoCAD,® Zenographic's Mirage™ and VersaCAD.®

Then, to move from GSP graphics to emulation of the IBM® Enhanced Graphics Adapter(EGA) mode, you simply soft-switch. And you're ready to run the popular PC packages you probably already use in CGA/EGA mode—standards like Lotus® 1-2-3,® Microsoft® WORD® and Microsoft® Windows,® to name just a few.

Last, but not least, Tek's PC4100 links you to a world of mainframe graphics. All you do is load Tek PC-05/PC-07.

Tek PC-05/PC-07 terminal emulation software gives you mainframe accessibility with the local processing power of your PC. Because Tek PC-05 and PC-07 terminal emulation software runs under MS-DOS® 2.0 and higher, you can run your mainframe-based

Copyright © 1987, Tektronix, Inc. All rights reserved. DISSPLA and TELL-A-GRAF, ANVIL-5000, SAS/GRAPH, DI-3000, ANSYS and NASTRAN are registered trademarks of ISSCO, MCS, SAS Institute Inc., Precision Visuals, Swanson Analysis Systems and MacNeal-Schwendler respectively. IBM, Texas Instruments and GSP, Lotus and Lotus 1-2-3, Microsoft, MS-DOS and Microsoft WORD and Windows, VersaCAD, AutoCAD and Mirage are registered trademarks of International Business Machines Corp., Texas Instruments, Inc., Lotus Development Corp., Microsoft Corporation, VersaCAD Corp., Autodesk, Inc. and Zenographics respectively. VPT 102 11W-7050

AND SETS YOU APART.

applications software on your PC as if it were a Tek 4105 or 4107 terminal.

Which means you can quickly access the power of Tek graphics—including 4107 segments, true zoom and pan, rubber-banding, definition of up to 64 viewports and more. You can use these highly productive features with a wide range of well-known designer software packages such as ISSCO's DISSPLA® and TELL-A-GRAF,® MCS's ANVIL-5000,™ SAS Institute Inc.'s SAS/GRAPH, Precision Visuals' DI-3000,® Swanson Analysis Systems' ANSYS® and McNeal-Schwendler's NASTRAN.

In addition, you can utilize software development tool sets like Tektronix PLOT 10® GKS, IGL, TCS and STI software as well as numerous driver support packages created for the 4105 and 4107.

Completing the picture: perfect color output with Tek's reliable ink-jet printers. At the push of a button, the Tek 4696 lets you produce exacting color reproductions of your on-screen display on either paper or transparencies.



Because of its 120 dots per inch addressability in both horizontal and vertical directions, you can achieve resolution of up to 1280 points x 960 points per "A" size image.

All the key tools for software development, right from the outset. The new Tektronix Graphics Interface™ (TGI) for the PC provides the basics of Tek graphics functionality to application programs running under MS-DOS. What's more, in-circuit emulator, C-compiler, assembler and linker are all available from Texas Instruments to help software developers write applications packages for the PC4100 graphics coprocessor board.

To enable sufficient workspace for custom interfaces or specific application programs, the PC4100 graphics coprocessor board comes standard with a full megabyte of program memory.

Put yourself on the sure path of Tek graphics evolution. Whether you choose Tek PC stand-alone graphics, Tek's high-resolution monitor, Tek terminal emulation or all three, you can be assured Tek will keep you current with the best and most productive graphics. Because like all our products, Tek Advanced PC Graphics features a smooth built-in pathway to higher-level graphics.

For more information about how Tek lets you stand alone and work together, contact your local Tek representative about Tek Advanced PC Graphics. Or call, 1-800-225-5434. In Oregon, 1-235-7202.



TEK GRAPHICS PROCESSING SYSTEMS

Tektronix®
COMMITTED TO EXCELLENCE

VPT 102 11W-7050



Structured Software Solutions, Inc.'s FACET 2.0 menu screen

Pascal-2 compiler package from Oregon Software

SOFTWARE

Structured Software Solutions, Inc. has announced **version 2.0** of **FACET**, a UNIX windowing environment that transforms an IBM PC into a windowed workstation when linked to a UNIX or XENIX host computer. FACET makes it possible for PC users to open as many as 10 individual UNIX session windows at any time on their PCs concurrently when they are running another program. It is a terminate-and-stay-resident program under DOS, that provides full-featured, host-to-terminal window management capabilities. Each FACET window on the PC emulates an ANSI terminal. FACET 2.0 operates over Ethernet networks running PC-Interface from Locus Computing. DOS version, $295; host driver, $195 to $495 (depending on UNIX host configuration).
Structured Software Solutions, Inc., 4031 W. Plano Parkway, Suite 205, Plano, TX 75075; 214/985-9901
CIRCLE 329 ON READER SERVICE CARD

Oregon Software has developed a DOS version of its **Pascal-2 compiler**, which was previously available on VAX, 68000, and PDP-11 environments. Pascal-2 generates compact code for the PC, and features a large-memory model and 32-bit integer support. Pascal-2 is certified at the highest level of the international standard. It includes a debugger, error step-through, the Intel CEL87 mathematics library, assembly language interface, execution profiler, and interface to the BRIEF text editor. $350.
Oregon Software, 6915 S.W. Macadam Avenue, Portland, OR 97219-2397; 800/367-2202; in Oregon, 503/245-2202
CIRCLE 321 ON READER SERVICE CARD

A comprehensive Common LISP system that interfaces to Microsoft C is now available from **Solution Systems**. **TransLISP PLUS** offers portability and an extensive development environment with more than 400 Common LISP primitives. Programs written carefully with TransLISP PLUS will be portable to any other Common LISP system on a micro-, mini-, or mainframe computer. The interface to Microsoft C lets a programmer customize LISP or combine C functions with LISP programs. Additional features include the integrated editor, pretty printer, trace facility, and cross reference. $195; runtime version, $150.
Solution Systems, 335 Washington Street, Norwell, MA 02061; 800/821-2492; 617/659-1571
CIRCLE 325 ON READER SERVICE CARD

Rapid Imaging Software has released the **Imaging Toolkit**, which includes a variety of tools for image generation, processing, and display. The library of

Shape produced with the Rapid Imaging Toolkit

functions is compatible with the Lattice C or Microsoft C version 3.0. The toolkit's functions include image capture, contrast manipulation, look-up table mapping, noise reduction filters, histograms, convolutions, and intensity transection. A complete library of three-dimensional geometric utilities is supplied for image generation including three-dimensional geometric transformations and ray-trace illumination models. A flexible library of device interface primitives provides pixel and raster setting and vector drawing. The package also includes FFT87-2D, a high-speed, fast-Fourier transform program. $699.
Rapid Imaging Software, P.O. Box 941, Tijeras, NM 87059; 505/243-9454
CIRCLE 333 ON READER SERVICE CARD

A **Modula-2** native code compiler is available from **farbware**. This full compiler produces object files compatible with the DOS link utilities. The compiler supports the full Modula-2 language as defined in Niklaus Wirth's *Programming in Modula-2* (Springer-Verlag, 1982). The package includes a UNIX-like **make** utility as well as the complete source and object code for the runtime system. No royalty is charged for the runtime object code, and the software is not copy protected. One of the modules for which source code is provided is the low-level DOS interface module that is coded using the IBM Assembler. This module demonstrates the interface between Modula-2 and assembler code. $89.95; manual alone, $25.00.
farbware, 1329 Gregory, Wilmette, IL 60091; 312/251-5310
CIRCLE 322 ON READER SERVICE CARD

An Ada language compiler/development system has been introduced by **Meridian Software Systems, Inc. AdaVantage** implements all Ada language features, including tasking, exceptions, fixed point, generics, and separate compilation, without additional memory boards or coprocessor boards. The AdaVantage compiler is accompanied by a set of tools used to manage an Ada program library database, as well as a standard Ada library. Utility packages for interfacing to DOS, computation of transcendental math functions, and examination of the programming environment are available. $129.95.
Meridian Software Systems, Inc., 23141 Verdugo Drive, Suite 105, Laguna Hills, CA 92653; 714/380-9800
CIRCLE 326 ON READER SERVICE CARD



Spectrum Software's MICRO-LOGIC II schematic editor screen



MICRO-LOGIC II timing simulation screen from Spectrum Software

MICRO-LOGIC II, an interactive design and analysis system for digital electronics, is available from **Spectrum Software**. The system includes an integrated mouse-driven schematic editor, component library editor, shape editor, data channel and clock waveform pattern editors, and a high-speed logic and timing simulator. Simulation results are displayed in a graphical form similar to logic analyzer displays. The schematic editor can handle as many as 1,000 components or integrated circuit (IC) packages per drawing. It is supplied with a library of more than 200 standard TTL/CMOS logic packages. The timing simulator can handle networks of up to 10,000 equivalent 2-input gates and features a high-speed, assembly language, event-driven routing capable of more than 1,000 events per second. $895.
Spectrum Software, 1021 S. Wolfe Road, Sunnyvale, CA 94086; 408/738-4387
CIRCLE 335 ON READER SERVICE CARD

Pick Systems has begun shipping its 10-user operating system for the PC/AT, complete with advanced virtual memory architecture and an integrated relational database. **Version 2.0** of the **Pick operating system** enhances peripheral connectivity with support for three parallel printer ports, streaming cartridge-tape units (QIC-60), serial I/O boards, and high-capacity hard-disk drives. The system is built around a dictionary-driven relational database structure; it does not limit data length and manages memory by moving from disk only data that are immediately needed rather than an entire file. Data retrieval access is performed via English-like statements. Another feature allows users to create a personalized vocabulary of terminal control language commands in place of the standard set, when desired, and Pick/BASIC includes the ability to execute those commands. For users running concurrent with DOS, sharing of a hard disk with another operating system is supported, and a utility for transferring data between Pick and DOS is standard. 10-user, $1,295; 6-user, $995; 3-user, $795; 3-user PC/XT, $495.
Pick Systems, 1691 Browning, Irvine, CA 92714; 714/261-7425
CIRCLE 327 ON READER SERVICE CARD

Gold Hill Computers has announced the **Golden Common LISP (GCLISP) 386 Developer** for the Compaq Deskpro 386. Gold Hill also announced a distribution agreement with Compaq to sell the Deskpro 386 models 40, 70, and 130. The GCLISP Developer provides

Gold Hill Computers' GCLISP 386 Developer

program developers a Common LISP programming environment for building expert systems and other AI applications. GCLISP can integrate C programs with AI applications. The package also supports a large memory interpreter and compiler, on-line help system, and an enhanced editor. This editor has more than 150 commands, uses EMACS keyboard mapping, and gives developers the option of defining their own keyboard mapping. The 386 Developer supports lexical scoping, packages, and transcendental functions. 386 Developer, $1,195; complete Deskpro 386 development system, $7,800 to $16,400.
Gold Hill Computers, Inc., 163 Harvard Street, Cambridge, MA 02139; 617/492-2071
CIRCLE 324 ON READER SERVICE CARD

A protected-mode, realtime, multitasking operating system that supports DOS 2.1 programs has been introduced by **Digital Research, Inc.** (DRI). Based on an earlier version of Concurrent DOS 286 and written largely in C, **FlexOS version 1.3** is being ported to a wide variety of 16- and 32-bit microprocessors. High-level language compiler support for FlexOS includes DRI's CBasic, MetaWare High C, MetaWare Professional Pascal, Ryan McFarland's FORTRAN 77, MicroFocus Level II COBOL, and an Ada/ED-C interpreter from New York University. FlexOS's graphics capabilities are based on DRI's GEM (Graphics Environment Manager) programming environment. Upgrades to version 1.3 are free to registered users of Concurrent DOS 286 release 1.2.

Available separately from DRI is **FlexNet**, the networking resource manager for FlexOS. Included with FlexNet is an electronic mail utility—a server/requester to IBM PC LAN and FlexOS functionality supported across the network. FlexOS 1.3, $750; development kit, $1,000; FlexNet, $250.
Digital Research, Box DRI, Monterey, CA 93942; 800/443-4200; in California, 408/649-3896
CIRCLE 328 ON READER SERVICE CARD

Version 2.0 of **Windows for Data** has been released by **Vermont Creative Software**. With Windows for Data, C language developers can incorporate advanced windowing, menu, and data entry capabilities into their programs. This version offers an internal debugging system that traces errors and reports memory corruption. Other capabilities include a screen layout aid, foreign language capability, multiple choice fields, scrollable subforms, free-flexibility in form and menu management. Features already present in Windows for C include pop-up data entry windows, validation and conversion for all variable types, multilevel menus, field specific

HERE'S HELP

Attachmate has answers to your questions about micro-mainframe communications. Hardware answers, software answers and now a guide packed full of answers to some important questions—questions worth asking *before* you make long-term decisions.

What should you know about IBM® standards, multiple sessions, windows, file transfer, API, and graphics?

You'll find the answers and solutions in Attachmate's *Quick Reference Guide for Micro-Mainframe Communications*—with a chart comparing IBM, IRMA®, and Attachmate. For a free copy, call toll free:

1-800-426-6283

Attachmate

Micro-Mainframe Technology: We put our heart in it!
Attachmate Corporation
3241 118th S.E., Bellevue, WA 98005
(206) 644-4010

Copyright ©1986, Attachmate Corporation. IRMA is a registered trademark of Digital Communications Associates, Inc. IBM is a registered trademark of International Business Machines Corporation.

CIRCLE NO. 165 ON READER SERVICE CARD

Lifeboat Associates' TimeSlicer multitasking library

db_QUERY SQL-based support package from Raima Corporation

and context-sensitive help, and full compatibility with both Microsoft Windows and IBM TopView. $295.
Vermont Creative Software, 21 Elm Avenue, Richford, VT 05476; 802/848-7738
CIRCLE 330 ON READER SERVICE CARD

Lifeboat Associates is introducing another entry in its Advantage Library Series. **TimeSlicer** is a multitasking library that allows developers of microcomputer software to offer the benefit of multitasking and realtime event processing in their applications. This linkable library allows DOS programmers to use concurrent tasks and realtime event processing for C++, C, and assembly language applications. The TimeSlicer also includes the capability for enabling tasks to optimize the efficiency of special event processing, support for both preemptive and nonpreemptive modes, two distinct methods for disabling the TimeSlicer, and the compatibility to extend the runtime of selected tasks. Header files for all three languages are included with TimeSlicer. $295.
Lifeboat Associates, Inc., 55 S. Broadway, Tarrytown, NY 10591; 914/332-1875
CIRCLE 334 ON READER SERVICE CARD

Raima Corporation is now offering its **db_QUERY**, an SQL-based, ad hoc query, and report writing support package for use with db_VISTA. Db_QUERY enables application developers to create a simple, relational view of db_VISTA's complex network database. Capabilities of db_QUERY include conditional expression evaluation, sorting formats, and support for special field types, such as money, date, and time. Db_QUERY is royalty-free and runs on DOS, UNIX, and VAX VMS systems; it is available in a source code version and for use with most C compilers. $195.
Raima Corporation, 3055 112th Avenue NE, Bellevue, WA 98004; 206/828-4636
CIRCLE 331 ON READER SERVICE CARD

VIM (for virtual machine), is a debugger from **Digital Dispatch, Inc.** VIM is an interpreter for 8088 machine code that executes in virtual memory on the PC, PC/XT, PC/AT, and compatibles. The VIM virtual debugging environment includes the entire addressing space of the processor, thus, the program under test can work with its own copy of DOS, interrupt vectors, RAM disks, device drivers, and resident utilities. VIM can optionally swap both display memory and modes at the start and end of interpretation. This allows the virtual program to reprogram the display adapter in any fashion it wants, and still provide VIM with a readable debugging screen. Even ill-behaved programs that bypass BIOS can be isolated. $69.
Digital Dispatch, Inc., 1580 Rice Creek Road, Minneapolis, MN 55432; 612/571-7400
CIRCLE 336 ON READER SERVICE CARD

Borland International, Inc. has produced the **Turbo Prolog Toolbox**, with a collection of more than 80 tools, 40 sample programs, and source code included for users of Turbo Prolog. User-interface design tools provide developers with a variety of menus (box, line, pull-down, and tree) suited to different types of applications. The Toolbox shows how to set up context-sensitive help menus within a program. Menus can be created in windows containing both text and graphic characters. The Toolbox also supplies predicates that allow the incorporation of status lines in programs being developed. Screen layouts can be designed for either the actual screen or for a virtual screen. A parser generator in the Toolbox breaks up a series or string of commands and translates it into Turbo Prolog source code. $99.95.
Borland International, Inc., 4585 Scotts Valley Drive, Scotts Valley, CA 95066; 408/438-8400
CIRCLE 332 ON READER SERVICE CARD

RPM Systems has announced **Mailman**, a fully functional electronic mail system. The Mailman user program runs on the PC and compatibles, while the heart of the multiuser system resides on an 80386-based computer. The Mailman's user interface is menu-driven, with a multilayered set of windows that show users where they are within the system at all times. Mailman can be used to send existing ASCII or binary files, but it also comes with a built-in word processor. Sending and receiving mail takes place automatically in the background on the PC during times specified by the user. Mailman is PC-Net LAN compatible and can be a node on a PC-Net LAN, or it can attach to other LANs through an RPM interface. Prices start at $2,000 for a 10-user system.
RPM Systems Corporation, 13 Corporate Plaza, Newport Beach, CA 92660; 714/720-0226
CIRCLE 337 ON READER SERVICE CARD

Three products for **Multi-C** have been announced by **Cytek, Inc. Multi-Comm** is a communications library that supports high-speed, interrupt-driven data transfers; multiple device types; and background communications by Multi-C tasks. Also included are drivers for Hayes-compatible modems and the XMODEM binary data-transfer protocol. **Multi-Windows** allows the creation of overlapping, pop-up display windows. **Multi-Forms** works with Multi-Windows to produce data entry and display screens quickly. Available for Microsoft, Lattice, and Computer Innovations C compilers. Multi-Comm and Multi-Forms, $149 each; Multi-Windows, $295.
Cytek, Inc., 805 Turnpike Street, North Andover, MA 01845; 617/687-8086
CIRCLE 338 ON READER SERVICE CARD

The material that appears in Tech Releases is based on vendor-supplied information. These products have not been reviewed by the PC Tech Journal *editorial staff.*

JLASER PLUS

COMBINES SCANNING AND PRINTING IN A SINGLE BOARD!







Recipe for
DESKTOP PUBLISHING DELIGHT

Main ingredient:
1 JLASER PLUS (EMS memory board with combination printer/scanner interface)

Other ingredients:
1 PC, XT, or AT style desktop personal computer
1 Canon-based 300 DPI laser printer
1 Canon IX-12 300 DPI scanner
Connecting cables
4 Banks of 256K RAM chips minimum. Total of 8 banks is optional if you like extra chips.
1 or more software programs that support JLASER or JLASER PLUS.

Directions:
Install JLASER PLUS with RAM chips in a single slot of the computer. Hook up scanner and laser printer with cables. Install desired software packages. Scan pictures of graphics. Mix with text and print out tasteful, professional-looking documents, newsletters, and graphic designs at full 300 DPI resolution and maximum speed.

Combined scanning and printing with JLASER PLUS. It lets you have your cake and eat it too.

Desktop publishing can be a piece of cake when you have the right ingredients. The quality of the ingredients will make all the difference. Don't be fooled by high-priced substitutes. Follow our recipe exactly. You'll be delighted with the results.

It makes desktop publishing a piece of cake!

Tall Tree Systems introduces another breakthrough in desktop publishing with JLASER PLUS. We've combined a 2 MB EMS memory board and an interface to both a Canon®-based laser printer and scanner. JLASER PLUS increases the performance of both devices and gives you a low-cost solution to the limitations you've been experiencing with them.

Furthermore, the same memory that is made available to your printer and scanner is also available for all your other conventional applications. You get system memory, expanded LIM memory, extended memory in an AT-type machine, RAM Disk and print spooler — all in a single slot!

Supporting JLASER PLUS is a host of software packages, such as PC Paintbrush + from ZSoft, Dr. Halo D.P.E. from Media Cybernetics, LaserGL from Software Express, Ventura Publisher from Xerox, Page Builder from White Sciences, Le Print from Le Baugh Software, Fancy Font and Fancy Word from SoftCraft, Inc., and many more to be announced.

It takes a technological innovator like Tall Tree Systems to provide a major advancement like JLASER PLUS. And we don't stop at performance. We also deliver value, which is truly icing on the cake.

TALL TREE SYSTEMS
2585 E. Bayshore Road
Palo Alto, CA 94303
(415) 493-1980
Telex: 9102404041

CIRCLE NO. 194 ON READER SERVICE CARD

TALL TREE SYSTEMS

Canon is a registered trademark of Canon, Inc. All software packages listed are trademarks of their respective companies.

©1986 by Tall Tree Systems. All rights reserved.

For the next generation
call the numb

of 3X communications, er on the right.

When you want to connect your IBM PC to your System 34/36/38, whom should you call?

Call the people on the right and you can emulate the most terminals, including the 5250 (with all 32 display attributes) and the 3180. You can support the latest laser-jet printers, the largest range of system printers, and the most up-to-date file transfer packages on the market—even IBM's. You can do windows and cluster with three other IBM PC's from your workstation. Most important, should you ever need help, the toll-free number on the right will put you in touch with a technical support team whose sole priority is to master PC based products.

Now call the people on the left, and you can emulate some terminals, a limited number of system printers, and not all of the 5250 display attributes. Of course you'll be able to work with IBM file transfers, but once the goods are delivered, can you work with virtually no support of PC based products?

So before you call the number on the left by force of habit, consider who's really giving you the best solutions in 3X communications. And ask yourself this.

Who should be emulating whom?

IDEAssociates™

IDEAssociates, Inc., 29 Dunham Road, Billerica, MA 01821, (617) 663-6878, Telex 4979780; France, Switzerland, Germany, United Kingdom.
IBM is a registered trademark of International Business Machines Corporation.
CIRCLE NO. 237 ON READER SERVICE CARD

THE PROGRAMMER'S SHOP

provides complete information, advice, guarantees and every product for Microcomputer Programming.

Pascal-2™ FOR MS-DOS

Have you reached the limit with Turbo? Upgrade to Pascal-2.

List: $395
Ours: $359

- Cut execution time by 200% over TURBO
- Cut executable program size by up to 50%
- Transport MS-DOS programs to VAX, PDP-11 and 68000 machines with only minor adjustments, and vice versa
- Speed error corrections and save development turn-around time with sophisticated error checking and reporting
- Use all of DOS-addressable memory through efficient large-memory model
- Access DOS services and network files
- Call Microsoft FORTRAN, C, Pascal and assembly routines

Quicksort Benchmark



UPGRADE WITHOUT LOSS – easy migration path from TURBO with compatible strings, equivalent procedures & access to TURBO graphics

Plus **Pascal-2 gives you more for the dollar! You get these extra features included free:**

- Interactive source-level debugger
- Error walkback to trace errors to their source
- Intel CEL87 math library
- High-level profiler

The following are trademarks: Oregon Software, Pascal-2, Oregon Software, Inc.; Intel, CEL87, Intel Corporation; MS, Microsoft Corp.; TURBO Pascal, Borland International, Inc.; PDP, VAX, Digital Equipment Corp.; MC68000, Motorola, Inc.

OREGON SOFTWARE

SoftProbe II/TX, a High-Level Solution for Embedded System Debugging.



FEATURES

- Source Level Debug
- Supports High Level Language Data Types
- C-like Command Language with Expression Evaluation and Flow Control
- Displays Program Execution Trace in High Level and Assembly Languages
- Friendly User Interface with Macros and On-line Help

TARGET SYSTEM

- Any iAPX-86/186 Based System with a USART
- IBM PC or Compatible.

BENEFITS

- Debug on Actual Target System
- Debug at High Level Language Level
- Mixed Language Debugging Facilitates Firmware Testing

LANGUAGE SUPPORT

- C
- PL/M
- ASM

SYSTEMS & SOFTWARE INC
3303 Harbor Blvd.,
C-11, Costa Mesa, CA 92626
(714) 241-8650 FAX (714) 241-0377

List: $750 Ours: $695

SoftProbe is a registered trademark of Systems & Software, Inc.
IBM PC is a registered trademark of International Business Machines Corp.

HOW TO BECOME A POWER PROGRAMMER

Introducing Two New Powerful Packages, BlackStar Basic Development Tools and "C" Function Library

BASIC DEVELOPMENT TOOLS features four-in-one "automatic programming" tools. Including SCREEN BUILDER, B+TREE, HELP MESSAGE SYSTEM and EZ SCREEN POP-UP WINDOWS. Can be used separately or together. Compatible with Microsoft Quick BASIC and Borland Turbo Basic. Comes with 220 page manual and two diskettes.

"C" FUNCTION LIBRARY New ANSI Standard with over 275 functions. A comprehensive development package for the latest "C" Compilers including Microsoft and Lattice. Complete source code and demo program, as well as small, medium and large memory models are included. Plus 350 page instruction manual and three diskettes.

SPECIAL OFFER!
$99.00 each, both for $175.00
ORDER TODAY! 1(800) 722-7853
(213) 306-3020 in California

STERLING CASTLE™ SOFTWARE

All trademarks acknowledged.

WANT TO ADD

WINDOWS, ICONS, FONTS, FAST GRAPHICS, DIALOG BOXES, PROCESS MANAGEMENT, AND DEVICE INDEPENDENCE

TO YOUR IBM PC PROGRAMS?

If you have ever wished that you could develop stunning Macintosh-like programs on the IBM PC without the overhead of an enormous operating environment like Windows or GEM, then you need the **SYNERGY DEVELOPMENT TOOLKIT, from Matrix Software.**

Using a memory resident runtime module only **20K** in size (versus as much as 300K for Windows), you can develop applications with: overlapped and tiled windows; pull-down menus with half intensity options and automatic sizing; fast graphics function calls to draw shapes, lines, boxes, and create intricate fill patterns in both regular and irregular areas; have full device independence (drivers for numerous devices, including CGA, EGA and Hercules are included); sophisticated text input and output, with fonts in different styles and sizes; full keyboard support (your programs won't need a mouse!) and powerful mouse support; and process management calls to efficiently manipulate system resources.

The Toolkit has gateways to support the following languages:

- Turbo Pascal
- IBM/MS Pascal
- Microsoft & Lattice C
- Macro Assembler
- Basic
- dBASE II/III Compilers

In addition, the Toolkit includes a powerful collection of tools including a graphics resource editor for developing your own icons and fonts.

NEW! The Toolkit also **includes a free copy of Synergy Layout**, a revolutionary software development tool that dramatically increases your productivity by actually generating bug-free source code in Macro, C, and Turbo Pascal.

For further information, contact Matrix Software at [617] 567-0037.

List: $395
Ours: $349

Call Today for FREE detailed information or try Risk-Free for 31 days.

800-421-8006
HOURS: 8:30 A.M. - 8:00 P.M. E.S.T.

THE PROGRAMMER'S SHOP™
Your complete source for software, services and answers
5-P Pond Park Road, Hingham, MA 02043
Mass: 800-442-8070 or 617-740-2510 2/87

CIRCLE NO. 220 ON READER SERVICE CARD

TECH NOTEBOOK 75

MICHAEL ABRASH

DOS Moves on the 80386

DOS can be programmed to force 32-bit moves, thus doubling block-move performance when running on the 80386.

The 80386 is the most powerful processor on the market that features full 8086—and hence DOS—compatibility. Existing DOS programs, which were written to run on 8088- and 80286-based computers, do not exploit its features, and in general, they benefit only from the greater speed of the 80386. DOS programs, however, can be written to take advantage of the 80386, and, at the same time, also work on the PC/XT and PC/AT. One example is the moving of blocks of data from one area of memory to another.

The 80386 is inherently capable of reading or writing 32 bits of data at a time, and the 32-bit form of the MOVS instruction can move a doubleword from one memory address to another in only seven cycles, memory performance permitting, of course. Unfortunately, MOVSW instructions performed in a DOS-compatible mode of the 80386 (real or virtual-8086 mode) default to moving only 16 bits at a time. A special prefix can be used to force 32-bit moves, allowing DOS programs approximately to double their block-move performance when they are running on an 80386.

The subroutine FastBlockMove in the listing below (FASTBLK.ASM) performs a block move in units of either 16 or 32 bits, as selected by the calling program. The key to this subroutine is the 66H prefix to the REP MOVSW instruction; this prefix forces the operand size of the following instruction to 32 bits. In the case where a 16-bit move is requested, the subroutine simply jumps directly to the REP MOVSW and executes the block move without the prefix, so the default 16-bit move is performed. For moves of both sizes, the count in CX, which is originally in bytes, is divided down to match the number of words or doublewords that are to be moved.

The 80386 performs best when it is using 32-bit operands that are doubleword-aligned—that is, at addresses that are multiples of four. FastBlockMove assumes that both the source and the destination blocks start on doubleword boundaries. With any other alignment, no performance gain is achieved over moving 16 bits at a time. Likewise, blocks that are moved by words should start on word boundaries in the ATs. The routine automatically handles block sizes that are not integral multiples of four bytes (for 32-bit moves) or two bytes (for 16-bit moves).

FastBlockMove can be used "as is" by a program that first determines whether an 80386 is installed. The processor-specific approach can be integrated readily into the main program more tightly for performance reasons. For example, a program could have separate 16- and 32-bit block-move subroutines, and at start-up could set a vector to the appropriate subroutine; the vector would then be used throughout the program to invoke the appropriate procedure without further testing. However it is done, the key point is that with some clever programming, even DOS programs can take advantage of some of the enhanced features of the 80386.

Michael Abrash is a senior software engineer for Orion Industries. He is coauthor of the book, Graphics for the IBM PC.

LISTING: FASTBLK.ASM

```
; Fast (32-bit) block move for 80386 computers.
; Calling program selects 16- or a 32-bit move.
; Calling program must be sure 80386 is present for 32-bit move.
; For best performance, source and destination blocks should begin on
;  doubleword (for 32-bit move) or word (for 16-bit move) boundary.
; Automatically handles block sizes with odd words and bytes.
; Input: DS:SI = source.
;        ES:DI = destination.
;        CX    = number of bytes to move.
;        AL    = 1 to perform fast 32-bit move (for 80386 only),
;                0 to perform standard 16-bit move (for 8088/86/286).
; Results:
;  CX & BX destroyed, SI points to the byte after the end of the
;  source block, DI points to the byte after the end of the
;  destination block, direction flag cleared.
;
cseg    segment word public 'CODE'
        assume  cs:cseg
        public  FastBlockMove
FastBlockMove   proc    near
        cld
        xor     bx,bx   ;clear odd-size flags
        shr     cx,1    ;convert move size to words
        jnc     CheckFor32BitMove
        mov     bl,1    ;indicate odd byte
CheckFor32BitMove:
        and     al,al   ;has caller requested a 32-bit move?
        jz      DoBlockMove
        shr     cx,1    ;32-bit move -- convert to dbl words
        jnc     Do32BitMove
        mov     bh,1    ;indicate odd word
Do32BitMove:
        db      66h     ;prefix to make the default size for the
                        ; following instruction 32 bits.
DoBlockMove:
    rep movsw           ;move the block -- the move normally defaults
                        ; to 16 bits at a time, but if the size
                        ; prefix was executed, 32 bits will be
                        ; moved on each iteration
        and     bh,bh   ;is there an odd word?
        jz      TestOddByte
        movsw           ;if so, move it
TestOddByte:
        and     bl,bl   ;is there an odd byte?
        jz      Exit
        movsb           ;if so, move it
Exit:   ret
FastBlockMove   endp
cseg    ends
        end
```

PC BRAND NOW PFEATURES PFANTASTIC

Phoenix

Today's professional programmer demands high performance tools that speed up and enhance the application development process. That's why more programmers rely on one company for the best engineered, highest performance tools available—Pheonix.

Phoenix offers a full line of powerful, yet easy-to-use, tools that help programmers more efficiently write, test and deliver the best applications possible. Complete, fully detailed documentation accompanying each tool enables quick mastery of the product. In addition, all Phoenix tools are backed by full-time customer support professionals respected throughout the industry for their commitment and expertise. As a result, many Phoenix tools are already established as industry standards and others are fast on their way.

Plink™ 86*plus*

Plink86*plus* is the only linkage editor containing advanced overlay capabilities. It handles any compiler or assembler producing standard Intel or Microsoft OBJ files, including COBOL and FORTRAN, Lattice C, CI C-86, Microsoft/IBM languages, and mbp/COBOL. Virtual memory management ensures ample capacity for symbol and common block names (35,000). Plink86*plus* supports an unlimited size file, an unlimited number of modules and up to 4,095 overlays nested up to 32 deep. Merges object modules, caches overlays in extended or expanded memory, and automatically reloads overlays upon function return. Includes Plib86 object library manager.
List: $495 PC Brand: $325

Plib™ 86

Plib86 is an object module librarian for Microsoft and Intel format object modules and libraries. With Plib86, you can add, delete or extract modules to or from libraries, and explode a library to its component modules with one command. Plib86 also produces program cross-reference listings in various formats to a disk file, screen or printer.

Originally listed at $195. Plib86 is now included with Plink86*plus*.

Ptel

A Pfantastic communications program for use with most popular modems such as Hayes and compatibles, DEC, Racal Vadic, Anchor, US Robotics and Novation. Ptel automatically adapts to Telink, XModem, Kermit or Modem 7 for CRC checking and for ufn and afn (i.e. "wildcard") file name list transfers, if the bulletin board or the other end computer supports them. With Telink, you'll even get a forecast of file transmission time, always useful in controlling telephone expenses.

In addition to saving received files, Ptel can create and save a transcript of the session commands and messages.

Highly configurable, with choices temporary or saved as altered defaults. Unique telephone directory of bulletin boards and other services, allowing access by service name. Ptel runs fully interactive or can be batch driven from a script. You can even exit to DOS move files around or run another application and then return to Ptel, all without dropping the line.
List: $195 PC Brand: $115

Pasm™ 86

Pasm86 provides both quick assembly and superior syntax checking, plus a wealth of other features and utilities to maximize programming productivity. It is a fully MASM-compatible 8086 macro assembler that supports 8087, 80286 and 80287 operating code mnemonics. Features include ability to: define local symbols in the current procedure, assemble files with up to 15,000 symbols, define symbols at assembly time, obtain listings of error lines only, with warning messages on questionable statements. Pasm's comprehensive documentation includes detailed descriptions and examples of each processor instruction. Now includes Pfix-Lite, a subset of Pfix86*plus*.
List: $195 PC Brand: $125

Pmate™

A full screen, single keystroke, fully customizable text processor/editor with advanced features including: ability to run in the background, C and FORTRAN specific macros, automatic disk buffering, ten individual auxiliary buffers, menu, mouse, or command driven with extensive macro command language, and horizontal scrolling. Pmate offers automatic word wrap, text formatting, global or local setting of margins, tab stops, indents, and a unique last-in, first-out "garbage stack" that saves deleted items for recovery.
List: $195 PC Brand: $115

Pre-C™

Now twice as fast! Similar to the Unix LINT for C, but with additional functionality. It crosschecks multiple source files and libraries at once, reporting incorrect, obsolete, and non-portable C usages that no compiler would catch. Pre-C immediately uncovers errors in interfaces between program modules which are very difficult to find using only a debugger. Pre-C accepts full UNIX System III C syntax, a subset of which is implemented by most MS-DOS C compilers, as well as ANSI proposed extensions. External libraries can be used with or without source code. Pre-C libraries for the latest releases of the Mark Williams, Lattice, CI, Microsoft, Wizard, and Aztec "C" compilers are included, and others can be added by supplying Pre-C with function names and arguments. All memory models are supported.
List: $295 PC Brand: $155

Pfinish™

Pfinish helps to "fine-tune" a software product by identifying inefficient or unnecessary sections of code that need to be rewritten for maximum performance. It analyzes your program during execution, producing reports and histograms that give a snapshot of which routines were reached, their callers, how many times each is executed, how much time is spent in each, how many instructions are executed in each, and more. Histograms and tabular reports, sorted by address or symbol, may be written in any page width or height, to a file, the console, or the printer. Pfinish, unlike other "profilers", can use symbol table information to produce much more meaningful analyses on overlays and interrupts.
List: $395 PC Brand: $235

Pdisk™

Pdisk is a complete disk management package that includes advanced Backup/Restore, Tree Management and Disk Cache utilites. Menu, command line or file-driven. Many options permit backup/restore inclusions/exclusions, whole and partial subdirectories, backups by date/time, file type, and backups of all files or files changed since last backup. It can also maintain a log of backups. Supports AT high-density floppies, PC floppies, and any storage device accessible through a device driver. Tree-oriented Directory, Delete, Copy, Compare, and Remove-Directory simplify management of complicated subdirectory structures. CACHE significantly speeds up disk operation on PC/XT/AT by keeping data in memory instead of disk. In addition. CACHE is compatible with the Lotus-Intel-Microsoft (LIM) expanded memory specification, as well as extended memory.
List: $195 PC Brand: $125

Pmaker™

Similar to the Unix MAKE utility, Pmaker keeps track of which modules in a program are changed, and recompiles, reassembles, and relinks those modules to produce a finished product—all with a single command. An essential tool for managing large, complicated, or distributed programming projects, Pmaker is easier to use than similar products, which require you to create lists of all your input files. Pmaker includes a utility that automatically creates and edits such lists based on answers to a few simple questions. Pmaker works with any compiled language, linker, or other tool you use.
List: $125 PC Brand: $85

Pfix™ 86*plus*

Pfix86*plus* is an easy to use, menu driven, multi-windowed symbolic debugger that works with any IBM or Microsoft compiled language. Pfix86*plus* accesses the full symbol table provided by MS Link or Plink86*plus*, and automatically handles Plink86*plus*-overlaid or resident programs. Source code, assembly language translations, stack, data areas, and breakpoints are displayed simultaneously. Features include: In-line assembler for temporary patches, temporary and permanent breakpoint settings, full speed or trace modes, user-assignable variables, dual-monitor support, up to 100-step traceback, debug log to disk or printer, synchronized source file display, breakpoints in source code, disassembly to disk, configurable menus, multiple code and data windows, and keystroke macros.
List: $395 PC Brand: $235

PforCe™

PforCe is a pre-coded optimized object-oriented toolkit of over 400 routines for C programmers. It includes data bases with B-trees, windows, interrupt-driven communications, string handling, menus, all of the basic DOS interfaces, and a complete set of low-level functions to interface directly to the hardware. PforCe comes complete with indexed reference manual, on line resident help, and quick reference card. It supports all memory models of the following C compilers: Lattice, Aztec, Microsoft, CI-86, and Wizard. PforCe includes full source code and there are no royalties on generated applications using the libraries. A demonstration diskette is also available.
List: $395 PC Brand: $235

Pfantasy Pac

A super value pac of Phoenix goodies. Includes Pfix86*plus*, Pmate, Ptel, Plink86*plus*, Pmaker and Pfinish.
List: $1295 PC Brand: $875

For Orders, Literature, or Catalogs, Call Us at...

800 PC-BRAND

That's (800) 722-7263. In NY State call (212) 242-3600
PC Brand, 150 5th Ave., New York, N.Y. 10011-4311
Telex: 667962 (SOFT COMM NYK)

© 1986 PC BRAND Prices, terms, and specifications subject to change without notice.

PC BRAND™: CAREFULLY CHOSEN PROGRAMMER TOOLS

BRIEF *Is Anything But. A Whopper of an Editor*

With a name that belies its thoroughness, Brief™ has every feature you've ever contemplated for your editor-in-chief. Text, from keyboard or files, is housed in multiple buffers, and scrolled through one or more windows you open, close, resize. A text buffer may be called to different windows to view two areas at once. A change in one changes both. Text blocks may be marked for printing, writing to files, movement to scrap buffers for cut and paste into other buffers, or deletion, with as many "undo" levels as you want.

Brief has text search abilities rivaling "grep", with wildcards for matching, indifference to intervening characters, acceptance of character ranges.

If you use Lattice, C86™, or Wizard, and have 320k, you can compile your C program without ever leaving Brief. It finds the lines with errors, and marches you through the text for repairs.

Parts of Brief were written with its own Lisp-like macro language which has structure, 32-character variable names, conditional execution, loops, and you can actually read it! Nothing like the hieroglyphs we've seen elsewhere. Bulletin board and public domain disks with macros. "Simply the best text editor you can buy", Dvorak *Infoworld*. (Needs 192k.)

Ask for:	List:	PC Brand:
U0590	$195	**Call**

HALO GRAPHICS SYSTEM *Multi-Board Graphics Library*

The premier graphics library that got the ball rolling for PC-based graphics and has grown so omnipotent that it supports over 25 graphics boards — including IBM's EGA and Nr. 9 Revolution's hi-res series — and has a multitude of mouse and printer drivers. All that in each box. Separate C versions for Lattice, M'soft, Aztec, CI86. What does Multi-Halo do? A down to the last pixel graphics library plus functions to reset drivers so distributed program can run on anything. Wonderful value for single license. Costly royalties though for redistribution. Specify: S0315 & Language. List: **$300.** We: **$219.** With Dr. Halo II, a free-standing "paint": List: **$440,** Us: **$299.**

WINDOWS for C/WINDOWS for DATA *Microsoft Windows™ and TopView™ Compatible*

Windows for C™is a library of over 80 functions to add the pizazz and practicality of window partitioning to your application. Unlimited windows, each defined in a C structure for easy reference throughout your program, can be made either to pop up or permanently overwrite the screen. Routines will scroll and highlight lists with arrow keys, will read and scroll ASCII files vertically and horizontally in windows, and even write to memory-loaded files off the screen.

Logical treatment of video attributes permits unchanged programs to run on color or monochrome. Colors of windows are set individually.

All functions are in separate modules; only those used are linked. Only buffers holding on-screen or temporarily obscured windows occupy RAM; others released dynamically. Best overall rating and fastest display in Bill Hunt's 7/85 *Tech Journal* review of five windowing products.

Windows for Data comprises all of Windows for C but takes in data through the windows as well. At the high level a single function lets you specify prompt string, field length, data type, screen location, picture, target variable, then sets lesser functions scurrying to get and process a user's input. There are utilities to get system date and time, mess with strings, create your own masks for fields.

Field options can require entry, prevent entry, permit insert or overtype, beeping on invalid or overflow keystrokes, and attachment of field-specific help messages and functions you want called to display messages or validate entries. And you decide which keys will clear a field, jump to the next or prior, quit, etc. Options diverse enough that a set of "fields" can be made to behave like a Lotus™ menu.

Specify Compiler:		List:	PC Brand:
T0100	Windows for C	$195	$149
T0150	Windows for Data	$295	$259

30-DAY MONEY-BACK GUARANTEE

We refund the purchase price of any product returned within 30 days in entirely resalable condition. **You can even try out programs themselves** if product code begins with E, T, or L through N — even if it means breaking the disk seal. Some developers do pose limits, so for products beginning with other letters, opening sealed disks constitutes acceptance. But you can at least review the manual. There's just nothing stopping your buying from PC Brand.

MICROSOFT C 4.0 *A Great C Battle Rages and You're Winning*

As the dreadnaughts pound each other with ever heavier ordnance, today's programmers reap the spoils of this war. Bundling a source debugger and a "make", and sporting a "huge" memory model permitting single data objects larger than 64k, the Microsoft C compiler has jumped a full version number to 4.0. But what's really impressive are the benchmarks reported in Dr. Dobb's (8/86) encyclopaedic survey of 17 C compilers. Microsoft's and IBM's C (licensed from Microsoft) run away with the contest winning 11 of 27 benchmarks.

The CodeView™ debugger, free for a limited time, uses windows to show everything on one screen: source alongside disassembled object, variables, stack and registers. Drop down windows—use a mouse if you like—obviate learning of commands. "A source-level debugger that puts the rest to shame" (Dobb's),

Microsoft C now has five memory models for code and data, plus non-library support for another thirteen, and boasts alternate math packages for speed versus accuracy, with or without 8087/80287 chips.

Both linker and library manager are part of the package, as is the "make", a UNIX™ name for a smart batch program which knows to expend minimum effort to rebuild any size of project by compiling and assembling only elements affected by new or changed modules.

It is reportedly used by Lotus, Ashton-Tate and, fittingly, Microsoft itself to develop Windows. Dobb's calls it "the best MS-DOS C development environment value today [for] virtually any kind of program conceivable." 320k suggested.

Ask for:	List:	PC Brand:
G0500	$450	$295

C-TREE & R-TREE *B-Tree File Manager Now Has Report Generator*

c-tree: The only major b-tree file manager that comes with built-in network support rather than a costly separate version, c-treeTM is sturdy code that has weathered many seasons of prolonged and widespread use. It comes in C source, so you can modify it to fit a special case; permits any number of keys for a data file—alpha, numeric, even floating point; handles files with varied record lengths; and multiple keys in one index file. In short, you get the works—and there are no royalties.

C-tree's design splits nodes to allow any number of users to access an index file simultaneously even when updates are in progress. So multi-user configurations and adaptation to networks are possible. Record-locking routines are provided for DOS 3.x, UNIX, XENIX.

C-tree can travel. Tests in many environments prove that c-tree gives your application a ticket to anywhere.

r-tree: thousands of c-tree users (and you) now have a suddenly expanded ability to produce ad hoc reports from files maintained by c-tree (v.4.1E or later), side-stepping the elaborate C coding usually entailed.

Once you link a description of the field characteristics of the data files to the r-tree library, you are free to use an ordinary text editor to write any number of report scripts with no further C coding. Reports can access data in several files, select to match complex searches, join the findings into new logical records, sort them, calculate new fields and columns, tabulate by any number of control breaks. Your script files show visual representations of report images—not just rows and columns, but customized layouts.

r-treeTM comes in source code and is designed for the same portability c-tree brings you. Fits any compiler.

	List:	PC Brand:
c-tree: F0660	$395	$329
r-tree: F0665	$295	$245
Combined: F0664	$650	$541

dBC *Lattice Library Maintains dBASE Compatible Files With the Power and Speed of C*

dBC™ links C to dBASE. It creates and maintains files and their indexes which exactly replicate dBASE file design. So dBASE can read and update them. And the reverse. dBC can use any files created by dBASE. Now C and dBASE can operate on the same data bases interchangeably.

That opens up the widespread culture of dBASE installations to exploitation by C programmers. Tap that market, avoid the resident dBASE language, and gain the advantages of C with this single product.

dBC's functions parallel all dBASE's file handling commands, many decomposed to give closer control. Each backed by demo source files on disk.

Use dBC for custom work for clients, or on its own. It's a complete ISAM file manager for C whether or not dBASE will be used in tandem, supports all four memory models, and can have sixteen index and data files open. Big discount to buyers of both dBASE II and III versions. Specify Lattice, Microsoft 3.x, or DeSmet.

Versions:		List:	PC Brand:
L00II	For dBASE II	$250	$195
LCCII	With Source	$500	$390
L0III	For dBASE III	$250	$195
LCIII	With Source	$500	$390

PANEL *Feature-Laden Screen Design Tool*

Writing your own screenware can blow completion dates and profits. Panel™ works with you interactively to set up foolproof screen displays and data entry forms rapidly. Output is C source code.

Not just single plane: layer your screen designs with up to ten overlapping images: Background pop-up lists, help boxes, and alternate input fields.

Panel builds in a user interface for keystroke movement within and between fields, supplies validation routines for checking user field entries. Diverse attributes may be selected for any field — size, data type, color, conversion of input to upper case; clearance of existing data when new entry is started; masks for standard formats (eg, dates); phrases which fill in when their first letter is typed; multiple-choice lists from which to choose by cursoring a highlighted bar. Fields may be multi-lined and scrolled if larger than the screen space allotted them. Specify: S0400 & Compiler. List: **$295**, Us: **$229**

WHY US?

- Shipped 24 hours or sooner
- Latest versions of all products
- Everything listed is in stock
- No surcharge for credit card or COD purchase. **NEED TERMS?** On-the-spot credit to most public companies, government, educational, medical institutions. **LOOKING FOR SOMETHING?** We can get many more products — just ask! **NEED MORE INFO?** Our Catalog and literature cover just about everything.

For Orders, Literature, or Catalogs, Call Us at...

800 PC-BRAND

That's (800) 722-7263. In NY State call (212) 242-3600

PC Brand, 150 5th Ave., New York, N.Y. 10011-4311

Telex: 667962 (SOFT COMM NYK)

©1987 PC BRAND

Prices, terms, and specifications subject to change without notice.

TODAY's TOP QUALITY AIDS TO PROGRAMMING PRODUCTIVITY

GREENLEAF *Bountiful Harvest* FUNCTIONS

C source, assembler source, and binary libraries of 225 functions for many compilers. Emphasizes tight functional groupings to minimize loading code which your application may never use. Manual helps select functions, bulletin board, too.

A sampling: *DOS* extensions for file and directory manipulation; *Screen:* to select mode, page, monochrome or color, palette; cursor shape, positioning; clearing and scrolling; pixel get and put; read light pen. *Strings:* Center, justify, etc.; efficient list operations which add, delete, sort string pointers for top speed. *Other:* graphics character primitives, keyboard status, function key assignment, time/date, read registers and memory size, peek and poke. Mature best-seller. Specify: S0770 & Compiler. List: $185, Here: $139

GREENLEAF *Hello World* COMMUNICATIONS

Want your application to communicate with other users or remote date bases by asynchronous communications built right into your C programs! Even if you don't need it now, that's a skill to have at the ready!

120 functions *and demo programs in both C and assembler source code* set up separate transmit and receive ring buffers for up to 16 simultaneous channels. Interrupt driven so you can halt an incoming record, display it, file it, let the user edit it, then continue. Goodbye separate communications software.

Supports up to 9600 baud, ASCII or binary, any parity or word length, 8250 UARTs, Xon/Xoff and Xmodem, WideTrack receive. Specify: S0750 & Compiler. List: $185, Us: $139

INTERACTIVE-C

Compiler-Compatible Interpreter, Editor, Debugger

Earlier C interpreters were miraculous compromises. Interactive-C shows how far C interpreters have come. More than an interpreter, Interactive-C is a fully-integrated development environment: a complete K&R interpreter bound tightly to its own editor and debugger.

Slice through programming projects like a hot knife through butter. Extensive error-checking insures immediate detection of program misbehavior. State of the art debugging tools include breakpoints, watchvalues, several stepping options and interactive viewing and modification of variables. An Interactive-C exclusive lets you interrupt to edit and "continue" from where you left off. Eliminates plodding replays of already debugged code—the ball and chain of other interpreters.

Operate Interactive-C using adjustable edit, command, and status windows. Toggle a second screen showing only your program's output—never any crowded intermixing. Or, boost productivity with twin CRTs. Load object code of functions you have already compiled. Or of commercial libraries. Interactive-C has immediate mode, syntax checking both as you type and run, and cursor positioning precisely pointing at an error, not possible with incremental or pseudo-compilers which leave source code behind.

100% compiler compatible—right down to header files and library calls. Port programs between Interactive-C and your compiler with no modifications whatever—not even tricky areas of dynamic memory allocation and I/O.

Specify:	List:	PC Brand:
E950 & Compiler	$249	$219

DAN BRICKLIN'S DEMO PROGRAM

Storyboard Your Program

The Legendary One has created Metaphor Two when the rest of us are still on Zero. Dan's first was the original electronic spreadsheet (VisiCalc™). This one is for programmers.

Words don't express program ideas because programs are screens! Dan's Demo creates slide shows. Create a screen — a snapshot of your planned product as it runs. Anything goes: words, borders, box rules, inverse and underlining of monochrome, fore- and background color. Copy this "slide" to an empty screen. Change it a little, to show the next instant of run-time. Do it again. Presto, a whole slide show of your program in action.

All 250 characters and attributes are available from scrollable lists which pop to the screen. All commands are layered in Lotus-style pop-up menus. Frequent choices mapped to function keys as well.

80x25 character mode, not bit-mapped.

Screen areas can be blocked for cut and paste or filled with color or characters, even blink. Slides can overlay on others, can be shuffled, deleted. Slides can proceed at time intervals or branch anywhere in the slide sequence depending on user keyhits.

Invaluable to prototype the program you are about to write, to position the labels, choose the color decor, smoothe out the keystroke interface. Or load the "capture" utility and snapshot the screens of any running program for an instant slide show.

Each copy entitles you to redistribute fifty of the slide projector program that runs demos. Plain manual, no binder keeps price of big product small. "Might . . . become *the* essential tool in . . .user interface prototyping," *Tech Journal.* Ask for: N0100. List: $75 US: $69

BASTOC OPTIMIZES!

Translates BASIC Into C

For a trifling price, BASTOC™ moves truckloads of BASIC code over to C. It's a translator which takes in Microsoft Extended BASIC and emits pure K&R C for Lattice 3.0. It will optionally convert your program into a single monolithic C function or decompose it into separate functions, one for each GOSUB label.

Version 2's optimization dramatically reduces execution time. Converts to integers those variables in BASIC programs which do not need floating point. Where BASIC uses full assignment statements to increment counters, BASTOC converts to C's compact form. Strings dynamically allocated ridding your application of BASIC's catatonic halts for garbage collection. Creates structure of even convoluted BASIC code. Huge worksaver.

Ask for:	List:	PC Brand:
S0375	$495	$399

Shopping List for the Power Workbench

	LIST	US
ASSEMBLERS & DEBUGGERS		
Advanced Trace-86 *Morgan, ASM Interpreter*	175	119
Codesmith-86 *Dubugger by Visual Age*	145	99
CSD Debugger *C source level by Mark Williams*	75	55
C-Sprite Debugger *by Lattice, source level*	175	139
Microsoft Macro Assembler *with Utilities*	150	109
PASM86 *by Phoenix, Macro Assembler*	195	125
Periscope I Debugger *Data Base Decisions*	295	235
Periscope II *Data Base Decisions*	129	99
Periscope II-X *software only*	115	74
Pfix86 Plus *by Phoenix, Symbolic Debugger*	395	235
BASIC LANGUAGE		
BetterBASIC *Summit Software*	195	165
8087 Math Support	99	85
Btrieve Interface	99	85
Run-Time Module	250	225
Microsoft BASIC Interpreter *for XENIX*	350	295
Microsoft QuickBASIC Compiler *full BASICA*	99	79
Professional BASIC *by Morgan*	99	69
True BASIC *True BASIC Inc*	150	99
Run Time Module	150	99
C COMPILERS		
C-86 Compiler *Computer Innovations*	395	289
Lattice C Compiler *from Lattice*	500	299
Let's C Compiler *by Mark Williams*	75	55
with CSD Source Level Debugger	125	90
MWC-86: Mark Williams C Development	495	369
Microsoft C Compiler *4.0*	450	295
C INTERPRETERS		
C-Terp *by Gimpel Software*	300	249
Instant C *by Rational Systems*	500	395
Interactive-C *by IMPACC with debugging*	249	219
RUN/C Professional *from Lifeboat*	250	185
RUN/C *without Loadable Libraries*	120	109
TEXT EDITORS		
Brief *from Solution Systems*	195	Call
Edix *by Emerging Tech...Multi-screen*	195	159
Epsilon *by Lugaru Software, like EMACS*	195	149
FirsTime *by Spruce Technology, C syntax*	295	229
Kedit *by Mansfield, similar to Xedit*	125	99
LSE, the Lattice Screen Editor *Multi Window*	125	100
Pmate *by Phoenix, with Macros*	195	115
Text Management Utilities *Grep, splat, diff, etc.*	120	100
Vedit *by Compuview*	150	99
Vedit Plus *by Compuview*	185	129
FILE MANAGERS		
Btrieve *by Softcraft, no royalties*	250	195
Btrieve Network *by Softcraft*	595	465
C-Tree *by FairCom - no royalties, source*	395	329
R-Tree *by FairCom-Report Generator*	295	245
C-Tree & R-Tree Combo *by FairCom*	650	541
dBC...*from Lattice...maintains DBASE files*	250	195
with source	500	390
dBC III Plus...*supports multi-user DBASE*	750	595
with source	1500	1185
dbVista *single user DBMS by Raima*	195	139
dbVista *multi-user DBMS*	495	399
Opt-Tech Sort *Can sort Btrieve files*	149	105
SCREEN DESIGN		
Curses *by Lattice, UNIX screen designer*	125	99
with Source	250	199
Greenleaf Data Windows.....*New*	225	169
with source	395	297
source purchased later	225	169
On-Line Help *from Opt-Tech Data*	149	105
Panel *by Roundhill, no royalties*	295	229
View Manager for C *by Blaise*	275	164
Vitamin C *by Creative Programming*	225	198
VC Screen *by Creative Programming*	100	81
Windows for C *Vermont Creative Software*	195	149
Windows for Data *includes Windows for C*	295	259
ZView *Data Management Consultants*	245	175
GRAPHICS		
Essential Graphics *by Essential, no royalties*	250	210
GSS Graphics Development Toolkit	495	375
GSS Kernel System *by Graphic Software*	495	375
GSS Metafile Interpreter	295	235
GSS Plotting System	495	375
Halo *by Media Cybernetics*	300	219
with **Dr. Halo II**	440	299
Halo for Microsoft *includes all fonts*	595	434
COMMUNICATIONS		
Asynch Manager *by Blaise, for C or Pascal*	175	117
Greenleaf Communications *by Greenleaf*	185	139
PTel *by Phoenix, Binary File Communicator*	195	115
UTILITY LIBRARIES		
Blaise C Tools Plus	175	117
Blaise C Tools	125	84
Blaise C Tools 2	100	67
C Food Smorgasbord *by Lattice*	150	109
C Utility Library *by Essential, 300 functions*	185	139
Greenleaf Functions *by Greenleaf Software*	185	139
PforCe *by Phoenix, vast library*	395	235
Software Horizons *Packages*	Var	Call
TopView Tool Basket *by Lattice, source avail*	250	199
DEVELOPMENT TOOLS		
Code Sifter *by David Smith Software, Profiler*	119	89
C-Worthy *by Custom Design Software*	295	269
C-Worthy for Network *Menus, help, errors*	495	449
Dan Bricklin's Demo Program *Prototyper*	75	69
LMK from Lattice *by Lattice, "make" like UNIX*	195	149
Microsoft Window Development Toolkit	500	365
PC-Lint *by Gimpel Software, after UNIX's "lint"*	139	125
PFinish *by Phoenix, EXE performance analyzer*	395	235
Plink86 Plus *Utilizes memory for overlays*	495	325
Pmaker *by Phoenix, like UNIX "make"*	125	85
Pre-C *by Phoenix, UNIX "lint"-alike*	295	155
Pfantasy Pac *six Phoenix products*	1295	875
OTHER TOOLS		
BASTOC *by JMI, convert BASIC to C*	495	399
BASIC-C *BASIC's functions added to C*	175	139
The HAMMER *by OES Systems*	195	139
Report Option *by Softcraft, Btrieve Report Gen.*	145	128
Xtrieve *by Softcraft, Query Utility for Btrieve*	245	220
FORTRAN COMPILERS & UTILITIES		
ACS Time Series *by Alpha Computer Service*	495	405
Forlib- Plus *by Alpha Computer Service*	70	45
Microsoft FORTRAN *Links with Microsoft C*	450	281
Microsoft FORTRAN *for XENIX*	695	546
RM/FORTRAN *by Ryan McFarland*	595	Call
Scientific Subroutine Package *by Alpha*	295	239
The Statistician *by Alpha Computer*	295	239
Strings & Things *by Alpha Computer*	70	45
OTHER LANGUAGES & UTILITIES		
Microsoft COBOL Compiler	700	499
Microsoft COBOL Compiler *for XENIX*	995	795
Microsoft COBOL Tools *with Source Debugger*	350	259
Microsoft COBOL Tools *for XENIX*	450	333
Microsoft Lisp *New Common Lisp*	250	189
Microsoft MuMath *includes MuSimp*	300	199
Microsoft Pascal Compiler *Links with M'soft C.*	300	199
Microsoft Pascal Compiler *for XENIX*	695	546
PDisk *Phoenix's new disk manager*	195	125
RM/COBOL *by Ryan-McFarland*	950	Call
RM/COBOL 8X *ANSI 85 COBOL*	1250	Call
Source Print...*source code formatter*	75	60
Tree Diagrammer...*source code diagrammer*	55	45
Help/Control *by MDS...123 style Help*	125	109

PRICED TO SAVE YOU MONEY, SHIPPED FAST ANYWHERE.

BEST PRICES YET!

RYAN-McFARLAND FORTRAN

NEW!

A Mighty Fortress Is Their FORTRAN

Picking over features of rival products is not necessary if FORTRAN is your need, still the citadel of scientific and engineering work. Ryan-McFarland has left the competition battering at the gates.

RM/FORTRAN™ is a complete implementation of FORTRAN-77 (ANSI X3.9-1978), the only PC FORTRAN certified by the General Services Administration at the highest test level. The reason: it's a big mainframe compiler moved to PCs, with the bonus that mainframe and mini applications can wander between environments.

Now, on your PC, you can develop large applications, with programs up to 640k (bigger using overlays), arrays over 64k, and using a long list of VS, VAX and FORTRAN-66 extensions you may have grown fond of — long symbolic names, "include", IRT bit functions — because R-M has left out nothing.

But what really sets RM/FORTRAN apart is optimization. The compiler reduces the number of instructions to the minimum which will actually execute, and even takes advantage of each processor's features to deliver lightning-fast object code. It runs 30%-40% faster than Microsoft 3.2, and could make your mainframe not worth the trouble.

Comes with an interactive symbolic debugger like that accompanying IBM VS FORTRAN, Plink86 subset, has a cross reference compile option, supports assembler and C subroutine calls, IEEE floating point, 8087 and 80287 chips.

"Compiler's documentation, ease of use, speed of execution, and debugger facilities place it first for recommendation" said the *Tech Journal* (10/85).

R-M has been writing FORTRAN compilers for IBM, DEC, etc. for 20 years. There is no greater expert.

Ask for:	List:	PC Brand:
I0300	$595	**Call**

SUPER SOURCE!

Aldebaran's Source Print

Structure is dandy but, face it, hard to find your way around in. Source Print's options can print your programs adding page numbers and headings, those mysterious line numbers your compiler refers to, vertical lines connecting "begins" and "ends" and curly brace structures, however long or nested, indents automatically so you needn't bother, and throws in a table of contents and cross-reference index for good measure! Leaves a truly professional audit trail. "Occasionally a utility comes along that makes a programmer's life much easier. Source Print is such a program" *PC Magazine*, 9/86. Ask for H0005. List: **$75**, Ours: **$60**.

...and Tree Diagrammer

Prints an organization chart of your program's structure showing the hierarchy of function, procedure, and subroutine calls. Shows at a glance what routines call each other for clearer debugging. Easy-to-use menu with point-and-shoot file selection. Ask for: H0007, **$55**, Ours: **$45.**

ZVIEW

Screen Design Aid

A complete package for screen design with full windows management as a bonus! Easy creation of screens with complex validation, such as range checking or required/optional data. Powerful Screen Paint utility for creating or editing applications screens. Built in security levels, set at run-time, control read or read/write access by field or screen. Automatic help screen processing for run-time aid per field or screen. Applications regain control during field tabbing, allowing run-time on-screen transaction processing or flow control. Run-time functions include Screen Read and Write with automatic transparent data conversion from screen image to data storage, Field Editing, Help Screen Processing, even a capability to change any field characteristic at run-time, plus Window Push Pop and Scroll. Versions for Lattice, Microsoft and Aztec C. Automatic free updates to registered users. No run-time royalties. List: **$245** PC Brand: **$175**

LATTICE C COMPILER

Major Upgrades to the Best Selling C Compiler

Lattice now embraces key UNIX™ enhancements which have entered the language since K&R: void functions returning no value, enumerated data types to assign stepped values to variables, data passing between structures by assignment.

The greatly expanded libraries (325 functions!) enable the file sharing and record locking provisions of DOS 3.1, provide a full complement of transcendentals, and a host of utilities to mimic the UNIX and XENIX™ environments.

Lattice 3.0 defaults to the ANSI proposed standard when you need strict adherence, but command line options restore leniency. And it adopts ANSI checking of external function arguments by data type to kill bug swarms when modules join up at link time.

Lattice now delivers smaller .EXE files, boasts very fast link times and a more efficient aliasing algorithm. New options generate code to use 80186 and 80286 features; 8087 of course sensed and utilized. Lattice has enjoyed pre-eminence so long that developers have created far more snap-on tools for Lattice C than any other compiler. William Hunt's *PC Tech Journal* review of 12 compilers awarded Lattice the only "very good" rating for add-on library availability.

Ask for:	List:	PC Brand:
S0100	$500	$299

FOREIGN POLICY

We ship anywhere. *Phone or Telex your order. Credit cards: We need card number, expiry date, name and address of card. Or wire funds to PC BRAND, c/o Chemical Bank, 126 East 86th St., NY NY 10028, Account No: 034-016058.* ***We'll ship immediately*** *and confirm by Telex if you provide number.*

BLAISE *C Tools Plus*

Nothing pays you back quicker than a function library, and Blaise has long been known as a great one. C Tools Plus, the top of the line, now has over 200 functions. Mature, tight, predominantly in C, they isolate hardware dependence, come in source and library, with no royalty. The rundown:

Screen Handling: either via BIOS or direct to video adapter; supports EGA, 43-line mode and multiple pages, twin monitors. Windows: any number, stackable, writable, wordwrapable, and erasable. Interrupts: well known for interrupt service routines in C, from which you can now access DOS functions. Directories: Create, change, or search directories, rename files, get and change their date/times. Memory: control DOS memory allocation, load a "child" process alongside your program, even create memory-resident programs—and remove them. Strings: international money, dates and character sets, plus superfunctions to perform several tasks with a single call. General: BIOS and DOS gates for direct access, memory copy, speaker control, it goes on. Our complete Blaise line:

	List:	PC Brand:
C Tools Plus	$175	$117
C Tools	$125	$ 84
C Tools 2	$100	$ 67
Asynch Manager	$175	$117
View Manager	$275	$164

GSS GRAPHICS SYSTEM

ANSI CGI STANDARD!

PRICES CUT!

Leave the Device Driving to GSS

GSS™ has reconfigured two components of its comprehensive graphics tools to conform with the ANSI Computer Graphics Interface (CGI) standard.

At the heart of the system is the Development Toolkit which contains all language interfaces and device drivers for keyboards, mice, joysticks, tablets, printers, plotters, cameras, and more. Drivers house management of vector graphics (plotters) and bitmaps used by raster input devices (scanners) to insulate the application program from concern for device idiosyncracy. No one else has implemented CGI that way. It means your programming remains generic; just switch drivers and the same program will drive a different device.

GSS Kernel™ conforms to level 2b of ANSI's Graphical Kernel System (GKS) and contains all its needed drivers and language bindings. Kernel has macro level tools to draw and color an object, store the sequential instructions, and recreate the object on its own, as well as segment it, transform it, etc. So powerful, a single command may represent several score lower level statements.

Plotting has the equivalent GKS tools for graph and chart generation and their captioning: hand it apples and oranges, say "pie", and it bakes the numbers into a digestible display for screen or plotters.

Kernel and Plotting have tools to convert images they create to ANSI Computer Graphics Metafiles (CGMs), a tokenized standard for storing every form of graphic image as data. The Metafile Interpreter reads the contents of a CGM and interprets it with full CGI capability for re-creation on various devices.

Quality software? IBM thinks so. They sell the GSS series under their own label.

Unit royalties and annual fees have been instituted for redistribution. Needs 256k.

Ask for:	List:	PC Brand:
GS010 CGI Dvlpmt Toolkit	$495	$375
GS020 Kernel System	$495	$375
GS025 Kernel for IBM RT	$795	$645
GS030 Plotting System	$495	$375
GS040 Metafile Interpreter	$295	$235

BTRIEVE

ASK ABOUT XTRIEVE & RTRIEVE

Queen B-tree File Manager Abdicates Royalties

There's no longer a tithe to incorporate Btrieve™ in applications, a welcome proclamation if royalties would ruin your profit margins. Btrieve takes complete charge of all file creation, indexing, reading, writing, insertion, deletion, space recapture, forward and backward searching. It builds function call "commands" right into the language you use: interfaces to C, Pascal, BASIC, and COBOL, with sample programs in all four, come with each copy.

Btrieve has mainframe specifications! Its balanced-tree indexing scheme finds any key in a million in four or less accesses. Files may have up to 24 indexes; fixed record length to 4090 characters; indexes up to 255 characters; files of 4 billion bytes. Can even extend a file across two drives — even two hard disks!

Version 4.x speeds DOS interaction for large multiply-keyed files; enables variable length records of virtually any length; verifies accuracy (optionally) with read after write, useful in gritty environments; offers password and data encryption.

There's also Xtrieve, for Btrieve file inquiry and data manipulation, and Rtrieve for report writing. All three in versions for any network that supports the MS-DOS 3.1 file sharing function.

Ask for:	List:	PC Brand:
S0650	$250	$195
S0652 Network Version	$595	$465

TERMS AND CONDITIONS OF SALE

Licenses: Each price is for a license to use a product on a single computer and does not constitute its ownership. We will inquire for you about site licenses. Except as otherwise indicated or where "#" follows the Product Code, products may be used to create programs for distribution without royalty payments or additional licenses, provided said programs do not substantially replicate the products themselves.

Compatibility: PC BRAND's standard products are designed to operate with the IBM® PC, XT or AT under PC-DOS and require no more than 128k of RAM unless indicated. Non IBM machines using MS-DOS: contact manufacturer about precise differences so we can advise.

Returns: See box page one. Defective parts will be replaced. Please call for authorization to return a product for refund.

Payment: We honor MasterCard, Visa, American Express (no surcharge), checks in advance, or funds wired to PC Brand, c/o Chemical Bank, 126 East 86 St., New York, Account 034-016058. COD (U.S. only) for cash, money order, certified check (no fee). NY State, add sales tax. Purchase orders accepted from larger corporations and institutions at our discretion if you agree to net 30 days plus 2% a month late penalty thereafter.

Shipping & Handling: U.S.: UPS Surface: 1st product $6, each add'l $3. UPS 2nd Day Air: 1st product $10, each add'l $4.50. UPS Next Day Air or Federal Express 1-2 Day Air: 1st product $18, each add'l $6. FedEx Next Day 10 AM: 1st product $28, each add'l $7. International: Charges vary by destination and carrier. $10 per shipping container for export forms. Air parcel post at your risk beyond collected insurable amount.

For Orders, Literature, or Catalogs, Call Us at...

800 PC-BRAND

That's (800) 722-7263. In NY State call (212) 242-3600

PC Brand, 150 5th Ave., New York, N.Y. 10011-4311

Telex: 667962 (SOFT COMM NYK)

©1987 PC BRAND

Prices, terms, and specifications subject to change without notice.

Dialects of dBASE



TED MIRECKI

Ashton-Tate's popular dBASE III has inspired the creation of compilers to enhance the language aspect of this database manager. Three quality products are considered here.

Although never formally defined as a programming language, dBASE III has all the earmarks of one. In terms of popularity it is more successful than many languages with blue-blooded pedigrees, written in Backus-Naur notation. Thus, it is not surprising that dBASE III has acquired that accoutrement of a true language, the compiler. Although none is available from Ashton-Tate, others have filled the gap. The three reviewed here are: Foxbase+ by Fox Software, Clipper by Nantucket Software, and Quicksilver by WordTech Systems.

The lure of a compiler, of course, is the promise of execution speed that cannot be matched by an interpreter. Users familiar with the 10- to 20-fold improvement that a BASIC compiler gives over the BASICA interpreter might expect a similar improvement from a dBASE compiler. But in the case of a database manager, the gain from compilation is not as great as that for a compute-intensive language such as BASIC. The main reason is that the database manager spends relatively more time reading disk files than reading the source code. If in a particular process the interpreter spends, say, 50 percent of its time waiting for disk I/O, the overall speed of the process cannot be speeded up by compilation by more than a factor of 2, no matter how much faster the compiled code is on the other 50 percent of the processing.

Another reason for the relatively small difference between compiled and interpreted dBASE code is the inherent efficiency of the dBASE language. A single statement, once interpreted, can trigger a massive amount of processing without further intervention from the interpreter. For example, when performing a sort, the interpreter need parse only the SORT statement itself, then turn control over to a canned routine. The time spent parsing and recog-



COMPUTER GRAPHIC • DOV JACOBSON

nizing that one statement is insignificant compared to the time spent executing the sort routine. Assuming that this routine is already executed from native code, the time for completing the sort would not change noticeably even if the time of interpretation could be totally eliminated. In fact, if a compiler implements a less efficient sort algorithm than the interpreter, the total elapsed time may well increase after compilation—as was observed in several of the tests performed for this article.

This does not mean that dBASE compilers are not useful. Even with the fourth-generation power of the language, many operations still must be coded in detail. Screen display, input validation, and calculation with memory variables can all benefit from compilation. In particular, the user will experience a perceptible improvement in response time if the processing of screen I/O can be speeded up.

But in the world of commercially distributed applications, a compiler addresses two important issues besides speed. The first is source code security. Whether it compiles to native code or to some intermediate form of pseudocode, a compiler protects the programmer's methods and algorithms from unintended viewing and prevents errant (or even beneficial) changes.

The other issue is the cost of licensing end users. When source code is distributed, every copy of an application requires a copy of dBASE III to execute it. This cost, when added to the cost of the application itself, may price the product out of reach of many potential clients. Even in a corporate environment, where a central group develops programs for distribution throughout the organization, providing a copy of dBASE for every machine that needs to run a dBASE program may not be economically justifiable.

A compiler, on the other hand, is typically sold with a license for unlimited distribution of end-user applications. Each copy of a compiler entitles the developer to sell an unlimited number of copies of a program, and each such copy runs without needing a copy of dBASE or of the compiler. If the finished application needs to be executed by a runtime system, such a system may also be obtained with an unlimited distribution license. Therefore, despite the relatively high initial cost of a compiler, a major consideration in using one is the cost savings from buying a copy of the compiler for each development machine, as opposed to buying a copy of dBASE for each end user system.

The design of a dBASE compiler involves several choices. The first is whether to produce stand-alone native code or semicompiled pseudocode. As will be shown, the former does not necessarily yield a performance advantage over the latter.

Another choice the designer makes is which mode of dBASE to support. Ashton-Tate's product is really meant to perform two functions. One is that of an interactive data entry and query environment; the other that of a traditional programming language. The dBASE III programming language functions are used far more than the interactive data entry and query functions. Many users execute applications, preprogrammed by others, without an awareness of the capabilities of the language that are not used in the particular application. Because of its prevalence and because this matches the traditional usage of other compiled languages, dBASE compilers typically have supported only this mode of operation.

But increasingly, sophisticated end users are discovering the full power of dBASE III and are beginning to use it in the interactive mode. They are also writing programs, but these are usually of an ad hoc, informal nature rather than the polished efforts of the professional programmer. The situation with these dBASE users is similar to that of the expert spreadsheet users, in which macro programs are written to support a primarily interactive mode of operation. Here, too, a compiler can help.

Both modes of dBASE use are covered among the three products that are reviewed here. Clipper and Quicksilver address only the preprogrammed mode of dBASE, while Foxbase+ attempts to improve on all areas in which dBASE can be used, including interactive processing. The compilers' features are compared in table 1. In that table, each compiler's memory requirement is the minimum free memory above DOS and other resident programs, that is, what is reported as memory available by CHKDSK. The compiler's total file size includes the compiler itself, the linker (if supplied), the debugger, and all libraries and object code modules. Stand-alone utilities and sample programs are excluded. The following is a look, first at each compiler's individual installation, operation, and documentation, then at the three as they compare head-to-head in various aspects of their implementation and performance.

TABLE 1: *Compiler Features*

	FOX	NANTUCKET	WORDTECH
PRODUCT	Foxbase+	Clipper	Quicksilver
VERSION	1.2	Autumn 86	1.0c
PRICE	$395	$695	$599
NETWORK CAPABILITY	$995[a]	Included	Add. $99
NATIVE/INTERMEDIATE CODE	Int.	Native	Both
LINK STEP NEEDED	○	●	Two
STANDARD DOS LINKER	N/A	●	● 1st step ○ 2nd step
LINKER SUPPLIED	N/A	●	● 1st step ○ 2nd step
USE dBASE INDEX FILES	○	○	●
SIZE			
Number of disks	2	3	8
Number of files	4	9	25
Total file size	632KB	461KB	1,250KB
SYSTEM REQUIREMENTS			
Free memory	375KB	200KB	256KB
Earliest DOS version	2.0	2.0	3.1
Uses 8087	●	●	○

● = *Yes* ○ = *No*
N/A = Not applicable
[a] *Total cost for version with network capability.*

Clipper and Foxbase+ produce native and intermediate code, respectively. WordTech's Quicksilver attempts to provide the best of both worlds by producing both.

Fox Software. Foxbase+ is the closest of the three compilers to dBASE, and it is, in concept, different from the other products reviewed. Besides being a compiler, or at least a pseudocompiler, it is also a full dBASE III work-alike, implementing almost all of the interactive features of the Ashton-Tate product. Although not a true compiler, it is included in this comparison for two reasons: it implements the most dBASE features, and it far surpasses the others in speed of both development and execution. As amazing as it seems, Foxbase+ pseudocode runs faster than the native code of either Clipper or Quicksilver, and its file operations match or surpass dBASE III Plus in speed. To keep the comparison meaningful, the emphasis will be on how Foxbase+ compiles and runs prewritten programs, not how closely its interactive features mimic the corresponding features of dBASE III. Suffice it to say that the capabilities and user interface of Foxbase+ are close enough to those of dBASE III Plus that for all practical purposes, the two are functionally identical. The plus sign (+) on the product's name identifies this version as compatible with dBASE III; the original Foxbase without the + is a dBASE II work-alike and is still available.

The installation of Foxbase+ is somewhat similar to that of the latest unprotected version of dBASE III Plus. Although the distribution disks are not copy protected, the main Foxbase+ file cannot be executed until it is activated with a serial number and password. The product comes with two passwords: one in a sealed envelope, the other open. The latter activates the demonstration mode, which limits Foxbase+ to working with databases of no more than 120 records. The user may test the product in this form and return it for a refund if it proves unsatisfactory, provided that the password that activates the production version remains in its sealed envelope. If the user decides to keep the product, he opens that envelope and repeats the activation procedure with the new password found there. All files, however, may be backed up both before and after activation.

Installation is completed by copying the activated main file and its overlays and other auxiliary files to working disks or directories; a batch file that automates this function is provided. Running Foxbase+ from diskettes, although somewhat cumbersome, is quite possible and is much more practical than running the other compilers or dBASE III itself on such a system.

The Foxbase+ compiler produces intermediate pseudocode in files with a .FOX extension. It can process a series of source files at one invocation; the list of files must be given on the command line that invokes the compiler. Each input file produces a separate .FOX file. The compiler assumes no default extension for source files, so the .PRG extension on those files must be specified for each file name. However, as compensation, the compiler allows standard DOS wild cards in the input file names, and processes all source files that match the specification. No link step is required.

The pseudocode is executed by the main Foxbase+ program, which is a full interactive dBASE III work-alike. Its user interface is uncannily similar to that of dBASE, and, as is the case in dBASE, that interface can be tailored by means of a CONFIG.FX file that performs the same function at start-up as the CONFIG.DB file does for dBASE. In fact, both products can be configured by the same file, because if Foxbase+ cannot find a CONFIG.FX file, it will instead use a CONFIG.DB file, if one exists.

Actually, interactive Foxbase+ can run either precompiled .FOX files or .PRG source files. When Foxbase+ needs to load a program or procedure file, it first searches for a .FOX file; if one is not found, it loads the .PRG file and compiles it on the fly. In either case, the execution time is the same because the program is executed as pseudocode. So why precompile? Because the load time is greater for .PRG than for .FOX files, and the difference is especially noticeable for large programs loaded from within other programs.

As further evidence of its close compatibility with dBASE III, Foxbase+ provides a functionally identical full-screen editor, and through the CONFIG file, the user also can specify an alternate editor to be invoked by MODIFY COMMAND. When a source file is changed with MODIFY COMMAND, the .FOX file, if any, is deleted, so that the next execution forces reloading and recompilation of the newly updated program. It would be better if the pseudocode from the newly compiled version were saved out to disk, but only the stand-alone compiler can write .FOX files. However, during development it is entirely feasible to work directly with source files, or a mix of source and pseudocode, thereby making it unnecessary to run the compiler after every change to a source file.

As with dBASE, Foxbase+ provides an optional runtime system that runs only precompiled pseudocode files, without providing any of the interactive facilities. The price of the runtime system ($500) includes a license for unlimited distribution of Foxbase+ applications. Thus, the total cost of a development and runtime system comes to about $900, which is less than the price of a functionally equivalent package consisting of dBASE III, plus one of the other compilers. However, for users who already own dBASE III, the $900 must be compared to the price of an alternative compiler alone.

The Foxbase+ documentation consists of a single, standard-sized binder containing some 330 pages. This manual covers not only the installation, configuration, and operation of the system, but also provides a complete, if somewhat terse, reference to the Foxbase+ language. Although it is nearly as complete as the comprehensive dBASE III documentation, it is not meant as a tutorial in either database systems or in the dBASE III language. The Foxbase documentation, rather, is in the tradition of most compiler documentation that assumes some knowledge on the user's part of the underlying language; as such it is quite good.

Clipper is the most traditional of the three dBASE products, operating in the familiar two-step process of a classic language compiler.

Nantucket Corporation. Clipper is the most traditional of the three products, operating in the two-step process of a classic compiler: compilation to standard object code, then linking to a produce a stand-alone .EXE file. And, as is the case with most such compilers, the license agreement allows unlimited distribution of compiled applications. Further, Nantucket has removed copy protection from the latest version of Clipper. The product is installed by copying all the files to working disks or directories, and a batch file is provided to automate this process. Instructions also are provided for installing and running Clipper on a diskette-drive-based system, although such operation is more than a little inconvenient.

The compiler accepts the name of a single source file on the command line, like dBASE. All source files that are mentioned in DO and SET statements within the root file, and the files mentioned in those, are automatically processed. Clipper is intelligent enough to differentiate between names of stand-alone files and of procedures, and will look for stand-alone .PRG files only for those procedure names that did not occur in procedure files. Each execution of the compiler creates one object file that contains the output of all the source files processed.

An alternate method of specifying the names of files to be compiled is by means of a control file containing a list of file names. In that case, the automatic compilation feature is disabled, and only the named files are processed. This may be used to specify files that have names generated by macro substitution (for example, SET PROCEDURE TO &SOMEFILE), or to split an application's object code into two or more files for sharing with other programs.

Clipper comes with a customized version of the Phoenix PLINK86 linker, but the standard DOS linker also can be used. The Phoenix product allows the building of overlays to accommodate large applications on systems with limited memory, but at the expense of significantly longer link times. Both the compiler and linker support full path names, and the compiler returns DOS error-level codes on compilation errors, allowing the efficient automation of the compile/link process with batch files. Several sample batch files are provided.

Clipper's documentation is the weak link in an otherwise fine product. The main manual is the familiar three-ring binder in a slipcase; its size matches the original dBASE III (pre-Plus) manual. But the current version, dated Autumn 1986, comes with a manual for the Winter 1985 version and a substantial supplement booklet in a totally different format—spiral-bound with pages that are a different size and shape. The supplement contains information on enhancements added to the Winter 1985 version, but it mixes together features that are new dBASE enhancements with those that are extensions of previous extensions to dBASE. This may be workable to users already familiar with Clip-

When you give PC TECH JOURNAL as a gift to a client or business colleague, you're giving valuable information on systems design and integration.

PC TECH JOURNAL is the recognized source of expert facts for designers, integrators and DP/MIS professionals who require current information and sophisticated applications and input.

Give a gift that's delivered 13 times* a year and save 50% off the annual single-copy price of $53.35.

*Your gift subscription includes the special PC TECH JOURNAL Directory issue published in November!

THIS CARD GIVES A COLLEAGUE A YEAR'S WORTH OF VALUABLE INFORMATION AND INSIGHT

FOR FASTER SERVICE CALL TOLL-FREE 1-800-852-5200!

Send Gift TO:
Mr./Mrs./Ms. _____ please print full name
Company _____
Address _____
City _____ State _____ Zip _____

Send Card FROM:
Mr./Mrs./Ms. _____
Company _____
Address _____
City _____ State _____ Zip _____

PC TECH JOURNAL P.O. BOX 2966 BOULDER, CO 80322 4Z70C

☐ Bill me
☐ Charge my credit card for $26.70 for 13 issues.

Check one:
☐ AmEx ☐ Visa ☐ MasterCard

Card No. _____

Exp. Date _____

Add $6 for postage outside USA, US currency only. P
allow up to 60 days for delivery of first issue.
Basic annual subscription price is $34.97.

per, but it is confusing for those new to this compiler, and unusable for those completely unfamiliar with dBASE. Nantucket does, however, plan to revise and integrate Clipper's documentation.

Using the two manuals (the base documentation with the supplement) would be bad enough, but even they are not complete. Additional information on still more changes and enhancements is provided in a READ.ME file and five .DOC files. What is more, this entire body of documentation must be used in addition to, not in place of, Ashton-Tate's voluminous dBASE manuals, because all of it covers only the differences from the base language definition—and no indexes are provided in either of the two main books.

WordTech Systems. Quicksilver is an update of WordTech's dB III compiler (which is no longer available). The previous product was a semicompiler that produced pseudocode for a runtime interpreter, but Quicksilver can produce native code. Otherwise, the two are quite similar in character, and Quicksilver can be considered a natural evolution from the last version of dB III. Through most of the development cycle, Quicksilver works just like dB III, because it produces pseudocode (called d-code) as an intermediate step. Testing and debugging is performed at this stage, with the conversion to native code performed only when the program is ready to go into production.

The package includes a demonstration version of the compiler that is limited to processing databases of no more than 16 records. Thus, a user may try out most functions before breaking the seal on the package containing the full version. If the product is found to be unsatisfactory, it may be returned for a refund as long as the operational copy remains sealed. This seems a reasonable approach, but it has one disadvantage. Although the demonstration version can compile any program the full version can, it cannot produce native code, and evaluating the compiler only at the d-code stage does not give a true picture of its performance.

Neither version of the compiler is copy protected, and installation involves simply copying the many files into working directories of a hard disk. (Although a hard disk is not mentioned as a requirement, operating Quicksilver on a diskette-drive-based system is not practical.) Also, the installation process is not documented very well: although the various files making up the compiler package are described in a READ.ME file, no information is included as to which are required, which are optional, and which must be in which directories. An installation program or batch file to perform the copy would be most useful. The supplied INSTALL program does not perform this function; it merely modifies the link library to reflect the hardware characteristics of the system. This phase of the installation is also inadequately described.

The creation of a stand-alone .EXE file from .PRG source code requires four steps: compilation to d-code, linking of the d-code modules, conversion of d-code to standard .OBJ files, and finally, linking with a standard DOS linker. This process is not as onerous as it seems, because testing and debugging are performed at the d-code stage, so only the first two steps are repeated during development. The final two steps are typically performed only prior to distribution, although they might be required more often if the purpose of the testing is to optimize the execution time of the native code.

Quicksilver's automatic compilation is a useful feature, but it cannot differentiate between procedures and stand-alone files.

The compilation step can process a series of source files in sequence; the list may be specified in the command line or in a separate control file. In addition to the files explicitly named by either of these methods, the compiler may be instructed to automatically process all files mentioned in DO <file>, SET PROCEDURE, and SET FORMAT statements in any of the named files. In many cases it is possible to compile all of the modules of an application merely by naming the root file; the most common reason for naming more files is when file names are generated by macro substitution, as in SET PROCEDURE TO &SOMEFILE. A separate d-code file is created from each source file.

This automatic compilation is a useful feature, but its implementation has limitations. Unlike Clipper, Quicksilver cannot differentiate between names of procedures and stand-alone files. Given the statement DO ABC, it always will look for the file ABC.PRG and issue a warning message if such a file cannot be found. An option is provided to turn off such warnings, but then no notification is given of a bona fide missing file error. On the other hand, if ABC exists both as a separate file and as a procedure in another file, both copies get converted to d-code and are subsequently linked into the executable file, and the path of execution may well go to the wrong one.

In operation, the compiler exhibits several anomalies. The first is lack of support for paths in source file names, both those explicitly named on the command line and those that are mentioned in DO and SET statements in the source file. This is documented in the READ.ME file as an "execution discrepancy." Presumably this problem will be fixed in a subsequent release.

The second problem is more serious because it is a direct result of the compiler's design; that is, WordTech Systems considers it a feature. D-code files produced by the compiler are identified by prefixing the source file name with an @ sign. For example, the source file ABC.PRG creates an output file named @ABC.PRG. If the source file name is already eight characters long, the last character is dropped. Alternately, a command-line switch can be set to instruct the compiler to overlay the first character instead. The DOS file-naming conventions are already restrictive enough, but this scheme effectively limits file names to seven characters—moreover, it is unnecessary because DOS provides a three-character extension just for the purpose of differentiating file types. With approximately 40 legal file-name characters, some 64,000 different three-character extensions are available. It seems that WordTech could have chosen one of those and left the user's file names alone.

The third problem is a result of the design of Phoenix's PLINK86 linker, which was used to construct the compiler .EXE file. If the compiler has been invoked with a specific path, such as \DBASE\QS\DB3C, and if that path is not part of the DOS search sequence that is specified by the user in the PATH command, then the compiler's overlays cannot be found.

Once all of an application's source files are compiled, the second step gathers together all of the d-code files. As with the compiler, the d-code linker automatically processes all files mentioned in DO and SET statements in that file and all subsequent files; however, unlike the compiler step, this feature cannot be turned off. In addition, an explicit list of files may be specified on

Our Development Tools Generate A Lot of Positive Feedback.

Jeffrey Zurkow, President of Avocet Systems

Avocet offers an entire line of low-cost microprocessor development tools.

Target Microprocessor Families Supported

1802/1805	68000/68010	COP400
6502/65C02	68020	HD64180
6801/6301	8048/8041	NEC 7500
6804	8051	TMS-32010
6805/6305	8085	TMS-32020
6809	8096	Z8
68HC11	F8/3870	Z80

Host Operating Systems

CP/M DOS VAX Unix VAX VMS

AVMAC Macro Assemblers ..... from $349

AVSIM Simulator/ Debuggers ..... from $299

Other Development tools ..... Call for full catalog

Microprocessor development tools without the shock of a big price tag.

The AVMAC family of assemblers from Avocet lets you develop microprocessor code on your personal computer or VAX. Avocet has been developing PC software since before there *were* PC's. Our products have been refined over several generations giving you powerful and flexible development tools. They work with your existing operating system and text editor, so they're easy to install and easy to use.

Do all of your development on a single PC or VAX without switching systems.

If your next project calls for a different microprocessor, just call Avocet. There are Avocet assemblers for most common microprocessor families. So modifying your development system is as easy as changing diskettes. Check the chart—the assembler you need is probably there.

With Avocet, you're wired into a family of support products you can trust.

Each assembler package includes the AVLINK linker, AVLIB librarian, AVREF cross-reference generator and other utilities. And Avocet also offers you a host of other tools you need, such as TRICE self-powered in-circuit emulators. AVPROM programmers, text editors and the AVSIM full-screen simulator/debugger. So the PC on your desk can hold a workbench full of development tools.

Try before you buy. And we'll ship in 48 hours or less.

You probably need your tools right away. And that's when you'll get them. When you order from Avocet, we'll also send you a complete demonstration kit for both our assembler and our AVSIM simulator/debugger.

Try the demo for thirty days—if you aren't completely satisfied, we'll refund your purchase price, less $35.00 for the demo disk. That's yours to keep, which is a good deal by itself! We're sure you'll find Avocet the best connection you've ever made.

Call **1-800-448-8500.**

Avocet Systems Inc., 120 Union St.
P.O. Box 490, Rockport, ME 04856

CIRCLE 221 ON READER SERVICE CARD

AVOCET
SYSTEMS, INC.

the command line or in a control file. As a consequence of the unfortunate naming convention at the d-code stage, the linker must be told if compiler output files are named by replacement of the first character instead of the last.

The d-code linker operates in two modes, depending upon whether the output is intended for execution as d-code or for conversion into a native code .EXE file. In the first case, three output files are produced. For an application with a root program named ABC.PRG, the output files would be ABC.EXE, ABC.OVL, and ABC.DBC. The size of the .EXE file is always 133KB, regardless of the size or nature of the application program; it is, in fact, the runtime system that interprets the application-specific d-code contained in the other two files. Each application therefore replicates the common runtime code, unnecessarily taking up processing time to create it and disk space to store it. It would be much more efficient to provide a single copy of the runtime system.

In the linker's other mode, only the .DBC file is created. It cannot be executed, but must be processed with the optimizer program into .OBJ format, then linked with a DOS linker. For a root source file, the optimizer creates five .OBJ files and a linker control file that provides the names of these object files, the name of the output .EXE file, and the names of link libraries. The optimizer automatically calls the DOS linker; a command-line parameter controls whether this is the standard LINK.EXE of DOS or Phoenix's PLINK86. However, neither one of these linkers is provided with the Quicksilver package.

With its four steps, Quicksilver is more complex in operation than the other two products. The process may be automated with batch files, but this is more tedious than it needs to be because of the incomplete path support and the fact that the various programs do not return DOS error-level codes. A compiler design such as this one makes sense only if stopping at the intermediate code stage saves a significant amount of time over the creation of native code .EXE files; however Quicksilver spends too much time doing unnecessary things at this stage. Although the concept is good, the implementation has a some major design flaws.

Quicksilver's documentation, however, is more than adequate. It consists of a single binder, in standard format with a slipcase, containing some 360 pages. All of the information is specific to Quicksilver, with no duplication of dBASE III documentation. Language features are described only to the extent that they differ from the dBASE standard. The operation of the compiler and considerations of program efficiency are covered very thoroughly. The major failing, as mentioned, is the sketchy description of the installation process. The manual does include a useful glossary and a good index.

dBASE III COMPATIBILITY

Regarding file compatibility, all database, label, and report files are interchangeable among dBASE III and the three compilers, but index files are a different matter. Clipper and Foxbase+ implement a different, incompatible index structure. They cannot use index files that have been created by dBASE, and dBASE cannot use theirs.

Within Foxbase+, the conversion from dBASE to Foxbase+ index format is performed automatically as required. Whenever an existing index file is accessed, Foxbase+ tests whether it is in its own format or that of dBASE; if it is the latter, a new index file is generated and saved on the fly, using the key expression obtained from the dBASE index file. Clipper provides a simple program for creating indexes, but the user must provide the key expression.

All database, label, and report files are interchangeable among dBASE III and these compilers, but index files are another matter.

These nonstandard indexes are identified by different extensions (.IDX in Foxbase+, .NTX in Clipper), so that both they and dBASE index files may coexist. However, updating files alternately with a compiler and dBASE eventually will render one set of indexes out of date. This is less likely with Foxbase+, which is so much like dBASE III that it is really unnecessary to use both products on the same set of data. However, it is quite likely that dBASE would be used for interactive testing of Clipper-developed programs.

The differences in index formats are supposedly for purposes of efficiency. But is the gain in performance really worth the problems of incompatibility and of maintaining two sets of indexes? As shown by Quicksilver and other products such as Fox & Geller's Quickindex, an index structure compatible with that of dBASE can produce results that are just as good. Quicksilver indexes, although not identical with those created by dBASE, are fully compatible, and provide performance that is better than that of Clipper and about equal to that of Foxbase+.

Each of these compilers supports a slightly different version of the language. Each is both a subset, because it does not implement all of the dBASE features, and a superset, because it adds some features; yet all three differ in the features they do not support and the features they add. Tables 2 and 3 summarize respectively the major deletions from and additions to the dBASE language by the three products.

Because the dBASE language is defined only in actual commercial releases of the product, it is inevitable that some lag will occur between a new Ashton-Tate release and the implementation of its features in the after-market. However, in the case of Clipper and Quicksilver, most of the missing features are not the result of playing catch-up, but of conscious design decisions.

It is certainly reasonable to assume that commands such as ASSIST, HELP, and MODIFY COMMAND, and SET options such as STEP, ECHO, DEBUG, and DOHISTORY, are used only from the dot prompt and are not needed under program control. (Even Ashton-Tate's dBRUN, the runtime system for executing encrypted .PRG files, omits support for these features.) It is also understandable that commands for interactive creation of databases, screens, reports, and mailing labels are not supported by the two compilers. In most cases, these are created once when an application is first installed, and it is not necessary to change them from within a program. Both Clipper and Quicksilver provide stand-alone file creation utilities (these are described later in the article). And, with the exception of index files as mentioned above, files for any of the compilers may be created by dBASE.

But the dBASE III language also provides a capability of creating data files under program control, not only from interactive input. This is accomplished via the CREATE command with the FROM option. The file that is named in the FROM clause is a structure file typically created by the command COPY STRUCTURE EXTENDED; it is a data file describing the fields of another data file. The structure file may be modified under program control, then used to

create a new data file. All three products implement the COPY STRUCTURE EXTENDED and CREATE FROM commands. In addition, Clipper accepts the plain CREATE command, but executes it differently than dBASE. Instead of asking the user for input to define the new file's structure, Clipper creates an empty structure file; then, records defining the structure may be written into the file under program control. It therefore would be possible, if not very useful, to duplicate through programming the interactive CREATE and MODIFY STRUCTURE commands of dBASE III Plus.

Both Nantucket and WordTech chose not to implement the interactive data input commands such as APPEND, BROWSE, CHANGE, EDIT, and INSERT. The Quicksilver documentation makes a persuasive point that such commands are a hazard to data integrity because they allow the input of unvalidated data directly into data files. WordTech argues that the proper way to enter data is to write a program to accept user input into memory variables, validate it, and only then apply it to the database.

Methods are available for ensuring data integrity even with automatic input procedures, and many traditional applications are programmed in such a way. This was amply demonstrated when an attempt was made to test these compilers on several large production applications: most of them used some form of input that is not supported by either Clipper and Quicksilver.

Foxbase+, on the other hand, attempts to duplicate most of the features of dBASE, including the interactive ones. Its list of missing and added features is the shortest, thus it is the closest in capabilities to dBASE. Although the most useful data entry commands are implemented, some of the newer conveniences, such as CATALOG, VIEW, and QUERY files, are missing. Because they are most useful in an interactive data query mode, it is not surprising that they are missing from Clipper and Quicksilver, but their absence from Foxbase+ makes that product less than an exact replacement for dBASE III Plus.

The enhancements offered by each of these products are mixed blessings. Some of them, such as memory arrays and multiple relations, address serious limitations of dBASE III and are indeed useful, but they come at a price. One of the major advantages of using dBASE III is that it is so widely accepted; like the IBM PC itself, it has come to be the de facto standard, shortcomings and all. Deviating from that standard should not be done lightly. Incorporating the en-

TABLE 2: *Compiler Language Deficiencies*

	FOX	NANTUCKET	WORDTECH
Product	Foxbase+	Clipper	Quicksilver
APPEND	●	○[a]	○[a]
ASSIST	○	○	○
BROWSE	●	○	○
CATALOG files	○	○	○
CHANGE	●	○	○
CREATE (database)	●	●[bc]	○[cd]
CREATE/MODIFY[e]	●	○	○
DISPLAY/LIST MEMORY	●	○	●
DISPLAY/LIST STATUS	●	○	○
DISPLAY/LIST STRUCTURE	●	○	●
EDIT	●	○	○
ERROR ( )	●	○	●
HELP	●	○	○
INSERT	●	○	○
LOAD	●	○	●
MESSAGE ( )	●	○	●
QUERY files	○	○	○
RETURN TO MASTER	●	○	●
SET (Menu-driven)	●	○	○
SET convers. items[f]	●	○	○
SET ORDER	●	●	○
VIEW files	○	○	○
Foreign file formats[g]	○	○	○

This list of dBASE III features is not complete—each of these commands is included here only to point out that it is not supported by one or more of these compilers.
● = *Implemented* ○ = *Not implemented*
[a] *APPEND FROM <file> and APPEND BLANK are implemented.*
[b] *Creates an empty Structure Extended file.*
[c] *CREATE <file> FROM <strucfile> is implemented.*
[d] *A stand-alone utility for creating databases is provided.*
[e] *CREATE/MODIFY COMMAND, LABEL, REPORT; MODIFY STRUCTURE.*
[f] *SET TALK, HELP, DEBUG, STEP, SAFETY, MENU, etc.*
[g] *SDF format is supported in COPY and APPEND, but not DIF, WKS, SLK, and PFS formats.*

Clipper and Quicksilver address only the preprogrammed mode of dBASE III Plus, while Foxbase+ supports most of its interactive processing features as well.

TABLE 3: *Major Language Enhancements*

	FOX	NANTUCKET	WORDTECH
Product	Foxbase+	Clipper	Quicksilver
Memory arrays	●	●	○
Multiple relations	●	●	○
Edit memo during browse	●	○	○
Memo manipulation routines	○	●	○
User-defined functions	○	●	●
C and ASM subroutines	○	●	●
Programmable end-user help	○	●	○
Execute interrupts	○	○	●
Command-line parameters	○	●	●
Menu structures	○	●	○
Windowing	○	○	●
Port I/O	○	○	●
Max. number of open files	48	15	80+

● = *Yes* ○ = *No*

Foxbase+, in keeping with its attempts to duplicate the implementation of dBASE III Plus, also provides the fewest enhancements to the language facilities.

hancements of one compiler into a program means that program cannot be executed under another compiler; more significantly, such a program cannot be tested interactively with dBASE.

The most welcome extensions—arrays and multiple relations—are provided by Clipper and Foxbase+. In Clipper, arrays are always private (local to the procedure in which they are declared) and limited to one dimension; Foxbase+ arrays may be either one or two dimensional and either public or private. Clipper allows as many as eight relations out of one data area; Foxbase+ sets no limit.

Clipper and Quicksilver both provide for user-defined functions (UDFs), which are value-returning subprograms similar to the built-in functions of dBASE III. It is possible to effectively expand the syntax of the language by adding what become key words. Although the same effect can be achieved with procedures that return values in global variables, UDFs create more readable code because it is immediately obvious that a value is being returned. Otherwise, the same variable scoping rules apply to UDFs as to other subprograms in dBASE III: variables known at the level of the calling procedure are available to the function; parameters and variables declared within the function are local.

UDFs may be written in C or assembly language, as well as in dBASE. This is an easier interface than the one provided by the LOAD and CALL statements of dBASE (also implemented in all three compilers) because the functions greatly simplify the returning of values from the foreign language to the dBASE calling procedure. Clipper and Quicksilver are both true compilers that produce linkable object code, thus at link time the incorporation of foreign language code is no more difficult than linking in separately compiled modules. Libraries of UDFs for Clipper are available, such as Tom Rettig's Library, Clipper Edition, (see Product Watch, Dave Browning, this issue, p. 179).

Foxbase+ and Quicksilver circumvent the operating system's limitation of 15 files open at once. DOS allows at most 20 file handles, then uses 5 of them for standard input, standard output, standard error, printer, and serial port, leaving 15 for use by the program. With clever programming, it is possible to create the effect of more files open at once by closing files whenever a new one needs to be opened and no more handles are available. The position in the file just closed is saved, so that it may be repositioned when reopened (perhaps causing the closing of another file) for the next I/O request. Files that have been accessed in this mode are said to be virtually open. The allocation of a small number of physical handles to a larger number of files is analogous to the process of virtual memory management, in which a small amount of physical memory simulates a larger amount of logical memory.

Foxbase+ uses this approach to expand the total number of open files to 48. Within this number, the program is allowed as many as 10 database files (the same as dBASE III) and no more than 21 index files. A smaller limit may be set in the CONFIG.FX file.

For Quicksilver, the upper limit on concurrently open files is not specified, but WordTech guarantees that 10 database files, each with as many as 7 index files, may be logically opened at one time. The runtime file system manages these files among 3 to 10 physical file handles; the number is set by modifying a link-time library with the installation program. The remaining handles (from the total of 15) are available for other types of files, such as format, alternate, report, and label. Note that file handles are never needed for procedure files, because procedures are incorporated into the load module at link time.

The most welcome extensions to the dBASE III language—arrays and multiple relations—are provided by Clipper and Foxbase+.

Of course, this capability also comes at a price. Virtual file processing takes more time because if a file is closed and later reopened, additional processing and disk accesses are required to close and open the file, and its data must always be read in from disk. When a file remains open, the data can remain in the system buffer, and, most likely, the next I/O request can transfer data without performing a time-consuming physical disk read.

When concurrent processing of a large number of files is mandatory, using a virtual file manager is certainly easier than programming the equivalent logic in standard dBASE III. But an immutable rule of system development states that if the program ever needs to be returned to the standard, the effort required to remove an enhancement is proportional to the fourth power of the effort saved by the enhancement.

Clipper and Quicksilver provide a means of switching the enhancements on and off. In the former, if a public variable named CLIPPER is defined, the compiler initializes it to the value .TRUE. To dBASE, this name has no special meaning, and it is initialized, as are all public variables, to a .FALSE value. Therefore, a program may incorporate the following logic:

```
IF CLIPPER
   Clipper enhancement statements
ELSE
   Normal dBASE statements
ENDIF
```

Quicksilver, on the other hand, compiles lines beginning with the special sequence *\, which dBASE considers as a comment (because it begins with a *). A compile-time switch may be set to ignore this feature, in case the source contains real comments beginning with these two characters.

The ability to turn off enhancements, of course, addresses only the problem of syntax errors that dBASE generates when it encounters unimplemented constructions in the source code. What this leaves unresolved is how to perform the equivalent functions in standard dBASE code. In most cases, it is not possible to emulate the enhancements, so that programs using a specific compiler's features effectively become a language foreign to dBASE.

Some of the more comprehensive enhancements are indeed hard to resist. Clipper implements two very useful features. The first is a menu system that automates point-and-shoot selections in several commands analogous to SAY, GET, and READ. Menus may be organized either horizontally or vertically, and a brief explanation may be specified for each entry. A highlight bar is moved through the selection with the cursor keys or by pressing the first letter of the menu text, and as each entry is highlighted, the explanation appears, 1-2-3 style, on a message line. A menu selection is made by pressing the return key, PgUp or PgDn, whereupon the relative number of the selected entry is returned in a menu variable.

Clipper's other major enhancement to dBASE is customized help. Pressing F1 during full-screen entry invokes a procedure called HELP.PRG (provided one had been linked into the load module, otherwise the keystroke will be ignored). As parameters, it receives the

BOB STANTON HAD A GREAT IDEA. AN HOUR LATER HE WAS TESTING IT.

Appointments. Everybody takes them — dentists, auto-body shops, dance instructors. And lots of computer applications need appointment screens.

Bob thought that a calendar made a terrific graphic metaphor for taking appointments. Simply use the arrow keys to pick an open date, then press the Enter key, and up pops an appointment window.



Lucky for Bob, he's a CLARION programmer, one of a fast growing cadre of super-productive application developers.

With CLARION's Screener utility, he painted a white calendar on a black background. Then he drew a white-on-blue track around the page and between the days. He typed in the days of the week — and *voila!* — a calendar!

CLARION knows that a PC monitor is refreshed from memory, so it treats a screen layout like a group of variables. Just move data to a screen variable, and it shows up on the monitor.

Bob set up dimensioned screen variables for the days of the month and a screen pointer for selecting a date, and he was done. Then Screener generated the code .

Then Bob drew the appointments window, built an appointment file, filled in the connecting code and tested it — ONE HOUR AFTER HE STARTED!

Testing was a breeze. Screener doesn't just write code, it compiles your source, displays a screen, gets the changes, then replaces the old code in your program.

So here are Bob's appointment screens. You can see the source listing to the right. We marked all the code Screener wrote for him.



WHY CLARION?

Why are application developers everywhere changing to CLARION?

Because CLARION gives you all the tools you need: a coupled compiler and editor; screen, report, and help generators; an import/export utility; a sort/backup/restore utility; a formatted file dump; a DOS shell — and much more.

Because with CLARION 's comprehensive data management routines, records can be locked and files shared on Novell®, 3COM®, IBM® PC Net & Token Ring, Multi Link®, and most other networks.

Because CLARION is *not* hardware locked or copy protected. Run-time systems are *free* and soon you will be able to translate CLARION into native machine code (.EXEs).

And best yet, the price of CLARION v1.1 is just $395 plus shipping and handling.

You'll need an IBM PC or true compatible with 320KB of memory and a hard disk drive. CLARION v1.1 also comes with a 30-day money back guarantee.

So call now and order CLARION v1.1. or ask for our detailed 16-page color brochure and reprints of major reviews.

800/354-5444

CLARION®
from BARRINGTON SYSTEMS, INC.

150 EAST SAMPLE ROAD POMPANO BEACH, FLORIDA 33064 305/785-4555

Copyright 1986 Barrington Systems, Inc. CLARION is a registered trademark of Barrington Systems, Inc. IBM is a registered trademark of International Business Machines Corporation Novell is a registered trademark of Novell, Inc. 3COM is a registered trademark of 3COM Corporation Multi Link is a registered trademark of Software Link, Inc. Dept. A9

CIRCLE NO. 105 ON READER SERVICE CARD

name of the calling program, the line within it where help was invoked, and the name of the variable that was waiting for input when F1 was pressed. Using this information, the program can display context-sensitive help messages. To facilitate this helpful aid, Clipper also provides commands to save and restore the screen display.

Quicksilver's major extension is a windowing system implemented by a series of commands that parallel the operations with databases. Windows are created, opened, written to, and closed; saving and restoring the screen underlying a newly opened window is performed automatically with no effort on the part of the programmer.

Quicksilver also adds support for the low-level functions of DOS and BIOS interrupts and port I/O. The latter is useful mostly for implementing sounds on the speaker, because most other I/O activities are supported by the high-level features of the language. On the other hand, the ability to invoke DOS and BIOS interrupts directly is quite useful, permitting access to a number of system services that would not otherwise be available.

Besides the features that are listed in tables 2 and 3, many other differences of a more minor nature are present among the compilers. Some are additional features implemented as extra functions or as new options in existing commands, others are minor, but annoying, deviations from the dBASE implementation. For example, Quicksilver requires that the fields present in a SORT statement be separated by plus signs instead of commas. The documentation makes light of this seemingly minor difference, but it misses one very significant point: a list delimited by plusses is one expression, and all the elements must be of the same type. On the other hand, the standard syntax allows sorting on a compound key made up of more than one type of variable. It is possible to insert functions to convert variables from one type to another, but this requires more changes than merely replacing commas with plus signs.

In general, Quicksilver contains more of these annoyances than the others. It requires that the ON phrase specifying the sort key precede the TO phrase specifying the output file; standard dBASE syntax allows either order. A PROCEDURE statement is accepted only if the first noncomment statement in the file is PROCEDURE, meaning that Quicksilver makes a distinction between procedure files and program files that can be called directly. This prevents the very useful construction, acceptable to dBASE, Clipper, and Foxbase+, of setting a procedure file from within itself:

```
* Within file ABC
SET PROCEDURE TO ABC
DO MAIN
PROCEDURE MAIN
...
...
PROCEDURE ... etc.
```

Also, in Quicksilver, UDFs must reside in a separate file, while in Clipper they can be included in the main procedure or in any procedure file.

Clipper has fewer of these implementation differences. The key word REST is not supported as a scope, but the equivalent WHILE .T. is suggested as a replacement. More significant is the fact that many standard dBASE functions are not included in the link library, but are supplied in several object files. The user must remember to specifically name them at link time, whereupon all are linked in without regard to how many are actually called. They also are provided in source code (dBASE, C, and assembly language), so the user may compile them and add them to the main Clipper library, or an auxiliary library can be created.

Users of traditional programming languages will require some adjustment to work with the error reporting of a dBASE compiler.

ERROR HANDLING

Users of traditional programming languages will require some adjustment to work with the error reporting of a dBASE compiler. Many seemingly simple errors are not caught at compilation, only at runtime. For example, mixing field names of different types in an expression is not noticed by the compiler because the database structure that defines the field types is not known until runtime. Similarly, referencing an undefined variable is not flagged because the compiler does not know if it is the name of a field in a data file or a public variable that has been defined in a previously executed procedure.

Given these limitations, all three compilers do a creditable job of discovering and reporting source code errors. In each case, the line in error and an error message are displayed on the standard output device. This output may be redirected to a printer or disk file. Using the latter approach, a programmable editor may be set up to highlight each error in the source code file.

Quicksilver generates a line count to show the progress of compilation. On screen, this displays odometer fashion on one line, but when redirected, each line number generates a separate line on the printer or in the output file. A compile-time switch is available to turn this feature off. Another inconvenience is that after each error, Quicksilver stops and requires a key press to either continue or abort. This too can be disabled, but it would be more logical to make continuous operation the default mode. If, indeed, output is redirected but continuous mode is not enabled, an error will appear to hang the system while the compiler waits for a keystroke for which no prompt actually appears on the screen.

Clipper also shows the compilation line count, but sends it to the screen regardless of output redirection. Error messages go to standard output. An option is available to suppress the creation of an object file, permitting quicker compiler passes for syntax checking only. Like Quicksilver, Foxbase+ sends everything to standard output, but it displays no progress messages and needs no user intervention.

For the most part, all three compilers were reliable both in operation and in generating robust code. Quicksilver had the most exceptions, as a result of its extremely conscientious error reporting in the documentation. Most of the bugs it reports are minor, and once known, easy work-arounds can be devised. However, one problem was somewhat misrepresented in the documentation. The SET ORDER command is documented (in the bug-reporting section of the READ.ME file) as not implemented, but it really should be tagged as not working. The command is compiled without complaint, but when executed it has no effect.

The Foxbase+ compiler seemed robust, although several minor problems were evident in the interface between the interactive Foxbase system and DOS. The RUN command uses the PATH, not COMSPEC, to locate the COMMAND.COM file; the command fails if the root directory containing COMMAND.COM is not in the path. If, as is common, the root contains no executable files besides the command

WHY LOGITECH MODULA-2 IS MORE POWERFUL THAN PASCAL OR C.

"A clear winner... The integrated editor is a joy to use." BYTE Magazine, Jan. '87



APPRENTICE PACKAGE $99

WIZARDS' PACKAGE $199

- **Separate Compilation w/inter-module typechecking**
- **Native Code Generation**
- **Large Memory Model Support**
- **Most Powerful Runtime Debugger**
- **Comprehensive Module Library**
- **Maintainability**
- **Translator from Turbo and ANSI Pascal**

NEW!

APPRENTICE PACKAGE $99

Everything you need to begin producing reliable maintainable Modula-2 code. Includes the Compiler with 8087 support, integrated Editor, Linker, and BCD Module. We're also including FREE our Turbo Pascal to Modula-2 Translator!

NEW!

WIZARDS' PACKAGE $199

This package contains our Plus Compiler—for professional programmers or for those who just want the best. The Plus Compiler with Integrated Editor requires 512K and takes advantage of the larger memory to increase compilation speed by 50%. Our Turbo Pascal to Modula-2 Translator is also included at no extra charge.

NEW!

MAGIC TOOLKIT $99

We've put our most powerful development tools into one amazing Toolkit for use with either the Apprentice or Wizards' packages. Highlighted by our Runtime Debugger, the finest debugging tool available anywhere, the Toolkit also includes our Post Mortem Debugger, Disassembler, Cross Reference utility and Version which keeps track of different versions of one program. Our MAKE Utility figures out module dependencies and automatically selects those affected by code changes to minimize recompilation and relinking. We also provide source code of our major library modules for you to customize—or just play with.

WINDOW PACKAGE $49

Now you can build true windowing into your Modula-2 code. Features virtual screens, color support, overlapping windows and a variety of borders.

ROM PACKAGE AND CROSS RUN TIME DEBUGGER $299

For those who want to produce rommable code. You can even debug code running in ROM from your PC.

Turbo Pascal is a registered trademark of Borland International.

Call for information about our VAX/VMS version, Site License, University Discounts, Dealer & Distributor pricing.

To place an order call toll-free:

800-231-7717

In California:

800-552-8885

WIN A FREE TRIP TO Switzerland

HOMELAND OF MODULA-2

Return your Modula-2 Registration Card or a reasonable facsimile* postmarked between March 1, 1987 and May 31, 1987 to be included in a once-only drawing!

Grand Prize: One week excursion for 2 in Zurich, Switzerland including a guided tour of ETH, the University where Modula-2 was created by Niklaus Wirth. European customers may substitute a trip to Silicon Valley, California.

Second and Third Prizes: LOGITECH C7 Mouse or LOGITECH Bus Mouse with Paint & Draw software—a $219 value, absolutely free!

*Write to Logitech, Inc. for a registration card facsimile.

YES! I want the spellbinding power of LOGITECH Modula-2!

☐ Apprentice Package	$99
☐ Wizards' Package	$199
☐ Magic Toolkit	$99
☐ Window Package	$49
☐ ROM Pkg/Cross RTD	$299

Add $6.50 for shipping and handling. Calif. residents add applicable sales tax. Prices valid in U.S. only.

Total Enclosed $_____

☐ VISA ☐ MasterCard ☐ Check Enclosed

Card Number _____ Expiration Date _____

Signature _____

Name _____

Address _____

City _____ State _____

Zip _____ Phone _____

LOGITECH

LOGITECH, Inc.
805 Veterans Blvd. Redwood City, CA 94063
Tel: 415-365-9852

In Europe:
LOGITECH SA, Switzerland
Tel: 41-21-879656 • Telex 458 217 Tech Ch

In Italy:
Tel: 39-2-215-5622

CIRCLE NO. 229 ON READER SERVICE CARD

processor, then the root directory does not really need to be in the path—every additional directory that DOS must search adds to the system's overall response time.

If the temporary exit to DOS is successful, the return to Foxbase+ is not quite clean: the last line of the DOS output is erased by the dot prompt. For example, if the user were running CHKDSK, the last line that gives the amount of free memory (often the very reason for running CHKDSK in the first place) gets overwritten.

Another problem is that Foxbase+ somehow manages to disrupt the DOS environment that is passed to the secondary copy of the command processor. Evidently the environment is not terminated properly, as shown by running the DOS SET command: it displays a garbage string at the end of the valid environment strings. Although no obvious problems were traced to this anomaly, such lack of attention to details undermines the user's confidence in the product. However, these problems are minor in comparison with the generally reliable operation of all three compilers in the majority of the tasks with which they were tested.

DEBUGGING DECISIONS

One of the major advantages of an interpreter is that it allows interactive execution for debugging purposes. Foxbase+ provides the same debugging facilities as dBASE: SET STEP executes programs a single statement at a time, SET ECHO displays each statement as it is executed, and SET DEBUG sends the echo output to the printer instead of the screen. In addition, the SUSPEND command allows temporary exit from a program to the dot prompt, while RESUME restarts the procedure. And, as in dBASE, an error while executing a procedure produces the same choice of CANCEL, IGNORE, or SUSPEND. The one facility not provided by either dBASE or Foxbase+ is the setting of breakpoints in the program, but given the interpreter's quick turnaround between editing and executing, it is quite practical to insert SUSPEND statements at strategic points in the source code.

The debugging facilities of a compiler, to a large extent, are an attempt to replicate the interactive mode of an interpreter. It might appear that a dBASE compiler would not need a debugger, because the Ashton-Tate interpreter is available for that purpose. But it may not always be possible to use interactive dBASE to debug Clipper or Quicksilver programs. First, the programs may make use of language extensions, and second, whether inadvertently or by design, the compiler may execute certain statements in a subtly different way. Therefore, using a compiler's own debugger is often the only way to find the persistently elusive bugs.

The Quicksilver debugger is more sophisticated and provides more of the capabilities of an interactive interpreter than that of Clipper. To debug a Quicksilver program, it must be compiled and the d-code linked with a special debugging option enabled. The link step is very quick, because no library routines are placed in the output, and no executable file is created. Instead, the d-code must be loaded and executed by the debugger program. (It is not clear why WordTech wouldn't implement a similar process with a nondebugging runtime in order to accelerate the normal link step that is performed so often during development.)

Quicksilver's basic mode of operation mimics dBASE with STEP and ECHO set on: each press of the Return key displays the next source statement and executes it. A comprehensive set of commands provides full control over program execution, output redirection, display and modification of memory variables, and manipulation of data files. A particularly useful feature allows backing out all changes made with the debugger to data files, returning them to the state they were in when the debugger gained control. For example, a user may switch through several data areas, move the record pointer around in each, then with one command restore all pointers and reselect the work area where he started.

Foxbase+ provides the same debugging facilities as dBASE, including SET STEP, SET ECHO, SET DEBUG, SUSPEND, and RESUME.

Although this debugger does not implement all of the features of the dBASE interpreter, the control it allows over a program's environment is fairly complete. Two major exceptions are the inability to change data in files, and to interactively open data, index, or format files from within the debugger. Fixing a forgotten USE or SET statement would save many a trip through the editor, compiler, and linker. On the other hand, the ability to set up as many as 12 breakpoints by line number or condition, and to display source code without invoking an editor, are conveniences not offered by dBASE. The Quicksilver debugger's greatest fault is the command structure: because commands are single characters, the set of 30 commands includes some very arbitrary choices. For example, K moves the record pointer in a data file, Z executes a script of debugging commands from a disk file,] clears the screen, and [ejects a page on the printer. This is somewhat mitigated by the ability to display a help screen of command codes, summoned by the easily remembered H command. On the whole, Quicksilver's debugger is a well-designed development tool.

Clipper's debugger is incorporated into programs by linking in an extra object module; no changes are required at the compilation step. This debugger is much more primitive than Quicksilver's, and is more reminiscent of DOS DEBUG than of dBASE. It cannot display source code, but refers to the source program by line numbers. This is analogous to DEBUG's references by address, and just as using DEBUG requires an address map, using the Clipper debugger requires a line-numbered listing. The compiler package includes a utility program that creates such listings.

The command set consists of only 14 commands. A maximum of nine breakpoints may be set by line number, but only one by condition. One useful feature (not available in the Quicksilver debugger) is the ability to execute DOS commands; this is often useful for renaming or copying files that are discovered to be missing in the middle of a debugging session. However, as a debugger for a database manager, this one is virtually crippled by its total lack of control over data files. Not only is it incapable of opening files and changing data in them, it cannot even display the contents of the files.

CREATING FILES

Clipper and Quicksilver each provide a stand-alone utility, invoked from the DOS prompt, that creates database files. Clipper's is the better of the two: it includes a full-screen user interface similar to the CREATE command of dBASE. Although it can modify the structure of an existing file, it is not equivalent to the MODIFY STRUCTURE command because it deletes all existing records.

Quicksilver's create utility has a scrolling teletype-style interface that

EZQueue 3000 . . . . Peripheral Sharing Plus!

The Giltronix EZQueue™ allows up to twenty-four computers to simultaneously share one or more laser printers, dot matrix printers, or plotters. In just a few minutes, you can configure the EZQueue to efficiently manage a single shared printer or multiple printers depending on your need. Ten simple to use and expandable models are offered, each with up to two megabytes of dynamic buffering.



Increased Productivity

EZQueue goes beyond the cost advantages of sharing expensive printer resources. In a communication environment, files containing data for printing mailing labels can be directed through EZQueue to a dot matrix printer. At the same time, files containing data for letter quality output requirements can be directed to a specific laser printer containing the desired paper style. Accounting departments can share the various printer resources needed to print invoices or checks. The flexibility of EZQueue can enhance productivity and reduce total system cost in virtually any workgroup environment.

Dynamic Buffering for Simultaneous Inputs

Buffering is dynamically allocated to one or more printer queues allowing simultaneous input from each of the attached computers with no waiting. When a shared printer is busy, files are stacked up in the EZQueue's buffer and output to the designated printer when it is ready to receive the next file.

Multiple Printer Sharing

EZQueue is ideally suited to simultaneously access and share multiple printer resources. Each EZQueue is provided with Giltronix GX software, a DOS compatible program that makes selecting a desired printer a snap. Once installed on a computer, a few keystrokes will invoke GX from within any software program to quickly select the desired printer resource. Both serial and parallel interfaces are supported.

Simple Installation

No special cables are required because each EZQueue serial port automatically adjusts to signal directions. "Smart" ports, a "21" step installation guide and Giltronix toll-free tech support guarantee a successful installation with minimal effort.

Expandability

Unlike competitive systems, EZQueue's buffer size and number of ports can be expanded as your system grows. A minimum EZQueue starts with six serial ports, two parallel ports and 256K bytes of dynamic buffering. Serial ports can be added in six port increments up to a total of twenty-four serial ports. Buffering can be added in 256K byte increments up to a total of 2 megabytes.

Headquarters
3780 Fabian Way
Palo Alto, CA 94303
(415) 493-1300
Telex 345542

Giltronix

Call Giltronix toll-free at (800) 531-1300
In California, call (800) 521-1330

CIRCLE NO. 172 ON READER SERVICE CARD

does not allow backing up to correct a previously entered field. It does not support the creation of memo or date fields, and cannot modify the structure of an existing file. Invoking it from within an existing file overwrites the file with no warning.

Clipper also provides programs that create label and report files. Again, the screen interface mimics that of the corresponding dBASE III commands, but in their pre-Plus versions. The name of the data file from which the labels or reports are created is not specified during the creation process; therefore no check is made on the validity of the field names. Quicksilver relies on dBASE III to create label and report files.

Because of the size of Quicksilver files, a large application may exceed the capacity of a diskette. To aid in distributing such an application, WordTech provides a SPLIT program that divides a file into subfiles of a specified size. The pieces may be recombined later with the DOS COPY command.

An opposite function is performed by the FOXBIND program from Fox Software. It combines a set of source files into one procedure file, preceding each module with a comment banner and a PROCEDURE statement. To be really useful, this program needs to be supplemented by others for more comprehensive source library maintenance, especially the replacement of a named module in the procedure file. As it is, input files are merely appended to the end of the output file without the compiler checking if procedures of the same name already exist within it.

NETWORK SUPPORT

All three products support networking; that is, programs created by each will run on a network and will handle multiuser access to databases. Nantucket provides networking capabilities with every copy of Clipper, Quicksilver needs the addition of an optional program costing $99, and Foxbase+ has a separate higher-cost multiuser version.

Clipper and Quicksilver programs were successfully installed and executed on the IBM Token-Ring Network under the IBM Network Control Program, but this was more a demonstration than a test. The following information is provided on the basis of each product's specifications, but the packages should be considered against a configuration's requirements before purchase.

All three products support the dBASE III networking commands and functions: SET EXCLUSIVE, USE EXCLUSIVE, FLOCK(), and RLOCK(). Therefore, concurrency control can be programmed in the same fashion in all of them. But differences exist in the degree of automatic concurrency control provided in the absence of explicit file and record locks. In dBASE III and Foxbase+, a file is automatically locked for the duration of any of 16 commands that operate on multiple records, such as APPEND FROM, COPY, INDEX, JOIN, and so on. Clipper performs no such automatic locking, leaving concurrency control entirely up to the programmer. Quicksilver, in its standard manual mode of concurrency control, provides automatic file locking for seven such commands: COPY, COPY STRUCTURE, INDEX, SET ALTERNATE TO, JOIN, SORT, and TOTAL.

But Quicksilver also provides an alternate mode, specified by the SET AUTOLOCK command, that extends automatic concurrency control beyond that provided by dBASE III Plus. With SET AUTOLOCK ON, the Quicksilver LAN control program will automatically lock files on the occurrence of any of 18 commands, and in addition will automatically lock an individual record for the duration of a REPLACE command. Also, in the event that a lock attempt fails because the file or record is already locked, Quicksilver automatically retries the attempt. The language extensions include commands to set the delay between attempts and the number of attempts before an error is generated. In dBASE III and Foxbase+, failure of an automatic file lock immediately results in a runtime error.

The multiuser version of Foxbase+ supports most of the features of dBASE III Plus Network Administrator, with the exception of the file encryption and the LIST USERS command. Otherwise, the syntax of programs written for the Administrator are acceptable to Foxbase+. However, significant differences are apparent during execution.

In Foxbase+, only the command USE EXCLUSIVE can prevent multiple read access to a database file. File or record locks applied with the FLOCK and RLOCK functions, and locks applied automatically by certain commands (the same ones as in dBASE III) are in effect only for write access; they do not prevent multiple read access. Although it is often useful to differentiate between read and write locks, the disadvantage is that this behavior is very different from that of dBASE and the other compilers. A program ported from another system, even though it compiles with Foxbase+, may have totally different results when executed. Whereas the single-user version of Foxbase+ is the closest to dBASE III, in this respect the multiuser version is the farthest removed from the standard.

A PERFORMANCE CODE

The performance of a compiler has two aspects. One is how fast it produces executable code, the other is how fast the code it produces executes. The speed of compilation was tested here using five programs varying from zero to more than 500 lines of source code. Although many commercial applications

TABLE 4: *Compilation Performance*

	FOX	NANTUCKET	WORDTECH	
PRODUCT	Foxbase+	Clipper	d-code	Native
EMPTY FILE				
Compile time	2	32	53	99
File size	40	125,740	192,188	119,312
DISP.PRG				
Compile time	3	35	57	100
File size	355	127,052	193,020	121,408
DBBENCH.PRG				
Compile time	3	38	60	123
File size	924	132,716	196,073	138,889
570-LINE PROGRAM				
Compile time	11	66	91	198
File size	9,933	139,516	222,338	182,866

Compile times in seconds.
File sizes in bytes.
The test system was a 6-MHz PC/AT with 640KB of RAM and a standard CMI 20MB hard disk. The times are the total for compilation and linking, where applicable, and include the time for loading compilers and linkers from disk. I/O files were also on disk; a RAM disk was not used.

Foxbase+ compiles the fastest since it produces intermediate code. Quicksilver takes longer to produce pseudocode than Clipper does to produce native code.

are larger than this, the dBASE language encourages modular programming, so that individual modules processed by a compiler should seldom exceed this size. The results of the compilation tests are provided in table 4.

The test system was a 6-MHz PC/AT with 640KB of RAM and a standard CMI 20MB hard disk. The times represent the total for compilation and linking, where applicable, and include the time for loading compilers and linkers from disk. I/O files were also on disk; a RAM disk was not used.

The empty file consisted of only an EOF mark, 1AH. The size of the resulting code indicates the size of the basic complement of library routines that make up the standard entry and exit modules placed in the output regardless of the source code. For Clipper and Quicksilver, essentially all of the time was spent in the link steps, where the base routines are copied from libraries to the output files. The compilation step itself, once the compiler was loaded from disk, took an insignificant amount of time to process the null file.

For Quicksilver, two results are tabulated. One is for the creation of d-code, the intermediate pseudocode created by compilation and the first link step. The program size for d-code is the total of the three files that are produced in this form; this includes a form of runtime system that interprets the d-code. This two-step process is the one most often used during development. The times shown for Quicksilver native code are totals for all four steps: compilation, d-code linking, conversion to object files, and final link to create the .EXE file. The second of these steps was limited to creating nonexecutable d-code expressly for the purpose of conversion to native code.

As shown in table 4, Foxbase+ far surpasses the other two in compilation speed. This is not surprising, since it requires no link step (the step in which the other two spend most of their time), and really does not process the source code very much, leaving it in an intermediate form for further processing by the runtime system. What is surprising is the poor showing of Quicksilver in producing pseudocode; it takes longer to do this than Clipper takes to compile and link to a native code .EXE file. Part of the reason could be that at each compilation, Quicksilver reinvents the wheel, as it were, by creating a new copy of the runtime system that will interpret the d-code. Clipper's times are quite respectable for a native code compiler, and most of this time is spent processing the large link library.

The linker used to produce the .EXE files for both Clipper and Quick-

FIGURE: *Standard Database Tasks*



Foxbase+ is the fastest in these tests. The runner-up, at least in the file-based tasks, is dBASE III. Clipper's code is especially slow in the disk-thrashing task of data import. (The average-to-date bar represents all database managers tested in *PC Tech Journal*'s series).

TABLE 5: *Benchmark Performance*

	AVG. TO DATE	ASHTON-TATE	NANTUCKET	FOX	WORDTECH	
PRODUCT		dBASE III	Clipper	Foxbase+	Quicksilver d-code	Quicksilver Native
STANDARD DATABASE TASKS						
Add 900 records to an empty database table	182	45	156	25	50	49
Index table on two fields (7 bytes)	53	14	11	7	5	6
Document and tally codes from one column	52	49	38	36	43	40
Mass change of one column (28 rows of 900)	22	5	2	2	4	4
Extract selected records to create a text file	11	2	2	2	1	1
ADDITIONAL TESTS						
Sort 900 records, two fields		50	117	16	76	71
Empty loop		15	3	2	7	4
Arithmetic		63	9	9	27	13
Character handling		126	28	18	52	25
Screen display		44	12	7	29	20

All benchmarks were run on an IBM PC/AT (6 MHz) with 640KB memory.
The tests were run in an 8MB partition on a CMI 20MB disk under DOS 3.0.

By most measures, Foxbase+ is the fastest by a comfortable margin. The runner-up, at least in the file-based tests, is dBASE III.

FIGURE: *Additional Tests*



Foxbase+ performed the sort the quickest, followed by dBASE III. In internal processing, Clipper and Quicksilver are approximately equivalent; they come close to the speed of Foxbase+, and comfortably outdistance dBASE III. Quicksilver's d-code is slow; however, the performance of its native code is quite competitive.

silver was Microsoft LINK version 3.05, which comes with version 4.0 of MASM. It ran considerably faster than the Phoenix PLINK86 included with Clipper.

The times turned in by Quicksilver for creating .EXE files are lengthened by the fact that the linker runs out of memory, even on a system with 640KB, and needs to create a scratch file on disk. This occurs only if the program that converts d-code to object code automatically calls the linker, and not if the linker is called directly from DOS. It seems that the conversion program does not release enough memory before executing the linker; by that time it should have completed its tasks and should be able to relinquish most of its memory allocation.

The small code files produced by Foxbase+ are not directly comparable to the output of the other compilers. For the others, each output file contains all the code it needs to run as a standalone program, whereas a Foxbase+ file needs more than 300KB of runtime system code to execute.

Performance of the generated code was tested using the same five benchmarks (and on the same machine) that comprise the PC Tech Journal Evaluation Suite for database managers (see "Evaluating Data Managers as Development Tools," Julie Anderson, August 1985, p. 46). The dBASE code was written by Dave Browning for his review of dBASE III Plus (see "The Evolving Standard," May 1986, p. 166). In addition, several other tests were devised to compare the internal processing performance of the three compilers to each other and to dBASE. The procedures implementing these tests are reproduced in the listing available on PCTECHline.

The benchmark results are shown in table 5 and charted in the accompanying figures. By most measures, Foxbase+ is the fastest compiler by a comfortable margin. This flies in the face of conventional wisdom that maintains that native code is inherently the fastest form of program. Whatever Fox Software did, it is to be commended for this particular bit of magic.

The product that shows the second-best times, at least in the file-based tests, is dBASE III Plus. As explained previously, an interpreter is not automatically at a disadvantage in disk-intensive tasks, and these results clearly illustrate this point. Clipper's code is especially slow in the disk-thrashing tasks of sorting and importing.

In the area of internal processing, Clipper and Quicksilver are approximately equivalent. They come close to the speed of Foxbase+, and outdistance dBASE III comfortably. Quicksilver's d-code is the slowest, but it is meant for testing, not production use.

COMPILING ADVANTAGES

Foxbase+ is clearly the most versatile of the three products. Purists may scoff at a pseudocompiler, but users interested in speed and convenience, not theory, must be impressed. It is the fastest in both compilation and execution speeds; for the former, up to two orders of magnitude faster. Its interactive capabilities make it almost an integrated development environment combining a compiler, editor, and debugger. Moreover, it implements a version of the language that is the closest to the current version of dBASE III Plus.

Foxbase+ has two drawbacks. If considered as a replacement for dBASE III, it lacks some of the interactive features of the Ashton-Tate product, such as ASSIST, and does not implement some of the newer features, also useful primarily in interactive mode, such as CATALOG, VIEW, and QUERY files. On the other hand, when considered only as an adjunct to dBASE for the purpose of compiling applications for commercial distribution, Foxbase+ is at a disadvantage in the area of price: the combination of the compiler (which is included only with the interactive development system) and unlimited runtime license is $900, or as much as 50 percent more than the others.

Foxbase+ is clearly the most versatile of the three products. It is the fastest performer in both compilation and execution tasks.

Quicksilver is recommended for those who insist upon a traditional native code compiler. This product is a vast improvement over WordTech's former dBIII compiler, but it is a close call over Clipper. Both products have many good features and some faults. It seems, at this point, that Quicksilver has more good points than does the current version of Clipper.

For one thing, Quicksilver offers a more complete implementation of the dBASE III language than does Clipper. As far as choosing between them on the basis of extensions to the language, each user must decide whether Clipper's memory arrays and menu system are more desirable than Quicksilver's file opening capacity and windowing facility. Another consideration, however, is that Clipper is a more established product, and has more support from third-party developers of link libraries and other support products.

Other areas in which Quicksilver is superior are the breaking of the DOS barrier of 15 open files, more convenient concurrency control in a network environment, a better debugger, and vastly superior documentation. Its manual is good by any measure, and more so in comparison with Clipper's disorganized material spread over more than half a dozen sources.

Clipper offers more speed in the compilation-link cycle, but the programs it produces are the slowest of all the products tested, including dBASE III Plus, especially in disk-intensive activities. Quicksilver offers the option of semicompiling during development and generating native code for finished applications, but the time it takes to perform even the shorter process is unpleasantly long. Also, its nonstandard file-naming conventions are an unnecessary imposition.

The rankings above reflect only the relative merits of these three dBASE compilers. Each is a high-quality product, very well suited for use in a professional development environment. Any one of these is capable of producing robust, reliable applications.

Fox Software, Inc.
27475 Holiday Lane
Perrysburg, OH 43551
419/874-0162
Foxbase+
CIRCLE 343 ON READER SERVICE CARD

Nantucket Corporation
P.O. Box 3621
Culver City, CA 90230
213/390-7923
Clipper
CIRCLE 344 ON READER SERVICE CARD

WordTech Systems, Inc.
P.O. Box 1747
Orinda, CA 94563
415/254-0900
Quicksilver
CIRCLE 345 ON READER SERVICE CARD

Ted Mirecki has been a contributing editor to this magazine for three years. He recently joined the editorial staff at its location in Columbia, Maryland, as a technical editor.



Free Subscription!

Receive a free one-year subscription to PC TECH JOURNAL from Raima Corporation when you buy db_VISTA™ or db_QUERY™ before May 15!

For product details, read our ad on the opposite page. Then order with the attached reply card or by calling 1-800-327-2462 toll-free. Or Call (206) 828-4636. VISA and MasterCard accepted.

For your **FREE SUBSCRIPTION** *be sure to complete and return the attached reply card.*

Order db_VISTA™ or db_QUERY™ before May 15 and receive 13 free issues.

Check the appropriate boxes.

☐ Extend my current subscription.
☐ This is a new subscription.

I want to order ☐ db_VISTA™ ☐ db_QUERY™

☐ Single user $195
☐ Single user with source .. 495
☐ Multi-user 495
☐ Multi-user with source ... 990

__VISA __MasterCard __C.O.D.
__Check payable to Raima Corp.

Card Number _____
Expiration Date _____
Name On Card _____
Signature _____
Date _____

Send to:

Name _____
Telephone _____
Title _____
Company _____
Street _____
City/State _____
Postal Code/Country _____
(International orders add $35 for shipping and handling.)

NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY MAIL

FIRST CLASS PERMIT NO. 798 BELLEVUE, WA

POSTAGE WILL BE PAID BY ADDRESSEE

RAIMA™
CORPORATION

3055 112th Avenue NE, Suite 100
Bellevue, Washington 98004

Free Subscription to PC Tech Journal

Turn over for details.

RAIMA™
CORPORATION

C Programmers!
db_VISTA™: high-speed Database written exclusively for C
NOW offers SQL-based Query

"db_VISTA™ has proved to be an all-round high performer in terms of fast execution..."

John Adelus, Hewlett-Packard Ltd./Office Productivity Division

High-speed data retrieval and access... just two benefits of using RAIMA's network model DBMS, db_VISTA. Combine these benefits with those of C—speed, portability, efficiency, and you begin to understand db_VISTA's real measure... performance.

db_QUERY™: new simplicity retains performance!

db_QUERY, our new C-linkable, SQL-based, ad-hoc query and report writing facility ... provides a simple, relational view of db_VISTA's complex network database. No longer will you give up performance for simplicity ... combine db_QUERY with db_VISTA ... you have both!

Independent Benchmark proves High-Speed model 2.76 times faster

An independent developer benchmarked db_VISTA against a leading competitor. Eleven key retrieval tests were executed with sequentially and randomly created key files.

*Result of 11 Key Retrieval Tests

db_VISTA	:671.24 seconds
Leading Competitor	:1,856.43 seconds

db_VISTA's high-speed network database model lets you precisely define relationships to minimize redundant data. Only those functions necessary for operation are incorporated into the run-time program.

Application Portability Complete Source Code

For maximum application portability, every line of db_VISTA's code is written in C and complete source code is available. db_VISTA operates on most popular computers and operating systems. So whether you write applications for micros, minis, or mainframes...db_VISTA is for you.

How db_VISTA works...

Design your database and compile your schema file with the database definition language processor. Develop application programs, making calls to db_VISTA's C functions. Edit and review your database using the Interactive Database Access utility. Compile and link your C program with the db_VISTA run-time library, and your application is ready to run.

Multi-user and LAN capability

Information often needs to be shared. db_VISTA has multi-user capability and supports simultaneous users in either multi-tasking or local area networking environments, allowing the same C applications to run under UNIX, MS-DOS, and VAX VMS.

Royalty-Free Run-Time

Whether you're developing applications for a few customers, or for thousands, the price of db_VISTA or db_QUERY is the same. If you are currently paying royalties for a competitor's database, consider switching to db_VISTA and say goodbye to royalties.

FREE Technical Support For 60 days

Raima's software includes free telephone support and software updates for 60 days. Technical support personnel are available to answer questions about our software or yours.

30-Day Money-Back Guarantee

Try db_VISTA for 30 days and if not fully satisfied, return it for a full refund.

Price Schedule

	db_VISTA	db_QUERY
☐ Single-user	$ 195	$ 195
☐ Single-user w/Source	$ 495	$ 495
☐ Multi-user	$ 495	$ 495
☐ Multi-user w/Source	$ 990	$ 990
NEW:		
☐ VAX Multi-user	$ 990	$ 990
☐ VAX Multi-user w/Source	$1980	$1980

Call Toll-Free Today!
1 (800) db-RAIMA
(that's 1-800-327-2462)
---OR Call 1-206-828-4636

MasterCard VISA

Read what others say...

"If you are looking for a sophisticated C programmer's database, db_VISTA is it. It lets you easily build complex databases with many interconnected record types. Raima's customer support and documentation is excellent. Source code availability and a royalty-free run-time is a big plus."
Dave Schmitt, President Lattice, Inc.

"My team has developed a sophisticated PC-based electronic mail application for resale to HP customers. db_VISTA has proved to be an all-round high performer in terms of fast execution, flexibility and portability, and has undoubtedly saved us much time and development effort."
John Adelus, Hewlett-Packard Ltd. Office Productivity Division

"On the whole, I have found db_VISTA easy to use, very fast with a key find, and powerful enough for any DBMS use I can imagine on a microcomputer."
Michael Wilson, Computer Language

db_VISTA Version 2.2

Features
- **Multi-user** support allows flexibility to run on local area networks
- **File structure** is based on the B-tree indexing method and the network database model
- **Run-time size**, variable—will run in as little as 64K, recommended RAM size is 256K
- **Transaction processing** assures multi-user database consistency
- **File locking** support provides read and write locks on shared databases
- **SQL-based** db_QUERY is linkable
- **File transfer** utilities included for ASCII, dBASE optional
- **Royalty-free** run-time distribution.
- **Source code** available.

Database Record and File Sizes
- Maximum record length limited only by accessible RAM
- Maximum records per file is 16,777,215
- No limit on number of records or set types
- Maximum file size limited only by available disk storage
- Maximum of 255 index and data files

Keys and Sets
- Key length maximum 246 bytes
- No limit on maximum number of key fields per record—any or all fields may be keys with the option of making each key unique or duplicate
- No limit on maximum number of fields per record, sets per database, or sort fields per set
- No limit on maximum number of member record types per set

Operating System & Compiler Support
- **Operating systems:** MS-DOS, PC-DOS, UNIX, XENIX, SCO XENIX, UNOS, ULTRIX, VMS
- **C compilers:** Lattice, Microsoft, IBM, DeSmet, Aztec, Computer Innovations, XENIX and UNIX

Utilities
- Database definition language processor
- Interactive database access utility
- Database consistency check utility
- Database initialization utility
- Multi-user file locks clear utility
- Key file build utility
- Data field alignment check utility
- Database dictionary print utility
- Key file dump utility
- ASCII file import and export utility

*The benchmark procedure was adapted from "Benchmarking Database Systems: A Systematic Approach" by Bitton, DeWitt and Turbyfill, December 1983.

PT47

RAIMA™ CORPORATION

High-Speed Programming Tools, Designed for Portability

Call Toll-Free Today!
1 (800) db-RAIMA
(that's 1-800-327-2462)

3055-112th Avenue N.E. • Bellevue, WA 98004 USA • (206) 828-4636 Telex: 6503018237 MCI UW

Speed Infusion

Part 2

A second group of accelerator boards for the PC are analyzed that incorporate an 8086 CPU operating at high clock speeds.

TED MIRECKI



PHOTOGRAPH • MARC DAVID COHEN

In the quest for better computing speed on the IBM PC, the simplest solution is to increase the frequency of the processor's clock. Six boards that implement this method were reviewed in "Speed Infusion, Part 1," (Ted Mirecki, February 1987, p. 126). But the brute-force application of megahertz quickly reaches the limits imposed by the response speed of the various integrated circuits (ICs) in the system. As a result, the speed increase possible with this approach is a modest 50 percent—barely noticeable. Exceeding the PC's speed limit by a significant margin requires more drastic action.

Two factors control the computational throughput of a computer: the clock frequency (the rate at which primitive microprocessor operations are performed) and the amount of work performed at each such operation. Once the first of these factors has been pushed to the limit, the next step is to increase the second. But the amount of work done at each clock cycle (or conversely, the number of clock cycles needed to perform a given operation) is an unalterable characteristic of a microprocessor. Therefore, the only way to increase this parameter is to replace the PC's microprocessor with another, more capable one.

Reviewed in this article are five boards that speed-up the PC by replacing the 8088: Microsoft's Mach 10, MicroWay's Number-Smasher/ECM with the MegaDOS memory management unit, Quadram's Quadsprint, and two boards from Univation—the PC Turbocharger and the Dream Board.

Several approaches are possible in designing an accelerator board around a new microprocessor. The most basic choice is which processor to use, as this determines other design criteria. Although in theory any microprocessor will do, the design is simplified and flexibility is gained by staying in the same hardware family. This means using one of the Intel microprocessors: an 8086, 80186, 80286, or 80386.

The next decision is whether the new CPU is to replace the original 8088 or be installed alongside of it. If the 8088 is replaced, the accelerator is known as an *emulator*, because the new microprocessor must emulate all


CLASS II

PHOTO 1: *Microsoft Mach 10*



PHOTO 2: *MicroWay Number Smasher/ECM*



PHOTO 3: *Quadram Quadsprint*



PHOTOGRAPHS • BLAKESLEE/LANE

PHOTO 4: *Univation PC Turbocharger*



PHOTO 5: *Univation Dream Board*



Two basic types of 8086 accelerator boards are represented: caching boards, which provide 4KB to 8KB of 16-bit memory, and full-complement boards, which provide at least 640KB of conventional memory on a 16-bit bus.

Photo 1: The Microsoft Mach 10 is a caching board with 8KB of high-speed, 16-bit memory. It incorporates an on-board mouse controller. The speed switch provides visual indication of the clock speed.

Photo 2: The MicroWay Number Smasher/ECM provides a full megabyte (1,024KB) of 16-bit memory, of which up to 1,016KB can be available to DOS.

Photo 3: The Quadram Quadsprint is a caching board with 4KB of high-speed memory. It does not have a mechanical speed switch; its speed is controlled by software.

Photo 4: The Univation PC Turbocharger board offers a full 640KB complement of memory accessible on a 16-bit bus.

Photo 5: The Univation Dream Board has 1MB of 16-bit RAM that provides 640KB of conventional memory; the rest is expanded memory, conforming to the specification.

of the functions of the original configuration. Of course, if the system is to run all of the same programs, the new processor must be compatible with the 8088 at the object code level. Therefore, this option is available only if the chosen CPU is one of the above-mentioned Intel models or a close compatible, such as the Nippon Electric Corporation (NEC) V20/30.

If the 8088 remains, the accelerator is called a *coprocessor*. This does not imply that the two CPUs do coprocess, that is, dynamically share the work load. In most cases, only one is active at any given time, and the switch between them is performed by the user. The advantage of this design is greater compatibility with the original PC configuration because an actual 8088 can be called upon when needed. The disadvantage is that the 8088 mode is available only at the original clock rate of 4.77 MHz, but an emulator can, to the extent of its compatibility, mimic the 8088, even at a high rate of speed.

A final design criterion (at least of those visible to users) is how to implement the interface between the accelerator's CPU and system memory. The whole point of adding a new CPU to the PC is to access memory 16 bits at a time instead of the system's original 8 bits, and to run at a clock rate that is not limited by the response time of the original memory chips. This requires high-speed memory and a 16-bit data bus on the accelerator board, but the designer has the choice of making all or only some of the system memory accessible at high speed.

To provide all of the memory on a high-speed bus, the accelerator card must allow for at least 640KB on board. Also, another 8KB or 64KB may be provided for copying the BIOS and BASIC code from ROM into high-speed RAM. Then, the only accesses to memory via the motherboard's 8-bit bus will be to the video buffer, unless the accelerator board also incorporates a video adapter.

If the accelerator is a coprocessor, it has its own memory separate from that of the original CPU on the motherboard. But if it is an emulator, only one CPU and one memory space are present, so the original memory is unused. Memory expansion cards can be removed, but motherboard memory must remain because the PC will not boot without memory on the motherboard. In a PC/XT, only one bank of 64KB must be left in place, but in an original PC, all four banks on the motherboard must be populated with chips if the memory space above it is not empty.

TABLE 1: *Features Comparison*

	MICROSOFT	MICROWAY	QUADRAM	UNIVATION	UNIVATION
MODEL	Mach 10	ECM	Quad-sprint	Turbo-charger	Dream Board
PRICE	$549	$1,199	$345	$995	$750
CLOCK SPEED (MHz)	9.54	9.54/11.62	9.54	9.54	9.54
MAX. ON-BOARD MEM.	8KB	1MB	4KB	640KB	2MB
SPEED CHANGE BY					
Toggle switch	●	●	○	●	○
Hot-key program	○	●	○	●	●
Transient program	○	●	●	●	●
I/O PORTS	—	C0H, E0H 1BEH, 2AEH	1F8H	C0H-DFH, E0H-FFH	C0H-DFH, E0H-FFH, 2x8[a]
OTHER FEATURES	Mouse port, Windows	DOS memory up to 1MB	—	—	EMS memory

● = *Yes* ○ = *No*

[a] *Where x is any one port 208H through 2F8H.*

The excessive use of I/O port addresses by some of these accelerators could cause compatibility problems—especially if they cannot be reassigned.

The alternative to providing a full complement of high-speed memory is to provide only a small area as a high-speed cache. This approach is based on the premise that in most programs, much of the time is spent in tight loops, and that a significant increase in overall speed can be achieved by storing only these loops, rather than the entire program, in high-speed memory.

A cache is typically implemented with 4KB to 8KB of high-speed memory to hold a copy of the information from the main memory, and an array of mapping bits that specify whether a particular address is or is not in the cache. At each read from memory, hardware logic tests the mapping array to determine whether the contents of the desired location are already in the cache; if not, the CPU is idled while the data are obtained at slower speed from main memory. The fetched information is made available to the CPU and simultaneously cached in the high-speed memory in anticipation of its subsequent reuse. When the same information is read again, the mapping array indicates that the data are already in the high-speed memory (this is called a *cache hit*) and it is fetched at high speed.

If the information is not needed again, caching provides no benefits. Caching does not improve the speed of writing to memory because, even if the target address is in the cache, writing is done to both high-speed and main memory simultaneously, and, thus, is limited by the latter's slower speed.

These variations in design provide several ways of categorizing accelerator boards: by the type of microprocessor, by whether they are emulators or coprocessors, or by how much high-speed memory they provide. In this series of articles, accelerators are classified by the type of processor. The first article described motherboard accelerators that use an 8088 or equivalent (Class I), this article reviews 8086 boards (Class II), and future installments will consider 80286 and 80386 boards (Class III). The general characteristics of the boards covered in the article are shown in table 1. Prior to examining each board individually, it would be useful to note some of their similarities and to review the characteristics of the 8086.

CLASS EMULATORS

All five boards run the processor at 9.54 MHz, obtained by doubling the motherboard clock frequency. Two of them (Quadsprint and Mach 10) have cache memory; the other three provide at least 640KB of high-speed memory on board. All five are emulators that replace the motherboard microprocessor; in all cases, a ribbon cable with a 40-pin plug at the end connects the board to the vacated 8088 socket. Because of the similarity of the two microprocessors, it is quite possible to fully emulate the 8088 with the 8086. Two basic differences exist between them. First, the data bus is 16 bits wide on the 8086 versus 8 bits on the 8088. Thus, each memory access on the 8086 can fetch a

12MHz SPEED . . .
. . . plus A MEGABYTE FOR DOS!



THEY ALL NEED NUMBER SMASHER/ECM™

Turn your PC or XT into the machine it should have been! The 12 MHz Number Smasher/ECM is the fastest accelerator on the market. It is also the most powerful, providing a **true megabyte** for DOS!

To break the 640K DOS barrier MicroWay designed a Memory Management Unit (MMU) that is tailored to DOS plus a 2000 byte resident driver – MegaDOS™. MicroWay calls this breakthrough Extended Conventional Memory. When you type CHKDSK with the board installed, your system will report 1,036,288 bytes total memory and 1,010,016 bytes free! Any conventional DOS program can utilize a full megabyte for data or *code* without changing a byte.

Downloading a mainframe application? ECM memory runs with any program that uses DOS for screen services including RM and MS FORTRAN and MS and LATTICE C! This means you have an additional 384K available for oversized applications. Programs which write directly to the screen require a simple patch to adhere to the new standard. MicroWay has already developed patches for the Lotus, WORDSTAR and AUTOCAD screen drivers. Release 1A of 1-2-3 jumps from 535,516 to 916,444 bytes available and runs faster than Release 2 for most worksheets.

Number Smasher/ECM is 100% compatible with all hardware and software including EMS and EGA boards. The compatibility is a result of control: its speed is switch, keyboard or software selectable from 4.77 MHz to 12.0 MHz. Applications which have not been upgraded to ECM can still be run by setting DOS to 640K or 704K and using the memory above DOS for I/O enhancers.

Number Smasher/ECM runs floating point bound programs faster than an AT or any other 80286 based machine. In fact, Number Smasher's 12 MHz 8087 runs a factor of three faster than the standard 80287 on the AT, delivering up to 125 kflops. Software is included for RAM Disk, print spooler, and disk caching, which speeds up floppy and hard disks by a factor of 2 to 10!

Number Smasher/ECM is the most cost effective productivity tool you can buy. The base board which runs at 9.54 MHz comes with 512K and costs only $599! The complete system which includes a motherboard accelerator, one megabyte of memory and a 12 MHz 8087 is just $1199. Call today to discuss your particular configuration. Remember: *"The advantage of buying from MicroWay is outstanding personal service."* (PC Magazine, 6/10/86 – p. 162)

MicroWay

The World Leader in 8087 Support

P.O. Box 79, Kingston, Mass. 02364 USA (617) 746-7341
32 High St., Kingston-Upon-Thames, U.K., 01-541-5466

Number Smasher, ECM and MegaDOS are trademarks of MicroWay, Inc. MicroWay is a registered trademark of MicroWay, Inc.

CIRCLE NO. 155 ON READER SERVICE CARD

word instead of a byte. Second, the 8086 instruction prefetch queue is 6 bytes long, and the bus interface unit fetches the next instruction word when the execution unit removes two bytes from the queue. The 8088's queue is 4 bytes long and an instruction byte is fetched from memory as soon as a single byte is removed from the queue. In theory, this difference in the queue architecture can cause problems with self-modifying code, but in practice such problems seldom arise.

Microsoft. The Mach 10 combines an accelerator and mouse interface card in one slot. It is usually bundled with the Microsoft Mouse and the Windows package. For the price, it seems like a terrific bargain, but all is not as it appears to be.

The Windows package that includes the Mach 10 is the same as the one available separately, the mouse package is not. Its minimal documentation describes how to copy the driver files and how to remove the ball for cleaning. The software that comes with it contains drivers for mouse-aware programs, such as Microsoft Word; the menu-building and other software required to interface it to other programs are sold separately. Although the cost is only an additional $50, it is disappointing that not all components of the package are completely functional straight out of the box.

The Mach 10 is basically a good, if unspectacular, product. It is a caching board with 8KB of high-speed memory. Jumpers set at installation control whether all data (including BIOS and BASIC code from ROM) or only data from RAM gets cached. Disabling ROM caching prevents problems with programmed delay loops in early BIOS versions; the documentation suggests that ROM code dated prior to 10/27/82 should not be cached.

The speed of the Mach 10 is controlled only by hardware, not by hot keys or the execution of programs. Two speed switches are provided. The first is a two-position toggle switch that is mounted permanently on the board's rear bracket. Depending upon the switch position, the system will boot up in either fast or slow speed. The second switch is a momentary-contact push button mounted in an attractive plastic box with the Microsoft logo and a pilot lamp that lights up in high speed. Of the five boards tested, this is the only one that provides a visual indication of the system's speed. This switch mounts to the system unit and connects to the board with a cable that plugs into a receptacle on the rear bracket. When connected, it disables the toggle switch, and the system always boots up in slow speed. The board can be switched into high speed, however, by pressing the button, even before the completion of the power-on diagnostics.

The connectors for both the removable speed switch and the mouse are the new Microsoft InPort style; they resemble scaled-down DIN plugs of the type used to connect the PC keyboard. To avoid confusion between the two receptacles on the bracket, they are plainly labeled and keyed so that each will accept only its matching plug.

The documentation follows the standard Microsoft format, and is well done. Detailed drawings illustrate every phase of the installation, and the instructions are clear and complete. A useful index is included. The only complaint is that the tone is aimed at a user with much less experience than the typical installer of something as advanced as an accelerator board.

The speed of the Microsoft Mach 10 accelerator board is controlled only by hardware, not by hot keys or the execution of programs.

The installation and operation of the Mach 10 went smoothly. Because all of the board's functions are controlled by hardware switches, it has no I/O ports, thus avoiding this potential area of conflict with other hardware. It seems conservatively and carefully designed to stay within the capabilities of the host system, and although that means less than spectacular performance, it also means reliability.

MicroWay. The Number Smasher/ECM accelerator board contains a full megabyte (1,024KB) of RAM, in four banks of 256KB, 150-nanosecond (ns) chips. Installation is straightforward. Besides the cable connecting to the 8088 socket on the motherboard, a noise suppression module, consisting of a black plastic box containing resistors, is plugged into the 8087 socket. The 8087, if used, must be rated at 10 MHz, and resides on the Number Smasher. A toggle switch protruding through the rear bracket changes the clock frequency from normal to double the frequency of the motherboard. The boot-up speed may be either fast or slow, depending on the position of the switch, and the system speed may be changed at any time by flipping the switch, by hot keys, or by running a DOS program.

At boot-up, only 512KB of memory are recognized; using any more memory than this requires installing the MegaDOS device driver and then running the Memset program. Why the default was chosen at 512KB and not 640KB is not clear. It is possible to change this by setting switches on the Number Smasher, but the required settings are not documented. Users wishing to change the boot-up defaults of the board should contact MicroWay technical support for instructions.

The ECM in this board's name stands for expanded conventional memory; it is a feature of the MegaDOS device driver that allows setting the memory recognized by DOS to any value up to 1,016KB. The remaining 8KB is reserved for copying the ROM BIOS into the top of RAM. Memory above 640KB is normally reserved for system use—segments A000H and B000H for video display buffers, and segments C000H through F000H for expanded memory specification (EMS) page frames and ROM. The Number Smasher supplies duplicate memory addressed at these locations, and it dynamically switches between its on-board memory and the original memory on video and disk controllers. Access to EMS page frames is not automatically recognized; therefore, ECM memory must be limited to the segments below those containing EMS frames when EMS memory is being used. But this problem is minor compared with the next one.

Switching video buffers in and out of the memory space works fine for video output performed via BIOS calls, but cannot help in cases of direct writing to video adapter memory. As a result, many major applications, such as Lotus 1-2-3, dBASE III, Microsoft Word, and WordPerfect 4.1, will not run when DOS memory extends into the video segments. MicroWay supplies video drivers that fix this problem for two standard application programs: MicroPro's WordStar and Lotus 1-2-3 release 1A. Other programs that write directly to video buffers limit the DOS memory to 704KB, or 640KB with an IBM EGA.

It is possible to run Memset to reduce the DOS memory allocation before running one of these ill-behaved programs and set it back up thereafter, but with two problems. First, instead of moving the DOS top-of-memory pointer on the fly, Memset performs a warm re-

BULLET PROOF



Why do we make it that way?

Customers expect all accelerator boards to run as promised. The sad truth is they don't. STD built it's reputation on fulfilling the promise..." We build Bullet Proof Boards!" Starting with our PC-286 accelerator board running DOS and Protected Mode XENIX, we continue to keep the promise with the newest member of our family, our 386 board.

Our reputation depends on it.

The new STD-386 16MHz board was designed to be compatible with 6 and 8MHz IBM PC/AT's and popular PC/AT Clones. It is EGA compatible and supports Real-and Protected-Mode software. It is a total hardware solution. From our experience, we know our approach insures full compatibility. The STD-386 is a plug-and-play 80386 CPU board taking up one slot and offering memory choices from 1 to 16 Megabytes of RAM. An optional 80387 coprocessor is available.

It all comes down to - It runs all your applications!

The STD-386 was designed from thousands of hours of experience building the world's most reliable 286 accelerator board. Before any board is ever shipped, it will go through nearly 100 hours of burn-in and testing. We know our reputation is on the line, and we proudly invite you to give us a call to find out how easy it really is to upgrade your company's AT's with the new world standard The STD-386 16MHz.

IBM PC/AT is a registered trademark

ASK ABOUT OUR DEVELOPER'S DISCOUNT PROGRAM.

STD

Listening To Customers Is Our Future.

Seattle Telecom & Data, Inc. 12277 134th Court Redmond, Washington 98052-2429 (206) 820-1873

CIRCLE NO. 170 ON READER SERVICE CARD

boot, losing any RAM-resident data and programs. Second, these types of applications are usually the very ones that would most benefit from a memory space larger than 640KB. But MicroWay does not aim the Number Smasher at the user needing large amounts of memory to run prewritten applications. Rather, this board is meant for systems running large custom-written programs, especially in the areas of scientific and engineering applications. For instance, ECM memory may be best for running a large FORTRAN program that needs 700KB to 900KB of memory, provided it uses well-behaved BIOS video calls.

Although the ECM scheme is less than successful, the Number Smasher's 1MB of RAM is not wasted because the memory above DOS can be used for other purposes. As previously mentioned, the contents of ROM may be copied into segment F000H of the on-board RAM; this may be limited to the 8KB of BIOS or may include the 32KB of the BASIC interpreter. Any memory remaining below the ROM image and above DOS may be used either for a disk cache or for a RAM disk.

In operation, the Number Smasher was not totally reliable. It pushes the PC's system to its limit, and occasionally beyond. At boot-up, spurious keyboard or hard-disk errors would crop up occasionally. The keyboard problems seemed to have no effect on the boot process and subsequent operations, but the hard-disk errors effectively would remove the hard disk from the system, so the system would boot up in cassette BASIC if the diskette drive was empty. On other occasions, after a successful boot-up the first keystroke would crash the system. Once up and running, however, no problems were encountered.

MicroWay also provides a way to run the Number Smasher at almost 12 MHz. This is done by installing a motherboard accelerator alongside the Number Smasher; the one supplied is a version of MicroWay's 87/88 Turbo reviewed in the previous article. The Number Smasher runs at either one or two times the motherboard clock rate, and the Turbo card runs the motherboard at either 4.77 or 5.81 MHz, giving a choice of four system speeds: 4.77, 5.81, 9.54, and 11.62 MHz. However, the Number Smasher/Turbo combination would not run reliably in the test system; often the system would crash when switched to a speed faster than 6 MHz. This was most likely the result of limitations of components on the motherboard, because the operation was more reliable in another, newer, PC with higher-rated components. As explained in the article on Class I accelerators, one of the requirements for installing the 87/88 Turbo card is a socketed 8284 clock-generator chip on the host system's motherboard. MicroWay also recommends an auxiliary cooling fan for 12-MHz operation.

The documentation, while not oriented toward the beginner, is seriously lacking in technical information for the more experienced user. The Number Smasher is a complex product, and some explanation of what it does and how it works would be beneficial to those apt to purchase it. The installation instructions are excellent, but no mention is made of several items: the I/O addresses used by the hardware (0C0H, 0E0H, 18EH, 2A8H), the fact that MegaDOS uses interrupt 61H or the purpose of 8 of the 11 switches on the board (these switches enable memory above 512KB at boot-up).

In operation, the MicroWay Number Smasher/ECM was not totally reliable. It pushes the PC system to its limit, and occasionally beyond.

All in all, when the Number Smasher works, it works well. But its lack of technical information and the unexplained intermittent failures that occurred during testing made using this product a frustrating experience.

Quadram. The Quadsprint is a caching board with 4KB of high-speed memory. As far as accelerators go, it is uncomplicated and reliable, but has the drawback that it does not support an 8087 coprocessor. There is no on-board socket for an 8087, and one left on the motherboard is ignored.

Switching between high and regular speed can be done only through software. Unfortunately, Quadram does not provide programs to perform the speed switching, but merely gives the BASIC OUT statements that produce high and low speeds.

An on-board jumper sets the boot-up speed of the board, but it also reverses the action of the speed-switching port. If the boot-up is performed at slow speed, writing a 1 to port 1F8H switches to high speed and writing 0 returns to slow speed. But if the jumper is set for booting at high speed, writing a 1 drops down into slow speed and writing 0 enters high speed.

The address of the speed-switching port can be changed by jumpers, but alternate addresses are not documented. Users who encounter problems are advised by the manual to contact Quadram's technical support for help.

The documentation regarding speed switching is not quite accurate. It states that the jumper and the ports disable memory caching only at low speed and enable it at high, but, in fact, the clock speed is also switched between 4.77 MHz and 9.54 MHz.

Otherwise, the documentation is acceptable. The installation instructions are clear and to the point, with useful illustrations. One good addition is Quadram's inclusion of a section on the theory of operation, although it is not well written. The extensive glossary that is included may bring new users more confusion than enlightenment, because it contains many terms and definitions not applicable to the Quadsprint. For example, the term *caching*, which is used extensively throughout the manual, is defined in the glossary only in terms of disk I/O caching, not memory caching as it applies in this instance.

Although no problems were encountered with installing and using the Quadsprint, it cannot be recommended enthusiastically. The do-it-yourself speed switching programs and the generally lackluster performance place it at a slight disadvantage in comparison with the other Class II boards.

Univation. Two accelerator boards from this company were reviewed: the PC Turbocharger and the Dream Board. The Turbocharger provides a full complement of high-speed memory in two banks of 256KB chips and two of 64KB, all of it rated at 150 ns. An option is available to address 64KB of this at segment F000H to hold a copy of the BIOS and BASIC ROM code. This is somewhat wasteful, first because the entire ROM code, including the BASIC interpreter, takes up only 40KB, and second because it is not possible to allocate only 8KB for a copy of the BIOS code. Users without interpreted BASIC must still lose all 64KB if they want to speed up BIOS operations. Further, the option to locate a bank in the ROM space is made with a jumper at installation, and cannot be changed without opening up the system.

Installation of the Turbocharger involves making the usual ribbon cable connection to the 8088 socket, and inserting a dual in-line package (DIP)

noise suppression unit into the 8087 socket on the motherboard. In addition, if the system is an early PC-1 model with a 64KB motherboard, two ICs on the Turbocharger must be removed and replaced with two others provided.

All three methods of speed switching are provided: a toggle switch on the rear bracket, a resident hot-key program, and a pair of programs that may be run from the DOS prompt or from a batch file. The speed at boot-up is controlled by the position of the toggle switch. Once running, however, no indication is given of the current system speed, and the position of the toggle switch does not help because its setting may have been overridden by software. Speed-switching was consistently reliable using any of the three modes.

The documentation is very good, with sections on hardware and software installation, operation, troubleshooting, and, most importantly, it includes a useful technical reference. The latter even includes the assembly language source code for the hot-key speed-switching program. The I/O port usage is documented, but no method is documented to change the port assignments in case of conflict with other devices. The number of ports to which the board responds seems inordinately large (see table 1), but the manual claims that these addresses "are not generally of use by software." IBM's hardware technical reference calls them "reserved."

Although its performance is not significantly different from the rest, the Turbocharger distinguishes itself by its superior documentation and reliable operation, making it the most trouble-free to install and operate.

Univation's second entry, the Dream Board, might be considered the ultimate multifunction board. It provides up to 2MB of high-speed RAM on a 16-bit bus: 640KB for conventional DOS memory, the rest for expanded memory complying with the Lotus/Intel/Microsoft standard. Optional daughterboards add a battery-backed clock/calendar and either two serial ports or one serial and one parallel port. A fully outfitted Dream Board adds a lot of power to a PC in a single slot.

The documentation is every bit as good as the Turbocharger's—the installation process is easy, yet the user is kept informed of what is being done. Before the Dream Board can be plugged into a system, an installation program is run to determine the current system configuration. The program's output guides the user in making the correct switch settings.

TABLE 2: *Benchmark Results*

	IBM	MICROSOFT	MICROWAY	MICROWAY	QUADRAM	UNIVATION	UNIVATION
MODEL	PC	Mach 10	ECM 9.5 MHz/	ECM 11.6 MHz/	Quad-sprint (ratio)	Turbo-charger (ratio)	Dream Board (ratio)
BUSPERF	0.045[a]	0.90	4.08	4.99	0.90	4.08	4.08
ATFLOAT							
No 8087	106	1.93	2.30	2.79	1.86	2.26	2.26
With 8087	22	1.69	2.00	2.44	—	2.00	2.00
VDISK ASSEMBLY	34	1.42	2.17	2.70	1.34	2.21	2.21
LOTUS 1-2-3							
No 8087	122	1.54	1.56	1.72	1.54	1.56	1.56
With 8087	41	1.35	1.39	1.39	—	1.39	1.39
dBASE SORT	119	1.21	1.38	1.38	1.19	1.35	1.35
WORD REPAG.	50	1.67	2.38	2.86	1.61	2.38	2.38

[a] *The numbers in this column are times in seconds for the base machine—an IBM PC with a 4.77-MHz 8088. The numbers in the remaining columns are percentages relative to the first-column unit figures (base 100), and represent the increase in PC performance yielded by the accelerator boards.*

Benchmarks improved twofold at best when the accelerator boards were installed.

As an accelerator, the Dream Board operates in a manner that is similar to the Turbocharger. One noticeable difference is that the copy of ROM, if desired, is kept in memory above 640KB and does not reduce the conventional memory available to DOS. Another difference is that the rear bracket carries two port connectors as well as the speed switch. As a result, the switch is placed up near the top of the bracket where it is inaccessible once the board is installed. This switch may be set at installation only, so its sole practical purpose is to determine the system speed at boot-up. However, it offers two other ways to change the speed: by running a program from the DOS prompt, or by installing a resident program that responds to hot keys.

Apart from its function as an accelerator, the Dream Board leaves much to be desired as an EMS board. Its Expanded Memory Manager does not implement the full set of EMS functions; it supports only the rudimentary ones numbered 1 through 8. (For a description of EMS functions, see "Expandable Memory," Ted Mirecki, February 1986, p. 66.) It is not clear whether the functions are missing because they were not programmed in the software, or because hardware-support is not there. Either way, it is a not a full implementation of the EMS standard.

Furthermore, the Dream Board's usefulness as a multifunction board is also somewhat flawed. Of the two kinds of daughterboards (serial-to-serial or serial-to-parallel), only one type will mount on any given Dream Board. Two models are available: one with connectors for two serial ports (one 9-pin and one 25-pin), and the other with connectors for one serial port and one parallel port. The I/O modules have no connectors of their own. Therefore, the commitment to the port configuration must be made at the time the baseboard is purchased, not when the daughterboard is added. The test unit came without the daughterboard.

Overall, the Dream Board cannot be recommended as highly as the Turbocharger. Although it is a capable accelerator, its functionality as an EMS board is seriously flawed. It might be worth considering for a system with a severe slot shortage, but in most cases, especially in a PC/XT or compatible, the same capabilities could be better provided by two or more boards (each tailored to a specific function).

ACCELERATED PERFORMANCE

The testing procedure for these board was the same as the that for the Class I accelerators as described in the first article of this series. The test system was an IBM PC-2 with 640KB (reduced to 256KB when testing boards with their own complement of high-speed memory), two diskette drives and a hard disk. The 8087 boards with a full complement of 16-bit memory, this performance can be directly measured by the BUSPERF program (published with the previous article, listings 1 and 2, pp. 156-157). The slight excess over 4.0 is due to lower overhead for dynamic RAM refresh, as explained in the earlier article on Class I accelerators.

For the caching boards, the results of BUSPERF do not reflect the effect of the high-speed cache memory, but only the speed of accessing the system's normal memory via the 8-bit bus at 4.7 MHz. This is a result of the straight-line sequence of instructions in BUSPERF, and points out the fact that a cache is useful only on second and subsequent accesses to a given memory location. For code fetches, this implies a loop that can fit within the cache memory.

When fetching code, the 8086 issues a bus transfer request for one word at a time, but the 8088 bus is capable of transferring only one byte per bus cycle. Thus, 2 bus cycles of 4 clocks each, or a total of 8 periods of the motherboard clock, must be performed for each request. In terms of the processor clock (which runs exactly twice as fast as the bus), it takes exactly 16 clock cycles to transfer each word from the main system memory, compared with 4 clock cycles for a transfer from high-speed on-board memory. From the processor's point of view, that is equivalent to 12 wait states per access. And if the bus cycle needs more than 4 clock cycles (for example, when transferring to or from an I/O port), each additional clock cycle on the bus inserts two processor wait states.

For reasons that could not be determined, both of the caching boards reviewed here (the Mach 10 and Quadsprint) inserted two additional processor wait states on every access to off-board memory. Their bus cycle is, thus, 18 processor clocks (instead of the minimum 16), resulting in a bus performance that is 10 percent lower than that of a standard PC.

The results of the benchmark tests are given in table 2. With the exception of BUSPERF, the tests are representative of practical applications performed on a typical business or development system. A brief description of each test follows; see the article on Class I accelerators for more comprehensive information.

ATFLOAT is a C program that performs a matrix multiplication. (See "Out from the Shadow of IBM. . .," Steven Armbrust, Ted Forgeron, and Paul Pierce, August 1986, p. 53. An updated version 1.02 of ATFLOAT is given in "Updating the Evaluation Suite," Steven Armbrust, Ted Forgeron, and Paul Pierce, March 1987, p. 70.)

The assembly test timed the assembly of the VDISK program supplied with DOS 3.2; it was converted from listing to source code format by a BASIC program (see "Same Language, New Architecture," Ted Mirecki, October 1985, p. 48). Microsoft's MASM version 4.0 was used; the input source file and output object file were both on RAM disk.

The Lotus 1-2-3 test generates a mortgage payment table for 80 different interest rates and 30 terms, using the Data Table 2 feature.

The dBASE test is a sort of 900 records of the author file from the sample application used for evaluating database managers (see "Evaluating Data Managers as Development Tools," Julie Anderson, August 1985, p. 46).

The word processor test is a repagination of a 19-page document with Microsoft Word. This was the only test that was timed using a stopwatch.

For operations with real numbers (ATFLOAT and Lotus 1-2-3), results are reported both with and without an 8087 numeric coprocessor. The Quadsprint does not support an 8087; the others provide an on-board socket for one. With these boards, an 8087 rated at 10 MHz is required. For the Number Smasher, a specially selected 8087 is required for operation at 12 MHz. Users wishing to operate this board with an 8087 at this speed should purchase it so equipped by MicroWay. Besides selecting a unit capable of operating at this clock rate, MicroWay also outfits it with a massive heat sink—a requirement for long-term operation at high speed.

A FULL COMPLEMENT

On several occasions during testing of these boards, a 301 keyboard error was indicated on boot-up in high-speed mode; this never prevented the system from coming up, and did not seem to affect its operation thereafter. This may be a warning that the PC is stressed to its limit, or may be only an anomaly of the keyboard controller.

As expected, the boards that provide a full complement of high-speed memory provide somewhat better performance than that of the caching boards. Although the difference is quite obvious in the measured results, it is barely noticeable in practice. With their lower prices, the caching boards provide respectable value—with some reservations. The Quadram Quadsprint does not support the 8087 and does not provide speed-switching programs, and the Microsoft Mach 10 does not provide full documentation and software support for the mouse. For these reasons, and not because of any inherent disadvantage of caching boards, neither one can be recommended.

At 9.5 MHz, the three full-complement boards provide almost identical performance. The MicroWay Number Smasher/ECM is a distinctive product for specialized applications, specifically scientific number-crunching chores requiring more than 640KB of memory. The 12-MHz capability, although almost unnoticeably different from operation at 9.5 MHz, can be useful when the last measure of performance matters. Because this product pushes significantly beyond the original design parameters of a PC, it does have reliability problems. This accelerator board will run only in selected systems, so it must be carefully tested before a commitment is made. Users who need the particular benefits provided by the Number Smasher, and who have a system that is capable of accommodating it, will find few other alternatives.

The other two full-complement boards come from the same company—Univation. The Dream Board, although a capable accelerator, is not satisfactory in its other functions, specifically, its EMS memory provision and its I/O ports. The PC Turbocharger is the clear choice as a general-purpose Class II accelerator board. Its advantages are reliability and superior documentation; its appeal lies in its ability to speed up the operation of the PC under the widest variety of conditions.

Microsoft
16011 N.E. 36th Way
Redmond, WA 98073-9717
206/882-8088
Mach 10
CIRCLE 339 ON READER SERVICE CARD

MicroWay
P.O. Box 79
Kingston, MA 02364
617/746-7341
Number Smasher/ECM
CIRCLE 340 ON READER SERVICE CARD

Quadram Corporation
1 Quad Way
Norcross, GA 30093-2919
404/923-6666
Quadsprint
CIRCLE 341 ON READER SERVICE CARD

Univation
1231 California Circle
Milpitas, CA 95035
408/263-1200
PC Turbocharger
Dream Board
CIRCLE 342 ON READER SERVICE CARD

Ted Mirecki has been a contributing editor to this magazine for two years. He recently joined the editorial staff at its location in Columbia, Maryland, as a technical editor.

Connect with
network more
TeleVideo

TeleVideo and users, for less.

With our new PM/286 network server, you can put together high-performance networks for up to 40% less than the cost of comparable systems.

Look at the chart. You'll see the TeleVideo PM/286 network server beats the others and still gives you all the power you're looking for.

The performance you want.

Our intelligent network Starboard is designed with an Intel 8088 microprocessor maintaining high throughput, even as users are added. And the PM/286 is powered with the Intel 80286,8MHz engine. So it can handle heavy loads, serving up files almost as fast as you can say "fetch."

The flexibility you need.

The PM/286 gives you more options. It's easy to add up to 24 users. With the PM/286, you can use IBM PCs,* other compatibles or TeleVideo diskless workstations. Our $999 diskless workstations feature built-in network connections, so installation is as easy as plugging them in.

You can select the PM/286 model that best suits your application: 40 or 71 Mbyte hard disk (and room for more); 1 or 2 MB RAM; and up to 24 users. All models include a 1.2 MB floppy, 60 Mbyte streaming tape back-up, and a high resolution monitor.

Software savings, too.

We maximize your software investment because the PM/286 runs a custom version of Advanced NetWare/286,* and is compatible with virtually any single user or multi-user application written for MS DOS, NetWare or NETBIOS. We also support the key programming languages.

Reliability you can count on.

The PM/286 is built on TeleVideo's five years experience in the multi-user network business, with over 87,000 workstations attached to TeleVideo file servers. *Plus, it's backed with our new, unmatched ONSITE warranty service.*

COST PER USER		
	8 User System	16 User System
TeleVideo PM/286	**$1,257**	**$ 926**
IBM Token Ring* Network	$2,058	$1,474
3Com 3Server 3 System*	$1,942	$1,268
Novell* Server System	$2,119	$1,357

Prices are manufacturer list for comparable configurations with hard disk, tape drive, RAM memory, network interface boards and network operating system. Dedicated file server only. No workstation.

Make the right connection.

Now's the time to find out just how much you'll save with the new TeleVideo PM/286 network server.

Call your TeleVideo representative, or 1-800-835-3228 today for more information, and to find out about the TeleVideo seminar coming to your area soon.

Make the best price/performance connection. Connect with TeleVideo.

TeleVideo®

TeleVideo Systems, Inc., 1170 Morse Avenue, Sunnyvale, CA 94088-3568, (408) 745-7760.
Regional offices: West (408) 745-7760; Southwest (714) 476-0244; South Central (214) 550-1060; Southeast (404) 447-1231; Midwest (312) 397-5400; East (516) 496-4777; Northeast (617) 890-3282.
European offices: Amsterdam 31.2503.35444; Paris 33.1.4687.34.40; London 44.9905.6464.

*IBM PC and Token Ring are trademarks of International Business Machines Corporation. Advanced NetWare/286 and Novell are trademarks of Novell, Inc., 3Com 3Server3 System is a trademark of 3Com Corporation. © 1987 TeleVideo Systems, Inc.

CIRCLE NO. 182 ON READER SERVICE CARD

A Multiuser Solution

Taking the best from timesharing and networking, Classic Technology offers a practical solution for multiuser systems.

PHOTOGRAPH • WALTER LARRIMORE/BLAKESLEE LANE

STUART BLAIR

Until the advent of the IBM PC/AT, sharing computers was practical only on minicomputers or mainframes. Rapidly increasing software applications for CPU cycles, memory, and I/O bandwidths still make the AT inadequate for many tasks. Nevertheless, broad categories of PC applications use only a fraction of the system capabilities that are available on an AT.

Users can benefit from a true shared PC environment—they can save money by sharing expensive computer components, control the storage and organization of data, simplify communications among system users, and increase system reliability. Companies are beginning to offer multiuser products that reside either on ATs or on PCs that have been enhanced with accelerator boards. These systems are based on three architectural avenues—timesharing, separate microprocessors, and networking. Classic Technology, Inc.'s Multiuser System is designed as a hybrid that incorporates timesharing and networking.

Proven timesharing technology has been borrowed from the minicomputer arena and recast to fit the capabilities and limitations of the PC microprocessor, with varying success. With short time slices and a fast enough CPU, each user perceives the illusion that his program is running continuously on a dedicated computer. Networking a collection of true PCs solves the PC software and video compatibility problems, as well as most of the throughput problems, but it increases the per-user cost. In some cases, the cost per PC of networking actually can exceed the price of the individual PC systems.


IBM

The proprietary hardware of the Classic system implements a traditional timesharing system with a single, fast CPU (a 10-MHz 80286), which is shared in an adaptive timeslicing algorithm among the currently active users. An array of fully IBM-compatible monochrome controllers is bank switched among the users to provide full video compatibility without having to suffer the performance penalties of software video emulation.

The operating system software includes PC-DOS 3.2 and Microsoft Networks. Together, these logically establish a network of virtual PCs, where the network "cable" is nothing more than the backplane of the PC. Transmissions along this cable adhere to definition of the ISO transport layer, but run at bus transfer speeds, which help minimize I/O bottleneck problems.

Classic Technologies offers two implementations of the Multiuser System, one for IBM Personal Computers, PC/XTs and compatibles (collectively referred to as XTs in this article) and the other for AT-class machines. Both systems are identical with one exception: the AT versions use the native 6- or 8-MHz 80286 CPU provided by IBM, while the XTs require a Classic 286 Speed Pak accelerator card containing a 10-MHz 80286 with zero-wait-state memory to augment the CPU horsepower.

Each person on the system uses a workstation with the display CRT and keyboard. The system supports two types of workstations. Classic Technologies supplies a complete unit consisting of an ergonomic (tilt and swivel) monitor, with a detached keyboard arranged in the AT-style key layout. Workstations also can be assembled by the customer using three components: an IBM-compatible monochrome monitor, an XT keyboard, and the Workstation Interface, a small self-powered adapter that merges the monitor and keyboard signals along with an optional serial port into a "network" connector. In either case, a heavy-duty, 25-pin shielded cable routes the signals between the computer and each workstation.

Network cables radiate to each workstation in a star topology from a Workstation Adapter card plugged into the XT motherboard. The Workstation Adapter serves as a controller for one to four workstations. By itself, this adapter contains the video and keyboard interface electronics for a single user as well as mounting positions for three small plug-in Workstation Modules, each of which supports one workstation. For larger systems, additional Workstation Adapters may be installed up to a limit of 16 users.

The system dedicates a complete alphanumeric video adapter to each user, complete with its own 6845 CRT controller chip and a 4KB video buffer. Both the adapter I/O registers and video refresh buffer are bank-switched. A special I/O port (see table 1) selects an active video adapter. When selected, a bank appears as a standard IBM monochrome controller to each workstation, thereby guaranteeing full compatibility with the PC alphanumeric video standard. Special differential drive circuitry allows the video output signal to be driven up to 500 feet to the workstation display CRT.

The operating system software includes IBM's PC-DOS 3.2 and Microsoft's Networks. Together, these products logically establish a network of virtual PCs.

In addition, the Workstation Adapter receives the keyboard input signals from each workstation unit. Any XT-compatible keyboard should work, but keyboards with AT-style electrical interfaces will not. However, many manufacturers supply keyboards with AT key layouts and XT electrical interfaces, which do operate correctly.

The Workstation Adapter is currently incapable of displaying graphics images. However, Classic Technologies is developing an EGA (enhanced graphics adapter) version of the Workstation Adapter based upon the Paradise Systems, Inc.'s PEGA controller chip. This is the same chip that is used in Paradise's AutoSwitch EGA card. By adjusting to the type of software that each user is running, the Workstation Adapter then will be able to automatically emulate any of the following modes of video operation: monochrome, color graphics (CGA), EGA, Hercules monographics, and Plantronics graphics.

The Classic Multi I/O controller card can provide private I/O ports dedicated to each workstation. Coupled with a Workstation Adapter, this controller contains four serial ports, one for each workstation, and a clock-calendar circuit. Classic workstations include an onboard serial-to-parallel converter; a toggle switch on the rear of the workstation selects between serial or parallel mode. Other workstations assembled with the Workstation Interface can tap only the serial port, unless they are configured with an external serial-to-parallel converter. With the Multi I/O option, users 500 feet from the host can run a local printer or mouse.

The 286 Speed Pak accelerator card forms the nucleus of the XT multiuser system, and also is marketed as a standalone product. Driven by a 10-MHz Intel 80286, this two-card module requires adjacent slots in the XT motherboard. (An 8-Mhz version of the 286 Speed Pak is also available, but was not tested.) In addition to the faster CPU, the accelerator contains a socket for the 80287 Numeric Data Processor, as well as a socket for the XT's 8088 CPU that must be relocated onto the accelerator card. A toggle switch on the rear panel of the card allows switching between operating in 8088 mode (standard speed) and 80286 mode (turbo speed), but the system must be powered off to shift gears. The 286 Speed Pak will be reviewed and compared with other

CLASSIC MULTIUSER SYSTEM

XT Base System: $2,595
10-MHz Speed Pak CPU (1MB RAM)
2.5MB RAM Memory Module
Workstation Adapter
MS-NET; Classic Operating System

AT Base System: $2,495
80286 Daughterboard Memory Management Unit
4MB RAM Memory Module
Workstation Adapter
MS-NET; Classic Operating System

Expansion options
Workstation Module: $195
(up to three per Workstation Adapter)
Workstation Adapter: $495
(one to four additional users)
Workstation Interface: $155
(for custom-built workstations)
Classic Workstation: $495
(includes built-in serial or parallel port)

Both the XT and AT base systems support two users if a CGA is used for the PC's display; only one user is supported if a monochrome display is used.

TABLE 1: *I/O Port Usage*

I/O ADDRESS[a]	FUNCTION
100	Memory manager control
102	Memory bank select
110-11F	Multi-I/O 8259 controller
330-334	Memory bank enable/disable
340-34F	Workstation card 8259 controller
370	Video RAM bank select
372	Multi-I/O bank select
3FO-3FF	Memory address configuration

[a]*I/O addresses are given in hexadecimal.*

These I/O port addresses control the custom memory management, keyboard ports, and video controllers; these addresses cannot be reconfigured.

cards in an upcoming article on 80286 accelerators for the PC.

The 286 Speed Pak contains 2.5MB 16-bit memory, expandable to 5MB on an additional card. The memory organization is proprietary to Classic; the system cannot support EMS memory expansion cards. An on-board memory management unit permits the system to create isolated 640KB *partitions* for each workstation, in which are contained a private copy of DOS and the application program for each user.

In addition, the XT's BIOS routines are copied into 16-bit RAM for faster execution. This technique of using IBM's BIOS guarantees a high degree of compatibility, although some device timing loops in the BIOS are reportedly patched after being loaded into RAM to provide proper performance with the accelerator. If an IBM computer is not used, the BIOS is not copied into faster RAM, and the performance advantage, therefore, is not realized.

A typical four-user XT-based system consists of these components:

- An IBM PC, XT, or Classic-approved compatible, with hard disk
- One 286 Speed Pak, a processor accelerator module containing an 80286 10-MHz CPU, and 2.5MB RAM
- One Workstation Adapter, a video controller card capable of supporting from one to four users
- Three Workstation Modules, small piggyback video controllers that mount on the Workstation adapter for users two through four
- Three workstations (displays and keyboards), in addition to the local display and keyboard provided with an XT

In an XT system, this relatively small configuration may require an upgrade from the standard 130-watt XT power supply. A PC system that is equipped only with the standard 62.5-watt supply certainly requires an upgrade. If the system is equipped with any additional option cards, then it probably will require an expansion chassis because with the piggyback cards and cables, the XT chassis is quite full.

The main difference between XT and AT implementations of the Multiuser System is that ATs do not use the 286 Speed Pak and RAM expansion hardware. Instead, a small Memory Management Unit daughterboard is attached at the AT's 80286 CPU socket, and a 4MB memory board is plugged into a bus slot. The Workstation Adapter and workstations themselves are identical to the XT configuration.

SYSTEM ARCHITECTURE

The system's proprietary hardware has been engineered to support two standard operating system software components, IBM's PC-DOS and Microsoft's MS-NET, which are coupled together by Classic's multitasking kernel. The system addresses both performance and compatibility issues by cloning an imaginary network of virtual PCs within one computer. These virtual PCs operate within their 640KB memory partitions carved from the system's 2.5MB to 16MB of memory, and function as workstations or as the network server.

The server partition manages most of the shared resources such as disks, directories, and printers. Because this network is physically a single timesharing system, it contains only one server to operate all shared devices. To conserve hardware resources, the server partition has no assigned console, although for diagnostic and configuration control purposes any workstation can be used as a console for the server partition using the NSWAP command.

The remainder of the virtual PCs operate as network workstations, each running programs for a single user. In essence, the workstations are configured as "diskless PCs" with 640KB of RAM, a console (video and keyboard), and a copy of DOS and MS-NET. Although the entire system is controlled by a multitasking kernel, each workstation partition runs only in single tasking mode. In other words, non-interactive batch programs (other than the spooler supplied with the operating system) cannot be run in the background. Unlike disk-based workstations on a network, the Classic workstations depend on the network server to perform all file reading and writing, as well as most printing. As the server is dedicated to managing shared resources, it cannot run application programs for users.

To provide the complete compatibility required for most PC software, Classic must run in the 80286 real mode. This means that ill-behaved or experimental software run by one user potentially can crash the entire system. Although memory management hardware provides separate memory partitions for each workstation, a program still can corrupt critical memory locations or I/O port addresses used to control multiuser operations.

All of the partitions share a single copy of the XT or AT ROM BIOS and BASIC, in addition to the multitasking kernel. The BIOS and BASIC are the standard ROM firmware modules loaded into 16-bit RAM for improved performance, so that compatibility should not be a problem. The kernel module, called XPORT.EXE, consists of three components: the multitasking timeslice algorithm, an I/O monitor, and the network transport function used to communicate between the partitions. The ROM BIOS and BASIC modules occupy their normal memory segment beginning at F000:0H, while the kernel resides at address E000:0H in the XT implementations and at D000:0H in ATs. Numerous I/O port addresses also are used by the hardware, and are documented in table 1.

A workstation partition's unique memory address space consists of the memory between 0 and 9000:FFFFH, plus the video memory at B000:0H. Whenever a partition has the CPU, it will be mapped into the processor's address space at the above-mentioned addresses. To provide isolation from user modification of low-memory interrupt vectors, a rarely-used 80286 feature is exercised that allows the interrupt vector addresses to be located at an address other than zero. Classic's software relocates the interrupt addresses into

Here's a plug for dBASE.™

Clipper™ NEWS RELEASE

FOR IMMEDIATE RELEASE

For information contact:
Nantucket
Nantucket Corporation®
12555 Jefferson Blvd.
Los Angeles, CA 90066
(213) 390-7923

CLIPPER™ NETWORKS DBASE APPLICATIONS

LOS ANGELES, California...Nantucket's Clipper now lets developers and business persons plug an unlimited number of workstations together to run their dBASE III and dBASE III PLUS applications, using Clipper's new networking capabilities.

This new release compiles programs to run on networks that support DOS 3.1 calls for networking functions, plus single-user programs for DOS 2.0 or greater.

Compiled Applications can be distributed freely, need no runtime module, no licensing fee or royalty. And there is no extra cost per user, regardless of how many users are connected to a Clipper network. Plus the new release now packs even more of Clipper's famous speed, on both single-user and networking applications.

The new Clipper also sports Expanded Memory support, additional functions and improve memo fields. The new release, dubbed Autumn '86, is not copy protected.

Clipper Autumn '86 is available for a suggested retail price of $695. Registered users of Clipper may upgrade to the new version for $139.

Clipper and Nantucket are trademarks of Nantucket Corporation.
Other products trademarked by others. Copyright 1986, Nantucket Corporation.

CIRCLE NO. 224 ON READER SERVICE CARD

FIGURE 1: *Timeslicing Operation*



The CPU is rescheduled on each tick of the 18.2-MHz system clock, called a timeslice. Workstations are normally serviced in 1-2-3-4 order. Keyboard interrupts give a workstation immediate CPU time. Requests to the server are expedited by having the workstation yield the remainder of the timeslice to the server.

kernel memory that remains at the same location (E000:0H for an XT, D000:0H for an AT) regardless of the active partition.

The kernel contains a process that monitors all of the software and hardware interrupts in the system and determines which partition should handle each one. For example, the video display interrupt (INT 10H) is executed within the current workstation partition, while keyboard hardware interrupts, which could be generated at any time by any of the keyboards, are handled in the kernel. Certain I/O devices can be configured to be non-shared, such as a modem port dedicated to one of the users. Interrupts from such a device are examined and then passed along to the proper workstation partition.

The timeslice algorithm controls the sharing of the CPU cycles among the partitions thereby solving a difficult problem in an elegant way. Multiuser operating systems generally use a combination of two methods to determine when to give CPU time to an application. The first method is to set a maximum time that an application can use the CPU; if it is not voluntarily relinquished by this maximum time, the operating system forcibly changes to another application. The second method is to change applications whenever the current application requests a potentially time-consuming I/O operation. Programs normally make this known indirectly with a system call that requests an I/O service from a device that is not yet ready to transfer data, such as a keyboard. It is through this system-call mechanism that multiuser operating systems determine which programs are really waiting for input or output, and therefore are idle.

However, single-user computers based on PC-DOS (as well as most other single-user operating systems) typically allow application programs direct access to all devices; in these systems there is no memory or I/O protection at all. PC-DOS application programs frequently take advantage of this environment to provide higher performance or some degree of concurrency of task execution. The benefits outweigh the costs here, because unused CPU cycles are free. When no input data are available to process, these programs often look for something else to do. For example, when waiting for the next keystroke, Lotus 1-2-3 will update a clock window on the screen, a seemingly innocuous and trivial task, yet one which entirely consumes the available CPU time. Similarly, WordStar never waits for the next input keystroke, but rather alternates between checking the keyboard status for "next character available" and checking the printer port for room to output the next character from WordStar's internal spooler.

These programs can easily deceive the system into believing that they are productively active, when in fact they may be accomplishing little or nothing. In that case, even inactive user partitions would receive a full timeslice, degrading the performance of users doing productive processing.

The Classic timeslice algorithm addresses this problem in an adroit fashion. As a general rule, the CPU cycles are divided into short bursts by each tick of the system clock. These bursts are called *timeslices* and have a duration of about 55 ms. The timeslices are allotted one at a time to each partition in turn, followed by the next partition, for all workstations and the server. This fundamental algorithm provides an even distribution of CPU cycles to each partition. If n is the number of workstations, $(n + 1)$ is the number of partitions including the server, and c is the network management overhead factor, then each workstation receives the following share of CPU time, t:

$$t = \frac{(1 - c)}{(n + 1)}$$

Classic has adapted this algorithm in several ways to improve overall performance. A depiction of Classic's timeslicing algorithm is shown in figure 1.

Consider an application program that reads a series of blocks from a hard-disk file. With a proper interleave value, it should be possible to read several sectors of data per disk revolution. With the disk spinning 60 times per second, this produces an effective throughput of several hundred sectors per second. Yet, if the program must wait for the server partition to execute each sector transfer, then two timeslices will be required for each sector, yielding a net throughput of (1 sec) / (2 * 55 ms) or about nine sectors per second. To circumvent this problem, the kernel recognizes when a workstation queues a server partition request and then borrows time from the current timeslice for the server to execute that request immediately. This eliminates the delay inherent in waiting for the next normal server timeslice for each disk transfer.

The kernel also recognizes when an application is continuously scanning the keyboard status with an empty keyboard buffer. After a few seconds, the CPU dispatcher begins to skip over this partition, gradually decreasing its CPU allocation to zero. Thus, when a user stops using the workstation, the CPU cycles are reallocated evenly to the other partitions. Since the timeslice allocation is restored to the partition when the next keyboard interrupt is received, this redistribution algorithm is fully automatic and transparent to the idle user. The other users simply notice improved performance whenever fewer workstations are active.

The dispatching algorithm is further configurable for Lotus 1-2-3 and Symphony users. Since these programs maintain a clock window on the CRT by calling the DOS Get Date and Get Time functions, they appear to the kernel to be doing useful work; hence, they continue to receive their full share of CPU

FIGURE 2: *System Software Diagram*



REDIR.EXE and SESSION.EXE handle server requests and are part of Microsoft Networks. SHARE.EXE, provided with PC-DOS, manages file sharing. Classic's component, XPORT.EXE, contains the hardware interface, timeslicing, and the network transport layer.

time. The manufacturer supplies a batch file that informs the dispatcher that a Lotus-like program is running, so it can switch to the next partition when date or time data are requested from DOS.

Although resident programs can be used by a workstation, Classic places some restrictions on them. Unfortunately, popular programs such as Borland's SideKick and SuperKey violate these restrictions. All programs must use BIOS interfaces, rather than direct hardware operations, to poll the keyboard. Also, a resident program must not depend on always receiving the 18.2/second clock tick. A clock-tick interrupt for a workstation occurs only during a workstation's own timeslice. If some other workstation has the timeslice, the resident program will not receive the tick. Resident programs can get a reliable tick count by using the standard IBM BIOS "ticks since midnight" doubleword at 0:46CH (correctly maintained by Classic).

SOFTWARE COMPONENTS

The MS-NET software that is provided by Classic also serves as the foundation for IBM's PC Network product. IBM has enhanced PC Network with certain desirable facilities, such as peer-to-peer communications (through NetBIOS).

Both PC-DOS 3.1 and 3.2 are supported by Classic and run without any patches. Each partition including the server contains a private copy of DOS. In the workstation partitions, each instance of DOS is responsible for handling non-shared resource usage functions such as process creation and termination, memory allocation, console I/O functions including ANSI terminal emulation via the ANSI.SYS video device driver, and file I/O to any local disk drives. Usually, local file I/O is limited to accessing a small RAM disk volume, which is stored within the 640KB memory partition, because the real disk drives must be shared.

The standard single-user DOS capabilities in the workstation partitions are augmented by three DOS extensions: the file sharing (SHARE.EXE), I/O redirection (REDIR.EXE), and session (SESSION.EXE) modules. The first of these extensions is distributed on the standard PC-DOS distribution diskette, while the latter two modules are components of MS-NET. All of the extensions are loaded as terminate-and-stay-resident (TSR) modules and are linked into DOS by way of software interrupt vectors. Each one of them is intended to be accessed by routines within DOS, rather than directly from application programs. This is consistent with the layered network service philosophy of the Open System Interconnection reference model. Figure 2 gives a schematic representation of how the operating system modules interrelate.

The SHARE.EXE module contains the support logic DOS requires for file sharing and diskette swapping protection. It introduces four *file-sharing modes*: Deny Read/Write, Deny Write, Deny Read, and Deny None. Deny Read/Write unconditionally forces exclusive access to a file, and fails if the file is open anywhere else in the system regardless of the usage mode. The Deny Write and Deny Read modes protect a file from being written or read by another program. The Deny None mode

places no restrictions on read or write access to file. This open mode updates a shared database file simultaneously from several partitions.

When a file can be concurrently written by several processes, some mechanism other than the open mode must be used to prevent "collisions" that can destroy the validity of the data. DOS provides a record locking system call that temporarily protects a contiguous region of a file by excluding other processes from reading or writing in that region. To be effective, the programs all must contain logic that properly locks either the entire file or an appropriate subset. Multiuser applications such as Ashton-Tate's dBASE III PLUS and Microrim's R:base 5000 contain this type of record-locking logic and work well within the Classic system.

The function of the redirector module is to recognize I/O requests for remote resources and reroute them to the network server. Both file I/O and printer character stream I/O redirection services are provided. The redirector examines file pathnames in the DOS calls OPEN, CREAT, as well as the directory and disk management functions to determine if a request should be executed locally or on the network. Local requests, such as RAM disk I/O, console I/O, and process creation and termination, are simply returned to the local DOS for execution.

Eventually, the redirected request arrives at the server. In a true network, the server would queue requests from all of the partitions and execute them on a first-in, first-out basis, finally returning the results to each originating redirector module when available. Here, however, it appears to the network software that disk requests are executed immediately upon arrival in the server, eliminating the need for any queuing. Shared printer requests generate character streams that also are redirected to the server, where the streams are stored in spool files.

Notice that although no physical network cable exists in this system, all of the underlying OSI network layers nevertheless are properly represented. Remote I/O requests from an application are trapped by the redirector and communicated over the session layer virtual circuit (layer 5). Sessions move data from one system to another with the assistance of the transport (layer 4), network (layer 3), and data link (layer 2) layers, which are all implemented concisely within the kernel. The lowest network layer, the physical layer, is actually the processor data bus.

ISN'T IT A PITY...



Everything Isn't As Accommodating As

c-tree™ / **r-tree**™

FILE HANDLER — REPORT GENERATOR

Performance and Portability

For all the time you devote to developing your new programs, doesn't it make sense to insure they perform like lightning and can be ported with ease?

c-tree: Multi-Key ISAM Functions For Single User, Network, & Multi Tasking Systems

Based on the most advanced B+ Tree routines available today, **c-tree** gives you unmatched keyed file accessing performance and complete C Source Code. Thousands of professional C programmers are already enjoying **c-tree**'s royalty-free benefits, outstanding performance, and unparalleled portability.

Only FairCom provides single and multi-user capabilities in one source code package, including locking routines for Unix, Xenix, and DOS 3.1., for one low price! In addition, **c-tree** supports fixed and variable record length data files; fixed and variable length key values with key compression; multiple indices in a single index file; and automatic sharing of file descriptors.

r-tree: Multi-File Report Generator

r-tree builds on the power of **c-tree** to provide sophisticated, multi-line reports. Information spanning multiple files may be used for display purposes or to direct record selection. You can develop new reports or change existing reports without programming or recompiling and can use any text editor to create or modify **r-tree** report scripts including the complete report layout. At your option, end users may even modify the report scripts you provide.

Unlimited Virtual Fields; Automatic File Traversal

r-tree report scripts can define any number of virtual fields based on complex computational expressions involving application defined data objects and other virtual fields. In addition, **r-tree** automatically computes values based on the MAX, MIN, SUM, FRQ, or AVG of values spread over multiple records. **r-tree** even lets you nest these computational functions, causing files from different logical levels to be automatically traversed.

Unlike other report generators, **r-tree** allows you to distribute executable code capable of producing new reports or changing existing reports without royalty payments, provided the code is tied to an application. Your complete source code also includes the report script interpreter and compiler.

How To Order

Put FairCom leadership in programmers utilities to work for you. Order **c-tree** today for $395 or **r-tree** for $295. (When ordered together, **r-tree** is only $255). For VISA, MasterCard and C.O.D. orders, call 314/445-6833. For **c-tree** benchmark comparisons, write FairCom, 2606 Johnson Drive, Columbia, MO 65203.

Complete C Source Code & No Royalties!

Xenix is a registered trademark of Microsoft Corp. Unix is a registered trademark of AT&T.

CIRCLE NO. 119 ON READER SERVICE CARD

"How to protect your software by letting people copy it."

By Dick Erett, President of Software Security

Inventor and entrepreneur, Dick Erett, explains his company's view on the protection of intellectual property.



Soon all software installation procedures will be as straightforward as this. The only difference will be whether you include the option to steal your product or not.

"A crucial point that even sophisticated software development companies and the trade press seem to be missing or ignoring is this:

Software protection must be understood to be a distinctively different concept from that commonly referred to as copy protection.

Fundamentally, software protection involves devising a method that prevents unauthorized use of a program, without restricting a legitimate user from making any number of additional copies or preventing program operation via hard disk or LANs.

Logic dictates that magnetic media can no more protect itself from misuse than a padlock can lock itself.

Software protection must reside outside the actual storage media. The technique can then be made as tamper proof as deemed necessary. If one is clever enough, patent law can be brought to bear on the method.

Software protection is at a crossroads and the choices are clear. You can give product away to a segment of the market, or take a stand against the theft of your intellectual property.

"...giving your software away is fine..."

We strongly believe that giving your software away is fine, if you make the decision to do so. However, if the public's sense of ethics is determining company policy, then you are no longer in control.

We have patented a device that protects your software while allowing unlimited archival copies and uninhibited use of hard disks and LANs. The name of this product is The BLOCK™.

The BLOCK is the only patented method we know of to protect your investment. It answers all the complaints of reasonable people concerning software protection.

In reality, the only people who could object are those who would like the option of stealing your company's product.

"...eliminating the rationale for copy-busting..."

Since The BLOCK allows a user to make unlimited archival copies the rationale for copy-busting programs is eliminated.

The BLOCK is fully protected by federal patent law rather than the less effective copyright statutes. The law clearly prohibits the production of work-alike devices to replace The BLOCK.

The BLOCK attaches to any communications port of virtually any microcomputer. It comes with a unique customer product number programmed into the circuit.

The BLOCK is transparent to any device attached to the port. Once it is in place users are essentially unaware of its presence. The BLOCK may be daisy-chained to provide security for more than one software package.

Each software developer devises their own procedure for accessing The BLOCK to confirm a legitimate user. If it is not present, then the program can take appropriate action.

"...possibilities... limited only by your imagination..."

The elegance of The BLOCK lies in its simplicity. Once you understand the principle of The BLOCK, hundreds of possibilities will manifest themselves, limited only by your imagination.

Your efforts, investments and intellectual property belong to you, and you have an obligation to protect them. Let us help you safeguard what's rightfully yours. Call today for our brochure, or a demo unit."

Software Security inc.

870 High Ridge Road Stamford, Connecticut 06905

203 329 8870

CIRCLE NO. 189 ON READER SERVICE CARD

SYSTEM MANAGEMENT

The server partition manages all of the shared resources in the system, including directories, printers, and disk drives. Rather than executing application programs and COMMAND.COM, this partition runs a dedicated network management program, SERVER.EXE. This routine accepts workstation requests to open, close, read, and write the shared resource files.

In addition, the server maintains a console display that is normally swapped into the background, meaning that it is not displayed on any of the workstation CRTs. The console queries system status and enters system management commands. It can be retrieved into the foreground by running the command NSWAP at any workstation. However, it cannot be returned to the background except from another workstation console, which can be inconvenient. Fortunately, the server console does not need to be accessed frequently by the system manager. Configuration commands to set up a particular server can be batched into an initialization file, OFFERS.I and processed each time the server is booted.

The system manager uses the SHARE command at the server console (not to be confused with the program SHARE.EXE, which manages the open file modes) to create a table of shared resources that are offered to the workstations. These resources, which are identified by a *shortname* of up to eight characters, can be password and permission protected to a degree. To share the diskette drive A:, the program library C:\BIN, a database directory C:\ACCT\DATABASE, and the shared serial printer attached to COM2: requires the following commands:

```
share floppya  = a:
share proglib  = c:\bin
share dblib    = c:\acct\database
share printer  = com2:
```

The shortnames **floppya**, **proglib**, **dblib**, and **printer** are arbitrary. Mapping the true pathname of a resource into the public shortname allows the system manager to be flexible in reconfiguring the server without modifying any of the applications in the workstation partitions. For example, as the hard disk C: nears its capacity because of growth in the inventory database file in the directory \ACCT\DATABASE, the manager can install a new hard drive D: and move the database directory there. In terms of software reconfiguration, the manager needs to modify only one share command; this is done by changing the DOS directory pathname and leaving the shortname **dblib** unchanged:

```
share dblib = d:\database
```

Workstations complete the mapping of the shared resources with another command, USE, that equates the resource shortname to an unused device name in the workstation. Thus, one partition might map the database directory to unused drive E:, while another might map the same directory to drive I:, and yet another might not attach that directory at all. The server printers, which are assigned shortnames such as **printer** and **printer2** (with the share command) are mapped to unused, typical printer device names such as PRN:, LPT1:, or COM2:. For example, a workstation might use the following collection of USE configuration commands:

```
use a:    \\server\srvra
use c:    \\server\proglib
use i:    \\server\dblib
use lpt1  \\server\printer
```

In conjunction with the SHARE commands listed above, these USE com-

Lattice® Works

LATTICE ANNOUNCES MICROSOFT WINDOWS SUPPORT IN VERSION 3.2

Version 3.2 of the Lattice MS-DOS C Compiler features full support for Microsoft Windows—including the "far," "near," and "pascal" keywords.

In addition, version 3.2 includes the ability to generate more than 64K bytes of static data and to declare objects larger than 64K bytes. It also includes improved support for ROM-based applications via the "const" data type. Version 3.2 is a significant release because it eliminates Microsoft's claimed monopoly on future MS-DOS C development tools. Now that the Lattice MS-DOS C Compiler supports a window interface, programmers using Lattice C can avoid the problems caused by switching to a different compiler. $500.00

LATTICE NOW OFFERS ENHANCED AmigaDOS C COMPILER

Version 3.1 of the Lattice AmigaDOS C Compiler offers a new library with 100 more functions than the standard AmigaDOS C Compiler. What's more, increased library modularity and new addressing modes help reduce load module sizes by more than 20%. The new version also features faster pointer and integer math, faster IEEE floating point routines, direct support of the Amiga's FFP format floating point library, and multi-tasking support.

With Version 3.1, Lattice has broken free of the reliance on the Amiga standard linker and object file format. This new release includes completely new expanded documentation, and a Lattice assembler and linker which remain compatible with previous software but allows professional programmers to take advantage of both the Amiga's speed and the industry's standardization.

Lattice AmigaDOS C Compiler with Lattice's Text Management Utilities, $225. Professional AmigaDOS C Compiler with, Text Management Utilities, Lattice Make Utility, Lattice Screen Editor, and the Metadigm MetaScope Debugger, $375. AmigaDOS C Compiler $150.

LATTICE RELEASES NEW VERSIONS OF C CROSS COMPILER AND LINKER

Version 3.1 of the Lattice C Cross Compiler to MS-DOS and version 2.12 of the Plink86Plus Overlay Linker are now available for Sun and Apollo workstations as well as the DEC VAX Family of processors running VMS, UNIX or Berkeley UNIX.

All Lattice C Cross Compilers possess the same functionality and generate the same code as the native Lattice MS-DOS C Compiler. This allows users to take advantage of the larger systems' speed and multi-user capabilities when creating applications for most popular PCs.

Contact Lattice Corporate Sales for details.

Lattice

(800)533-3577 In Illinois (312) 858-7950 TELEX 532253 FAX (312) 858-8473

INTERNATIONAL SALES OFFICES: Benelux: Ines Datacom (32)2-720-51-61
Japan: Lifeboat, Inc. (03)293-4711 England: Roundhill (0672)54675
France: Echosoft (1)4824.54.04 Germany: Pfotenhaur (49)7841/5058
Hong Kong: Prima 85258442525 A.I. Soft Korea, Inc. (02)7836372
Australia: FMS (03) 699-9899 Italy: Lifeboat Associates Italia (02) 46.46.01

CIRCLE NO. 160 ON READER SERVICE CARD

Better BASIC

NOW INTRODUCING VIRTUAL MEMORY SUPPORT

BetterBASIC with the optional Virtual Memory Manager can now address 400,000,000,000 bytes of memory!

BetterBASIC Application Development System **$199.00**

The BetterBASIC Application Development System provides very close compatibility with PC-BASICA and GW-BASIC, yet provides numerous new and sophisticated language features such as: program Block Structures, recursive Procedures and Functions with local variables, structures, Records and Pointers and last but not least support of large memory.

Virtual Memory Manager **$99.00**

The Virtual Memory Manager expands BetterBASIC's data space into the giga-byte range and finally breaks the 640k byte barrier for array sizes. Not only can you directly address all expanded memory supported by LIM/EMS memory boards, you can also address any RAM Disk, Hard Disk or even a Floppy Disk as if they were ordinary RAM.



Virtual Memory Manager-Network Version **$250.00**

This version of the Virtual Memory Manager allows Virtual Memory to be distributed throughout a Local Area Network. It also provides File, Records and Field Locking to control access to shared data.

C-Link **$99.00**

This software package allows BetterBASIC to access C-language library functions from within BetterBASIC. Currently supported are Lattice and Microsoft C.



Screen Design System **$199.00**

This package truly takes the drudgery out of creating display screens and data entry screens. An interactive Screen Editor lets you "paint" your display screens exactly as you want them to appear in your program. The completed screens take the form of disk resident images. A run time library module provides many new BetterBASIC procedures and functions for interacting with the display screens to simplify the use of pop-up menus and data entry screens.



Btrieve™ Interface **$99.00**

This is a high level BetterBASIC interface to the ever popular Btrieve™ file manager from SoftCraft. Instead of Assembly language calls this module provides high level BetterBASIC program access to all Btrieve™ functions. Use it to design your own database application in BetterBASIC.

8087/80287 Math Module **$99.00**

This module allows you to use the 8087 or 80287 co-processor to significantly accelerate programs which are floating point calculation intensive.



Decimal Math Module **$99.00**

If you are a business programmer, you are probably frustrated by the many roundoff problems caused by ordinary IEEE format floating point numerical operations. The BetterBASIC Decimal Math Module which offers variable precision from 6 to 24 digits, drastically reduces roundoff problems in business applications.



BetterTools™ **$99.00**

This is a collection of more than 150 useful extensions to BetterBASIC such as time and date computations, encryption and decryption, low level file directory access, hyperbolic function and much more. No BetterBASIC programmer should be without BetterTools™.

Call our Toll Free Order Line

1-800-225-5800

Summit Software Technology, Inc.™
106 Access Road
Norwood, MA 02062
(617) 769-7966

Better BASIC

CIRCLE NO. 195 ON READER SERVICE CARD

mands provide the following resource mapping for this workstation:

Workstation Device Name	Server	Resource
a:	a:	(diskette)
c:	c:\bin	(directory)
i:	d:\dblib	(directory)
lpt1:	com2:	(serial printer)

Note that each partition, or system on the network, is assigned a network node name. The server partition is called SERVER, while the workstations are named CONSOLEA, CONSOLEB, and so on. These names can be reassigned, but without an electronic mail facility in MS-NET, the names only appear in the server status display.

The MS-NET printer spooler included with this system provides a substantially enhanced feature set in comparison to the DOS printer spooler, PRINT.COM, which it replaces. The acronym *spool*, derived from the term Simultaneous Peripheral Output On-Line, refers to the facility of printing concurrently with other program execution on a system. The spooler allows workstation users or application programs to generate printouts on one or more of the logical printers.

Character streams to each of the logical printers are automatically redirected to files in the system spool directory. When the application closes an LPT file, or terminates, then the spool file becomes a candidate for printing on a real printer owned by the server. In addition, a special TSR utility allows the user to release a spool file by pressing Ctrl-Alt-PtrSc. This technique prints the file without stopping the application. The collection of all the spool files waiting to be printed is called the *queue*. Normally, the server automatically prints files in the print queue on a first-in, first-out basis; however, several useful commands exist that enable a user to manage the queue.

Programs can generate spooled printer output through a variety of DOS, BIOS, and hardware interfaces. All of the normal DOS paths to the printer function correctly: DOS function 5 (the printer output), writing to file handle 4 (the standard printer device), and opening and writing to device LPT1. Programs also can print using the ROM BIOS print driver, interrupt 17H, and have the character stream automatically redirected to the spooler. Programs that issue output instructions to the printer port, however, will bypass the spooler entirely, and these programs will conflict with it if the spooler is trying to manage the device as well.

This spooler supports one or more physical printers for use in concurrent printing. Each workstation also may have several logical printers open simultaneously, thereby generating several different reports; this useful configuration facilitates certain multiuser business applications. For example, in a system consisting of four workstations and three physical printers, the spooler could be capturing 12 different print streams for later printing. Furthermore, the printers do not always have to be shared; they can be detached from the server and assigned to a workstation for direct, nonspooled printing. This satisfies the requirement of many applications that print special forms, such as invoices and checks, that must be printed immediately or may require special operator attention for forms alignment or security purposes.

THE SYSTEM'S HARDWARE

Regardless of whether the host computer is an XT or AT, the task of installing the Multiuser system hardware requires at least several hours and is rec-



from any 1600 bpi tape into your IBM PC/XT/AT or compatible with Digi-Data's 2000 PC™. Transfer data at over 1 megabyte/minute, in up to 64K blocks with our easy to use DOS/XENIX software. Read entire tapes in EBCDIC or ASCII or select particular files. Backup your data, either in mirror image or by individual files.

Let Digi-Data, with 25 years experience in the manufacture of quality tape drives, resolve your data interchange, disc backup or archival storage needs with a Digi-Data 2000 PC. Call us today at (301) 498-0200.

Ask us about DEC systems too.

DIGI-DATA CORPORATION
8580 Dorsey Run Road
Jessup, MD 20794-9990
(301) 498-0200
Telex 87-580
® . . . First In Value

In Europe contact: Digi-Data Ltd. • Unit 4 • Kings Grove • Maidenhead, Berkshire England SL6 4DP • Telephone No. 0628 29555/6 • Telex 847720

™2000 PC is a trademark of Digi-Data Corporation. PC/XT/AT are trademarks of IBM Corporation.

CIRCLE NO. 123 ON READER SERVICE CARD

ommended only for the technically self-assured. Although the manufacturer provides 26 pages of illustrated installation instructions, these directions include several errors, omissions, and unclear topics. Those who are not familiar with removing and installing chips and changing jumpers will find it worthwhile to pay an experienced dealer to set up this hardware.

The system used for this review was configured as a four-user computer, a size that is considered typical by the manufacturer. The multiuser hardware was installed in an XT originally configured with 640KB RAM, a Hercules video controller, an IBM diskette controller and single diskette drive, and an NCL/Centan Corporation's hard-disk controller and 20MB drive.

The hardware installation procedure involves four general phases: removing incompatible or unnecessary hardware from the host computer, installing the CPU accelerator (XT only), installing the workstation controller hardware, and assembling the workstations and attaching them to the host.

The Hercules card is incompatible with the bank switched video hardware and was removed first. Replacement candidates to provide video for the primary workstation are an IBM monochrome or CGA card, a Classic Monochrome Graphics Adapter, or a channel from the four port Workstation Adapter. In the reviewed system, a Workstation channel was used because it saved one slot in an already crowded chassis, saved power, and was readily available.

The combined +5 volt power requirement for the accelerator card, RAM expansion, and Workstation Adapter is approximately 9.8 amps. Combined with the XT motherboard and disk drive/controller requirements, this taxes the standard XT power supply's output limit of 15 amps. Because the accelerator card provides all of the system memory, Classic recommends removing memory chips in XT memory banks 1 through 3, and all memory chips on multifunction adapter cards to eliminate unnecessary power drain, or replacing the standard 130-watt power supply with a larger model suitable for the total configuration. An extraction tool is supplied for removing the memory chips.

The 286 Speed Pak accelerator card requires two adjacent expansion slots. The manufacturer recommends that they be located in the two full-length slots nearest the power supply. The 8088 is replaced with a ribbon cable and plug from the Speed Pak. The CPU is relocated to a socket on the Speed Pak to allow switching back to normal speed mode if necessary for compatibility or for diagnostic purposes.

Several jumpers and switches must be set on both the XT motherboard and the Speed Pak for proper operation, and herein lies some of the installation confusion. First, set the memory size switch on the motherboard to 64KB. Next, determine if the XT was manufactured after April 1986 (check the BIOS date code, using DEBUG to dump locations FFFF:5H through FFFF:CH). For post-April 1986 XTs only, jumper E2 on the motherboard must be opened. Also, the documentation states that jumper PWR ON ROM on the 286 Speed Pak is to be set closed for the older XTs and open for the newer XTs. This is incorrect; the reverse is actually true. Much later in the evaluation this misprint was determined to be the cause of both diskette format and intermittent hard-disk errors.

The third phase of installation is to assemble and install the Workstation Adapter(s). Each adapter supports from one to four users; instructions are provided for a single adapter card only. For larger systems, the installer should call Classic for proper configuration instructions for the additional adapters. Each Workstation Module daughterboard is snapped onto the Adapter. The Adapter card is then mounted in the slot farthest from the power supply, to minimize the video-clock noise coupling onto the Speed Pak cards. A connector box containing the cable interface jacks for the four workstations is mounted on the rear of the XT. The fit is very tight, and it may be necessary to leave the expansion slot that is adjacent to the Workstation Adapter empty.

An undocumented set of jumpers near the Workstation Adapter's edge connector selects the interrupt level used to read workstation keyboard input; it was factory configured for interrupt level 12. After several calls to Classic, it was determined that this should be reset to interrupt level 2 for the XT system. The IBM *PC/XT Technical Reference* manual indicates that this is the EGA or PC Network interrupt.

The individual workstations for the review were assembled from IBM monitors and keyboards. Signals from each monitor and keyboard are combined in a small workstation interface box. The box is powered by a 9-volt wall transformer and is attached to the Workstation Adapter's connector box with a 25-pin shielded cable.

Configuring the TaskMaster system software is straightforward. The hard

Search 5,000
Source Code Files
in 5 seconds!

ZyINDEX
Your personal researcher™

The ultimate programmers source code retrieval software. Find any information created by the popular word processors or ASCII files, in seconds — without having to set up a database or do programming. Scan a 20 Mbyte hard disk or a collection of floppies and instantly display all occurrences of a variable name, a procedure, a number, or anything else you need to find. Save hours of manual searching.

FEATURES

• **Comprehensive searches** create a search request with any combination of AND, OR, NOT, and WITHIN (WITHIN refers to how far apart two words or phrases can be — up to 30,000 words).
• **Wild Cards,** for example: type "micro*" to get (microcomputer, microcomputing, micro-processor, etc.). • **Mark and Save** retrieved information to create a new file.
• **Highlights** search-words and phrases in retrieved text. • **On Line Help Menus.** • **Find Function** automatically displays search request in the retrieved file. • **Phrase Search,** in addition to single word search.

SYSTEM REQUIREMENTS MINIMUM

• 256K • Two Disk Drives • DOS 2.0 or above • Designed for IBM PC, XT, AT, compatibles, and most MS-DOS computers.

ZyINDEX Standard $145
Searches up to 500 files

ZyINDEX Professional $295
Searches up to 5,000 files

ZyINDEX Plus $695
Searches up to 15,000 files with LAN capabilities.

30 Day Money Back Guarantee.

ZyLAB Corporation™ 233 East Erie Street Chicago, Illinois 60611 • (312) 642-2201
(800) 544-6339 For orders and information

CIRCLE NO. 212 ON READER SERVICE CARD

disk is formatted with either DOS 3.1 or 3.2, and the DOS system commands are installed into the directory C:\BIN.

The distribution software diskette contains a batch file called INSTALL that performs the remainder of the task, stopping to prompt for key parameters along the way. In doing so, it either sets up or modifies boot control files, such as CONFIG.SYS and AUTOEXEC.BAT. INSTALL will copy all of the TaskMaster software from diskette to the appropriate directories on the hard disk.

Certain resources can be allocated to the server or reserved for a user during the installation process. For example, each serial port can be marked shareable or private. In addition, the partition sizes assigned to each user can be varied from 256KB to 640KB each.

Finally, the INSTALL procedure creates the MULTI.BAT start-up file in the root directory, C:\. This command must be executed in order to commence multiuser operation. One possibility is to place it in the final line in AUTOEXEC.BAT.

A great deal of flexibility is provided for start-up initialization. The AUTOEXEC.BAT file contains only system startup commands. Commands that should be run by all workstations at start-up are placed in AUTOCMN.BAT. Start-up commands for each workstation are placed in files named AUTO*XX*.BAT, where *XX* is the letter designation (A, B, C, D) of the workstation, which is repeated a second time.

SCANT DOCUMENTATION

Three manuals are provided with Classic: the *User and Manager Guide*, the *Troubleshooting Guide*, and the *Applications Software Guide*. The manuals are not well organized and do not have indexes. Multiple readings of the manuals will probably be required to run the system successfully. Section headings in the tables of contents are only marginally useful guides to the information contained in a section.

The *User and Manager Guide* is a 140-page manual. The publishing of these two guides as a single volume is inappropriate because it contains much information needed only during installation and configuration.

Most of the *Manager Guide* covers the installation process discussed above. The incorrect documentation for the setting of the PWR ON ROM switch, also mentioned above, is an error that should have been corrected before the manual was released by Classic.

The *User Guide* is a scant 30 pages long; it covers the essential details of using the network commands to access shared resources and control the print spooler. An appendix lists the error messages that may be encountered, and suggests corrective action in some cases. Additional appendixes that discuss restrictions on BIOS interrupt 13H (the absolute disk read function), system calls for multiuser extensions, and hardware technical specifications.

The *Troubleshooting Guide* is a 23-page manual that outlines problem solving for the system, both hardware and software. It covers problems that may be encountered during installation, power-up, and operation. This guide should be used in conjunction with the *Manager Guide* during installation.

The installation and operation of specific products are covered in the *Applications Software Guide*. Some of the products that Classic does include instructions for are: BPI's General Ledger; Ashton-Tate's dBASE III PLUS, Multimate, and Framework; Lotus 1-2-3; WordPerfect Corporation's WordPerfect 4.1; MicroPro's WordStar; Microrim's R:base 5000; Data Access's DataFlex; mbp

The Advanced Programmer's Editor That Doesn't Waste Your Time

EPSILON

- **Fast, EMACS-style commands—completely reconfigurable**
- **Run other programs without stopping Epsilon—concurrently!**
- **C Language support—fix errors while your compiler runs**
- **Powerful extension language**
- **Great on-line help system**
- **Multiple windows, files**
- **Regular Expression search**
- **Unlimited file size, line length**
- **Supports large displays**
- **30 day money-back guarantee**
- **Not copy protected**

Only $195

Lugaru Software Ltd.

5740 Darlington Road
Pittsburgh, PA 15217

Call (412) 421-5911

for IBM PC/XT/AT's or compatibles

CIRCLE NO. 125 ON READER SERVICE CARD

THE MAKERS OF VTERM/220 ARE PLEASED TO ANNOUNCE THE FOLLOWING COMPANIES HAVE CHOSEN OUR DEC TERMINAL EMULATION SOFTWARE.



Among our largest customers are ~~General Electric, Westinghouse, Bankers Trust, Lotus Development Corp., Exxon,~~ And the ~~U.S. Department of the Navy.~~

Big institutions can be very close-mouthed about the competitive edge they get from a powerful tool like VTERM/220. So while they'd prefer that we not name names, we can still tell you the reasons why we have more satisfied users than all our competition combined.

First of all, giant institutions don't stay giant by being sloppy. They spec things down to a gnat's eyebrow. That's why we're proud to say that VTERM's biggest fans are large corporate, scientific and government installations that perform very serious evaluations of communications software. They give VTERM the highest praise for accuracy of emulation, ease of use, multiplicity of features, speed of execution, and just plain quality.

Just look at VTERM/220's outstanding features:

- Plug compatible VT220 and VT100 video and keyboard emulation with customizable key mappings.
- Powerful file transfer including the most thorough implementation of KERMIT available on the PC, plus XMODEM, and our proprietary protocol VTRANS with complete host-side software for VMS,™ RSTS/E,™ RSX11 M/M+ ™ and UNIX.™
- Host data capture and conversion to Lotus® 1-2-3,® Symphony® and dBase.®
- 132-column display via horizontal scrolling or optional video board.
- Scrollback buffer for redisplay of up to 2,000 lines (eighty screens!).
- "Hot Key" toggle between host session and PC DOS.
- Programmable softkeys with script-like capabilities.
- Full support for multinational and national character sets.

VTERM/220 is not the only thing we have to talk about. There's also our VT100 emulator VTERM III, and our Tektronix™ 4010/4014 graphics emulator, VTERM/4010. Both of these VTERM's have a lot of the power of VTERM/220, including file transfer.

So if you're looking for terrific terminal emulation programs for your IBM PC or other compatible computers, you and 50,000 other users have found it at Coefficient. We're the leader in DEC Emulation Software. Just ask AT & oops.

Call us today at 212- 777-6707 ext. 503.



Coefficient

Coefficient Systems Corporation
611 Broadway, New York, N.Y. 10012

CIRCLE NO. 213 ON READER SERVICE CARD

TABLE 2: *Benchmark Results*

BENCHMARKS	W1[a]	W2	W3	W4
All TIMER	23	23	23	23
Idle Workstation	0[b]	31	30	31
WordStar 60 WPM	10	38	29	15
WordStar 120 WPM	22	39	22	9
WordStar File Load	17	28	26	21
Read Buffered File	17	13	31	31

All figures are percentages of CPU time used.
[a] Designated workstation.
[b] For tests other than All TIMER, W1 was calculated as 100 – W2 – W3 – W4 – SO, where SO is the system CPU overhead derived as 8 percent in the All TIMER test.

In most cases, the CPU time was fairly distributed among the workstations. The priority given to keyboard input keeps user response time acceptable.

COBOL, and the Smart Software Series. Changes or clarifications to the vendor's standard procedures are provided.

The best way to learn about the Classic system is to serve an apprenticeship under someone who has already installed and used one. The manuals will discourage many users from attempting a first-time installation. Once the learning curve has been conquered, with the aid of phone calls to Classic, subsequent installations should prove much less formidable.

OPERATIONAL TESTING

Both 50- and 500-foot workstation cables were provided with the review system, and while the 50-foot cables performed flawlessly, the 500-foot cable introduced several intolerable problems, including poor video quality. Video quality was very good at 50 feet, with no noticeable degradation from a conventionally-located PC monitor. At 500 feet, image degradation was noticeable. Single pixels were lost in either normal or reverse video, causing indistinct serifs on characters. Noise or transmission errors caused some pixels to flicker randomly on the Amdek monitor. At this longer distance, occasional keyboard transmission errors occurred.

On the XT, if a user attempts to use a diskette while others are operating the system, all of the workstations will lose keystrokes while the diskette is being accessed. This is because the memory management unit must "lock-in" one partition (CPU and DMA always transfer to/from current partition) while the diskette comes up to speed and transfers the data. This seems to be a design problem; keystrokes could be buffered in shared memory and transferred to the BIOS keyboard buffer when the partition is dispatched.

Classic indicated that this situation is not a problem, because users will normally use the hard disk exclusively in a multiuser environment. Nevertheless, there are legitimate uses for diskettes, such as new software release installation, restoring damaged files from backup diskettes, or transferring data or document files to or from other systems. Users do not expect to lose keystrokes for no apparent reason.

Much of the system's hardware does not come from IBM, therefore, the standard IBM diagnostics provide little help in identifying problems. This system needs a thorough set of diagnostic programs, both for the manufacturer and customer's benefit. For example, the first CPU board received for this evaluation was defective and caused occasional system failures and there was no reliable way to identify the problem.

Because the entire Classic system is essentially one computer and a single bus, it can be susceptible to problems with grounding. Improper grounds can cause shock when attaching cables to the network interface box. A disconnected workstation cable or disconnected keyboard sometimes causes the system to crash. If a workstation is unpowered, it can generate a high interrupt load, which prevents the entire system from booting.

The complete system has not yet received either FCC Class A (office) or Class B (home) certification. Customers could be held responsible for eliminating any unexpected radio frequency interference emanating from the workstation signal cables (which could act as excellent antennas for transmitting the high frequency video signals). Classic has indicated that it is in the process of obtaining both FCC and Underwriter's Labs (UL) certification.

Workstations do not contain a speaker and cannot generate beeps to draw the user's attention. The speaker in the host PC can be left operative, but Classic recommends that it be disconnected. Otherwise, any use of the speaker within a program at a remote workstation generates an unnecessary noise at the host PC.

TAKING THE TESTS

The operation of the timeslice algorithm is crucial to the performance of the Classic system. If situations such as busy-waiting for keyboard input are not detected correctly, performance will suffer greatly. A measurement program, TIMER.C, was created to determine the behavior of the timeslice algorithm under a variety of test conditions. This program is shown in listing 1.

The TIMER program examines the BIOS clock in low memory to determine the passage of time. Many factors affect the operation of the timer program, including CPU speed and C compiler optimizations. The constant CALIB was chosen so that the program reported 100 percent CPU usage when running as a single-user system. Although the BIOS timer tick actually steals time from a program running under DOS, it is not significant to the measurements. The same BIOS timer tick overhead exists in multiuser mode, and its effects can be safely ignored.

After calibration, the system was started in multiuser mode. The results of each performed test are summarized in table 2. The first test was to run TIMER on all of the four workstations to determine CPU usage when all workstations were compute-bound. As the results show, an equitable division of the CPU time was performed by Classic's algorithm; each received 23 percent of the CPU. In addition, the overhead of the multiuser operating system can be determined to be about 8 percent (using $100\% - 4 * 23\%$) for the CPU-bound case. In later tests, an overhead figure of 8 percent was used to derive the CPU percentage of workstation that was not running the TIMER program.

A second test measured the CPU used by an idle workstation. Workstation 1 was waiting for input at the DOS prompt while the remaining programs ran TIMER. CPU time was fairly divided among the non-idle workstations, and the idle workstation received no CPU time. A character typed at workstation 1 appeared immediately, indicating that CPU is given to the workstation as soon as it is needed.

The next two tests, WordStar 60 WPM and WordStar 120 WPM, attempted to measure the effect of keyboard input on the timeslice allocation. An operator entering text into WordStar was active

at one workstation, while the other workstations ran the TIMER program. Two measurements were taken, one with characters being entered at 60 words per minute (about 2 characters per second), and another with 120 words per minute. In both cases, WordStar received adequate CPU time to update information, although full-screen scrolling was sometimes performed in hesitant bursts of activity. The priority preference that Classic gives to programs that have just received keyboard input maintains a respectable response time. Such programs are rarely compute-bound, and can relinquish CPU time to other workstations after the keystroke has been processed. The partitioning of the remaining CPU time becomes unbalanced; whether this is a problem is largely application-dependent.

In the fifth test, WordStar File Load, a 33KB file was loaded and positioned at the end of the file. This took approximately five times longer in multiuser mode when all other workstations were running TIMER. However, this should be viewed as a worst-case performance because usually all other workstations would not be compute-bound at the same time. Therefore, the timeslices and elapsed time are still respectable.

The last test read a file that was small enough to be cached into the DOS buffers. One workstation continuously read through a small file until the end-of-file, then repositioned to the beginning and repeated the process. The percentage of CPU time used by this test was the same as in WordStar File Load, but the CPU distribution to the remaining workstations changed.

These tests indicate that the Classic Multiuser System can provide respectable response time for as many as four users. Using an XT as the foundation for Classic is not recommended. The need for an accelerator board, the resulting loss of bus slots, general admonitions in the installation manual about "noise," and the taxing of the power supply are some of the deterrents to an XT-based system. An AT-class machine, preferably one with high-performance characteristics, would be a better match. Classic has begun to sell its own 15-MHz AT compatible.

The Classic Multiuser System is an effective way to obtain many advantages of networks without the cost and performance penalties. It is a very capable platform for creating turnkey applications that involve stable software packages. In particular, network data managers should benefit from Classic's bus-speed network medium. By building upon the foundations of PC-DOS and MS-NET, Classic has made a large body of application software available for immediate and productive use.

Stuart Blair is the president of Stanford Software Institute, a software consulting and product development company specializing in DOS and UNIX operating systems.

LISTING 1: TIMER.C

```
/*
 *      timer:
 *
 *      This routine consumes CPU cycles, and periodically
 *      displays a CPU usage factor on the CRT.
 *
 *      The program increments a counter during an interval of time.
 *      The CPU usage factor is proportional to the value of that
 *      counter at the end of the time period.  An empirically
 *      derived calibration constant is used to scale the counter
 *      value to a percentage (from 0 to 100 percent CPU busy).  The
 *      percentage is displayed at the end of each interval.
 *
 *      The report time period is specified in seconds as the first
 *      argument in the command line.  To select a 5 second interval:
 *
 *          timer 5
 */

#define CALIB    550            /* calibration constant         */
#define TIMER    0x006C         /* rom bios TIMER_LOW offset    */
#define BIOSDSEG 0x0040         /* rom bios TIMER_LOW segment   */

main(argc, argv)
int argc;
char *argv[];
{
        long count;             /* raw CPU busy measure         */
        int  scale;             /* factor to convert "count" to */
                                /* a percentage of CPU busy.    */
        long round;             /* rounding correction          */
        long delay();           /* CPU busy timing routine      */
        int  time = 1;          /* default 1 sec report period  */
        int  ticks;             /* "time" in system clock ticks */
        int  begin, end;        /* actual limit of sample period */
        long busy;              /* CPU busy percentage          */

        if (argc > 1)           /* alternate reporting interval */
            time = atoi (argv[1]);

        scale = CALIB * time;   /* scale factor for converting  */
                                /* count to percentage of CPU   */
                                /* busy, for the specified      */
                                /* reporting period.  This is   */
                                /* the number of counts per 1%  */
                                /* of CPU busy.                 */
        round = scale / 2;      /* rounding correction value    */
        ticks = time * 18;      /* approximate number of timer  */
                                /* ticks per report period, at  */
                                /* about 18 ticks per second    */

        delay (1);              /* synchronize with system clock*/
        while (1)               /* forever */
        {
            begin = peek(TIMER, BIOSDSEG); /* actual start time */
            count = delay(ticks);          /* count thru interval */
            end   = peek(TIMER, BIOSDSEG); /* actual end time   */
            /*
             *  Due to the scheduling algorithm, the sample period
             *  may be several ticks longer than what was requested.
             *  Correct for this error, then convert to percentage.
             */
            busy = (count * ticks)/(end - begin);
            busy = (busy + round) / scale;
            printf ("busy = %d%%\n", (int) busy);
        }
}

/*
 *      Delay a minimum of "tc" ticks of the system clock, and
 *      increment a counter during this time period.  Return value
 *      of counter as a raw measure of the CPU time allocated to
 *      this partition.
 */

long delay (tc)
        int tc;         /* measurement interval is timer ticks  */
{
        int begin = peek(TIMER, BIOSDSEG);
        long count = 0;

        while ((peek(TIMER, BIOSDSEG) - begin) < tc)
            ++count;
        return (count);
}

/* Compile with -DMSC for Microsoft C, it has no peek() function */

#ifdef MSC
int peek(where)
        int far *where; /* treat segment:offset as a far pointer */
{
        return(*where);
}
#endif
```

PC TECH JOURNAL



And the winner is...

Congratulations to Jim Eddings, DP Manager, Ithaca Industries Inc., Gastonia, NC, the winner of PC TECH JOURNAL's System Builder Contest.

Those of you who were at Fall COMDEX probably remember the System Builder Contest—the one that had over 4000 system experts and MIS/DP professionals going from booth to booth to complete their "chassis" with the hope of winning the system expert's "ultimate system."

PC TECH JOURNAL editor Will Fastie (left) congratulates SYSTEM BUILDER CONTEST grand prize winner Jim Eddings.

Grand Prize

The "ultimate PC system", determined by our contestants, is composed of:

	Reader Service #
• An Access 386 by ALR	291
• The Vega deluxe EGA board from Video-7	290
• A Princeton HX-12E EGA monitor	292
• Iomega's Bernoulli Box	293
• An ITT Qume Laser 10 Printer	294
• Omni Tel's 2400 HB modem	295
• Crosstalk	289
• Quarterdeck's Desqview	296
• Modula-2 from Logitech	288
• Knowledgeman/2 by Micro Data Base Systems	287
• AutoCAD by Auto Desk	297
• Fifth Generation's Fastback	298
• Lifeboat's Advantage C++	286

Jim represents a typical PC TECH JOURNAL reader; a system professional in an end-user environment responsible for system integration, micro-to-mainframe communication, identifying needs, evaluating and recommending products, designing, building, and maintaining PC and larger systems, and training company employees in using these systems—a job made easier thanks to the information he gets every month from PC TECH JOURNAL.

First Prize

Intel Inboard 386/AT

Mike Johnson	PC Systems Support Manager Trans Oklahoma Inc.

Second Prize

WordPerfect 4.2

Daniel F. Burm	President Woodson Computers
Edwin E. Sund	Sr. Engineer PC Weyerhaeuser Corp.
Alan Tipton	Systems Analyst Texas A & I University
Richard Hall	Director Dimensions West
Larry Shaw	PC Coordinator Nordstrom, Inc.

Third Prize



Borland SideKick

Jim Roberts	President Pied De Grue Systems
David Halpern	President Emanon
Frank Stein	Sett Manager Citizen Utilities
David McGibbon	Technician CAM-X Service
Stephen P. Richard	President RichComp
Paul Biddle	Director Lencar
Jim Davis	ADO USAF
Richard Busch	Systems Analyst T.I.S.
W.R. Renner	Owner Budget Buys
R. David Richards	President Microtech Systems

Runner-Up Prize

1 Year Renewal/Subscription to PC TECH JOURNAL

Dave McConnell	Vice President Sales Computer Resources Management
David Norris	Microsoft
Jay J. Levine	Director Computer Tax Price Waterhouse
Paul King	President King Computer Systems
Stephanie Levine	Manager Paramount Pictures Corp.
Bobby Williams	Owner Software Systems of Texas
Richard Messeder	Computer Applications Engineer Southern California Edison
Arthur G. Mulanax	Consultant A&S Computers
Gary Rittenbach	Director Walla Walla College
Mel Barnum	Manager, PC Services Maritz Inc.
Robert Ash	President Ameritel
Waleed Sophie	General Manager Oyster International
Roxanna D. Madson	Accountant ATMS
Rick Shindell	Owner Shindell Consultants
David E. Anselmi	C.E. Staff Officer US Army USA15E1C
Kenneth Avellind	Sr. Programmer Analyst Los Church
Janet K. Lang	Vice President O.S. LTD
N.W. Fuerst	Project Engineer Hughes Acpt. ED56
Karl Konnerth	Tech Specialist Syntex
C. Michael Bell	Consultant Technical Consulting
Roger Thompson	Owner Sunnyside Computers
Frank Bromberg	Sr. Director/Dealer Support Western Union
Cathy Miller	Software Development Medirec
Donald E. Orifia	President Micro Works Corporation
Nilsa Stensho	Planpart AB

In addition to congratulating Jim, we'd also like to take this opportunity to thank the COMDEX exhibitors who were kind enough to participate in the contest, and took the time to "install" the "components" involved.

System Unit
ITT – Xtra/286 ATW
Atronics International, Inc. – ATI System 286
Multitech Electronics Inc. – Multitech 900
Univation – Slimline
Televideo – TeleCAT-286
Advanced Logic Research – Access 386
American Mitac – Computitan
Cordata – AT Compatible
Toshiba America Inc. – Information Systems Div

Graphics Adapter Board
STB Systems – Multi Res
Mylex Corp – MYLEX EGA
ATI Technologies – EGA Wonder
Tecmar – EGA Master
Alps America – Image Enhancer
American Mitac – Mega Plus Graphics EGA Board
ATD – Zuckerboard – Monochrome graphics 1/2 card-Zuckerboard
Atronics International, Inc. – Mega Graph Plus
Paradise – Autoswitch EGA
Video 7, Inc. – Vega Deluxe
Everex – Graphics Adapter Board
Univation – Dreamboard

Graphics Display Monitor
Sakata USA Corp. – EGA Performer
Princeton Graphics – HX-12E
Aydin Controls – Patriot Enhancer

Add-in Expansion Memory
IDEAssociates – All Aboard 286
Univation – Dreamboard
Teleware West – Above Disk

Multi-Function add-in Board
Microway Inc. – Number Smasher EC/M
Applied Reasoning – PC Elevator 286
Univation – Dreamboard
Intel – Inboard 386/AT

Modem
BARR Systems – BARR 208AB MODEM
American Mitac – Mitac Modem
Omnitel – Internal Modem

Printer
Cordata – Laser Printer
Toshiba America Inc. – Information Systems Div
ITT QUME – Laser Jet
Citizen America Corp. – any printer

PC Communications Products
Tiara – TiaraLink
Fifth Generation – Logical Connection
Crosspoint System – Crosspoint 8
Videx – Bar Code Reader
Datacopy – JetReader and Model 730
Crosstalk Communications – Crosstalk
Micro Data Base Systems – MDBS III LAN
Star Gate Technologies – OC8000 Board
Kimtron – KT-7
Nestar Systems, Inc. – Plan 5000 File Service
WordPerfect Corporation – WordPerfect
Gateway Communications Inc. – Gateway

Mass Storage/Tape Backup
Core International – CORE HC150
Irwin Magnetics Systems Inc. – BACKUP
Tallgrass Technologies – Grasshopper/Back track s/w
Dynatech Computer Power, Inc. – Turn On
Flagstaff Engineering – 9-track tape
Iomega Corporation – Bernoulli Box
Mountain Computer, Inc. – Racecard 286, 47-MB Drivecard, Series 4000 40MB Tape Back-up System
Sysgen, Inc. – Sysgen Image
Xebec – 97TC
Plus Development Corp – HardCard 20M
Overland Data – Tape linx/9-track tape
Fifth Generation Inc. – Fastback
Maynard Electronics – MaynStream
Weltec Digital Corp

Operating System/Environment
Quantum Software Systems Ltd. – QNX
Xebec – Amnesia Board
Quarterdeck – Desqview

Programming Language/Development Tool
STSC, Inc. – APL* +
Logitech, Inc. – Modula-2
Micro Data Base Systems – Guru

Data Manager
Data Languages – Progress
Data Access – Dataflex
Micro Data Base Systems – MDBS III, Knowledgeman-2
Zanthe – ZIM
UNIFY Corporation – UNIFY
Cosmos Inc. – Revelation
Software Merchants – SIMPLE
Nantucket – Clipper
Informix Software – Informix-SQL
WordTech

Scientific, Engineering, Graphics or Statistical Software
STSC, Inc. – STATGRAPHICS
Autodesk – AutoCAD
Generic Software – GenericCAD
Foresight – Drafix 1

Desktop Utilities
Fifth Generation – Fastback
WalSoft – dFlow

Programmer's Utilities
Lifeboat – Advantage C + +
Gazelle Systems – Q-DOS or Back-It
Microtech Research – C-Cross Compiler
Nostradamus, Inc.
Instant Replay, Pascal Plus, CPlus, Screen Genie, Word Genie, No Blink, DOS/BOSS, Turbo Plus
Opt-Tech – Opt-Scroll, Opt-Tech Sort

Micro-to-Mainframe Communications Products
Digital Communications Associates – IRMA
INS – INS PC Adapter
Persoft – Smarterm 240
Quadram – Quad 5251
CXI, Inc. – P-Cox Family
Information Technologies – Link-Up
Link Technologies, Inc. – PC Term
Gateway Communication Inc. – Gateway
IDEAssociates – IDEAComm 5251

TECH PC JOURNAL

And for those of you who didn't win...
remember there's always next year!

When it comes to choosing the best monitor, you can't get more serious than the Princeton HX-12E.

The HX-12E switches automatically from CGA to EGA for complete IBM compatibility at the best value. And Princeton delivers performance to meet your immediate needs today. And every day. Right away.

But that's just part of how serious we are. At Princeton Graphic Systems, we believe the best monitor is still the monitor with the best picture.

The Princeton HX-12E set the image standard in display technology. Our advanced design features the finest dot pitch (.28mm) to create the sharpest, clearest and most colorful image of any monitor in its class. It's a difference you can see, and it's the difference that gives you the visible edge.

So the next time you're wondering who makes the best monitor, take a look at the Princeton HX-12E. It's where you'll find the finest components matched to the highest engineering standards for uncompromising performance and value.

And we simply can't picture it any other way. And that's no fooling.

PRINCETON®
GRAPHIC SYSTEMS
THE VISIBLE EDGE

IBM Model 5154 .31mm dot pitch, NEC Multisync .31mm dot pitch, Princeton HX-12E .28 mm dot pitch.

601 Ewing Street, Bldg. A, Princeton, New Jersey 08540 (609) 683-1660 Ext. 82

CIRCLE 161 ON READER SERVICE CARD

How to 386



It's simple.

With Intel's Inboard™ 386/AT.

It fits right into your IBM® AT or compatible, and gives you all the performance of a 386 system.

Without having to buy a 386 system. (Which, if you've priced one lately, is about three times as expensive.)

Inboard 386 is based on the revolutionary 32-bit, 16 MHz 80386 chip *we* invented. So it'll work with all the software you've got sitting on your desk. As well as any add-in boards you may have hiding in your computer—like, just for instance, the Above™ Board. Which we also invented.

Inboard 386 lets you whiz through recalcs with Lotus® 1-2-3.® And it makes your network server serve you even faster. In fact, it'll make any program serve you faster.

And with 386 control software,

Inboard and Above are trademarks and Intel a registered trademark of Intel Corporation. IBM is a registered trademark of International Business Machines Corp. Lotus and

your AT.



you can take advantage of exceptional multitasking capabilities. Like putting together a presentation while your computer is downloading data. (A slightly more efficient way of doing business.)

Don't forget our five-year warranty. Or toll-free technical support line.

To find out more, check with your favorite computer dealer or call us at (800) 538-3373.

And see why Inboard 386 beats the system.

intel®

1-2-3 are registered trademarks of Lotus Development Corp. © 1986 Intel Corporation

CIRCLE NO. 216 ON READER SERVICE CARD

THE PROGRAMMER'S SHOP

helps save time, money and cut frustrations. Compare, evaluate, and find products.

RECENT DISCOVERY

Turbo Expert by Thinking Technologies - Menu driven expert system generation package details reasoning, comes with tutorial, manual, demos. "Corporate" supports up to 4000 rules. "Startup" up to 400. Corporate $359, PC Startup $129

AI-Expert System Dev't

Arity System - use with C	MS	$ 259
Auto-Intelligence	PC	$ 749
Experteach - Powerful, samples	PC	$ 349
Exsys	PC	$ 309
Runtime System	PC	$ 479
Insight 2+	MS	$ 379
Intelligence/Compiler	PC	$ 749
SQL Dev't Package	MS	$ 259
Texas Instruments:		
PC Easy	PC	$ 439
Personal Consultant Plus	PC	$2599

AI-Lisp

Microsoft MuLisp 85	MS	$ 179
PC Scheme LISP - by TI	PC	$ 85
TransLISP - learn fast	MS	Call
TransLISP PLUS		
Optional Unlimited Runtime		$ 150
PLUS for MSDOS		$ 179

Others: IQ LISP ($155), IQC LISP ($269)

AI-Prolog

APT - **A**ctive **P**rolog **T**utor - build applications interactively	PC	Call
ARITY Standard - full, 4 Meg		
Interpreter - debug, C, ASM	PC	$ 309
COMPILER/Interpreter-EXE	PC	$ 699
With Exp Sys, Screen - KIT	PC	$1129
Standard Prolog	MS	$ 79
MacProlog Complete	MAC	$ 295
MicroProlog - intro	MS	$ 85
MicroProlog Prof.	MS	$ 339
MPROLOG P550	PC	$ 175
Prolog-86 - Learn Fast	MS	$ 89
Prolog-86 Plus - Develop	MS	$ 229
TURBO PROLOG by Borland	PC	$ 69

Editors for Programming

BRIEF Programmer's Editor	PC	Call
EMACS by UniPress - Source: $929		$ 299
Epsilon - like EMACS	PC	$ 155

Atari ST & Amiga

Manx, Lattice, & Metacomco.		Call
Amiga - LINT by Gimpel	Amiga	$ 79
Cambridge LISP	Amiga	$ 200
Lattice C	ST, Amiga	$ 139
Lattice Text Utilities	Amiga	$ 75
Megamax - tight, full	ST	$ 200

FEATURES

r-tree - report generation for ctree. Multiple file handling, fixed or variable length. Many built-in functions like Boolean, computational functions, string, date handling, numeric to string conversion. Source in C. PC $ 249

Advantage C++ - Object-oriented enhancements for most major C compilers also maintain compatibility with existing C code. Write reusable easily maintainable code, develop large applications with fewer bugs. Call

Free Literature
Compare Products

Evaluate products. *Compare* competitors. Learn about new alternatives. One *free call* brings information on just about any programming need. Ask for any ***"Packet"*** or Addon Packet □ AI □ ADA, Modula □ BASIC □ "C" □ COBOL □ Editors □ FORTH □ FORTRAN □ PASCAL □ UNIX/PC or □ Debuggers, Linkers.

Our Services:

- **Programmer's Referral List**
- **Compare Products**
- **Help find a Publisher**
- ***Evaluation Literature FREE***
- **BBS - 7 PM to 7 AM 617-826-4086**
- **Dealers Inquire**
- **Newsletter**
- **Rush Order**
- **Over 700 products**
- **National Accounts Center**

C Language-Compilers

AZTEC C86 - Commercial	PC	$499
Datalight C - fast compile, good code, 4 models, Lattice compatible, Lib source. Dev'rs Kit	PC	$ 77
Datalight Optimum - C	MS	$ 99
with Light Tools by Blaise	PC	$168
Lattice C - from Lattice	MS	$275
Mark Williams - w/debugger	MS	$369
Let's C Combo Pack	PC	$ 99
Let's C	PC	$ 59
Microsoft C 4.0- Codeview	MS	**$279**
Uniware Cross Assemblers	MS	$249
Cross Dev't Tools	MS	Call
Rex - C/86 by Systems & Software - standalone	MS	$695
Wizard C	MS	$359
Rom Development Package	MS	$299

C Language-Interpreters

C-terp by Gimpel - full K & R	MS	$229
C Trainer - by Catalytix	PC	$ 89
INSTANT C - Source debug, Edit to Run-3 seconds, .OBJs	MS	$379
Interactive C by IMPACC Assoc.	PC	$209
Introducing C-self paced tutorial	PC	$105
Run/C Professional	MS	$169
Run/C Lite	MS	$ 89

C Libraries-General

Blackstar C Function Library	PC	$ 79
C Essentials - 200 functions	PC	$ 83
C Function Library	MS	$119
C Tools Plus (1 & 2) - Blaise	PC	$135
C Utilities by Essential	PC	$137
C Worthy Library - Complete, machine independent	MS	$249
Entelekon C Function Library	PC	$119
Entelekon Superfonts for C	PC	$ 45
Greenleaf Functions-portable, ASM		$139
LIGHT TOOLS by Blaise	PC	$ 69

C Libraries-Files

FILES: C Index by Trio - full B+ Tree, vary length field, multi compiler		
/File is object only	MS	$ 89
/Plus is full source	MS	$319
CBTREE - Source, no royalties	MS	$ 99
CTree by Faircom - no royalties	MS	$319
rtree - report generation	PC	$249
dbQUERY - ad Loc, SQL - based	MS	$159
dbVISTA - full indexing, plus optional record types, pointers, Network.		
Object only - MS C, LAT,	C86	$145
Source - Single user	MS	$399
Source - **Multiuser**	MS	$799

RECENT DISCOVERY

F2C by Solution Systems - Fortran 66 or 77 to C. No max program size $3000. Pioneer. 1000 line max: $ 795

dBASE Language

Clipper compiler	PC	Call
dBASE II	MS	$329
dBase III Plus	PC	$479
dBASE III LanPack	PC	$649
dBXL Interpreter by Word Tech	PC	$139
FoxBase+ - single user	MS	$349
QuickSilver by Word Tech	PC	$499

dBASE Support

dBase Tools for C	PC	$ 65
dBrief with Brief	PC	Call
DBC ISAM by Lattice	MS	$179
dBx Translator to C	MS	$319
dFlow - flowchart, xref	MS	Call
Documentor - dflow superset	MS	$229
Genifer by Bytel-code generator	MS	$299
QuickCode III Plus	MS	$249

Fortran & Supporting

50:More FORTRAN	PC	$ 99
ACS Time Series	MS	$399
Forlib+ by Alpha	MS	$ 59
MACFortran by Microsoft	MAC	$229
MS Fortran - 4.0, full 77'	MS	**$299**
No Limit - Fortran Scientific	PC	$115
PC-Fortran Tools - xref, pprint, screen	PC	$179
RM/Fortran	MS	Call
Scientific Subroutines - Matrix	MS	$139
Statistician by Alpha	MS	$249
Strings and Things-register, shell	PC	$ 55

MultiLanguage Support

BTRIEVE ISAM	MS	$199
BTRIEVE/N-multiuser	MS	$465
Flash-Up Windows	PC	$ 79
GSS Graphics Dev't Toolkit	PC	$375
HALO Graphics	PC	$209
I/O Pro - screens, full char.	PC	$349
Informix - by RDS	PC	$639
Informix 4GL-application builder	PC	$799
Informix SQL - ANSI standard	PC	$639
Opt Tech Sort - sort, merge	MS	$115
PANEL	MS	$215
Pfinish - by Phoenix	MS	$229
PolyLibrarian by Polytron	MS	$ 79
PolyBoost - speed I/O, keyboard	PC	$ 69
PVCS Version Control	MS	$329
QMake by Quilt Co.	MS	$ 84
Rtrieve - Xtrieve option	MS	$119
Screen Sculptor	PC	$ 95
SRMS - source control	MS	$109
Xtrieve - organize database	MS	$199
ZAP Communications - VT 100	PC	$ 89

FEATURE

Sapiens V8 - virtual memory management for C programmers on PC's provides 8M workspace, 64-bit emulation, virtual stack library and heap. Link to MS, Lattice, Aztec. PC $300

We support MSDOS (not just compatibles), PCDOS, Xenix-86, CPM-80, Macintosh, Atari ST, and Amiga.

CIRCLE NO. 162 ON READER SERVICE CARD

THE PROGRAMMER'S SHOP

provides complete information, advice, guarantees and every product for Microcomputer Programming.

Special Features

COBOL & C Screen Management

Finally . . . Easy Screen Handling for COBOL Saves Time, Adds Flexibility: Screenplay

Menus, Help, and Data Entry Screens can be created ("painted") interactively. When you are satisfied Screenplay performs all screen handling for you in any of more than 9 compilers.

Save valuable time by avoiding the tedious, time consuming process of writing screen handling source code. Screenplay's easy-to-use panel painter allows you to create I/O panels, pop-up windows or menu panels.

True screen handling flexibility is yours. Override default panel settings to design practically any type of screen imaginable — even change just about any panel characteristic at runtime.

Prototype your draft screens before you write a single line of COBOL source code. In addition, you can link Screenplay by interrupt or directly to your application. And if your compiler doesn't allow a direct link, use the dynamic load option for linking Screenplay to your application.

You can assign practically any keyboard key to serve as a specific cursor function and define exactly which keys will return control to your application. Entirely reconfigure the keyboard for your program.

Screenplay's panel painting process is a one step approach. There's no need to go through a separate process to establish fields on your I/O panel. What's more, you can use any ASCII character in your Screenplay panels. You also have full control over character attributes such as foreground and background color, intensity, and blinking.

Panels are stored in a compressed ASCII file save memory and disk space. Copy panels across and within files, rename, delete, test and print panel details. Even print an image of the panel for your documentation. No royalties. Not copy-protected. Supports IBM, MS, Realia, Ryan-McFarland (including 8X) COBOL.

201-895-4724 **PCDOS List: $175 Ours: $155**

Multitasking Technology

Multitasking, Windowing for C, Turbo Pascal, or dBASE or . . . in only 12K!

SYNERGY Development Toolkit

The highly efficient design of Synergy by Matrix gives you the benefits of powerful graphics, windows, pull-down menus, dialog boxes, sophisticated text and icon management, math support, multitasking, and SPEED, all for an incredibly small **12K RAM** requirement.

The Synergy Runtime provides character and graphics support for menus, windows, dialog boxes, and more, so you can write programs that work in either mode, with very reasonable, low runtime fees.

Functions include: window management with capabilities like tile and overlap, variable size and placement, process management, to support multitasking and sub-process generation, menus, dialog, and icon management, graphics, text (including a variety of fonts and sizes), and console management.

The Synergy Development Toolkit is a collection of sophisticated tools designed for software developers writing new applications using Synergy, or modifying existing applications to take full advantage of Synergy. Tools include: graphics resource editor for creating and modifying icons and text fonts, graphics resource compiler to construct and manage resource data files, font compiler and manager, debugging tools, sample library, and more.

Supports IBM or Microsoft Macro Assemblers, Turbo, IBM, and Microsoft Pascal, IBM and Microsoft BASIC, Lattice and Microsoft C, and dBASE II and III. CGA, EGA, and Hercules monochrome graphics support.

MATRIX **617-567-0037** **PCDOS List: $395 Ours: $375**

Expert System Shell & Language

Add AI Power to Existing Applications

Insight 2+

"Insight 2+ is an awesome system . . . this may well be the best expert system generator on the market." — ONLINE

Choose a knowledge engineering tool that makes your current database solutions work smarter with a built-in PASCAL-like knowledge engineering grammar that minimizes your training time. Insight 2+ works with your installed software and database and has intrinsic dBASE II and III operators, plus Level Five's powerful, flexible Production Rule Language.

Insight 2+ is a highly connective, integrated expert systems shell that adapts to your needs. Its detailed interactive reporting system lets you see *inside* the reasoning process of the knowledge base. You can see reports on the lines of reasoning, known and unknown facts, alternate rule pathways to a shared conclusion, or knowledge trees, showing all possible goals, conclusions, and paths of reasoning hierarchically — and more. You can even step forward and back in a rule chain from beginning to end.

Create "what-if" scenarios by saving, editing, and re-using knowledge base contexts, or customized reporting to track end-user sessions.

Insight 2+ performs backward and forward chaining inference, supported by object attribution and goal outlining, outside program activation, and full parameter passing capabilities.

Insight 2+ supports very large knowledge bases which can be linked — the number limited only by disk space. Full scientific and math capabilities include logarithmic and trigonometric functions and floating point notation; ideal for engineering and scientific applications.

305-729-9046 **PCDOS List: $485 Ours: $389**

Screen Management

Get a Cleaner, Faster, User Interface with

The Screen Ace Form Master

Coded in assembler to give you the power for creative design, and the speed not available in other packages.

Form Master supports all 256 color and monochrome attributes. Paint screens with the screenbuilder (allows changes without recompiling!) and save to a DOS file, define screens within your program at runtime, or combine these techniques, to modify screens on the fly.

400+ lines and 2000+ fields per screen; the number of screens limited only by available memory.

Permits flexible function key definition, toggling field colors and attributes at runtime. Switch between screens without losing data.

DESQview, TopView, MS Windows compatible, Lattice, MS C (all models), APL*Plus/PC, Assembler. Call for a $3 demo with tutorial.

PCDOS List: $195 Ours: $179

818-989-5329

O/S ADDON

NOW: Full Shell Programming with MSDOS:

PolyShell with

UNIX-Like Utilities

PolyShell gives you a UNIX-compatible command environment PLUS a full set of UNIX-like utilities — yet DOS commands and batch files are always immediately accessible.

Alias and Command Macro Substitution save keystrokes, let you access and customize DOS internal commands. With History Substitution, edit, re-execute previous commands or portion of command.

'C-Shell' and Bourne Shell compatible I/O redirection, very flexible filename expansion capabilities.

Includes 30 powerful utilities from the UNIX world (like grep, diff, sed, cut, paste). Shell and utilities can be loaded separately. Requires only 30K RAM total. PolyShell is NOT UNIX; no UNIX license needed.

PCDOS List: $149 Ours: $129

503-645-1150

Call for a catalog, literature, advice and service you can trust

VISA HOURS MasterCard

8:30 AM - 8:00 PM EST.

800-421-8006

THE PROGRAMMER'S SHOP™

5-P Pond Park Road, Hingham, MA 02043

Mass.: 800-442-8070 or 617-740-2510 1/87

"The scope and detail of services you provide are exemplary — it's obvious you have given a lot of thought to what information people need . . . For someone like myself, critical appraisals of software and comprehensive collections of offerings such as you have are really useful."

A. Bruce Cyr
Foundation of American College of Health Care Administrators

CIRCLE NO. 151 ON READER SERVICE CARD

ALR ACCESS 386:

Poised for Tomorrow

Continuing a tradition, Advanced Logic Research brings up-to-date technology to affordable 386-based systems.

MICHAEL ABRASH and DAN ILLOWSKY

Advanced Logic Research (ALR), Inc., has built a product line of IBM-compatible computers that not only costs less, but also outperforms the originals from IBM. With the introduction of the Access 386, ALR has continued that tradition by bringing to market a reasonably priced, extremely powerful AT compatible built around the 32-bit Intel 80386 processor.

Three Access 386 models, differing in price and in hard disk, memory, and display adapter configuration are available. (See the accompanying sidebar for their features and prices.) The system reviewed in this article was the Access 386EC, with the following options: a 2MB, 32-bit memory expansion board, an enhanced keyboard, and a 10-MHz 80287 floating-point coprocessor. A 16-MHz 80387 will be available as soon as the 80387 is on the market.

The Access 386 sports a somewhat more stylish appearance than does the average AT, owing to horizontal openings in the grill across the front of the system unit rather than the usual vertical grid. Otherwise, the Access 386 system box is similar to that of the AT. The dimensions of the system unit are almost the same at 21.25 by 16.5 by 6.5 inches. Only the height is larger. The power-on and hard-disk-access indicator lights and the key lock are present in the same front panel locations as on the AT; the power switch is located in the same position, at the back of the right side of the system unit.

ALR has improved on the AT system unit by expanding the drive bay opening at the right of the front panel. Three half-height devices, rather than the standard two, can be accessed through the drive bay opening, so that a user can have a high-density drive, a 360KB drive, and a tape backup unit installed together. A second drive bay to the left of the first bay normally contains the hard disk, and it is not accessible from the outside.

The key lock works the same way as the AT key lock does. When the Access runs through its power-up tests, it checks to see whether the key lock is locked. If it is, a message is displayed to that effect, and the Access 386 waits until the F1 function key is pressed. This feature can save a user from thinking that the keyboard is defective when in fact it is only locked. However, if the

PHOTOGRAPH • MARC DAVID COHEN


ACCESS
386

PHOTO 1: *Original Keyboard Comparison*

PHOTO 2: *Enhanced Keyboard Comparison*

PHOTO 3: *Back Panel of System Unit*



PHOTO 4: *Inside the System Unit*



PHOTO 5: *System Motherboard*



PHOTO 6: *2MB Expansion Board*



Photos 1 and 2: The Access 386 keyboards are similar to their IBM counterparts (shown in the bottom of each photo.)

Photo 3: The rear panel shows the cutouts for the serial and parallel ports, between the fan and the expansion slots.

Photo 4: Inside the system unit, the hard disk is mounted in the left bay; the diskette drive is mounted in the right bay.

Photo 5: The 80386 is in the top right-hand corner. The 80287 option card is plugged into the 80387 socket.

Photo 6: Up to two 32-bit memory expansion boards can be installed for total of 4MB of 32-bit expansion memory.

computer is operating unattended, it cannot automatically restart itself after a power interruption has occurred. This can be a problem in remote and network applications.

Two keyboards are available with the Access 386. One version is similar to IBM's original AT keyboard, and the other resembles the new enhanced AT keyboard. ALR now packages the enhanced keyboard with the Access 386, but the original version is available on request. Both keyboards were tested with the reviewed system and worked well. The original AT-style keyboard features green LED indicators on the NumLock, ScrollLock, and CapsLock keys rather than providing the separate indicator area used on the actual AT keyboard. Photo 1 compares the original IBM keyboard with ALR's version. This keyboard has a stiff feel, but, unlike all of the IBM keyboards, it does not provide tactile feedback. The keyboard cable is not long enough. The keyboard plugs into the back of the system unit, and the cable has to be stretched in order to position the keyboard in front of the system unit. Laptop typing, therefore, is not feasible.

The enhanced keyboard, shown in photo 2, is the preferable option. Like the keys on IBM's keyboards, the keys on ALR's enhanced keyboard have a maximum resistance point about halfway down, below which the key descends more easily. ALR's keyboard provides less tactile feedback than does IBM's, but in extended service it is still comfortable for a touch-typist. The cord on the enhanced keyboard is of more than adequate length. The enhanced keyboard that was reviewed displayed a minor peculiarity: when the system unit was powered on, the keypad sometimes came up in numeric mode and sometimes it came up in cursor mode. Likewise, on warm boots the keypad would come up in either mode, seemingly at random. The NumLock status indicator, however, always reported the state correctly, and otherwise the keypad operated in a normal fashion.

Certain keystrokes (for example, Alt-F10) are less convenient on the enhanced keyboard layout than they traditionally have been. While ALR's enhanced keyboard is generally a better keyboard than the standard AT-style version, prospective buyers of the Access 386 may want to consider how well the new layout will function with their favorite software.

The system unit generates a faint click with every keystroke. The clicking is so muted that it scarcely can be heard over the noise of the keys being pressed, and becomes apparent only when a key is held down and repeats. Lacking in the manual is the information that the click volume can be changed by pressing Ctrl-Alt-+ (the + on the numeric keypad). Eight volume levels are possible.

The reviewed system included ALR's enhanced graphics adapter (EGA) and color monitor. The ALR EGA is a full-length board built around the Chips and Technologies (C&T) chip set that has become the standard in the EGA-compatible market. For a review of C&T-based boards, see "Evaluating the EGA: The EGA Spectrum, Part 1 and Part 2," John T. Cockerham, October 1986, p. 80 and November 1986, p. 147.

ALR's EGA is fully compatible with the IBM EGA. Unlike some EGA-compatible boards, ALR's EGA does not support downward compatibility below the BIOS level with a color-graphics adapter (CGA) or any compatibility with the Hercules Graphics Card. It does not offer extended modes such as 640-by-480 pixel graphics or 132-column text. An extra feature provided by the ALR EGA is a built-in printer port, which is on the backplane connector of the EGA, just as it is in the monochrome adapter. This printer connector arrangement is convenient. To create the space that it occupies on the back panel connector of the EGA, ALR eliminated the feature connector jacks and moved the configuration switches to the middle of the EGA board, where they are inaccessible from outside the system unit.

The performance characteristics of ALR's color configuration are identical to that of the IBM EGA: resolutions of 640 by 350, 640 by 200, and 320 by 200 pixels, with up to 16 of a possible 64 colors available. The ALR EGA can drive a monochrome monitor, but because the EGA is bundled with a color monitor in the Access 386EC, it was evaluated as a color board only. The fonts used by the ALR EGA are markedly different from the IBM EGA fonts; they are more angular and feature fewer serifs, but are eminently readable.

The ALR EGA BIOS, from Phoenix Technologies, Ltd., is stored in a 16KB-

ALR ACCESS 386 VITAL STATISTICS

Since this article was written, ALR has reconfigured its product line. The display board and the 32-bit memory board are no longer bundled with the system, and an EGA board and monitor are offered as options. The monographics board and monitor are no longer available. The 1MB of memory is filled by the 16-bit Challenger multifunction board.

Access 386B: $3,990
512KB memory
Parallel and serial ports
1.2MB diskette drive
Realtime clock
Diskette/hard-disk controller
Enhanced keyboard

Access 386-40: $5,699
1MB memory
Parallel and serial ports
1.2MB diskette drive
Realtime clock
Enhanced keyboard
Diskette/hard-disk controller
40MB, 28-ms hard disk

Access 386-80: $6,569
1MB memory
Parallel and serial ports
1.2MB diskette drive
Realtime clock
Enhanced keyboard
Diskette/hard-disk controller
80MB, 25-ms hard disk

Access 386-130: $8,490
1MB memory
Parallel and serial ports
1.2MB diskette drive
Realtime clock
Enhanced keyboard
Diskette/hard-disk controller
130MB, 20-ms hard disk

Memory capacity on system board
512KB

32-bit memory capacity of system
4.5MB now, 15.5MB to come

Expansion slots
32-bit: 2
16-bit: 4
8-bit: 2

Options available
360KB diskette drive: $199
2MB, 32-bit memory board: $1,695
10-MHz 80286 coprocessor kit: $795
ALR EGA board: $399
EGA color monitor: $699

by-8-bit ROM. The 8-bit data path to the ROM causes data and especially instruction fetches from the BIOS to occur much more slowly than fetches from motherboard memory—as much as eight times more slowly.

The color display is compatible with the IBM Enhanced Color Display supporting display modes of 320-by-200, 640-by-200, and 640-by-350 pixels and 64 colors. The monitor produces accurate colors and sharp, readable text on a dark background. The edges of the display area in the reviewed display are not quite linear (bowing out on the sides and in on the top and bottom) when measured against a straight edge, but the deviation is not obvious during actual use. The brightness, contrast, and on/off controls are thumbwheels on the right side of the monitor, where they are easily accessible without impinging on the available display area, as do controls located on the front panel of many EGA-compatible displays. Two lights indicate whether the power is on and whether the monitor is in 200- or 350-scan-line mode.

A monochrome display system was not included with the reviewed system. The Access 386EM model, however, features a monochrome display system, including Hercules-compatible monographics and a monochrome monitor. The base Access 386 system, the 386B, comes without a display system.

The monitor rests on an adjustable pedestal base, which allows the user to change the angle, but which also makes the monitor sit a bit too high for comfortable viewing when placed atop the system unit. The ideal configuration for the Access 386EC is with the monitor sitting directly on the desktop, with the system unit off to one side or under the desk. The monitor cable is approximately three feet long, making it possible to move the color display away from the system unit.

The diskette drive included with all Access 386 models is a standard AT-style 1.2MB drive. The drive is spring-loaded and ejects diskettes about an inch when the latch is opened.

AVAILABLE PORTS

A serial port and a parallel port are built into the motherboard. Both can be used via short cables terminating in standard PC-style, 25-pin, D-shell connectors in special cutouts on the back panel of the system unit (see photo 3). The cutouts are located between the power supply fan and the expansion slots. The serial port can be configured as COM1 or COM2 or disabled. The parallel port can be configured as LPT1 or LPT2 or disabled. All of the Access 386 models have these ports built in. The Access models 386EC and 386EM include the ALR Challenger multifunction board, which adds a serial port and a parallel port, as well as up to 2MB of 16-bit memory. These additional ports can be configured in the same way. The display boards included in the Access 386EC and 386EM models also include parallel ports that can be configured as LPT1 or disabled.

In the reviewed Access 386, the motherboard parallel port was disabled and left unconnected, and the parallel ports on the ALR EGA and the Challenger board occupied the two parallel port locations available to non-monochrome-adapter parallel ports. The motherboard parallel port was thus redundant. In the Access 386EM, however, the parallel port on the monochrome display board is at the location reserved for monochrome-adapter parallel ports; with the proper cable to hook up the motherboard parallel port, it should be possible to have three rather than the

VAX
"EDT on my PC!"



AVAILABLE NOW on MS-DOS, UNIX, ULTRIX-32 and XENIX

With PC/EDT you can use "your editor" on non-DEC systems! Quickly move between VMS, MS-DOS, UNIX and other operating systems without losing productivity!

PC/EDT has full VAX EDT capability...Standard EDT Keyboard Layout...All LINEMODE Commands...Journal and Command Files...User-Defined Keys...Support for Color...Command Macros...and much more!

PC/EDT is only $250. Call us at **(617) 683-7920** and we'll send you more details...or write us at Riverwalk Center, 360 Merrimack Street, Lawrence, MA 01843 Telex 9102405742

Use Your Knowledge . . . Use PC/EDT

BOSTON BUSINESS COMPUTING, LTD.

The DEC™ Compatible Software Company

VAX, VMS, ULTRIX-32, and DEC are trademarks of Digital Equipment Corporation.
UNIX is a trademark of AT&T. MS-DOS and XENIX are trademarks of Microsoft.

CIRCLE NO. 178 ON READER SERVICE CARD

ORCHID'S JET 386™: POWER FOR THE FUTURE NOW

SPECIAL PRICE $1199.00

Jet 386 is the Ultimate Accelerator Upgrade for Your AT

Announcing an end to obsolescence. Orchid Technology's Jet 386™ accelerator card extends the life of your computer investment into the 1990s—it puts power in your AT that you won't outgrow.

Three Times Faster than an AT

It's up to three times faster than an AT depending on the application, and speed is just one benefit. Unequalled compatibility and provisions for upcoming 386 software mean your Jet 386 will handle whatever the future has in store: CAD, spreadsheets, networking...

Easy Upgrade

Easy to use, there's nothing new to learn and no new programs to buy. At 25% of the cost of buying a new 386 PC, it's easy on your pocketbook, too.

From the People Who Started It All

Orchid combined 80386 power with the technology perfected for the XT in the TinyTurbo and PCturbo 286e. Like these critically acclaimed accelerators, Jet 386 is built for lasting value.

Call Orchid to find out how you can experience the future today. And ask how Orchid can modernize your whole office with turbos, graphics, networking, and multifunction products.



ORCHID
Innovative Add-Ons

45365 Northport Loop West
Fremont, CA 94538
415/490-8586 Tlx: 709289

CIRCLE NO. 159 ON READER SERVICE CARD

Jet 386, PCturbo 286e and TinyTurbo 286 are trademarks of Orchid Technology. All other products named are trademarks of their manufacturers.

microDCF™
Text Workstation

IBM DCF3 Compatible Text Processing System For Your PC

- IBM Script language
- IBM GML language
- macro libraries
- symbol support
- multi-pass processing
- high performance
- laser printer support
- table of contents
- back-of-book index
- user-definable languages
- modular print manager
- and much more...

$795.-
Quantity Discounts
Site Licenses
Full Maintenance

APS/SPF™
Programmer Workstation

IBM ISPF Compatible Program Development Tools For Your PC

- ISPF PDF editor
- dialog manager
- dialog panel editor
- utilities
- multitasking while editing
- directory file selection
- customizable master menu

from $145.-

ALSI

Arrix Logic Systems Inc.
PO Box 142, Don Mills Stn.
Ontario M3C 2R6, Canada
(416) 292-6425
TELEX 06-986766 TOR
IBM is a registered trademark of International Business Machines Corp.

CIRCLE NO. 122 ON READER SERVICE CARD

advertised two parallel ports available in the Access 386EM.

ALR's Access 386 is more than just a well-designed, solidly built AT compatible. The Intel 80386 processor makes this computer special. This is a true 32-bit processor that can support as much as 4GB of linear memory, multitasking with task protection, memory paging, and full 8086 compatibility while running one or several DOS sessions simultaneously. None of these features is supported by the 80286 processor that is used in the AT. For a discussion of the implications of the various modes of operation of the new 80386, see "The New Standard," Steven Armbrust and Ted Forgeron, March 1987, p. 48; "Upward to the 80386," Caldwell Crosswy and Mike Perez, February 1987, p. 50; and *Introduction to the 80386*, Intel Corporation, 1986.

The 80386 can run at twice the clock rate of the 80286 in a standard AT; it is about twice as fast as the 80286, even running programs that do not take advantage of the 32-bit operation of the 80386—a category that includes virtually all of the current DOS software. As software becomes available that takes full advantage of the 80386's 32-bit instruction set, the performance advantage of the 80386 relative to the 80286 will increase. This 32-bit software will run only on 80386-based machines. Eventually, the most powerful software will demand nothing less than an 80386.

The 80386 in the Access 386 runs at 16 MHz, twice the speed of the 80286 in the 8-MHz IBM AT. The Access 386 supports all modes of operation of the 80386: real mode, protected mode, and virtual-8086 mode. All of the currently available 80386-based computers feature 16-MHz operation. Significant performance differences between 80386-based computers will result primarily from memory system architecture. While the 80386 itself is an extremely fast processor, inexpensive memory in a standard configuration cannot supply information as fast as the 80386 demands it. Consequently, considerable ingenuity has gone into designing 80386 memory systems, and the design of an affordable memory system that can support the high performance of the 80386 is a difficult task that can be approached in a number of ways.

APPROACHES TO MEMORY

A brief summary of memory architecture options will help to place the Access 386 in the spectrum of 80386 computers. An 80386-based computer could be built with readily available, relatively inexpensive DRAM chips, as is done in the AT. This approach, however, results in several wait states on every memory access and effectively slows the computer to near-AT speeds. One of the simplest approaches to developing a high-performance 80386 memory system is building a system in which all of the memory is fast enough to let the 80386 run with no wait states. This requires SRAM chips with an access time of approximately 60 ns (nanoseconds); the expense of such chips makes this option impractical for most purposes.

The Compaq Deskpro 386 is designed to use an 80386 memory system static-column RAM. In this architecture, system memory consists of a number of fairly small pages (2KB in the Deskpro 386). Repeated accesses within a single page occur with no wait states, while an access that falls in a different page from the previous access does incur wait states. The overall performance of a static-column RAM memory system is dependent on the extent to which successive memory accesses tend to be local within the same page.

Considerable ingenuity has gone into designing 80386 memory systems that are able to support the high performance of the 80386.

Another approach is the use of a memory cache. In this case, a relatively small (usually 64KB or less), fast SRAM memory is used to store a copy of the most recently accessed locations in normal memory. Because most accesses (generally more than 90 percent) occur to the fast cache memory, performance improves dramatically. The extent of the improvement is dependent on the *hit rate* of the cache, the frequency with which accessed memory locations tend to be in the cache. Memory caching becomes more important as processor speed increases. A 24-MHz 80386 without a cache would likely be severely bound by memory speed because any type of memory (such as the static-column RAM used in the Deskpro 386) that is affordable enough to be used in megabyte quantities would not be able to run as fast as the 80386 and would greatly slow the processor by inserting many wait states. It is not clear, how-



Imagine the speed and power of a $100,000 minicomputer in a desktop PC costing under $7,000. Now imagine all that power going to waste because the operating system you chose was never meant to take advantage of a computer this powerful. It will take more than just a "window environment" or an outdated operating system to unlock the 80386.

It will take PC-MOS/386™.

The First 80386 Operating System. Specifically designed for the 80386 computer, PC-MOS/386™ opens doors. Doors to more memory and multi-tasking. Doors to thousands of DOS programs as well as upcoming 80386-specific software. It's the *gateway* to the latest technology..., and your networking future.

Memory Management Without Boards. PC-MOS exploits the memory management capabilities built into the 80386. So, up to four GIGABYTES of memory are accessible to multiple users and to future 80386-specific applications requiring megabytes of memory.

Multi-Tasking, Multi-User Support for One, Five or 25 Users. PC-MOS/386™ allows up to 25 inexpensive terminals to be driven by a single 80386 machine. So the features of the 80386 can be utilized at every terminal. And it comes in three versions so you can upgrade your system as your company grows...without having to learn new commands or install new hardware.

UP TO 25 USERS.

MADE FOR THE 80386.

RUNS DOS PROGRAMS.

MULTI-TASKING

Software Support for Thousands of DOS Programs. Although PC-MOS/386™ totally replaces DOS, it doesn't make you replace your favorite DOS programs. So you can run programs like Lotus 1-2-3, WordStar, dBASE III, and WordPerfect on the 80386. Best of all, it uses familiar commands like DIR and COPY–so you'll feel comfortable with our system.

The Gateway to Endless Features. Distinctive characteristics like file/system security, remote access, file/record locking, and built-in color graphics support for EACH user set PC-MOS/386™ apart from all previous operating systems.

Open the Doors to Your Future TODAY! Call The Software Link TODAY for more information and the authorized dealer nearest you. PC-MOS/386™ comes in single, five & 25-user versions starting at $195.

THE SOFTWARE LINK, INC.

Developers of LANLink™ & MultiLink® Advanced

8601 Dunwoody Place, Suite 632
Atlanta, GA 30338 Telex 4996147 SWLINK

CALL: 800/451-LINK

In Georgia: 404/998-0019
Dealer/OEM Inquiries Invited
Dealers: 404/998-0700 OEMs: 404/641-8554

THE SOFTWARE LINK, INC./CANADA
CALL: 416/477-5480

More Than Just Windows, We've Opened Doors.

TRADEMARK ACKNOWLEDGEMENTS: MultiLink® is a registered trademark of The Software Link, Inc. PC-MOS/386,™ MultiLink® Advanced, and LANLink™ are trademarks of The Software Link, Inc. Lotus 1-2-3, WordStar, dBASE III, & WordPerfect are trademarks of Lotus Development Corp., MicroPro, Ashton-Tate, & WordPerfect Corp., respectively. Prices and technical specifications subject to change.

CIRCLE NO. 196 ON READER SERVICE CARD

ever, that the additional cost of cache logic and memory is justified in a 16-MHz 80386 computer.

The Access 386 uses memory interleaving for building an 80386 memory system. System memory is divided into two banks, with sequential 32-bit memory addresses alternating between the banks. As an example, addresses 0-3 would be located in one bank, addresses 4-7 would be located in the other bank, and addresses 8-11 would be back in the first bank. DRAM chips require a waiting period after a memory access before they can be accessed again; in the case of the 120-ns DRAM chips used in the Access 386, this extra waiting period amounts to two 80386 wait states. With memory interleaving, one of the banks can recover while the other bank is accessed—as long as successive accesses occur to different banks. Ideally, all memory accesses would alternate banks, and the 80386 would operate at maximum speed. In fact, patterns of memory accesses vary and the performance of an 80386 with an interleaved memory system depends on the tendency of the application to alternate between banks.

The 80386 can perform address pipelining, placing memory addresses on the address bus one cycle early in order to give the memory system a chance to get started early with the next access. If idle bus cycles occur, address pipelining must be restarted on the next memory access, at a cost of one wait state. Address pipelining can be used only with memory that takes advantage of it. The 32-bit memory in the Access 386 has been designed to take advantage of this feature.

The Access 386 combines memory interleaving and address pipelining in an affordable system. The 512KB of motherboard memory is divided into two 256KB interleaved banks and supports address pipelining. These techniques are used with 120-ns DRAM chips, which would provide only about half the performance required to allow the 16-MHz 80386 in the Access 386 to run without wait states.

Code that is register-intensive should allow the Access 386 to run at almost top speed, because most memory accesses will be instruction prefetches, which are 32-bit fetches to alternating banks, except when branching. As a result, although the 80386 performs memory accesses much faster than does the 8088, memory access is still a bottleneck, and astute register use remains a key to high-performance code. Most code does not access memory sequentially, however, because instruction prefetching and operand accesses are mixed together; there is no reason to expect a bank-alternating relationship between the two types of memory access.

Another consideration is the memory access characteristics of code written for 8088s and 80286s, which does not access memory in 32-bit units. As an example, REP STOSB runs more slowly on the Access 386 than does REP STOSD (which stores 32 bits at a time), because REP STOSB accesses the same bank four times in a row and then accesses the other bank four times in a row. It therefore is able to gain the advantages of interleaving only once out of four memory accesses.

When running normal software, the memory system in the Access 386 often inserts wait states because of failure to alternate banks; indeed, the performance tests examined later in this article indicate that two to three wait states are inserted on average. The insertion of wait states in the Access 386 does have one advantage. If idle bus cycles

dBASE Users:

DON'T CHANGE A THING! FoxBASE+ does it all.

Ask The Reviewers . . .

"FoxBASE+ Maintains Stunning Speed, Adds dBASE III PLUS Compatibility. . . FoxBASE+ zooms to the head of the dBASE-compatible class."
—Glenn Hart, PC Magazine, December 9, 1986.

"FoxBASE+ is the fastest and easiest-to-use dBASE product on the market."
—George Goley, Data Based Advisor, November, 1986.

"FoxBASE+ BLOWS dBASE III PLUS AWAY!! . . . ran every dBASE program I had with NO changes whatsoever!"
—James Gates, Atlanta Data Base Users Society Newsletter, November, 1986.

WHAT FoxBASE+ CAN DO FOR YOU

- YOU DON'T CHANGE YOUR PROGRAMS. FoxBASE+ runs **your** dBASE III PLUS applications more than 6 times faster *without changing one line.*
- Forget about conversion woes. You don't have to do a thing to your databases or other dBASE files to use FoxBASE+.
- You don't have to bend over backward to use FoxBase+ . It's used in *exactly* the same, familiar, user-friendly way you use dBASE III PLUS. As a dBASE user you already know how to use FoxBASE+.
- FoxBASE+ lets you keep using the best parts of dBASE III PLUS. It's a **fully interactive** compiler so you can still use great features like EDIT, BROWSE, etc.
- FoxBASE+ doesn't make you spend hours compiling and linking your programs like some "speed-up" products.
- FoxBASE+ runs your compiled programs twice as fast as Clipper and 3 times faster than Quicksilver.
- Best of all, Single-user MS-DOS FoxBASE+ costs just $395 and Multi-user FoxBASE+ $595 with a **money-back guarantee.** *Royalty-free runtime also available.*

If you like dBASE III PLUS, YOU'LL LOVE FoxBASE+ !!

So call (419) 874-0162 now for the details. After all . . .

Nothing Runs Like a Fox.

FoxBASE™

FoxBASE+ is a trademark of Fox Software. dBASE Iii PLUS is a trademark of Ashton-Tate. Clipper is a trademark of Nantucket. Quicksilver is a trademark of WordTech Systems inc. MS is a registered trademark of Microsoft Corporation.

Fox Software
27475 Holiday Lane, Perrysburg, OH 43551
(419) 874-0162 Telex 6503040827

CIRCLE NO. 180 ON READER SERVICE CARD

CLARIFY YOUR SOURCE CODE

C, BASIC, Pascal, dBase, Modula-2 programmers: Be more productive with two new utilities from Aldebaran Laboratories!

"Occasionally, a utility comes along that makes a programmer's life much easier. SOURCE PRINT is such a program. It contributes to the programmer's job by organizing code into a legible format and by helping to organize the documentation and debugging process."

— PC Magazine
Sept. 16, 1986

FOLD HERE WITH THIS SIDE OUT. TAPE CLOSED.

No Postage Necessary If Mailed in the United States

BUSINESS REPLY MAIL
FIRST CLASS MAIL PERMIT NO. 74 CONCORD, CA

POSTAGE WILL BE PAID BY ADDRESSEE

Aldebaran Laboratories Inc.
3339 Vincent Road
Pleasant Hill, California 94523

MAIL THIS CARD TODAY

Source Print organizes your source code, simplifies debugging, makes documentation a snap!
* Index (Cross-Reference list)
* Structure Outlining
* Automatic Indentation
* Table of Contents

$75

Tree Diagrammer shows your program's overall organization at a glance. It prints an "Organization Chart" showing the hierarchy of calls to functions, procedures, and subroutines.

$55

Both of these tools have easy-to-use menus, so you can put them to work for you immediately.

FOLD HERE WITH THIS SIDE INSIDE. TAPE CLOSED.

Aldebaran Laboratories 3339 Vincent Rd.,
Pleasant Hill, CA 94523 415-930-8966

Yes! Rush me ☐ Source Print @ $75. _____
☐ Tree Diagrammer @ $55. _____
☐ Both $115. Ship/Handling $5.
For CA—add 6% tax _____ Total _____
Name _____
Company _____
Address _____
City _____ State _____ Zip _____
☐ Check enclosed ☐ VISA
☐ MasterCard ☐ American Express
Card # _____ Exp. Date _____
Signature _____ Phone # _____

NO-RISK 60-DAY UNCONDITIONAL MONEY-BACK GUARANTEE.

800 257-5773
In CA 800 257-5774
Dept. 34

Clarify your source code

C, BASIC, Pascal, dBASE, Modula-2 programmers: be more productive with two new utilities from Aldebaran Laboratories

"Occasionally, a utility comes along that makes a programmer's life much easier. SOURCE PRINT is such a program. It contributes to the programmer's job by organizing code into a legible format and by helping to organize the documentation and debugging process."

— PC Magazine Sept. 16, 1986

Source Print and Tree Diagrammer both have easy-to-use menus with point-and-shoot file selection, and let you search for files containing a given string. For IBM PC and compatibles with 256K.

Join thousands of programmers who are working more efficiently using Source Print and Tree Diagrammer. Order these indispensable tools today. We ship immediately, and there's no risk with our 60-day money-back guarantee. **Order both and save. Only $115.00.**

800-257-5773 Dept. 34
In California:
800-257-5774 Dept. 34

MasterCard, VISA, American Express, COD. Add $5 for shipping.

Source Print and Tree Diagrammer are trademarks of Aldebaran Labs. dBASE is a trademark of Ashton Tate.

Source Print™

organizes your source code, simplifies debugging, and makes documentation a snap! It lists one or more source files with informative page headings and optional line numbers, while offering invaluable features:

The Index (Cross-Reference list) saves you time by showing exactly where variables are used and where functions, procedures, and routines are called.







$75.00

Locations where new values may be assigned to variables are shown, making it easy to track down that mysterious value change.

Structure Outlining solves the problem of hard-to-see nested control structures by automatically drawing lines around them.

Automatic Indentation of source code and listings reduces your editing time and ensures indentation accuracy.

Plus . . . Source Print generates a table of contents listing functions and procedures. Keywords can be printed in boldface on most printers. Multi-statement BASIC lines can be split for readability. Functions and procedures can be drawn by name from one or more source files to form a new file.



Tree Diagrammer™

shows your program's overall organization at a glance. Ordinary program listings merely display functions, procedures, and subroutines sequentially, but do not display the relationships between these routines. Our revolutionary new Tree Diagrammer automatically creates an "organization chart" of your program showing the hierarchy of calls to functions, procedures, and subroutines. Recursive calls are indicated and designated comments in the source code will appear on the chart.

Tree Diagrammer helps you organize your program more logically. And you'll be amazed at how easy it is to debug when you see how your routines interact.



$55.00

Aldebaran Laboratories 3339 Vincent Rd. Pleasant Hill, CA 94523 415-930-8966

YES! Rush me ☐ Source Print @ $75. _____ ☐ Tree Diagrammer @ $55. _____
☐ Both $115. Ship/Handling $5. For CA add 6% tax _____ Total _____
Name _____
Company _____
Address _____
City _____ State _____ Zip _____
☐ Check enclosed ☐ VISA ☐ MasterCard ☐ American Express
Card # _____ Exp. Date _____
Signature _____ Phone # _____ 34

CIRCLE NO. 106 ON READER SERVICE CARD

occur, address pipelining is turned off. The Access 386 is relatively memory-bound because of memory wait states, and as a result the memory bus is active almost all of the time. Idle cycles are rare, so the one-wait-state penalty that occurs when address pipelining is turned off is not invoked very often.

The memory system in the Access 386 is considerably faster than that of an AT, but slower than a no-wait-state architecture would be. Further evaluation for the performance-oriented user can be made by testing specific applications of interest on the Access 386.

The motherboard provides only 512KB of 32-bit memory rather than the expected 640KB. Additional interleaved, address-pipelined 32-bit memory can be added in the two 32-bit expansion slots. The address decoding logic for these slots is built into the motherboard, making them extensions of the motherboard memory system and not general-purpose 32-bit expansion slots.

Currently, 2MB of memory can be installed in each slot; 8MB boards will be available soon, bringing the maximum total to 15MB of 32-bit expansion memory. Memory cannot be added beyond address 0FFFFFFH: although the 80386 is capable of addressing up to 4GB of physical memory, the limit in the Access 80386 is slightly less than 16MB. The virtual memory features of the 80386, however, can be used to make the address space seem as large as the available disk space.

The 128KB area of memory from the 512KB boundary to the 640KB boundary is not supplied on the ALR's motherboard. This area of memory can be filled out with the 16-bit memory on the Challenger board with the associated reduction in performance, or the 32-bit memory board can be used with the Quarterdeck Expanded Memory Manager (QEMM) to backfill the memory using its EMS emulator feature. Quarterdeck Office Systems' DESQview contains QEMM and is supplied with the Access 386 setup/utilities diskette.

The Access 386 memory system is a fairly high-performance, low-cost solution to keeping up with the 80386 processor.

While 16-bit memory works in the Access 386, it works much more slowly than does 32-bit memory. Two accesses to 16-bit memory are required to fetch 32 bits, while only a single access is needed to fetch 32 bits from 32-bit memory. Existing DOS software is written for the 16-bit 8088 and 80286 processors. Code written specifically for the 80386 accesses memory in units of 32 bits. If this memory is 16-bits wide, two memory accesses are required to obtain a single 32-bit doubleword, causing the code to run up to two times slower than optimum.

Another reason for the slower performance of 16-bit memory is that 16- and 8-bit boards are run at 8 MHz in the Access 386. This lower speed is necessary because these boards are designed for 8-MHz ATs and will not operate properly at 16 MHz, but it also means that 16-bit memory runs at half the speed of 32-bit memory. Some expansion boards, such as the Intel Above Board and the Cheetah memory card, do not operate reliably above the AT's 8-MHz standard. See "PC's Limited 286[12]" (Steven Armbrust and Ted Forgeron, February 1987, p. 94) for a discussion of this limitation of a 12-MHz bus.

AT-style 16-bit memory is not interleaved and does not support address pipelining. The net effect of these factors is that accesses to 16-bit memory can take from 33 percent to more than 500 percent as long as the same access performed to 32-bit memory.

A similar slowing occurs while accessing ROM in the Access 386, such as the 16-bit ROM BIOS. An 8-bit ROM, like the EGA BIOS, will be even slower. In the worst case, a 32-bit read from 8-bit memory can take more than 10 times as long as a 32-bit read from 32-bit memory. Other 80386-based computers have addressed this by copying ROM chips into 32-bit RAM; the Access 386 does not do this. ROM performance is rarely crucial, because time-critical applications tend to bypass the ROM and go directly to the hardware. Also, because ROM operations generally are interleaved with the operation of a program running in RAM, the overall high performance of the Access 386 tends to mask the slow ROM operation.

In summary, the Access 386 memory system is a fairly high-performance, low-cost solution to building memory that can keep up with the 80386. This is balanced with the need to maintain an AT-compatible bus that will run all add-in boards reliably.

After memory performance, disk performance is perhaps the most im-

DISnDATa 2.0
The *Only* Disassembler
That Tracks Down DATA!!!

- Fully disassembles both .EXE *and* .COM files!
- Performs recursive flow- and Segment Register data-trace to determine SEGMENT, PROC & *Data* Areas (even within 'CODE' segments)!
- Outputs appropriate SEGMENT and PROC pseudo-ops at proper places within the assembly-language output!
- Outputs data areas using most appropriate form of DB or DW (ASCII printable text as a character string, others as their hex value).
- Chooses data lengths (DB or DW) to match byte or word data references in *code*, allowing most memory references to be free of BYTE or WORD length operators.
- Outputs large, all-zero areas with "DB/DW nn DUP (?)" to prevent excessive output from large buffers, uninitialized arrays, etc.
- Fully labels both code and data. Labels are of the form 'Hxxxxx', where 'xxxxx' is the hex offset of labelled item from the beginning of the program.
- Outputs code, data & pseudo-ops in IBM* and Microsoft** MASM assembler format. (Output may be directed to display, printer, and/or disk.)
- For IBM* PC*/XT*/AT* & compatibles, 128K + RAM, 1 or more disks, DOS 2.X+.

#8634-22 PC-DISnDATa 2.0 (SSDD 5-¼– diskette) and manual $165

U.S. Funds Only. Add $3 shipping (U.S. & Canada), $10 (overseas air) per item. Ohio residents please add 6% sales tax. *Registered trademark, IBM Corporation. **Registered trademark, Microsoft.

pro/am Software

To order, phone (513) 435-4480 (M-F, 9 A.M.-5 P.M. EST), or send check, money order, or VISA/MasterCard information (name, street address (no P.O. Box please), card number, expiration date, and your telephone number) to:

PRO/AM SOFTWARE
220 Cardigan Road
Centerville, OH 45459

Professional Software for both Novice and Expert
Dealer Inquiries Welcome.

CIRCLE NO. 252 ON READER SERVICE CARD

portant factor to consider when evaluating the speed of an 80386-based computer. The 42MB hard disk used in the Access models 386EM and 386EC has a 28-ms (millisecond) access time; this is considerably faster than the hard disk used in the IBM AT. However, it is comparable to the Compaq's 40MB disk access time of 25 ms.

The Access 386 offers a slowdown mode, also known as *deturbo mode*, in which the Access 386 runs at approximately the speed of an 8-MHz AT. Deturbo mode operates by inserting processor hold states, which are superior to wait states for slowing the processor because they do not affect the bandwidth of the system bus for DMA operations. This mode is useful for running copy-protected software or for slowing down programs that are too fast to use at normal Access 386 speeds. It is not slow enough to allow software designed for the PC, most notably games, to run at normal speed. Unfortunately, few users may learn the deturbo mode, since it is not referenced in the manual. Deturbo mode is selected via Ctrl-Alt-1, and normal mode is selected via Ctrl-Alt-2. The system always is set back to normal speed by a warm boot.

A LOOK INSIDE

No user installation is required for the Access 386 as it is shipped from the factory. However, the user who wants to install options and accessories in the system unit will find the process the same as that used with the AT because the physical layouts are similar. Five Phillips-head screws on the back panel hold the cover on the system unit. Although other Phillips-head screws are nearby, the screws that hold the cover can be easily identified. Once the screws are removed, the cover can be slid off the system unit over the front panel, as with the AT.

The inside of the system unit is shown in photo 4, and the motherboard itself in photo 5. The eight expansion slots on the motherboard are located as they would be in an AT, and expansion boards are installed and anchored in the familiar AT fashion. Some effort was required to install boards, as the back panel of the system unit did not align perfectly with the ends of the expansion boards. The two 32-bit expansion sockets are keyed so that 16-bit boards cannot be installed into these slots, although 8-bit boards can be used.

Removal and installation of the motherboard is not particularly difficult. After removing all of the expansion boards and disconnecting the power leads and several other wires, then the motherboard is extracted by removing two screws, sliding the whole board to the left, and lifting up. The disk drives do not have to be removed.

Disk drives slide into the two drive bays from the front and are anchored at either side. The left bay can contain one full-height or two half-height hard disks. The small panel that contains the key lock and the power indicator light must be removed in order to get a drive into or out of the top slot in the drive bay. The right drive bay has slots for three half-height drives, but there is only room for two diskette drives and a shorter drive, such as a tape backup unit. All of the drives installed in the right drive bay can be accessed from outside the system unit when the system is closed up. In the tested system, the half-height 42MB hard disk occupied the left bay, while the 1.2MB diskette drive occupied the topmost of the three slots in the right bay.

The disk controller supports up to two hard disks and two diskette drives. A second diskette drive can be daisy-chained to the same connector as is the first diskette drive. A second hard disk can daisy-chain to one of the hard disk connectors, but it requires one additional cable not supplied with the Access 386. The standard hard disk that is shipped with Access models 386EM and 386EC is a 42MB, 28-ms access time unit; an 80MB, 28-ms hard disk is available as an option.

Two of the three ribbon cables from the controller to the drives in the reviewed unit were not keyed to ensure installation with pin 1 of the connector attached to pin 1 of the cable. All three cables did have markings indicating the side to be connected to pin 1, but novice users may not know what those markings mean.

Only 32MB out of the 42MB disk space in the tested system was usable, because a special driver is required in order to get DOS to support disks larger than 32MB, and ALR does not ship such a driver with the Access 386. In "Breaking the 32MB Barrier," (May 1986, p. 94) Thomas V. Hoffmann reviewed a method used to configure a large hard disk into a large single volume or two separate volumes. ALR is apparently relying on dealers to configure the Access 386 with third-party software. If necessary, however, ALR will recommend an appropriate driver to owners of the Access 386 who can then purchase and install it.

Third-party hard disks are supported by the ROM BIOS of the Access

Storage Dimension's
SpeedStor 286 BIOS
from Award Software

for use with PC ATs and
XENIX System V
Novell Advanced Netware



- Overcome drive table limitations
- Includes low-level initialization and disk drive advanced diagnostics
- 30% faster than IBM's BIOS
- $129– Retail. Dealer and distributor pricing available

Supports **Seagate ST4096, Miniscribe 6085** and the following:

Seagate	ST251, ST4051, ST4096
Maxtor	XT1085, XT1105, XT1140, XT2085, XT2140, XT2190
Miniscribe	6074, 6085
Micropolis	1325
Control Data	Wren II 94155-86
Microscience	HH1050
Newbury	NDR1085, NDR1140, NDR2190,
Priam Vertex	V150, V170, V185, 519
Toshiba	MK54F, MK56F

STORAGE DIMENSIONS
The Experts in High Capacity PC Storage

408-395-2688
981 University Ave.
Los Gatos, CA 95030

Storage Dimension's family of high performance products for PC storage.

- SpeedStor subsystems from 42MB to 640MB
- SpeedStor hard disk integration software
- 60MB tape backup (DOS, Xenix, Novell)
- SpeedCache caching software
- Extended drive table ROMs
- SpeedStor 286 BIOS

CIRCLE NO. 176 ON READER SERVICE CARD

TABLE 1: *Disk Drives Supported*

DRIVE TYPE	NO. OF CYLINDERS	NO. OF HEADS	CAPACITY (MB)	LANDING ZONE CYLINDER	PRECOMPENSATION CYLINDER
1	306	4	10.1	305	128
2	615	4	20.4	615	300
3	615	6	30.6	615	300
4	940	8	62.4	940	512
5	940	6	46.8	940	512
6	615	4	20.4	615	−1[a]
7	462	8	30.6	511	256
8	733	5	30.4	733	−1
9	900	15	112.0	901	−1
10	820	3	20.4	820	−1
11	855	5	35.4	855	−1
12	855	7	49.6	855	−1
13	306	8	20.3	319	128
14	733	7	42.5	733	−1
16	612	4	20.3	663	0
17	977	5	40.5	977	300
18	977	7	56.7	977	−1
19	1,024	7	59.5	1,023	512
20	733	5	30.4	732	300
21	733	7	42.5	732	300
22	733	5	30.4	733	300
23	306	4	10.1	336	0
25	615	4	20.4	615	0
26	1,024	4	34.0	1,023	−1
27	1,024	5	42.5	1,023	−1
28	1,024	8	68.0	1,023	−1
29	512	8	34.0	512	256
35	1,024	9	76.5	1,024	1,024
36	1,024	5	42.5	1,024	512
37	830	10	68.8	830	−1
38	823	10	68.3	824	256
39	615	4	20.4	664	128
40	615	8	40.8	664	128
41	917	15	114.1	918	−1
42	1,023	15	127.3	1,024	−1
43	823	10	68.3	823	512
44	820	6	40.8	820	−1
45	1,024	8	68.0	1,024	−1
46	925	9	69.1	925	−1
47	699	7	40.6	700	256

[a]The −1 values mean that no write precompensation is used for the drive.

The Access 386 supports 41 hard-disk types. This allows ample flexibility in selecting an alternative hard disk. Several of the AT disk types do not appear in this list.

386. The SETUP program lists 41 disk types that are supported (see table 1). The disk types supported by the AT are not supported by the Access 386 with the same type numbers; in fact, several of the AT disk types do not appear in the Access 386 SETUP program's list of disk types at all.

The power supply includes three cables for powering peripherals. Two of the cables have two connectors and the other has one, indicating that a total of five peripheral devices can be connected, although their combined power demands must be within the power supply's capacity of 200 watts.

While the 80386, ROM BIOS, and 80387 sockets are all fully visible from above, they are in a hard-to-reach area between the left drive bay, the disk controller board, and the power supply. Realistically, at the least the disk controller board has to be removed in order to work easily with any of these chips.

The 16-MHz Intel 80386 is a large square chip mounted in a socket at the center-right of the motherboard, just to the back of the left drive bay (see photo 5). The ROM BIOS chips are socketed to the right of the 80386, and similarly are not obscured by any equipment.

The 80387 socket is to the right of the ROM BIOS between the left drive bay and the power supply; while the socket itself is not obscured, it is difficult to reach without removing the motherboard. The reviewed system came with a socketed 10-MHz Intel 80287 numeric coprocessor option, a small adapter board that plugs into the 80387 socket. The 80287 option card extends well under the drive bay, and the motherboard had to be taken out in order to remove the 80287 card. It will be possible to use a 16-MHz 80387 in this socket as soon as that chip becomes available.

To this point, the configuration for the Access 386 has been very similar to that for the AT, except for the two 32-bit slots. Unlike the AT, the motherboard on the Access 386 is lacking switch blocks; this makes configuration more difficult. More than a dozen jumpers are used to set the serial and parallel port operation, indicate whether a numeric coprocessor is installed, select a color or monochrome primary display, indicate whether and how many 32-bit memory expansion boards are installed, and perform a number of more esoteric functions.

Unfortunately, these jumpers are scattered around the motherboard, many of them are in hard-to-reach locations, and often more than one is required to configure a single feature of the Access 386. For example, the three jumpers that indicate what 32-bit memory boards are installed are located between the disk controller and the left drive bay and are not accessible (or even visible) unless the disk controller is removed. A pair of needlenose pliers is required to change the jumpers, and the proximity of several jumper pins makes the task difficult. The jumpers could pose a problem to users accustomed to switch blocks that can be toggled with a ballpoint pen.

The Access 386 offers eight expansion slots: two 8-bit slots, four 16-bit

Here's how $25 can ease you into the world of expert system development.

Texas Instruments would like you to prove for yourself the simplicity and capabilities of our Personal Consultant™ Series of expert system development tools.

The Personal Consultant Series—get started and keep going.

This Demonstration Package will introduce you to the Personal Consultant family of compatible expert system development tools. As the lowest priced member of the family, Personal Consultant *Easy* is designed to get you started immediately in learning about and creating medium-scale expert systems for use on standard personal computers. The more advanced Personal Consultant *Plus* lets you expand your expert system with the additional features and capabilities needed to create larger, more complex applications for AT-class personal computers.

The Personal Consultant Series—proven performance, practicality, and support.

Personal Consultant products have been helping thousands of people just like you build practical applications of expert systems on TI, IBM,® and compatible personal computers since 1984. And, to support you, we provide the proven performance of these development tools, low-cost application delivery, hotline support, a range of training programs, and knowledge engineering services to help your company get started or expand existing programs.

See for yourself. You can experience a hands-on demonstration for only $25.

Our easy-to-use Personal Consultant demo will let you:

- Interact with an actual expert system application.
- Modify this application by adding additional knowledge.
- Develop and save your own 10-rule system to show your colleagues.

(Requires 512K memory.)

Get started today! To order your Demonstration Package, or for more information, call toll-free:

1-800-531-6789

VISA and MasterCard are accepted.

TEXAS INSTRUMENTS

Personal Consultant is a trademark of Texas Instruments Incorporated.
IBM is a registered trademark of International Business Machines Corporation.
© 1987 TI

261765-04D

slots, and two 32-bit slots. The 32-bit slots are the second and third slots from the right in photo 4. The rightmost slot is a 16-bit slot that is used for the disk controller; this positioning means that the disk cables do not have to traverse other expansion boards. Each 32-bit slot consists of two connectors. One of these connectors is a standard 8-bit connector, into which 8-bit boards can be plugged. The second connector is keyed in the middle; this keying means that 16-bit boards cannot be plugged into 32-bit slots. However, 8-bit boards can be plugged into any of the eight expansion slots, so long as the skirt on the board does not hit the extended 16- or 32-bit connector; as in the AT, the two 8-bit slots are the only slots in which 8-bit boards with such skirts can be installed.

As discussed above, 32-bit memory is essential to high performance when running software that takes full advantage of the 80386. The 32-bit slots are actually extensions of the motherboard memory system and can be used only for memory boards. Currently, the only available expansion boards that can take advantage of the 32-bit slots in the Access 386 motherboard are 2MB boards manufactured by Intel (see photo 6). Two of these boards can be installed at one time, for a total of 4MB of 32-bit expansion memory. Neither of the 32-bit slots is occupied normally because the Access 386 is delivered with 16-bit expansion memory only. Optional 32-bit memory boards are, however, available from ALR.

Of the remaining five slots, one 8-bit slot is occupied by the video adapter and one 16-bit slot by a multifunction memory board. (The base model, the Access 386B, does not come with any expansion board other than the disk controller.) In the Access 386EM, the video adapter is a Hercules-compatible monographics board and the multifunction board is ALR's Challenger board, with a serial port, a parallel port, and 512KB of 16-bit memory installed, expandable to 2MB. The reviewed system, the Access 386EC, comes with an IBM EGA-compatible video adapter and a Challenger board with a full 2MB of 16-bit memory installed.

The motherboard contains 512KB of memory, consisting of two interleaved 256KB banks of eight 64KB-by-4, 120-ns DRAM chips each. Eight 64KB-by-1, 120-ns DRAM chips are used for parity bits. No memory expansion is possible on the motherboard. The Challenger board is split addressed to top off DOS with 16-bit memory and to add extended memory starting at 1MB. This prevents the use of 32-bit memory expansion boards, which must start at 1MB and would conflict with the Challenger memory. ALR has solved this problem by making available a new memory decode PROM for the Challenger board that allows it to top off DOS, and then address the remaining 16-bit memory above the 32-bit memory.

The motherboard in the Access 386 is the iSBC 386AT, designed and manufactured by Intel. The reviewed model came with version 3.03 of the Phoenix ROM BIOS. This version of the motherboard corrects several of the problems that were encountered by motherboards with version 3.0 and earlier of the BIOS. One of these problems was the failure to support the EGA's vertical interrupt properly, and another was an inability to get the 80287 to pass IBM AT Advanced Diagnostics. The motherboard had a number of soldered wires running across it; these are probably recent fixes, indicating that the last bugs have only recently been ironed out of the motherboard.

A Contradiction!

Running Under PC DOS

>750 million bytes formatted in two volumes for the "Eagle" (one volume/drive)...M2361A can hold 552MB/volume...data transfer rate up to 2.4MB/sec....data access time - 18ms/drive...variable interleave capability...partitioning possible...drives built to mainframe specifications with mainframe reliability...greater than 20,000 hours MTBF.

For further information contact:

Upper Bound Micro

18 Elizabeth Street, W. Conshohocken, PA 19428
(215) 825-0505 FAX (215) 828-8618

The "Eagle" is a trademark of Fujitsu America, Inc.
PC DOS is a trademark of IBM.

CIRCLE NO. 169 ON READER SERVICE CARD

Announcing Magic PC – the first breakthrough for database applications developers in over 20 years:

Now you can develop professional applications 1000% faster than your 4GL or DBMS, totally free from programming, commands and syntax!



A Magic PC program looks as simple as this. To design an application you quickly fill-in menu-driven decision tables **without having to write a single line of code.** For example, just by highlighting the Execute Program operation on this screen and also highlighting the Item List program in the Program Menu, you tell Magic PC to pop-up the Item List window shown in the adjacent screen, when the end-user hits the Zoom key.



Magic PC gives your end-user the power to harness and retrieve data instantly, **without any commands or syntax** because at runtime you already have built-in options to Add, Delete, Modify, Query and get on-the-spot ad-hoc information simply by highlighting selections from menus. Dats validation, security and error-checking are done automatically for you by Magic PC without programming.

Who needs another DBMS?

At last, Magic PC gives you the ultimate applications design tool, far ahead of 4GL's, DBMS and Application Generators.

Magic PC breaks through the language barrier with the revolutionary Un-Language concept:

NO PROGRAMMING, COMMANDS OR SYNTAX!

Free yourself from your programming language

Magic PC makes you, the professional, completely free from the drudgery of procedural programming. No more cryptic commands, syntax or unforgiving procedural structures, because Magic PC does all the programming automatically. There's your competitive edge. The rest is up to you . . .

The Professional Choice

Already an international success, Magic PC is a profit maker and career booster for DP Consultants, System Integrators, VARs, MIS professionals, System Analysts, Programmer Analysts and Software Engineers. If you design PC applications professionally, you can't afford not to Un-Language now.

IBM France: "IBM encourages this introduction and can not help but salute such evolution . . ."

Israeli Air Force: "We were convinced that it was not possible to have a design tool powerful enough to implement real-life applications without a programming language. Magic PC changed our mind . . ."

Jeff Duntemann, PC Tech Journal: "It's probably the best integrated database applications and screen generator that I have ever seen . . .very smooth system, and smoothness comes at a premium these days . . ."

The Magic PC Secret

You're so much more productive with Magic PC because there is **absolutely no programming** to slow you down. You design a Magic PC application by simply filling-in the **Data Dictionary Tables** (Files, Fields, Keys) and the **Task Description Tables** (Operations and Expressions).

Only 13 design **Operations** harness the power of Magic PC. Operations are specific enough to eliminate the need for tiresome syntax, yet elastic enough to produce robust custom applications. Use the Operations to describe **what** you want and Magic PC makes it happen. It's that simple.

Make Task nesting power available with a single **Execute Task** Operation. This powerful instruction triggers Magic PC to execute and display additional tasks or even external applications through **Window Zooms.** The 3-dimensional effect of Window Zooming lets you probe deep into your application through nested windows and manipulate the data underneath.

You describe a Magic PC Task or Program (composite Tasks) by filling your system analysis flow into the Task Description Tables. Choose the participating Data View, and Magic PC executes your desired Operations. You interface with the Tables by highlighting your selections from pop-up menu-driven windows. There's nothing to edit except your headings.

You're not confined to any particular design sequence as you are with most procedural languages. You can enter and change any Table spontaneously, on the fly, as ideas come to mind and Magic PC automatically maintains the application integrity.

A **Magic Inference Engine** automatically orchestrates your Task Description Tables into a single file of internal **Knowledge Base Rules** for optimum, bug-free performance. Knowledge Base Rules are executed by the **Magic Run** engine for stand-alone runtime operation, or by the **Magic Lan** engine for unrestricted Novell network sharing. You're free to design the Knowledge Base without worrying about the internal structure.

Discover fast, language-free programming at no risk for only $19.95



See for yourself how fast you can program language-free applications with our low-cost limited offer.

You'll get the full Magic PC software unprotected and limited to 100 records and 450 page documentation complete with a **free** Order Entry sample application. You'll also get our **free** telephone support for 90 days!

And your $19.95 will be credited towards the full $695 Magic PC purchase price. Even if you don't buy Magic PC right away, keep your $19.95 Magic PC Trial as your application prototyping tool at this bargain price.

Our No-Risk Guarantee!

You have our no-risk 30-day money-back guarantee: if you're not completely satisfied for any reason, even Magic PC Trial for $19.95, send it back for a refund.

Order now while supply lasts

Call this toll free number now with your Visa, MasterCard or American Express for immediate delivery, or send the Order Coupon below today to Aker.

1-800-345-MAGIC
in CA call 714-250-1718

VISA MasterCard AMERICAN EXPRESS

Yes, please rush me:

☐ Magic PC Trial	$ 19.95
☐ Magic PC	$695.00
Add shipping	$ 5.00
In CA 6% tax	$_____
Prices valid in US only.	Total $_____

Ship to:_____

Address:_____

City/ST/Zip:_____

Phone:_____

AKER

Aker Corp. 18007 Skypark Circle B2, Irvine, CA 92714
(714) 250-1718, Elec. Mail Dialcom 41:AKR 001 Telex 4931184
AKR UI OEM and VAR inquiries are welcome.

Min. requirements PC DOS 2.0, IBM PC or 100% compatible with 512K and hard disk.

©1986 Aker Corp. Printed 1/87 **Trademarks:** Magic PC, Un-Language, Window Zoom, Magic Run, Magic LAN and Magic PC Trial are trademarks of Aker Corp., IBM PC and PC-DOS are trademarks of IBM Corp., Novell is a trademark of Novell Inc.

CIRCLE NO. 153 ON READER SERVICE CARD

When comparing 386-based computers, it is wise to check the motherboard. Other computers built around the iSBC 386AT are likely to share many of the characteristics of the Access 386, in which case other considerations such as hard disks, bundled software, and price will take on added importance.

According to the label on the rear panel of the system unit, the Access 386 system unit complies with the FCC regulations for a Class A (commercial) computing device.

STANDARD SOFTWARE

ALR provides a setup/utility diskette and the DESQview multitasking windowing package as standard software with the Access 386. Neither DOS nor BASIC comes with the computer; a separately purchased copy of PC-DOS 3.2 was used for this review. No diagnostics other than those performed at power-up are provided, although IBM's Advanced Diagnostics runs on the Access 386 and can be used if necessary.

The setup/utility diskette contains Phoenix's SETUP program, used to set the contents of the battery-backed CMOS RAM that stores the computer's configuration. Configuration information is stored in battery-backed CMOS RAM present on an MC146818 realtime clock chip, just as in the AT. This program is similar to the SETUP program on IBM's AT Advanced Diagnostics disk, with the useful addition of a table of the characteristics of 41 hard-disk types supported by the Access 386. Neither the documentation nor the hard-disk housing indicates which of the 41 drive types was installed in the test computer. ALR is relying on the factory and dealers to configure computers, rather than the user. It would be a good idea for Access 386 owners to run the SETUP program to check which type of hard disk is installed, just in case they lose the contents of the CMOS RAM and have to set up the system themselves.

The SETUP program itself works well; however, it is not documented in the manual, and only a single entry in the main README file on the setup/utility diskette tells how to use it or what to use it for. Each of the other programs on the setup/utilities diskette has at least a short README file; this is better than nothing, but is no substitute for good coverage in the manual. In addition, the README files are incomplete and full of typographical errors.

ALR provides a SPEED utility for selecting between normal and deturbo operation, as an alternative to Ctrl-Alt-2 and Ctrl-Alt-1. When run, the program prompts the user for the new speed. This utility would be more useful if it accepted a command line parameter for the speed selection, allowing it to be used in batch files without requiring the user to type a response. The file README for the SPEED utility, which is the only documentation for the program, indicates that SPEED is only for the ALR Dart 012 computer, but the utility was delivered with and appeared to work on the Access 386.

Other utilities include a hard disk formatting program, a monochrome display adapter mode control program, and a driver to support 3½-inch diskette drives. The final program on the setup/utilities diskette is QEMM, a device driver from Quarterdeck that provides expanded memory management. It has an installation program that installs it into the CONFIG.SYS file. QEMM makes the extended memory in the Access 386 (memory above 1MB, which is not used by DOS) appear to be expanded memory of the Lotus/Intel/Microsoft (LIM) specification to DOS programs that can take advantage of LIM expanded memory, such as Lotus 1-2-3, Living Videotext's Ready!, and Intel's QUIKMEM2 RAM disk.

The virtual-8086 mode of the 386 makes it possible to make extended memory work like expanded memory. QEMM operates by modifying the page tables of the 386 to map the desired areas of extended memory into the page frame through which expanded memory is accessed. It puts the 386 into virtual-8086 mode because such mapping is not possible in real mode (the power-up state of the 386, in which the 386 acts as a fast 8086). Normally, virtual-8086 mode is used to run multiple copies of DOS simultaneously, with each copy thinking it has an 8086 computer all to itself. In the case of QEMM, however, virtual-8086 mode is used to run just one copy of DOS, just as in real mode, the difference is that extended memory is mapped into the expanded memory page frame.

The manner in which QEMM works is transparent to DOS and applications that used expanded memory. Virtual-8086 mode does have one slight drawback, however; all interrupts in virtual-8086 mode cause a trap to QEMM, slowing performance slightly. The actual performance loss will vary from one application to another.

One benefit of QEMM is that it allows programs that use expanded memory to run without requiring a separate expanded memory board. Few programs can use the extended memory

COBOL'S DOUBLE STANDARD.



There's ANSI 74 Cobol. And there's ANSI 85 Cobol.

But why not have it all? RM/COBOL-85 is really GSA-certified error-free for *both* Cobol standards in one compiler.

If you need high-level 74 features like Sort-Merge or Interprogram Communications, RM/COBOL-85's got it for you. The big difference: our newest version compiles your applications two times faster and runs them up to eight times quicker compared to our earlier RM/COBOL. Plus, your files can store up to five times more data.

Best of all, RM/COBOL-85 is upward compatible with all your existing RM/COBOL applications. They can be recompiled without any modifications to give you all the high-performance advantages.

Then in the same application, at the touch of a switch, you can add features from the new 1985 ANSI standard and combine all this performance with the convenience and maintenance advantages of structured programming.

Because you can mix and match 74 and 85 features the way *you* want, you can move your applications to the 85 standard when it's convenient for *you*.

Either way, RM/COBOL-85 delivers all this flexibility whether you're in a DOS or UNIX environment.

And, it gives you built-in compatibility with the most popular pc networks—including IBM's PC Network, IBM's Token-Ring, Novell's Advanced NetWare, 3Com's 3Plus, and more.

Want to know about the hundreds of applications and tools that are currently available? Just fill out the coupon below. Or contact your Ryan-McFarland representative.

Ryan-McFarland
609 Deep Valley Drive
Rolling Hills Estates, CA 90274
Or call 213/541-4828

RYAN-McFARLAND

PCT-4

Okay. Okay. Tell me more! Send me, free:

☐ RM/COBOL applications directory
☐ "Does COBOL Have a Future" booklet describing advantages of COBOL-85

Name _____

Company _____ Title _____

Street _____

City _____ State _____ Zip _____

Phone ( ) _____

CIRCLE NO. 137 ON READER SERVICE CARD

above 1MB directly; many more can use expanded memory. QEMM makes a great deal of expanded memory available at no cost because the reviewed configuration of the Access 386 comes with nearly 2MB of extended memory.

The second benefit of QEMM is its synergy with DESQview, which was written originally for the 8086. While DESQview works well on 8086s, programs running on the 8086 cannot be protected from each other or allowed true multitasking in which each program has a full 640KB and a separate screen available. The virtual-8086 mode of the 386 makes all of the above possible, and when DESQview is run with QEMM loaded, virtual-8086 multitasking is supported. Installed memory permitting, as many as nine virtual PCs can be run simultaneously. DESQview worked well in the *PC Tech Journal* tests, although it was hard to be certain exactly how DESQview was taking advantage of the 80386 because the copy of DESQview that accompanied the Access 386 included no documentation whatsoever pertaining to operation with QEMM.

HOW TO BECOME A POWER PROGRAMMER

Introducing Two New Powerful Packages, BlackStar Basic Development Tools and "C" Function Library



BASIC DEVELOPMENT TOOLS features four-in-one "automatic programming" tools. Including SCREEN BUILDER, B+TREE, HELP MESSAGE SYSTEM and EZ SCREEN POP-UP WINDOWS. Can be used separately or together. Compatible with Microsoft QuickBASIC and Borland Turbo Basic. Comes with 220 page manual and two diskettes.

"C" FUNCTION LIBRARY New ANSI Standard with over 275 functions. A comprehensive development package for the latest "C" Compilers including Microsoft and Lattice. Complete source code and demo program, as well as small, medium and large memory models are included. Plus 317 page instruction manual and three diskettes.

Special Offer! $99.00 each, both for $175.00
For IBM PC and compatibles. M/C, VISA, add $3.00 for shipping and handling. California residents add 6.5%. Shipping outside U.S. and Canada add $15.00.

60 Day Money Back Guarantee.

ORDER TODAY! (800) 722-7853
(213) 306-3020 in California
24-Hour Rush Shipment (credit card orders only).

Sterling Castle, 702 Washington Street, Suite 174
Marina del Rey, CA 90292.

STERLING CASTLE™
SOFTWARE

Distributed by Kenfil Software. **All trademarks acknowledged.**

CIRCLE NO. 198 ON READER SERVICE CARD

PERFORMANCE TESTING

As is standard in the *PC Tech Journal* Compatibility and Performance series, the Access 386 underwent two types of tests. First, commonly used hardware and software products were installed to test the AT compatibility of the Access 386. Next, the *PC Tech Journal* AT Evaluation Suite of compatibility and performance tests was run. (See "Updating the Evaluation Suite," Ted Forgeron, Paul Pierce, and Steven Armbrust, March 1987, p. 70.) The results were compared to the 8-MHz IBM AT and the Compaq Deskpro 386. All testing was performed on an Access 386EC, with an enhanced keyboard and a 10-MHz 80287 numeric coprocessor option.

The hardware products were a 10-MHz 80287 numeric coprocessor chip, an Intel Above Board with 4MB of memory, Microsoft serial and bus mice, a Cheetah zero-wait-state 1.5MB memory board, an IBM Game Adapter, and a Hayes Smartmodem 1200B internal modem. The EGA was also tested, but the tests were run using ALR's EGA, not the IBM board.

Two hardware products failed to run properly on the Access 386: Cheetah zero-wait-state memory and the Microsoft bus mouse. The Access 386 would not even boot when a Cheetah board configured for zero-wait-state operation was installed. When the Cheetah board was configured for one-wait-state operation, however, both the board and the Access 386 functioned normally.

The Microsoft bus mouse did not work when used with Microsoft Windows. The mode of failure was erratic; often Windows would fail to start up, and even when it did, the display was generally garbled and the mouse was always nonfunctional. This was true with the interrupt select jumper on the bus mouse board set in all four possible positions. The bus mouse did work with Microsoft Word and with other software, and Microsoft Windows worked well with the Microsoft serial mouse. The problem seems to be a specific interaction among Windows, the bus mouse, and the Access 386.

While the IBM Game Adapter functioned properly in the Access 386, software that relied on timing loops to read the position of the joystick attached to the Game Adapter did not work well. Even software that automatically calibrated the joystick before using it sometimes concluded that the joystick was broken because the Access 386 ran so rapidly that the joystick counts seemed to be out of any reasonable range. Software that uses the system timer to pro-



UNIX* Tools for Your PC

PC/VI™

PC/VI™ is a complete implementation of the most powerful and most widely used full screen editor available under the UNIX operating system. Fully compatible with all MS-DOS† and PC-DOS systems, **PC/VI** provides both power and flexibility for programming and text editing through features such as:

- Full Undo capability.
- Global search or search and replace using regular expressions.
- Cursor motion, deletions and changes on a character, word, line, sentence, paragraph or global basis.
- Shell escapes to DOS.
- Macros and Word abbreviations.
- Auto-indent and Showmatch.
- MUCH MUCH MORE!

PC/VI is available for IBM-PC's and generic MS-DOS systems for only $149. Included are CTAGS and SPLIT utilities and an IBM-PC specific version which enhances screen performance by as much as TEN FOLD!

PC/TOOLS™

PC/TOOLS are Sleek, Fast and POWERFUL utilities—the same ones that make UNIX so versatile! Now the most powerful and popular of the UNIX utilities are available for your PC! Each is a complete implementation of the UNIX program. Open up our toolbox and find:

BANNER	GREP	SEE
BFS	HEAD	SORT
CAL	MAKE	SPLIT
CHMOD	OD	STRINGS
CUT	PASTE	TAIL
DIFF	PR	TOUCH
DIFFH	RM	TR
DIFF3	SED	WC

All of these for only $49.00; naturally, extensive documentation is included!

PC/SPELL™

Get a SMART spelling checker! **PC/SPELL** is a complete implementation of the UNIX spelling checker, renowned for its understanding of the rules of English. **PC/SPELL** determines if a word is correctly spelled not only by checking its database, but also by testing transformations such as pluralization and the addition and deletion of prefixes and suffixes. **PC/SPELL** is the first and last spelling checker you will ever need!

PC/SPELL has a vocabulary of over 34 MILLION words! Starting with a database of over 24,000 word stems, **PC/SPELL** uses dozens of prefix and suffix rules to build its extensive vocabulary. This database can be customized by the user for additional flexibility.

PC/TOP™

A powerful text output processor which accepts *dot* commands in a manner similar to UNIX's nroff and troff to control the format of the document. Although **PC/TOP** is small (<35KB .EXE file) and FAST (typically 3 pages/second on a PC/AT) **PC/TOP** is also POWERFUL! Capabilities include: right-margin justification, macros, centering, underlining, chapters, appendices, sections, revision bars, table of contents, and much, much more! All for only $49 including extensive documentation!

Users' Endorsements

Our customers speak for our products:

- *"This is Great! Now we have a decent programming editor. I wish we had found this earlier."*
- *"Excellent Product—Performs extremely well, very satisfied."*
- *"The manual is extremely well written and has taught me things I never knew about VI."*
- *"Your Support so far has been very helpful and friendly and greatly appreciated."*
- *"Very impressive. Good documentation."*

CSS CUSTOM SOFTWARE SYSTEMS

P.O. BOX 678 • NATICK, MA 01760 • 617-653-2555

Don't miss out on the powerful utilities that the UNIX community has enjoyed for so long. Call or write for additional information about our products, package prices and multi-site licenses. Available in all MS-DOS disk formats. AMEX, MC, VISA accepted without surcharge; MA residents add 5% sales tax. NOT copy protected.

**UNIX is a trademark of AT&T. † MS-DOS is a trademark of Microsoft.*

CIRCLE NO. 261 ON READER SERVICE CARD

Turbo Programmers:



Find the culprit fast with T-DebugPLUS.™

You're programming, getting all your ducks in a row, but there's a culprit in there, a bug. T-DebugPLUS, the new symbolic run-time debugger, helps you find that bug and fix it faster than ever before.

In Command. In Control.

See what happens *as* your Turbo Pascal programs run...examine variables...change values...be in control. The top half of your screen displays the source code, current line highlighted. You debug interactively on the lower half. All variable types are accessible, local and global. Set breakpoints at a procedure, function, or statement number.

Instant Gratification.

T-DebugPLUS integrates invisibly, automatically loading Turbo Pascal. Switch instantly between the debug and output screen. Jump instantly to the editor to fix that bug.

New...Debug in Overlays.

Debug in overlays with release 1.04. Examine areas of memory and CPU registers. A MAP generation utility even lets you use an external debugger on your program. T-DebugPLUS is only $60.

"T-DebugPLUS: Don't program in Turbo Pascal without it."

Neil Rubenking
PC Magazine

More Power. More Productivity.

Turbo EXTENDER™ helps you break the 64K barrier for both code and data; use all 640K. A source code converison program, make facility, and run-time routines make writing and compiling large programs dramatically easier. Turbo EXTENDER is only $85.

TurboPower Utilities™ supplies nine powerful programs. Four Pascal utilities, including the acclaimed Pascal Structure Analyzer and Execution Timer, help you write programs that are bug free, faster, and easier to document. Five PC-DOS utilities help you analyze, change, and find your program files. TurboPower Utilities is only $55 for executable, $95 with source.

"Impressive products...I recommend them."

Philippe Kahn, President
Borland International

Satisfaction guaranteed or your money back within 30 days.

Call toll free for credit card orders:

800-538-8157 x830
outside California or
800-672-3470 x830
in California



Shipping and taxes prepaid for U.S. and Canadian customers. Others please include $6 per item for shipping.

TurboPower Software products require Turbo Pascal 3.0 (standard, 8087, or BCD) and require PC-DOS 2.X or 3.X, and run on the IBM PC/XT/AT and compatibles.

TURBO Power

TurboPower Software, 3109 Scotts Valley Dr. #122
Scotts Valley, CA 95066
Call 408-438-8608 for more information (M-F 9AM-5PM PST).

CIRCLE NO. 219 ON READER SERVICE CARD

vide a constant time base when performing joystick readings should work properly in the Access 386.

Microsoft Windows 1.01 and Microsoft Word 3.1 were run to test graphics capabilities and the mouse. Microsoft Word 2.0 was run to test the ability of the Access 386 to run copy-protected software. Borland's SuperKey 1.03A, SideKick 1.56A, and Turbo Lightning 1.00A tested memory-resident programs. Living Videotext's Ready! 1.00d and Intel's QUIKMEM2 RAM disk were used to test expanded memory— both Above Board expanded memory and QEMM's emulated expanded memory. IBM's VDISK 3.2 was used to test the ability to switch into and out of protected mode. FastBack, from Fifth Generation Systems, tested DMA, and Hayes' Smartcom II tested the Smartmodem 1200B. IBM's AT Advanced Diagnostics 2.0 software, which includes IBM's SETUP program, gave a check of AT compatibility.

The only major incompatibility encountered while using the tested software was between Microsoft Windows and the Microsoft bus mouse. Another compatibility problem was encountered with Windows, but it is neither major nor unique to the Access 386. Microsoft's RAMDrive program, which creates an extended-memory RAM disk, failed to load. RAMDrive uses an undocumented 80286 instruction that is not supported by the 80386. The failure of RAMDrive to run is not a serious problem because IBM's VDISK, which comes with DOS and performs the same function, works perfectly on the Access 386.

Ready! displayed an odd incompatibility when used with the Intel Above Board and Intel's EMM (expanded memory manager). When Ready! was memory-resident with this hardware configuration, EMM would report an error and fail to reinitialize on a warm boot. On the next warm boot, however, EMM would initialize properly. When Ready! was used with Quarterdeck's QEMM expanded memory manager, warm boots did not present a problem.

Following the standard hardware and software tests, five programs were run from the *PC Tech Journal* AT Evaluation Suite. ATBIOS checks the BIOS and BIOS data areas. ATKEY checks for keyboard compatibility. ATFLOAT measures floating-point operations with the numeric coprocessor installed. ATDISK measures hard-disk performance. ATPERF measures CPU and numeric coprocessor clock rates, as well as memory access times. Table 2 lists the results of the Access 386 in comparison with the IBM AT and the Compaq Desk-

Visual COBOL

The COBOL that pays for itself... the very first time you use it!

Programming costs can be expensive. Even when you create a simple data entry screen like the one you see here. This one took about 8 hours to create using extensions to the ACCEPT/DISPLAY verbs you'd find in any other COBOL. When you consider the hourly rates of programmers, development costs can quickly get out of hand. And there goes the budget.

But there's a better way. With Visual COBOL's integrated Screen Management System, you can create the same screen in less than 30 minutes. You save a full day of development time. And several hundred dollars in programming costs. Which means your budget for software development will go a lot farther.

Beyond its incredible Screen Management System, Visual COBOL is also a high performance native code COBOL compiler that features fast execution, a powerful interactive debugger, blazing SORT, multi-keyed ISAM, extended CHAINing utilities, GSA certification, and much more.

Visual COBOL. The only COBOL that pays for itself. Again and again and again. Call mbp today for complete details. It can help you make the most out of your development budget.

Visual COBOL. $795.

No copy protection. No runtime fees. Superb technical support.

Versions available: IBM PCs and compatibles under MSDOS/PCDOS and SCO XENIX V; CTOS; UNIX V; IBM PC and Novell Networks.

mbp Software and Systems Technology, Inc.
1131 Harbor Bay Pkwy, Suite 260
Alameda, California 94501

800-231-6342
800-346-4848 In Calif.



Visual COBOL is a trademark of mbp Software and Systems Technology, Inc./UNIX is a trademark of AT&T Corp./SCO is a trademark of SCO, Inc./IBM is a trademark of IBM Corp./Novell is a trademark of Novell, Inc./XENIX is a trademark of Microsoft Corp.

CIRCLE NO. 225 ON READER SERVICE CARD

pro 386 on these tests. Bar graphs in figure 1 present comparisons for RAM instruction fetch, RAM read and write times, ROM read times, and EMM read and write times.

ATBIOS showed that the Access 386 uses the BIOS data area in the same way that the IBM AT does. The BIOS has a Phoenix Technologies copyright and a date of 10/28/86. ATKEY verified the compatibility of the ALR enhanced keyboard with the IBM AT keyboard. ATFLOAT reported that the Access 386 processes floating-point operations 2.2 times as fast as an 8-MHz AT. This is a reasonable finding because the 80386 runs at 16 MHz and the 80287 runs at 10 MHz (as opposed to 8 MHz and 5.33 MHz, respectively, on the AT). ATDISK found that the 42MB hard disk in the Access 386 is a high-performance drive, with significantly faster track-to-track and average seek times than the drive in the AT.

Given the potential for extremely high performance by the 80386, the results of ATPERF indicate that the Access 386 is a very fast AT, but perhaps not as fast as might be expected with a 16-MHz 80386 and interleaved, address-pipelined, 32-bit memory. The Access 386 does excel at instruction fetching, because of the sequential nature of instruction fetches and the interleaved memory architecture of the Access 386. In no other performance category does the Access 386 outperform the AT by as much as 25 percent; expanded memory and video memory access is actually slower than the AT. By contrast, the Compaq Deskpro 386 outperforms the Access 386 by a considerable margin in all areas of the performance tests save instruction fetching.

The slow EMM access time compared with the Compaq 386 is explained by the differences in memory architecture. However, the Access 386 is faster than the 8-MHz AT.

The slow video write time is a function of the way the Access 386 handles 8-bit expansion boards. In the Access 386, 8-bit boards are effectively slowed down even below the 8-MHz speed at which 16-bit boards are run; 13 cycles are required to access 8-bit memory rather than the 8 cycles required to access 16-bit memory. This is due to the more conservative synchronizing and timing specifications on the Intel iSBC bus than those found on the Compaq Deskpro 386. Because video memory is 8-bit memory, these extra cycles are inserted into each CPU display memory access, and these extra cycles slow video memory performance.

FIGURE 1: *Performance Comparison*



The Compaq Deskpro 386 has a copy of its 16-bit ROM in 32-bit RAM. This enables its DWORD ROM read time to be much faster than that of the Access 386.

TABLE 2: *Compatibility and Performance Tests*

	8-MHz AT, 30MB DISK[a]	DESKPRO 386, 40MB DISK	ACCESS 386, 42MB DISK
ATBIOS			
ROM BIOS date	11/15/85	08/19/86	10/28/86
ATPERF			
Average RAM instruction fetch (μs)			
BYTE	.250	.19	.19
WORD	.403	.14	.13
DWORD	N/A	.23	.20
Average RAM read time (μs)			
BYTE	.401	.13/.26	.35
WORD	.401	.13/.26	.33
DWORD	N/A	.14/.26	.33
Average RAM write time (μs)			
BYTE	.401	.13/.26	.35
WORD	.401	.13/.26	.33
DWORD	N/A	.13/.26	.27
Average ROM read time (μs)			
BYTE	.401	.13/.26[b]	.32
WORD	.401	.13/.26[b]	.33
DWORD	N/A	.13/.26[b]	.79
Average CGA video write time (μs)			
BYTE	1.208	1.21	1.55
WORD	2.415	2.42	2.80
DWORD	N/A	4.83	5.62
Average EMM read time (μs)			
BYTE	.402	.13[c]	.34[d]
WORD	.402	.13[c]	.33[d]
DWORD	N/A	.14	.33
Average EMM write time (μs)			
BYTE	.402	.13[c]	.35[d]
WORD	.402	.13[c]	.33[d]
DWORD	N/A	.13	.27
CPU clock rate (MHz)	8.0	16.0	16.0
Numeric coprocessor clock rate (MHz)	5.3	8.0	10.0
Refresh overhead (%)	7.1	15	6.1
RAM read/write wait states	1/1	0/0	3/2
ROM read wait states	1	2	3
Video write wait states (CGA)	8	17	22
EMM read/write wait states	1/1	0/1[c]	3/2[d]
ATFLOAT			
Performance as percentage relative to AT	100	180	220
ATDISK			
Sectors/track	17	17	17
Heads	5	5	5
Cylinders	731	978	1,022
Total space (million bytes)	31.81	42.56	44.48
Track-track seek time (ms)	6.0	4.1	4.1
Average seek time (ms)	37.1	4.1	30.4
Effective transfer rate (KB/sec)	170.1	254.5	170.1
DOS file I/O (sec)	7.3	7.4	5.3
Interleave	3	2	3

[a]The figures for the IBM AT are the average results from several machines, whereas the results from the ALR Access 386 and the Compaq Deskpro 386 are taken only from the review sample model.
[b]Same as RAM read (see "The New Standard," Steven Armbrust and Ted Forgeron, March 1987, p. 48).
[c]EMM measurements were taken using the Deskpro 386's CEMM driver and built-in memory.
[d]EMM measurements were taken using the Access 386's extended memory configured as expanded memory with the QEMM expanded memory manager.

The Access 386 video write time is fairly long. The RAM read times for ATPERF show that the interleave memory is being read with two or three wait states.

The relatively slow RAM access times are explained by the nature of the test and show that the ATPERF test ran with the memory system inserting two wait states. Testing the performance of 80386-based computers is a complex matter, involving the interaction of code and the memory system, and no single test can be a reliable indicator of overall performance. The times reported in ATPERF for RAM reads and writes are not the best times of which the 80386 and the memory system in the Access 386 are capable, indicating that on many memory accesses the interleaved bank being accessed had not yet recovered from the previous access. A custom designed test for the ALR machine could show the memory system working at its best theoretical performance of one wait state, but performance will vary from application to application. In day-to-day use, the Access 386 proved to be much faster than an 8-MHz AT—an informal estimate is that it is nearly two times as fast.

WEAK DOCUMENTATION

Documentation is currently a weak point of the Access 386. It appears to have been done in a hurry, no doubt because ALR wanted to introduce the Access 386 quickly. (The company's promotional material indicates that it is "the company that first put the power of the 80386 on your desk.")

The documentation consists of a single 87-page, spiral-bound *User's-Technical* Manual. It is rife with typographical errors, is sometimes inaccurate, is often incomplete, and lacks an index. As the title implies, the manual is half a user's guide and half a technical manual. The user's guide section describes an earlier version of the Access 386 than the review machine, with photos and drawings to match.

The user's guide portion provides basic set-up and installation instructions. Topics such as how to take care of a diskette and how to unpack the computer are covered in detail. However, the guide never makes reference to the SETUP program used to set the CMOS RAM. In fact, as discussed above, the only documentation for the software on the setup/utilities diskette is contained in README files on that diskette.

Other important topics are covered in a scattershot and sometimes misleading fashion. For example, only two sentences are devoted to DOS, while three pages are spent on a step-by-step discussion of partitioning a hard disk.

The technical portion of the manual contains highly technical informa-

tion about both the system unit and options, some of which appears to have been photocopied from other ALR manuals. ALR's options are available for AT- and XT-compatible computers as well, and the documentation of the options tends to refer to these computers rather than the Access 386.

An operations manual is included with DESQview, which is bundled with the Access 386 system. This manual is well done, but it makes no reference to the ability of DESQview to take advantage of the virtual-8086 mode of the 80386 in order to process up to nine separate DOS tasks concurrently.

In short, the documentation for the Access 386 is simply not up to the high standards of the machine itself.

ALR's warranty covers parts and labor for a full year, a significant improvement on the usual 90-day coverage. Warranty repairs can be performed either by an ALR-authorized dealer or by factory depot service. Technical support is available with ALR's technical support telephone line between the hours of 10 a.m. and 8 p.m.

AN AFFORDABLE DOOR

The Access 386 is a solid workhorse among 386 machines, filling two roles well. As an AT compatible it is spectacularly fast, proving in day-to-day use to be roughly twice as fast at running currently available software as an 8-MHz AT. As a 386-based computer, it fully supports the features that will make possible the transition from DOS to more powerful environments, including 32-bit operation, a 4GB linear address space, multitasking, and virtual-8086 mode. While the Access 386 is not the most sophisticated or fastest 386-based computer, it is nonetheless comparable to its competitors in functionality—especially in the basic Access 386B configuration—and it is significantly less expensive than the current 386 standard, the Compaq Deskpro 386.

The Access 386 does have some rough edges, however. Microsoft Windows does not work with Microsoft's bus mouse, although it does function properly with the serial mouse, and the bus mouse does work with Microsoft Word. Cheetah's zero-wait-state memory does not work at all. Software running in high DOS memory may slow down to near-AT speed unless QEMM and the 32-bit memory board are used to top off DOS. The many jumpers on the motherboard are difficult to use and should be replaced with switch blocks. Finally, ALR must expand and improve its documentation.

While the above items cannot be considered trivial, they are minor in light of the tremendous capabilities of this computer. By using the 80386 processor and pricing the Access 386 between ATs and competing 80386-based computers, ALR has opened an affordable door to the 80386-based environments and applications of the future. ALR has built a computer that should be judged today as a very high-performance AT compatible at a reasonable price—with the tremendous potential of the 80386 built in, awaiting the 32-bit software of tomorrow.

Advanced Logic Research, Inc.
10 Chrysler
Irvine, CA 92718
714/581-6770
Access 386

CIRCLE 346 ON READER SERVICE CARD

Michael Abrash and Dan Illowsky are senior software engineers for Orion Instruments in Redwood, California; they are coauthors of Graphics for the IBM PC *(Howard W. Sams Company, 1984) and publishers of arcade games for the PC from Funtastics, Inc.*

Do You Ever Get the Feeling That No One Speaks Your Language?

Arity/Prolog. The Language That Spans the Generation Gap.

Arity listens to what you ask for. You want a serious, versatile language that will go the distance for you. There are two very good reasons for you to use Prolog—to do your work smarter and faster. That's exactly what the Arity/Prolog development environment will help you do. Our powerful tools, based on the general purpose programming language Prolog, will significantly reduce your development time and allow you to solve a wide range of application problems.

No translation required Our development environment for the IBM PC family and all MS-DOS compatibles includes the Arity/Prolog Compiler and Interpreter, the Arity/Expert System, and Arity/SQL. And you can tie them all together. You can interface with several other programming languages and build extensions to your existing applications. You'll be truly multilingual—what better way to span the generation gap?

It can take you to new places You'll discover amazing speed, power, and flexibility using the Arity/Prolog programming environment, with its one gigabyte of virtual memory and fast, compact compiled code, for conventional applications. And if you're working in new territories, like expert systems or sophisticated database management systems, you'll be speaking the native tongue.

Speak it freely Our products are not copy protected and we charge no royalties, so you can use them in as many end-user applications as you'd like. Why keep the language of solutions all to yourself?

Join the thousands of assembly and C programmers who already use Arity/Prolog—the language of solutions.

Call 1-800-PC-ARITY Today.

Masschusetts residents call 617-371-1243.

Software that roars.

ARITY CORPORATION
30 Domino Drive, Concord, MA 01742 U.S.A.
1-800-722-7489 or in Massachusetts call 617-371-1243

CIRCLE NO. 136 ON READER SERVICE CARD

PERFECT PARTNERS

Datalight C & LIGHT TOOLS

DATALIGHT C

Datalight C compilers are among the fastest and most versatile language compilers available today. Their unique combination of low price and high performance make them an unsurpassed value for both the professional and occasional programmer alike.

Datalight Developer's Kit

The *Datalight Developer's Kit* is a complete high performance C development system. It supports the full C language with recent extensions and five memory models. Compilation speeds are three times faster than many other C compilers. Execution speed is very fast and often better than other higher-priced C compilers.

Optimum-C

Optimum-C combines the complete *Datalight Developer's Kit* with an additional optimizing compilation step that cuts the execution time of computation-bound programs by up to 30 percent. You can choose either faster compilation for developing your program or faster execution for creating the finished product.

Library Source Code

Datalight's UNIX-compatible library includes complete source code. The library also includes many MS-DOS specific functions and Datalight's own BIGBUFF fast buffered I/O scheme.

Easy-to-use

Datalight compilers are easy to install and use. You can compile, link and even create COM files in one easy step using the DLC compiler control program. Concise documentation is contained in one IBM-sized 3 ring binder including nine chapters, an index and easy-to-follow examples.

The Datalight Developer's Kit and new *Optimum-C* compilers are a perfect choice for developing high quality C language programs. And when combined with *LIGHT TOOLS* by Blaise Computing, the result is an MS-DOS program development system that is unsurpassed in price and performance.

by Blaise Computing

Introducing *LIGHT TOOLS* by Blaise Computing—the perfect partner for Datalight C. This useful library of C routines is a compatible subset of Blaise Computing's *C TOOLS PLUS* and is specifically adapted to take full advantage of Datalight C compilers.

Fast Video

LIGHT TOOLS gives you fast video I/O using BIOS services or direct access to video memory. You can detect installed video adapters and their switch settings, select which adapter to use, perform I/O on any display page, control cursor position and size, and turn the cursor on or off. Support is also provided for the Enhanced Graphic Adapter's 43-line mode.

Windows

You get full-functioned windows that can be stacked, removed and can accept user input. There is no limit, other than available dynamic memory, to the number of windows you can construct and use. Abundant support is provided for performing I/O independently on different windows.

Interrupt Service

There is complete interrupt service support for polite, robust, resident applications. The underlying interrupt dispatcher mechanism is solidly designed to be compatible with other resident software.

Keyboard and More

You get complete access to BIOS keyboard services and the keyboard buffer. *LIGHT TOOLS* also includes general utility functions including sound, disk volume label support, management of memory outside your *Datalight C* program and BIOS time of day.

All Blaise Computing products come with complete, fully-documented source code, sample programs and a comprehensive, indexed reference manual.

programmer's connection

136 SUNNYSIDE ST. HARTVILLE, OHIO 44632

CIRCLE NO. 175 ON READER SERVICE CARD

YOUR QUALITY CONNECTION...

blaise products

	LIST	OURS
ASYNCH MANAGER *Specify C or MS Pascal.*	175	119
C TOOLS PLUS	175	119
LIGHT TOOLS *for Datalight C. . . . . New*	100	78
PASCAL TOOLS *for MS Pascal*	125	94
PASCAL TOOLS 2 *for MS Pascal*	100	74
PASCAL TOOLS & PASCAL TOOLS 2	175	119
TURBO ASYNCH PLUS *for Turbo Pascal*	100	78
TURBO POWER TOOLS PLUS *Turbo Pascal*	100	78
VIEW MANAGER *Specify C or MS Pascal*	275	179

datalight products

Datalight C Compiler *Small Model Only*	60	43
Datalight Developer's Kit	99	74
Optimum-C *New*	139	109

Prices include FREE UPS surface shipping to all U.S. customers. Express services are also available at the shipping carrier's standard rate.

Please refer to our main advertisement in this journal for more information and the largest advertised selection of programmer's development tools for IBM personal computers and compatibles.

PROGRAMMER'S QUALITY INTEGRITY Service SUPPORT PRICE CONNECTION

CALL TOLL FREE

U.S.	800-336-1166
CANADA	800-225-1166
OHIO and ALASKA (Call Collect)	216-877-3781
OVERSEAS	216-877-3781
CUSTOMER SERVICE	216-877-1110

DOS Exception Handling

DOS error and exception handling methods allow an application program to run smoothly under worst-case conditions.

DAN ROLLINS

A seamless user interface is taken for granted in a professionally designed application. Colorful screens of pop-up windows, pull-down menus, and neatly framed status lines are expected to remain functional despite any abuse that a user might subject them to. An attempt to write to an empty disk drive should not paste the "Abort, Retry, Ignore" message in the middle of a carefully constructed screen. Even more important than cosmetics is the reliability of an application, and that too should not be compromised by user actions. Applications should be designed to operate under worst-case conditions. For example, can the application's data survive a Ctrl-Break in the middle of writing a file?

Ctrl-Break handling and critical device errors tend to be overlooked during program development and take on ominous importance about one week before an application's release date. A critical error is a device error that forces DOS to shut down activity until the problem is resolved. Ctrl-Break is usually defined as a request to abort or abnormally end an executing program. By default, Ctrl-Break causes an immediate exit to DOS.

At the lowest level, the keyboard interrupt (09H) is generated by the hardware every time a key is pressed or released. The routine that services this interrupt (normally residing in BIOS, unless replaced by a terminate-and-stay-resident utility) interprets each keystroke, usually placing an ASCII or extended ASCII value into a keyboard buffer. Certain keystrokes are given special treatment. The Shift-PrtSc keystroke, for example, invokes interrupt 05H to print the contents of the screen, and the SysReq key on ATs causes an interrupt 15H. Similarly, the Ctrl-Break keystroke causes an interrupt 1BH.

Interrupt 1BH can be intercepted at this lowest level. For example, setting interrupt 1BH to point to an IRET that is located somewhere in ROM causes Ctrl-Break to be ignored throughout the system. However, DOS provides a level of insulation for application programs that makes this low-level interception unnecessary and undesirable.

The DOS Ctrl-Break handler for interrupt 1BH sets an internal flag to indicate that a break has occurred. This flag may go unnoticed until DOS deigns to look at it. By default, DOS checks its break flag only during character I/O, specifically when processing the standard I/O, printer, and auxiliary devices. Because some programs run a long time without using these functions, a press of Ctrl-Break may not have the immediate effect desired.

DOS can be forced to pay more attention to the break status with the DOS command BREAK ON, or by placing BREAK=ON in the CONFIG.SYS file, or by using DOS function 33H (Ctrl-Break check) with AL=1 and DL=1. When BREAK is ON, DOS checks its break flag upon entry into nearly all DOS functions. The only exceptions are functions 06H (direct console I/O) and 07H (direct console input without echo). These functions are useful for password-input routines and for input routines used in processing Ctrl-Break and critical errors.

When DOS recognizes that a Ctrl-Break has occurred, it invokes the DOS break interrupt (23H). This interrupt is normally set to execute code within COMMAND.COM, which aborts the executing process and, if a batch file is being processed, displays the "Terminate batch job (Y/N)?" prompt.

The documented and the most acceptable method for performing Ctrl-

COMPUTER GRAPHIC • NATALEBAST



Break handling is to intercept interrupt 23H. Any custom handler installed in this interrupt is temporary; the original handler is restored when the program exits, even if the installing program remains resident in memory.

The following DOS features make this interrupt safe and easy to use:

- DOS function 25H (set interrupt vector) can be used to point interrupt 23H to the custom break handler.
- When Ctrl-Break is pressed, the break flag is set by interrupt 1BH. Subsequently, when a function that tests the break flag is about to be performed, DOS invokes interrupt 23H, passing control to the custom break handler.
- When the break handler receives control, the registers are set as they were on entry to the DOS function that detected the break flag. This feature can be used to find which DOS function was interrupted by the sensing of the break flag. If execution of this function is to be resumed after the break handler is finished, then any registers to be used within the break handler should be saved.
- DOS is in a relatively stable state. The *DOS Technical Reference* manual, version 3.2, claims that a break handler is unrestricted in the DOS functions it can perform. In reality, DOS can lock up while the break handler is executing if certain DOS I/O functions are performed and the user then presses Ctrl-Break again.
- After closing files, setting flags, and cleaning up the screen, the user can return to a program by executing an IRET. This causes the interrupted DOS function to be restarted, so any registers that have been used must be restored before returning. The application then will continue as if the break did not occur.
- If control is to be returned to the parent process without resuming the interrupted program, then the break handler must set the carry flag and execute a far return. A far return with the carry flag clear is equivalent to an exit via an IRET. The break handler also can terminate the program by using a DOS termination function, interrupt 20H or function 4CH.

Listing 1 (BRK_TEST.ASM) illustrates the basic concepts of capturing and using the Ctrl-Break interrupt. The first part installs the local interrupt handler and then begins printing a message in an endless loop, using routines included from listing 3, CE_CONIO.ASM, (also used in listing 2). When DOS recognizes Ctrl-Break, the BRK_HANDLER procedure displays a prompt, receives user input, and then acts upon it either to resume the program or exit to DOS.

DOS function 09H (print string) was used in an earlier version of BRK_HANDLER to display messages and DOS function 0AH (buffered keyboard input) to receive user input. This worked until Ctrl-Break was pressed while the break handler was active, causing the system to lock up. The machine had to be turned off to clear the problem. Several unsuccessful modifications were tried, including redirecting interrupt 23H to an IRET within the break handler. One reliable method uses only DOS function 06H (direct console I/O) to display and input characters. Another approach redirects interrupt 1BH (the BIOS break vector) to an IRET instruction while processing Ctrl-Break and restores its value upon leaving the break handler; this disables BIOS break notification to DOS.

The most desirable approach is to have a program recognize Ctrl-Break as soon as possible. Listing 1 uses DOS function 33H (Ctrl-Break check) to force extended break testing. (Some programs may not work well with BREAK turned on; see "A Resident Exception Manager," Programming Practices, Ted Mirecki, this issue, p. 170).

Proper break handling is important in two other areas. Pop-up programs may need to take special action to avoid problems with Ctrl-Break while they are active. Any interrupt 23H break handler put in place when the pop-up program

FIGURE 1: *Interrupt 24H Handler Error Indicators*



Upon entry into an interrupt 24H critical error handler, the AX and DI registers indicate the condition that caused the error and available corrective actions. If the error type (AH bit 7) is a disk error, AL contains the drive number.

Adapted from the IBM PC-DOS Technical Reference *manual*

FIGURE 2: *Interrupt 24H Handler Stack Upon Entry*



When the critical error handler is called, the stack top contains the far return address to the failing DOS function. Further into the stack are the application's registers and return address, saved when the DOS call originally was made.

Adapted from the IBM PC-DOS Technical Reference *manual*

is installed is disabled after the installation. DOS restores COMMAND.COM's break handler upon termination, even when the program is exited via one of the terminate-and-stay-resident services (interrupt 27H or DOS function 31H).

When the pop-up program becomes active, the break vector for the interrupted program continues to be in effect. Interrupt 23H should be intercepted to execute a local break handler while the pop-up program is active, then the vector is restored when the user exits the pop-up program.

DOS shell programs are an important consideration. When a program uses DOS function 4BH (EXEC) to load and execute a child process, DOS saves the current interrupt 23H vector into offset 0EH of the program segment prefix (PSP) of the child process. It then sets interrupt 23H to point to the code directly following the call to the EXEC function. The result of a Ctrl-Break is an immediate return to the parent. When the child program exits, DOS restores the parent's Ctrl-Break vector from the child's PSP. This is significant because a parent process must provide Ctrl-Break services for its children.

The parent can determine how the child process is terminated by calling DOS function 4DH (get return code). The high-order byte of the code returned by this function is 0 for normal termination via interrupt 20H or function 4CH, 1 for termination with Ctrl-Break, 2 if terminated by a critical error, and 3 if terminated with function 31H (terminate and stay resident).

However, if a child process is executed indirectly by means of a second copy of the command processor, as is done frequently in DOS shell programs, then the return code comes from COMMAND.COM, and not from the child program. COMMAND.COM, in this case, repoints interrupt 23H to its own Ctrl-Break handler, so that the parent does not need to make provisions for servicing interrupt 23H. In fact, one of the primary reasons for invoking COMMAND.COM is to use its built-in interrupt handling routines.

CRITICAL ERROR HANDLING

The most common critical errors are disk problems, but printers and other devices can cause critical errors. The standard DOS critical error handler is the routine that displays the infamous "Abort, Retry, Ignore" prompt. For most applications, the primary concern is to avoid this line and display a friendlier message. A secondary consideration is to limit the user's options—depending on circumstance, either the abort or ignore alternatives may be unacceptable.

Interrupt vector 24H contains the address of the current error handler. The address of the error handler of a program's parent (the default error handler for the program) can be found in the PSP at offset 12H.

As with the Ctrl-Break handler, intercepting and replacing the critical error handler is fully documented. Just like the Ctrl-Break handler, a custom error handler is temporary; the parent's interrupt 24H is restored from the PSP when a program terminates.

When the error handler is given control, the following takes place:

- The AH register and the lower 8 bits of the DI register indicate what the cause of the error was (see figure 1). If it is a disk error, the drive number is in the AL register.
- The registers of the program that made the failing DOS request are put on the stack (see figure 2).
- The register pair BP:SI contains the address of the device header of the device driver that indicated the failure (see figure 3).
- Because DOS is non-reentrant, the error handler must not use DOS functions higher than 0CH, with the exception of 59H (which is extended error reporting).
- The DOS direct disk access services, interrupts 25H and 26H, do not invoke the error handler. When the error handler receives control, it is certain that an interrupt 21H function was disrupted by the critical error.

Typically, the error handler should try to solve the problem—for example, by asking the user to close the diskette drive door or turn the printer on. The values in AX and DI can be used to decide which message, if any, to display.

After processing the error, the user can return to DOS via an IRET, passing back one of the exit codes shown in table 1. For DOS 2.x compatibility, the only options are to abort, retry, or ignore. Version 3.x offers the user an alternative: DOS can be told to cancel the operation and return to the application with a DOS error return code.

Listing 2 (CE_TEST.ASM), contains a typical critical error handler. It copes with common disk errors and provides general-purpose handling of character-device problems. The error handler has two options: retry the operation or cancel. A cancel request passes control back to the application with the carry flag set and a DOS error return code.

CE_TEST.ASM repoints the interrupt 24H critical error vector to the local routine CRIT_ERR, which will handle any errors encountered in the subsequent I/O operations. The first of these operations is the creation of a file on drive A:. To activate the error-handling routine, the user opens the

PROTECT YOUR COPIES OF

PC TECH JOURNAL

Make your collection of PC TECH JOURNAL a handsome addition to your office or home—and protect and organize them for easy reference!

PC TECH JOURNAL Magazine Binders and cases are made of durable luxury-look leatherette over quality binder board. Custom designed for PC TECH JOURNAL, every order receives FREE transfer foil to mark dates and volume numbers.

FOR FAST SERVICE CALL TOLL-FREE 1-800-972-5858

MAGAZINE BINDERS

Hold your issues on individual snap-on rods. $8.95 each; 3 for $25.75; 6 for $48.75.

OPEN BACK CASES

Store your copies for individual reference. $7.95 each; 3 for $22.95; 6 for $43.95.

PC TECH JOURNAL P.O. Box 5120 Philadelphia, PA 19141

Please send ☐ Binders ☐ Cases Quantity _____

Payment enclosed $_____.* Add $1 per order for postage & handling. (Outside USA, add $2.50 per unit ordered, US currency only.)

Charge my:
☐ Amex ☐ Visa ☐ MC (Minimum order $10.)

Card No._____ Exp. Date_____

Mr./Mrs./Ms._____
please print full name

Address_____

City_____

State_____ Zip_____

*PA residents add 6% sales tax.

FIGURE 3: *Device Header Structure*

OFFSET	SIZE (bytes)	DESCRIPTION
00	4	Far pointer to next device header (OFFFFH = last driver)
04	2	Device attribute (bit 15 is 1 if character device)
06	2	Offset of device strategy (preparation) routine
08	2	Offset of device interrupt (action) routine
0AH	8	ASCII name (character device) or binary subunit (block device)

Upon entry into the critical error handler, the BP:SI register pair contains the segment:offset of the header of the device driver that signaled the error.

Adapted from the IBM PC-DOS Technical Reference *manual*

drive door or inserts an unformatted disk when prompted.

In the next step, CE_TEST.ASM attempts to write some text to the printer. Leaving the printer off-line or removing the paper shows how CE_TEST.ASM deals with an error.

Unplugging the printer cable during the printer-error test results in a long delay before the error message is displayed. This is because DOS retries the device three times before it decides to invoke the error handler, and it must wait for a printer time-out on each retry. This delay can be avoided by using interrupt 17H (BIOS printer functions) with AH=2 to read the status of the printer before starting to print. Then the critical error handler works as a backup in case the printer is turned off or runs out of paper while printing.

The CRIT_ERR routine in listing 2 displays an error message and prompts the user to determine what to do next. Depending upon the response, it exits to DOS or to the application. The error handler tries to be as invisible to the program as possible; it saves the screen contents, displays messages in a reverse-video window, and restores the screen upon finishing its tasks.

CRIT_ERR recognizes disk errors by testing AH and composes a different message for character device errors. The nature of the problem is determined by the value in DI. The name of the device is found from AL (for disks) or from the device header passed in BP:SI (for character devices).

The user can retry or cancel the operation. The retry logic simply restores the registers as they were upon entry and returns to DOS via IRET, passing back a code of 1 in AL. DOS then repeats the call to the I/O function.

The cancel logic is compatible with both DOS 2.x and 3.x. Using the stack structure shown in figure 2, it discards from the stack the return address and flags saved by the DOS routine when it executed interrupt 24H, then it restores the application's registers. The resulting state of the stack is such that a subsequent IRET returns not to the DOS routine that encountered the error, but directly to the program that invoked the DOS I/O function. Before returning, the error handler places an appropriate error code in AX and sets the carry flag. Note that the carry must be set not in the current flags, but in the flag image on the stack, from where it will be restored when the IRET is executed.

The effect is that the application receives a recognizable DOS error code that it can process as it sees fit. The error code returned to the application is calculated by adding 13H to the entry-value of DI, so that the critical error codes are mapped to the corresponding

THANKS FOR THE MEMORIES

Have you ever noticed how time seems to change everything? Fashions change. Technology changes. Even the microcomputers we use change. Maybe that's why so many of our customers are saying goodbye to IBM in favor of a "good buy" from Wells American.

As time goes by, more and more computer users are realizing what an extraordinary value our A★Star II® truly is. It's the *only* AT class microcomputer that can run at 6, 8, 10 *and* 12 MHz! It's also the *only* PC/AT compatible that's "network ready." Better yet, each A★Star II now comes with your choice of keyboards - the original AT version or the enhanced "RT" style. Best of all, A★Star II prices start at only $995!

But what about quality and support? Don't worry! We've been making microcomputers *longer* than IBM! And it shows. Our A★Star® computers have been top rated by leading industry trade journals. Even so, we've heard that some "big blue" old-timers still worry about trading their IBM "security" blanket for better priced, higher performance equipment. (Remember how difficult it was to give up *your* baby blanket?) That's why we've arranged for RCA, one of the world's largest technical service organizations with 18,000 employees, to provide low cost, nationwide maintenance for our A★Star II. And if that's not enough, every unit includes free schematics and a no risk money-back guarantee.

THE A★STAR II IS MADE IN THE USA.

Still need a blanket? We've got you covered! Try out one of our A★Star II's and we'll send you one. It's baby blue, monogrammed and...it's absolutely free! We'll also include a $395 option, at no charge, with your first A★Star II purchase. This offer *is* limited, so call or write us today. Just because you'll be saying goodbye to IBM doesn't mean you'll have to say goodbye to quality, support *or* security. Besides, at least you'll still have your memories...and your money!

Wells American®

Corporate Headquarters: 3243 Sunset Boulevard • West Columbia, South Carolina 29169 • 803/796-7800 • TWX 510-601-2645

IBM, Personal Computer AT and AT are trademarks of International Business Machines.

CIRCLE NO. 124 ON READER SERVICE CARD

DOS codes. This is convenient for most applications, but the user can choose to return any error code if desired.

However, the documentation states that returning to the application in this way leaves DOS in an "unstable state" until a function higher than 0CH is called. Stability will be restored only if the subsequently called function does not itself encounter a critical error. One possibility, which is demonstrated in the CE_TEST program, is to call function 19H (get current disk drive), which cannot return an error.

If the application is running under DOS 3.x, steps similar to the retry logic can be followed: IRET to DOS with a return code of 3 in the AL register. DOS eventually returns to the application with the carry flag set. The DOS 3.x-specific application, upon querying DOS function 59H, will learn that error number 53H (device failure) occurred, but not the reason for the failure.

While in the error handler, DOS function 30H should not be used to determine which version of DOS is active. If it is necessary to execute separate logic for DOS 2.x and 3.x, the user must determine the DOS version number before an error occurs and put it in a global variable where the error handler is able to find it.

TABLE 1: *DOS Error-recovery Action*

AL	DESCRIPTION
0	Ignore the error.
1	Retry the operation. This is invoked after the user is given a chance to close the drive door, fix the printer, etc.
2	Abort. This causes DOS to execute interrupt 23H, the DOS Break routine. This normally causes an exit to the parent process.
3	Fail. This tells DOS to return to the application, indicating an error occurred during the operation. Do not return this value unless DOS 3.x is active.

When an error handler returns to DOS, it passes back a value in AL to indicate how execution is to proceed. Option AL=3 (fail) was introduced with DOS 3.0.

Pop-up programs and shells must pay special attention to the DOS critical error vector. When a pop-up program is activated, it must direct control to its own error handler; how an application will handle an error is unpredictable. If the existing error handler were to abort to DOS, the machine would be left in a very disrupted condition.

Shell-type programs (any program that uses DOS function 4BH to execute a child process) must be aware that the error handler in effect at the time the EXEC function is invoked will be used as the default error handler for the child process. In most cases the normal DOS error handler should be restored before EXEC is invoked, because the child program's error handler is not likely to manage all error conditions as well as the normal COMMAND.COM error handler. The easiest method of reinstating the DOS error handler is to EXEC COMMAND.COM, letting it in turn, EXEC the child program.

EXTENDED ERROR REPORTING

Beginning with version 3.0, DOS has provided a service to consolidate and simplify normal error handling for applications. DOS function 59H (get extended error) returns the information shown in table 2. This service can be used only after a DOS function has returned an error indication. It returns codes describing the specific error, the class of error, where the error occurred, and a suggested action to take.

This function works after any DOS error, including errors on old-style file control block (FCB) operations indicated by AL=0FFH, errors indicated by the carry flag being set, and device errors handled by customized interrupt 24H critical error handlers. Error codes 13H through 1FH returned by function 59H are the same as codes 0 through 0CH that are found in the DI register by a critical error handler.

DOS function 59H allows the developer to write general-purpose exception routines to eliminate some in-line code. A general-purpose error handler subroutine is a convenient way to link into a variety of application programs. Such an error handler could display prompts, get user input, and take actions in a generic way.

This extended error reporting function is a mixed blessing. The majority of applications must continue to write down to DOS 2.x to maintain the broadest possible compatibility. Applications that use DOS file locking or are specifically written for the PC/AT or PC Convertible (and thus must run on DOS 3.0 or later) can take full advantage of this function. Other applications must rely on DOS 2.x error conventions or

Microstat®

HIGH POWER WITHOUT THE HIGH PRICE

Microstat® has been the most popular statistics package for microcomputers since we introduced it in 1978. In the past two years, Microstat has been requested by name on more military contracts than any other statistics package. When it comes to coverage, ease of use, accuracy, and value, Microstat is unbeatable. Just some of it features include:

- Data Management Subsystem for file creation and management.
- Data Transformations
- Hypothesis Testing
- Three types of ANOVA
- Simple, Multiple, Stepwise Multiple Regression
- 11 Nonparametric Tests
- Factorials, Permutations, Combinations
- Batch or Interactive Operation
- Read external files (e.g., Lotus, dBaseII, ASCII)
- Descriptive Statistics
- Scatterplots
- Correlation Analysis
- Time Series
- 8 Probability Distributions
- Crosstabs and Chi-Square
- User's Manual

Microstat® is available for MSDOS, PCDOS, CP/M80, CP/M86. The price is $375.00. Multiple copy discounts and cost-effective site licenses are available.

To order, call:
800-952-0472
(for orders)
or
317-255-6476
(tech. info.)



Ecosoft Inc.
6413 N. College Ave.
Indianapolis, IN 46220

MasterCard VISA AMERICAN EXPRESS

CIRCLE NO. 131 ON READER SERVICE CARD

UNIFY DBMS/DOS. The UNIX World Leader Brings A New Dimension To DOS Application Development.

What happens as the DOS world expands? As a new generation of hardware takes over? As networking becomes more important? The potential is enormous. But until now, the tools to achieve it have been limited.

Now a leader from another world unleashes that potential: UNIFY® DBMS. The leading relational DBMS in the UNIX™ world. And now, the most advanced set of application development tools in the DOS world.

With UNIFY DBMS, DOS developers have new power to build more sophisticated applications than ever before possible.

The power to write high performance "C" programs that will access the data base, using Unify's Direct Host Language Interface.

The power of an industry standard query language—SQL.

The power of unmatched speed in production applications. Only UNIFY DBMS is specifically engineered for transaction throughput. With unique performance features like PathFinder™ Architecture multiple access methods, for the fastest possible data base access.

The power of comprehensive program development and screen management tools. Plus a state-of-the-art fourth generation report-writer.



What's more, with UNIFY DBMS, the potential of networked applications becomes a reality. Unlike DBMS systems which were originally single-user (and which have a long stretch to accommodate more users), UNIFY DBMS is a *proven* multi-user system.

And because UNIFY DBMS/DOS is the best of two worlds, it offers you the most powerful benefit of all: DBMS applications that can grow as your needs grow. From single user DOS. To networked DOS. To multi-user UNIX. All without changing your applications.

Call the Unify Information Hotline for our free booklet: The New DOS World.
(503) 635-7777

UNIFY
CORPORATION
4000 Kruse Way Place
Lake Oswego, OR 97034

© 1986 Unify Corporation. UNIX™ is a trademark of AT&T Bell Laboratories.
CIRCLE NO. 156 ON READER SERVICE CARD

#1 C interpreter

C-terp

The professional C development environment

Your C compiler creates great final code . . . but as a programming tool, it's too, t o o s l o w.

With C-terp you can edit, debug, and run without the wait. Nothing, but nothing, is faster for developing professional C programs.

Choose the perfect C-terp companion for your C compiler

C-terp/Microsoft
C-terp/Lattice
C-terp/Mark Williams
C-terp/XENIX
C-terp/Aztec
C-terp/C86

Link in all your compiler's functions, your own functions, add-on libraries, assembly routines, and data objects. Get instant access to everything in the C-terp interactive environment.

Only C-terp offers all this and more

- **Full K&R with common ANSI enhancements**
- **Source level interactive debugging**
- **Software paging for your big jobs**
- **Complete multi-module support**
- **Run-time pointer checking**
- **Unsurpassed reconfigurable screen editor**
- **Dual display and full graphics support**
- **Large model** ■ **Call-in**

ORDER C-terp TODAY (specify compiler)

C-terp runs on IBM PC, AT or compatibles.

Price:
MS-DOS 2.x and up - $298,
Xenix System V 286 - $498
MC, VISA, COD
30-day money-back GUARANTEE

Trademarks: C-terp (Gimpel Software), C86 (Computer Innovations), Lattice (Lattice, Inc.), Xenix, Microsoft, MS-DOS (Microsoft, Inc.), Aztec (Manx Software), Mark Williams (Mark Williams Company), IBM (International Business Machines, Inc.)

GIMPEL SOFTWARE

3207 Hogarth Lane, Collegeville, PA 19426

(215) 584-4261

TABLE 2: *Extended Error Codes*

REGISTER CONTENTS	DESCRIPTION
ERROR CODE IN AX	
00	No error
01	Invalid function number
02	File not found
03	Path not found
04	Too many open files (no file handles available)
05	Access denied
06	Invalid file handle
07	Memory control blocks destroyed
08	Insufficient memory
09	Invalid memory block address
0AH	Invalid environment
0BH	Invalid format
0CH	Invalid access code
0DH	Invalid data
0EH	Reserved
0FH	Invalid drive number
10H	Attempt to remove current directory
11H	Not same device
12H	No more matching files (after file-searching operation)
13H	Disk is write protected
14H	Unknown unit (invalid drive number)
15H	Drive not ready (door is open or no diskette is in the drive)
16H	Unknown command to the device driver
17H	Disk data error (CRC error)
18H	Bad request structure length
19H	Seek error (device driver could not access the requested track)
1AH	Unknown media (device driver could not recognize disk format)
1BH	Sector not found
1CH	Printer out of paper
1DH	Device write error
1EH	Device read error
1FH	General failure (or no appropriate error code exists)
20H	File-sharing violation
21H	File-locking violation
22H	Inappropriate disk change
23H	Too many FCBs in use (no FCBs available)
24H-4FH	Reserved
50H	File exists
51H	Reserved
52H	Cannot make
53H	Failure indicated by interrupt 24H (critical error handler returned AL=3)

Adapted from the IBM *PC-DOS Technical Reference* manual

provide two exception-handling paths, depending upon the version of DOS that is active.

Currently, DOS continues to be fully compatible with previous versions; that is, if the carry flag is set upon return from a DOS function, a valid error code can be expected in the AX register. However, the *DOS 3.x Technical Reference* manual does not list the specific errors expected for each function, and it states that new services in future releases of DOS may not provide accurate error information unless function 59H is used. Thus, when using file locking or other DOS 3.x-specific features, the developer is advised to invoke function 59H when an error is encountered.

Using function 59H is fairly straightforward. A typical sequence is

```
mov ah,fn_num
int 21H          ; DOS fn. Any error?
jnc no_err       ; no, continue
mov ah,59H       ; yes, get error info
int 21H
jmp err_proc     ; handle the error
no_err:          ; else continue
```

REGISTER CONTENTS	DESCRIPTION
ERROR CLASS IN BH	
1	Out of resource; no more memory, disk space, etc.
2	Temporary situation; try again later (file is locked, but it may become unlocked in a little while).
3	Authorization error; user was not allowed to do this.
4	Internal DOS error
5	Hardware failure
6	System software failure; DOS internal problem
7	Application program error; for example, DOS function 4FH (find next) before function 4EH (find first)
8	Not found; no more matching files, etc.
9	Bad format; usually unknown disk media format
0AH	Item locked
0BH	Media failure; usually disk read/write error
0CH	Already exists
0DH	Unknown error class; no appropriate code exists
SUGGESTED ACTION IN BL	
1	Retry now; try again immediately and the problem may be solved.
2	Delay and retry; wait a few seconds then retry. This is the action recommended when a file is locked (it may become unlocked in a few seconds).
3	User input error; the program tried to open a file (or take other action) on a drive or directory that does not exist. If the filespec was obtained from user input, then the user should be prompted to enter a different drive or path or filespec.
4	Abort the program; this usually indicates that the program contains a programming error; for example, a DOS function 4FH (find next) service was invoked before function 4EH (find first). The error has not damaged DOS, so any necessary clean-up may be performed before exiting to the parent.
5	Immediate exit; DOS is in an unhealthy state and should be exited immediately, without closing files or performing other clean-up operations.
6	Ignore the error.
7	Retry after user action; prompt the user for action (inserting a different diskette), then retry the failing DOS function.
LOCUS IN CH	
1	Unknown; DOS cannot pinpoint an area where the error occurred.
2	Block device error; error occurred on a disk drive
3	Reserved
4	Character device error; this is usually a printer error.
5	Memory error

DOS function 59H provides extended error reporting for applications that run under DOS 3.0 and above. This list includes all error codes defined up to DOS 3.2.

where the ERR_PROC routine handles errors depending upon the error code in AX, error class in BH, suggested action in BL, and error locus in CH.

Although DOS supplies a no error code of 0, the code does not appear following a successful DOS operation. Function 59H always reports on the most recent error, and the documentation does not suggest a way to reset the error code. Therefore, it is not possible unconditionally to call function 59H and then to branch depending on the results that are returned by it.

The manual warns against coding for specific error numbers and, instead, recommends using suggested actions to determine what to do. Note, however, that some of the suggested actions are slightly misleading. For example, BL=3 suggests that a user error occurred and that the program should prompt for new input. This action is recommended when the user tries to open a file or create a directory on a drive or path that does not exist. DOS cannot tell if a filespec was input by a user, hard-coded into a program, or obtained from the

CQL

SQL Compatible Query System adaptable to any operating environment.

CQL Query System. A subset of the Structured English Query Language (SEQUEL, or SQL) developed by IBM. Linked files, stored views, and nested queries result in a complete query capability. File system interaction isolated in an interface module. Extensive documentation guides user development of interfaces to other record oriented file handlers.

Portable Application Support System

Portable Windowing System. Hardware independent windowing system with borders, attributes, horizontal and vertical scrolling. User can construct interface file for any hardware. Interfaces provided for PC/XT/AT (screen memory interface and BIOS only interface), MS-DOS generic (using ANSI.SYS), Xenix (both with and without using the curses interface), and C-library (no attributes).

Screen I/O, Report, and Form Generation Systems. Field level interface between application programs, the Query System, and the file system. Complete input/output formatting and control, automatic scrolling on screens and automatic pagination on forms, process intervention points. Seven field types: 8-bit unsigned binary, 16 bit signed binary, 16 bit unsigned binary, 32 bit signed binary, monetary (based on 32 bit binary), string, and date.

Including Source Code

$395.00

File System interfaces include C-tree and BTRIEVE.

HARDWARE AND FILE SYSTEM INDEPENDENT

KURTZBERG COMPUTER SYSTEMS

41-19 BELL BLVD.
BAYSIDE, N.Y. 11361

VISA/Master Charge accepted
(718) 229-4540

*C-tree is a trademark of FairCom

IBM, SEQUEL, PC, XT, AT are trademarks of IBM Corp.
MS-DOS and Xenix are trademarks of Microsoft Corp.

CQL and the CQL Logo are trademarks of Kurtzberg Computer Systems.

CIRCLE NO. 148 ON READER SERVICE CARD

DOS environment or other means—it always suggests that the user be prompted to reenter input.

When DOS suggests that the program "Abort with cleanup" (BL=4), it is usually saying that a programming error has occurred. For example, DOS recommends a shutdown if a file operation is attempted with a nonexistent handle or if function 4FH (find next matching file) is used before function 4EH (find first matching file). Even justified errors, such as requesting too large a block of memory in order to find the largest available block, cause DOS to suggest that the program should abort. This cowardly advice also is given for hardware errors such as a printer error encountered by a critical error handler.

Furthermore, a generic message, based on an error code and class, cannot be depended upon to provide meaningful information about a particular error. For example, if DOS function 56H (rename file) is used and the target filespec names a file that already exists, DOS indicates an "Access denied" error (AX=5) with an error class of "Permission problem" (BH=3). This may seem absurd, because the error class of "Already exists" (BH=0CH) is documented and would be ideal.

Because of the global nature of the way DOS handles extended error codes, a pop-up program might cause an interrupted application program to receive misleading error codes and advice from DOS. This could happen if a pop-up program were activated directly after a failing DOS operation but before the interrupted application could process the error. If the pop-up program experienced its own error, then when control returned to the application, it would receive the wrong error codes. Although this is an unlikely sequence of events, it is possible.

The most obtrusive errors are those that allow an unwanted exit to DOS or cause TTY-style messages to be scrawled upon the screen. Carefully crafted service routines that capture the Ctrl-Break and critical error interrupts can remedy most of these situations.

The method used to handle normal errors such as a full disk or an illegal file name, is a matter of programming style, common sense, and creative testing. The DOS extended error reporting function might help to simplify some exception processing for programs running under DOS 3.x. Considering the problems and inconsistencies with function 59H, and the fact that it must not be used in a DOS 2.x environment, it is not a complete answer to normal error handling. The best approach is the tried-and-true technique: simulate each potential error and see how DOS responds, then code the application to take action depending upon the context in which the error occurred.

Even if a program runs without a glitch 95 percent of the time, the other 5 percent will be noticed by end users. If developers could be certain that their programs would never run into a full disk or an off-line printer, programming would be much simpler. End users, however, inevitably will subject an application to worst-case conditions, and an application that is not reliable under those conditions eventually will not have many users. Error and exception handling is a prime consideration that should be built into a program in the early stages.

Dan Rollins is a consultant and freelance technical writer. He is the author of IBM PC: 8088 Macro Assembler Programming *(Macmillan, 1985). He also wrote the Flambeaux Software program DOS Help!, which won a Computer Press Association award.*

REQUIRED READING FOR ALL IBM PC SYSTEMS EXPERTS

If you're a systems expert, microcomputer specialist, or MIS/DP professional working with IBM PCs, you need the comprehensive information PC TECH JOURNAL provides 13 times a year!

It's the only magazine that provides you with the technical information to help you increase the performance of your multi-component system. It talks to systems experts and systems designers in the language you understand—about the applications and products you have to know about!

As part of your annual subscription to PC TECH JOURNAL, you'll receive the special PC TECH JOURNAL Directory issue published in November, the most comprehensive guide and index to the products in the PC marketplace and PC TECH JOURNAL's coverage!

Don't leave a gap in your required reading, subscribe to PC TECH JOURNAL now and *save 50%!*

For faster service call Toll-Free 1-800-852-5200 today!

PC TECH JOURNAL *P.O. Box 2966—Boulder, CO 80322*

Send me PC TECH JOURNAL for: **SAVE 50%!**

☐ One year (13 issues) for $26.70.
☐ Two years for $53.35.

Savings based on annual single-copy price of $53.35.

Mr./Mrs./Ms. _____
(please print full name)

Company _____

Address _____

City _____ State _____ Zip _____

☐ Bill me ☐ Payment enclosed

Add $6 per year for postage outside USA, US currency only. Please allow up to 60 days for delivery of first issue. Annual Basic subscription price is $34.97. 4Z684

The 3-in-1 applications development tool for every Tom, Dick and Harriett.



Presenting the first database applications development tool that delivers the promises of 4th-generation languages on the microcomputer.

It's SIMPLE Software.

SIMPLE stands for SYSTEM IMPLEMENTATION by EXAMPLE™ and it delivers the absolute best balance of power and ease-of-use.

SIMPLER THAN EVER BEFORE.

SIMPLE lets you jump in at any level of experience and unleash the full processing power of the PC. It has a totally non-procedural way of doing things that flattens-out the learning curve. You can automate everyday business tasks or prototype new applications without ever having to write a single line of procedural code.

SIMPLE enables experienced programmers to achieve higher levels of productivity. And for developing mainframe applications, SIMPLE is the perfect prototyping tool—combining ease-of-use, speed, and high-quality system documentation.

YOU GET 3-IN-1.

1. IT'S A DESIGN TOOL.

SIMPLE allows you to quickly prototype applications on the microcomputer—sit right down and draw, edit, and specify processing logic with a few keystrokes. SIMPLE aids in the process of structured design by organizing development efforts in a building-block fashion. Experienced developers move quickly and easily from task to task. Less experienced users are literally guided through the entire applications development process.

2. IT'S A RELATIONAL DATABASE MANAGER.

SIMPLE offers exceptional speed performance. It is written in Assembler and incorporates a highly optimized B-tree data access method that eliminates record sorting. SIMPLE also uses a dynamic single-record index. You can have an unlimited number of indices in any record. Each index may be either a single or concatenated key. SIMPLE's relational joins are easy to construct and more efficient to process. Joins are accomplished dynamically at time of processing and support one-to-many and many-to-many relationships.

3. IT'S AN APPLICATIONS GENERATOR.

It is the most practically functional applications generator on the market today. SIMPLE is completely non-procedural, never forcing you back to procedural methods, letting you accomplish even the most complex databased applications in the most easy-to-use-and-understand fashion.

A SINGLE, VISUAL 4GL LANGUAGE.

Uniquely, every step in program development from input screens, to reports, to complex processing logic is accomplished in SIMPLE's all-visual worksheets. It is fully non-procedural and totally picture-oriented. Design right on the screen, and SIMPLE's built-in pattern-recognition logic automatically generates all the application code for you. You never have to leave SIMPLE's 4GL non-procedural technique.

POWERFUL WORKSHEETS.

SIMPLE provides three powerful, yet easy-to-learn worksheets—a File Worksheet, Specify Worksheet and Design Worksheet. You need only to define a file, then SIMPLE creates the basic program for you. Enhancements are done on SIMPLE's Design and Specify Worksheets.

In the Design Worksheet, you simply paint or draw an example of the input screen or report you want.

Company Managers like Tom **easily develop customized applications like this Branch Reporting System which reports information from support service calls. Tom now has a system which validates certain information and provides a customer history to improve the branch's support capabilities. With SIMPLE's Specify Worksheet on screen, Tom simply joins data from four different files and establishes their relationship.**

Information Center Staff Members like Dick **easily create new microcomputer applications systems like this Lead-Tracking System. Dick is able to sit down with the Director of Marketing and review the main entry screen developed on SIMPLE which shows the prospect demographic information, the media source and date from which each lead was generated, and the fulfillment literature to be sent.**



System Analysts/Programmers like Harriett **easily prototype design changes while interacting with Department Heads. Harriett has prototyped some requested changes in a Mainframe Payables System. With the help of SIMPLE, she has built a test database with data imported from the mainframe and is able to review the check-ledger report, in the Controller's office on her portable computer.**

The Design screen may be painted exactly as you want using SIMPLE's built-in, full-screen editor which offers a wide range of capabilities to aid you—including the ability to delete or insert a character or an entire line, move or copy blocks of information, lasso text or variables, and window to other worksheets in one or two keystrokes. Powerful specification macros are invoked providing application users the ability to pop-up a window and browse through another file, interrupt data entry to perform another program, provide context-sensitive help, and perform conditional processing based on the user's input.

In the Specify Worksheet, you implement your processing logic. You never have to fall back to procedural programming to get the processing power you need. Range checking and data validation are easily implemented, visually. Conditional processing statements are quickly set up. Arithmetic operators, date operators, and a full set of string functions are available. You specify an example of how you want your data processed, and SIMPLE creates the program.

A POWERFUL MENU GENERATOR.

SIMPLE's power gives you the easy flexibility to generate unlimited levels of user-guidance menus, as your applications require. There are limitless design options for effective "point-and-shoot" menu creation. And you have total freedom to build menus before, during or after development, unmatched in other systems.

SIMPLE, SIMPLER, SIMPLEST.

Ask for SIMPLE at your computer dealer. Or call us direct for the dealer nearest you and a full-functioning SIMPLE demo package with a Quick-Start manual for only $9.95*.

*Includes shipping and handling. California residents add sales tax.

SYSTEM IMPLEMENTATION BY EXAMPLE is a registered trademark of Accuphase, Ltd.
IBM PC is a trademark of International Business Machines, Corp.

SIMPLE

SYSTEM IMPLEMENTATION BY EXAMPLE™

Published by Software Merchants Unlimited

Software Merchants Unlimited
2252 Fillmore Street, Suite 401
San Francisco, California 94115
415-567-5071

CALL 800-8 SIMPLE

Introducing multi-channel communications boards 400% faster than what you're probably using now.



Introducing the DIGIBOARD COM/Xi Series front-end processor. Intelligent multi-channel communications boards 400% faster than the industry standard.

Like our popular COM/X Series, they provide users of PC/XT/AT-compatible computers with four or eight individually addressable serial ports. But with the new COM/Xi series we've added:

- an 80188 co-processor operating at 10 MHz
- 256K of dual-ported RAM + 16K of ROM, all accessible to user/ programmers for application and security software development
- a modular design that allows us to custom-tailor I/O to individual customer requirements.

On-board intelligence means more speed for multi-user operating systems and multi-channel data collection and dissemination.

And makes the new DIGIBOARD COM/Xi Series a more intelligent choice for you.

DigiBoard
Plugging you into Tomorrow.

Call **1-800-344-4273.** In Minnesota, (612) 922-8055.

CIRCLE NO. 110 ON READER SERVICE CARD

LISTING 1: BRK_TEST.ASM

```
;=============================================================================
; BRK_TEST.ASM                  Dan Rollins              December 15, 1986
; This program illustrates techniques for intercepting and replacing
; the DOS Ctrl-Break handler.
;
; This program installs an INT 23H handler, sets DOS break-checking to
; ON, then goes into an endless display loop, wating for Ctrl-Break.
; Upon Ctrl-Break, it displays a message and lets the user continue or
; abort.
;
; This is a COM-format program and must be processed with EXE2BIN

;=============================================================================
; Code and data to install and test the break handler
;=============================================================================
code_seg segment
         assume  cs:code_seg, ds:code_seg, es:code_seg
         org     100H                ;COM-format program

brk_test proc    near
         jmp     start

test_msg db      "Press Ctrl-Break...  $",0

start:   mov     al,23H              ;DOS Ctrl-Break interrupt number
         mov     ah,25H              ;fn replaces an INT vector
         mov     dx,offset brk_handler
         int     21H                 ;local break handler is in place

         mov     al,1                ;change break-checking level
         mov     dl,1                ;set BREAK=ON
         mov     ah,33H              ;DOS break_check service
         int     21H

bt_10:   mov     dx,offset test_msg
         mov     ah,9                ;DOS display_msg servce
         int     21H
         jmp     bt_10               ;this loops endlessly until you
                                     ; press Ctrl-Break or Ctrl-C
brk_test endp

;=============================================================================
; Start of Ctrl_Break handler code and data
;=============================================================================

brk_msg  db       " *Break* detected before DOS function "
fn_no    dw       ?
         db       " ",0dh,0ah
         db       " Exit or Continue? (Press E or C) ",0

brk_handler proc far
         push    es      ;save registers of interrupted DOS function
         push    ds
         push    bp
         push    si
         push    di
         push    dx
         push    cx
         push    bx
         push    ax
bh_10:
         mov     bx,cs               ;address local data
         mov     ds,bx

         mov     al,ah               ;put DOS function number in AL
         mov     ah,0
         mov     bl,10
         div     bl                  ;break into two decimal digits
         or      ax,3030H            ;force into ASCII characters
         mov     fn_no,ax            ;store into the message

         mov     dx,offset brk_msg ;display the message
         call    disp_msg

bh_20:   call    beep
         call    get_key
         or      al,32               ;force response to lowercase
         cmp     al,'e'              ;request to Exit?
         je      bh_30               ; yes, go
```

2,000,000 Dots Per Screen. That's What It Takes.

At least in order to get on-screen resolution of this quality. And to get an accurate representation of what a facing-page spread—*one that you can actually read*—will look like when it's printed.

Introducing the LaserView™ Display System.

From Sigma Designs.

LaserView consists of a large screen monitor, complete with display adapter, available in your choice of 15 and 19* inch models. Big enough to put everything from simple graphs and charts to Desktop Publishing to CAD in an entirely new perspective. And at virtually full size.

Offering a *noninterlaced* screen resolution of *1664 x 1200*—equal to 8 EGA™-sized or 11 Macintosh™ screens—LaserView's "easy-on-the-eyes" paper-white display brings workstation-quality graphics and text to the PC level. It can even generate *four levels of gray* for increased on-screen detail in photos and drawings.

LaserView works with all programs that run under Windows™ and GEM™ including programs like Aldus Pagemaker™ and Ventura Publisher™—plus familiar PC programs like Lotus 1-2-3™ and AutoCAD.™ We've even included a copy of PC Paintbrush Plus® to help you get started with LaserView.

So call Sigma Designs. Because if you're serious about making it to the big screen, Sigma Designs has what it takes today.

LaserView.

Sigma Designs Inc.
46501 Landing Parkway
Fremont, CA 94538
415.770.0100

CIRCLE 227 ON READER SERVICE CARD

S I G M A D E S I G N S

Trademarks: LaserView: Sigma Designs, Inc.; EGA: International Business Machines Corporation; Macintosh: Apple Computer; Windows: Microsoft, Inc.; GEM: Digital Research Inc.; Pagemaker: Aldus Corporation; Ventura Publisher: Ventura Software Inc.; Lotus 1-2-3: Lotus Development Corporation; AutoCAD: AutoDesk Inc.; PC Paintbrush Plus: Z-Soft Corporation. *For commercial use only.

```
        cmp     al,'c'          ;request to Continue?
        je      bh_40           ; yes, go

        jmp     bh_20           ;invalid: loop back

bh_30:  stc                     ;set carry to indicate Exit
        jmp     bh_exit

bh_40:  clc                     ;clear carry to indicate Continue

bh_exit: pop    ax
        pop     bx
        pop     cx
        pop     dx
        pop     di
        pop     si
        pop     bp
        pop     ds
        pop     es
        ret                     ;FAR return to DOS
brk_handler endp

include ce_conio.asm            ;insert general-purpose routines

code_seg ends
        end     brk_test
```

LISTING 2: CE_TEST.ASM

```
;=====================================================================
; CE_TEST                 Dan Rollins                 December 15, 1986
; This program illustrates techniques for intercepting and replacing
; the DOS Critical Error handler.  It shows how to:
;    * save and restore the application screen
;    * make the error message popup in a window
;    * allow the error handler to return directly to the application
;      program, passing back a DOS error code (even for DOS 2.x).
;
; After installing an INT 24H handler, it attempts to open a file on
; drive A, then attempts to send characters to the printer.
;
; This is a COM-format program and must be processed with EXE2BIN

;=====================================================================
; MACROS used in this listing
;=====================================================================
$set_csr macro  line,clm        ;;this positions the cursor
        mov     dx,((line)*256)+clm
        mov     ah,2
        mov     bh,0
        int     10H
        endm
$disp   macro   string          ;;this displays a string
       ifnb    <string>
         mov     dx,offset string   ;;if string given, point DX to it
       endif                        ;; otherwise, assume DX is set
        call    disp_msg
        endm
;=====================================================================
; Code and data to install and test the error handler.  This is
; the "application program" that is disrupted by a critical error.
;=====================================================================
code_seg segment
        assume  cs:code_seg, ds:code_seg, es:code_seg
        org     100H            ;must have for COM-format programs

ce_test proc    near
        jmp     start

filespec    db  "a:\erase.me",0         ;filespec used in disk test

test_msg    db  "This is a test message ",0dh,0ah ;for printer test
MSG_LEN     equ ($-test_msg)

prtr_msg    db  "Printer error test.  Press a key...",0
disk_msg    db  "Disk A: error test. Press a key...",0
new_line    db  0dh,0ah,0

no_err_msg  db  "Returned from DOS function without error.",0dh,0ah,0
ret_err_msg db  "Error "
ret_code    dw  ?               ;this is filled with 2 ASCII digits
            db  " upon return from DOS function.",0ah,0dh,0
```

```
start:  mov     al,24H          ;DOS critical error interrupt number
        mov     ah,25H          ;function to replace an int vector
        mov     dx,offset crit_err
        int     21H             ;local error handler is in place

        $disp   disk_msg        ;display a message and await a key
        call    get_key
        $disp   new_line

        ;------ disk test just attempts to open a file on drive A
        mov     dx,offset filespec
        mov     cx,0            ;normal attribute
        mov     ah,3cH          ;create file
        int     21H
        jnc     ct_20           ;if no error, continue

        push    ax              ;else, stabilise DOS
        mov     ah,19H          ;  with dummy call to function 19H,
        int     21H             ;  get current drive
        pop     ax
        mov     bl,10           ;setup string with error number
        div     bl
        add     ax,3030H        ;force binary to ASCII
        mov     ret_code,ax
        $disp   ret_err_msg     ;and display the resulting string
        jmp     ct_30
ct_20:
        $disp   no_err_msg

ct_30:  ;------ printer test sends text to standard printer device
        $disp   prtr_msg        ;display a message and await a key
        call    get_key
        $disp   new_line
        mov     bx,4            ;handle reserved for standard printer
        mov     cx,MSG_LEN
        mov     dx,offset test_msg
        mov     ah,40H          ;DOS write_handle function
        int     21H
        jnc     ct_40           ;if no error, continue

        push    ax              ;else, stabilise DOS
        mov     ah,19H          ;  with dummy call to function 19h,
        int     21H
        pop     ax
        mov     bl,10           ;setup string with error number
        div     bl
        add     ax,3030H
        mov     ret_code,ax
        $disp   ret_err_msg     ;  and display it
        jmp     ct_exit
ct_40:
        $disp   no_err_msg
ct_exit: mov    ah,4cH          ;DOS exit function
        int     21H
ce_test endp

;=====================================================================
; Start of Critical Error handler code and data
;=====================================================================
WIN_TOP  equ    10              ;these equate describe the popup
WIN_LEFT equ    20              ;window used by the error handler
WIN_HIGH equ    4
WIN_WIDE equ    40
WIN_ATTR equ    70H             ;reverse video screen attribute

devhdr_addr label dword         ;these values are saved upon entry
devhdr_off      dw ?            '
devhdr_seg      dw ?
save_ax         dw ?
save_di         dw ?

save_sp         dw ?            ;these are used in a CANCEL request
app_err         dw ?

response_msg    db "Retry or Cancel? (press R or C) ",0

crit_err proc   far
        mov     cs:save_sp,sp   ;save the stack position at start
        push    ax              ;save DOS's registers
        push    bx
        push    cx
```



SAVE UP TO $53.35 WHEN YOU SUBSCRIBE

GET YOUR FREE COPY OF PC TECH JOURNAL'S DATA MANAGER REVIEW

If you're a systems integrator, designer, consultant, or DP/MIS pro involved in technologically advanced applications, you need **PC Tech Journal**. You'll receive 13 issues a year—including **The PC Tech Journal Directory Issue**, a complete, indexed reference to the products, applications and innovations covered in **PC Tech Journal**! *Special Offer*—Act today and you'll also receive the PC Tech Journal Data Manager Review, a comprehensive report covering 7 leading data managers—with benchmark tests!

Your PC Tech Journal Data Manager Review will be shipped upon payment.

Please begin my subscription to PC Tech Journal for:

☐ One year (13 issues) for **26.70**—I'll save over $26!
☐ Two years (26 issues) for **$53.35**—I'll save over $53!

SAVINGS BASED ON ANNUAL SINGLE-COPY PRICE OF $53.35

Mr./Mrs./Ms. _____
Please Print Full Name 4S754

Company _____

Address _____

City _____ State _____ Zip _____

ADD $8 per year for postage outside USA. US currency only. Please allow up to 60 days for delivery of first issue. Basic annual subscription price is $34.97.

☐ Bill me later ☐ Payment enclosed

Please complete the following questions:

1. Is above address:
A. ☐ Business B. ☐ Home C. ☐ If home and business are the same.
(If home address, please provide your business information.)

Company Name
Division
Company Street Address
Company City State Zip Code
Telephone

2. How would you describe your company or organization. (Check one only):
A. ☐ Value-Added Reseller, Value-Added Dealer or Systems House
B. ☐ Computer Consultant
C. ☐ Computer Retailer
D. ☐ Distributor of Computer Products
E. ☐ Manufacturer/Publisher of Computer Hardware or Software
F. ☐ End-User Company or Organization that does not manufacture, distribute or resell computer products.
G. ☐ Other _____.
please specify

3. What is your primary job function as it relates to computer activities within your own organization? (Check one only):
A. ☐ Systems Design/Integration/Analysis
B. ☐ Data Communications
C. ☐ DP/MIS Management/Operations
D. ☐ Inside Consulting
E. ☐ Outside Consulting
F. ☐ Software Engineering
G. ☐ Hardware Engineering
H. ☐ Programming
I. ☐ Research and Development
J. ☐ General Management/Administration
K. ☐ None of the Above

4. Which of the following systems activities takes place in your department. (Check all that apply):
A. ☐ Application Development
B. ☐ Programming
C. ☐ Systems Integration/Development
D. ☐ Networking of PC to PC or PC to Mini/Mainframe
E. ☐ None of the Above

5. Check the products that you personally evaluate, recommend or select. (Check all that apply):
A. ☐ IBM or Compatible Microcomputers
B. ☐ Peripherals
C. ☐ Software
D. ☐ Communications Products
E. ☐ None of the Above

Date _____ Signature _____

Z015

SAVE UP TO $53.35 ON PC TECH JOURNAL

AND RECEIVE YOUR FREE COPY OF THE PC TECH JOURNAL DATA MANAGER REVIEW!

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

BUSINESS REPLY MAIL

FIRST CLASS PERMIT #66 BOULDER, COLORADO

POSTAGE WILL BE PAID BY ADDRESSEE

TECH JOURNAL

P.O. Box 52079
Boulder, Colorado 80321-2079

The expert's solution to complex systems problems.

When there's a question concerning networking, systems design and integration, applications development, data-communications, PC-to-mainframe connections—just about anything that deals with computers—we'd bet that others in your company turn to you, the systems expert.

Being knowledgeable about microcomputers is very demanding, and not many people take the time or trouble to stay up-to-date. But you do, and that's what keeps you in such high demand.

That's why PC TECH JOURNAL is so important to you. As a regular reader of PC TECH JOURNAL you receive comprehensive, hands-on reviews of the software and applications you have to know about. You'll find well researched articles about systems design and integration, and discover technological innovations that will help you increase the performance and efficiency of your system.

Only in PC TECH JOURNAL can you find expert coverage on iRMX based real-time operating systems, evaluations of 6 BASIC interpreters, 9-track tape subsystems, and how to best obtain the performance of a 5251 terminal on PCs, XTs and ATs.

PLUS, you'll receive our special 13th issue, the PC TECH JOURNAL DIRECTORY, the most comprehensive, indexed reference guide and resource to the products and applications covered in PC TECH JOURNAL.

Subscribe today and save 50% OFF the annual single-copy price of $53.35.

Mail the attached post-paid card or *call 1-800-852-5200 today!*

ONE YEAR (13 ISSUES) ONLY
$26.70—*SAVE 50%*
TWO YEARS (26 ISSUES) ONLY
$53.35—*SAVE 50%*
4Z676



```
        push    dx
        push    si
        push    di
        push    bp
        push    es
        push    ds

        push    cs
        pop     ds
        mov     devhdr_off,si   ;save address of the device header
        mov     devhdr_seg,bp
        mov     save_ax,ax      ;save err type & read/write bit flags
        mov     save_di,di      ;save error code

        and     di,00ffH        ;get critical error code
        add     di,19           ;convert to DOS error code
        mov     app_err,di      ;save in case we return directly to
                                ; the interrupted application
        call    save_scrn
        call    clr_window

        mov     ax,save_ax
        test    ah,80H          ;disk error ?
        jnz     ce_10           ; no, process character device error
        call    disk_err        ; yes, process disk error
        jmp     ce_20
ce_10:  call    char_err
ce_20:
        $set_csr <WIN_TOP+3>,<WIN_LEFT+1>
        $disp   response_msg  ;display "Retry or Cancel" message


ce_30:  call    get_key
        or      al,32           ;force response to lowercase
        cmp     al,'c'          ;request to Cancel?
        je      ce_50           ; yes, go
        cmp     al,'r'          ;request to Retry?
        je      ce_40

        call    beep            ;else, invalid response
        jmp     ce_20           ;go back an wait for a vaild response

ce_40:  ;------------------- action taken on RETRY request
        call    restore_scrn  ;leave screen as it was before error
        pop     ds            ;restore DOS registers
        pop     es
        pop     bp
        pop     si
        pop     di
        pop     dx
        pop     cx
        pop     bx
        pop     ax
        mov     al,1          ;set "Retry" return code
        iret                  ;and exit to DOS

ce_50:  ;------------------- action taken on CANCEL request
        call    restore_scrn  ;leave screen as it was before error
        mov     sp,cs:save_sp ;locally-saved regs are irrelevant
        pop     ax            ;and discard DOS IP
        pop     ax            ;           DOS CS
        pop     ax            ;           DOS flags

        pop     ax            ;restore application's registers
        pop     bx
        pop     cx
        pop     dx
        pop     si
        pop     di
        pop     bp
        pop     ds
        pop     es

        push    bp              ;set the carry flag (on the stack)
        mov     bp,sp           ; so the application will
        or      word ptr [bp+6],1  ; notice that an error occurred
        pop     bp
        mov     ax,cs:app_err   ;and pass back a DOS error code
        iret
crit_err endp
```

```
;=========================================================================
; Start of  code and data specific to character device errors
;=========================================================================
gen_msg         db "General failure on ",0
paper_msg       db "Printer out of paper on ",0
read_msg        db "Error reading from ",0
write_msg       db "Error writing to ",0
device_msg      db "device '"
dev_name        db 9 dup(?)

char_err proc   near
        $set_csr <WIN_TOP+1>,<WIN_LEFT+1>

        mov     bx,save_di      ;fetch the error code
        mov     dx,offset gen_msg ; assume "general failure" error
        cmp     bl,9            ; is it a "paper out" error?
        jne     ch_10           ; no, go.
        mov     dx,offset paper_msg
ch_10:  cmp     bl,0aH          ; is it a "write fault" error?
        jne     ch_20           ; no, go.
        mov     dx,offset write_msg
ch_20:  cmp     bl,0bH          ; is it a "read fault" error?
        jne     ch_30           ; no, go.
        mov     dx,offset read_msg
ch_30:  $disp

        ;------- now find the name of the malfunctioning device
        push    ds
        lds     si,cs:devhdr_addr
        add     si,0aH          ;point to device name in driver header
        push    cs
        pop     es
        mov     di,offset dev_name  ;point to local buffer for name

        mov     cx,8        ; 8 characters max
ch_40:  lodsb               ; get a character
        cmp     al,' '      ;end of device name?
        je      ch_50       ; yes, go
        stosb               ; no, add to local string
        loop    ch_40       ; get next character
ch_50:
        pop     ds

        mov     al,"'"      ;close quote on the device name: 'PRN'
        stosb
        mov     al,0        ; and make string ASCIIZ
        stosb
        $disp   device_msg
        ret
char_err endp

;=========================================================================
; Start of code and data specific to disk errors
;=========================================================================
disk_read_msg   db "Disk read ",0
disk_write_msg  db "Disk write ",0
disk_err_msg    db "error on drive "
disk_id         db "A:",0

write_prot_msg  db "Disk is write-protected.",0
not_ready_msg   db "Drive door may be open.",0
bad_media_msg   db "The disk media seems to be flawed.",0
gen_fail_msg    db "General failure of the drive.",

disk_msg_tbl    dw write_prot_msg, gen_fail_msg, not_ready_msg ;1,2,3
                dw gen_fail_msg, bad_media_msg, gen_fail_msg   ;4,5,6
                dw bad_media_msg, bad_media_msg, bad_media_msg ;7,8,9
                dw gen_fail_msg, gen_fail_msg, gen_fail_msg    ;a,b,c
                dw gen_fail_msg                                ;d

disk_err proc   near
        $set_csr <WIN_TOP+1>,<WIN_LEFT+1>

        mov     ax,save_ax
        add     al,'A'
        mov     disk_id,al

        mov     dx,offset disk_read_msg ;assume read error
        test    ah,1
        jz      de_10
```

I didn't know it was a crime

They told me those copies of programs I made for my computer could cost the company hundreds of thousands of dollars. Maybe even cost me my job.

Few people realize that software piracy is a Federal crime. At ADAPSO, the computer software and services industry association, we're doing everything we can to inform the public of the problem. And the penalties.

You could unknowingly put your company on the receiving end of a lawsuit by making illegal copies of software. Maybe even put yourself on the receiving end of a pink slip. And that's why ADAPSO wants you to know the facts.

Return the coupon for a brochure that explains the risks of software piracy. It's free. And it may help you keep your job.

Send this coupon or your business card for more information.
Or call us at (703) 522-5055 and ask for Marilyn.

ADAPSO, 1300 North Seventeenth Street, Arlington, Virginia 22209

NAME _____ TITLE _____

COMPANY _____

ADDRESS _____

CITY _____ STATE _____ ZIP _____

ADAPSO

Software Piracy is a Federal Crime

```
        mov     dx,offset disk_write_msg
de_10:  $disp                   ;display "Disk Write " or "Disk Read "

        $disp   disk_err_msg ;display "error on drive x:"
        $set_csr <WIN_TOP+2>,<WIN_LEFT+1>

        mov     bx,save_di      ;look up which message to display
        mov     bh,0
        shl     bx,1            ;each address entry is 2 bytes long
        mov     dx,disk_msg_tbl[bx]
        $disp
        ret
disk_err endp
;=========================================================================
; Start of general-purpose and library routines
;=========================================================================

include ce_conio.asm            ;insert console I/O routines
;-------------------------------------------------------------------
; CLR_WINDOW
; This function clears the error message window.
; Window position, size, and display attributes are set by equates.
;-------------------------------------------------------------------
clr_window proc  near
        mov     ch,WIN_TOP
        mov     cl,WIN_LEFT
        mov     dh,WIN_TOP + WIN_HIGH
        mov     dl,WIN_LEFT + WIN_WIDE
        mov     bh,WIN_ATTR
        mov     al,0            ; AL=0 means clear window
        mov     ah,6            ;BIOS scroll_window service
        int     10H
        ret
clr_window endp

;-------------------------------------------------------------------
; SAVE_SCRN
; This function save's the application's screen
; and cursor position.  Doesn't work for graphics-mode screens
;-------------------------------------------------------------------
```

```
save_scrn proc  near
        push    ds
        push    es

        mov     bh,0            ;assume video page 0
        mov     ah,3
        int     10H             ;get cursor position
        mov     cs:save_csr,dx  ;save for restore_scrn function

        int     11H             ;locate video memory segment
        mov     bx,0b800H       ;assume color card
        and     ax,30H
        cmp     ax,30H
        jne     sc_10
        mov     bx,0b000H       ;must be mono card
sc_10:
        mov     cs:scrn_seg,bx  ;save for restore_scrn function

        mov     ds,bx           ;source is video memory
        mov     si,0
        push    cs              ;destination is local scrn buffer
        pop     es
        mov     di,offset scrn_buf
        mov     cx,2000         ;count of words on entire screen
      rep movsw

        pop     es
        pop     ds
        ret
save_scrn endp
;-------------------------------------------------------------------
; RESTORE_SCRN
; this function restore's the application's screen
; and cursor position
;-------------------------------------------------------------------
restore_scrn proc near
        push    ds
        push    es

        mov     dx,cs:save_csr  ;fetch application's cursor pos
```


C Cross Compiler 68000/08/10/20

Introducing XRAY 68K Source Level Debugger

Features:

- Full, Standard C
- Easy to Use Compiler Options
- Complete User Documentation
- Global Code Optimization
- Optional Register Allocation Via Coloring
- ROMable and Reentrant Code
- Comprehensive Royalty Free Run-time Library
- Floating Point Library Routines
- Intermix MCC68K C with ASM68K Assembly Language or Microtec PAS68K Pascal
- Optional Assembly Language Listing Intermixed with MCC68K C Source Line Number
- Symbolic Debug Capability

The Microtec MCC68K C Cross Compiler is a complete implementation of the 'C' programming language as defined in The C Programming Language by Kernighan and Ritchie with extensions.

MCC68K emits highly optimized assembly language code for the Microtec ASM68K Motorola compatible assembler.

The Microtec MCC68K package includes the compiler, relocatable macro assembler, linking loader, run-time library, and comprehensive user's guide.

Host computers include: DEC VAX, DG MV-Series, Apollo, IBM PC and PC-compatibles..

We're **Functional** and **Fast** and **Serious** about our products. We've been providing flexible and economical solutions for software developers since 1974.

Beginning with product concept, through development, quality assurance, and post-sales support - **Quality**, **Compatibility** and **Service** are the differences which set Microtec Research apart from others.

If you're a serious software developer, shopping for software development tools, call or write today for more information:

800-551-5554,
In CA call (408) 733-2919.

3930 Freedom Circle, Suite 101, Santa Clara, CA 95054
Mailing Address: P.O. Box 60337, Sunnyvale, CA 94088

MICROTEC® RESEARCH

```
        mov     ah,2
        mov     bh,0                    ;assume video page 0
        int     10H                     ;set cursor position

        push    cs                      ;source is local screen storage
        pop     ds
        mov     si,offset scrn_buf

        mov     es,cgasscrn_seg         ;destination is video memory
        mov     di,0
        mov     cx,2000                 ;count of words on entire screen
      rep movsw

        pop     es
        pop     ds
        ret
restore_scrn endp

scrn_seg dw  ?                          ;used by save_scrn and restore_scrn
save_csr dw  ?
scrn_buf label   word                   ;local screen storage begins here

code_seg ends
        end     ce_test
```

LISTING 3: CE_CONIO.ASM

```
;=========================================================================
; General-purpose console I/O routines
;   For Break Handler (BRK_TEST) & Critical Error Handler (CE_TEST)
;=========================================================================

;-------------------------------------------------------------------
; GET_KEY
; Clears the keyboard buffer, waits for a key and returns it in AL.
; Returns -(key) for extended ASCII keystrokes
;-------------------------------------------------------------------
get_key  proc    near
        mov     ah,0cH          ;clear kb buffer
        mov     al,07H          ;console input function
        int     21H

        cmp     al,0            ;extended ASCII?
        jne     gk_exit

        mov     ah,07H          ;get the extended ASCII code
        int     21H
        neg     al
gk_exit: ret
get_key  endp

;-------------------------------------------------------------------
; DISP_MSG
; This function displays an ASCIIZ message at the current cursor pos
; DS:DX = address of start of the string
; Uses BIOS services only.
;-------------------------------------------------------------------
disp_msg proc    near
        mov     si,dx
dm_10:  lodsb
        cmp     al,0            ;done with the string?
        je      dm_20           ; yes, exit
        mov     bh,0            ; no, select video page 0
        mov     ah,0eH          ;      use write_tty service
        int     10H             ;      to display a character
        jmp     dm_10           ; loop back for next character
dm_20:
        ret
disp_msg endp

;-------------------------------------------------------------------
; BEEP
; sounds the bell by printing an ASCII 07H via BIOS write_tty service
;-------------------------------------------------------------------
beep    proc    near
        mov     al,07H
        mov     ah,0eH  ;BIOS write_tty service
        int     10H
        ret
beep    endp
```


The ultimate solution for information interchange . . .

The ultimate 9-track magnetic tape subsystem for the IBM-PC/XT/AT and compatibles!

"LEO" is a state-of-the-art PC tape controller that lends itself to the most sophisticated applications including real time data acquisition, multitasking and true streaming disk back-up. "LEO" comes standard with an impressive list of features that include a dedicated microprocessor, up to 64K of RAM for buffering, high speed thruput with memory mapping I/O—no DMA channel required, ASCII to EBCDIC code conversion and external cable connectors for easy installation.

Supplied on a 5 1/4" diskette is the most comprehensive set of software drivers and utilities available. Users have a choice between an installable I/O driver with modules to "Basic" and "C" languages, or an MT-DOS device driver, which allows direct tape access under any language supported by DOS 3.1. Also included is "ANSI," a sophisticated file transfer utility, "TAP" a comprehensive disk back-up and restore utility and "TCMD" tape command, a valuable tool for inspecting tape data and format. All utilities are menu driven with help screens for user friendly operation.

IDT manufactures the complete subsystem . . . controller and tape drive. With a commitment to excellence, IDT staffs a complete customer service department, offering you assistance to assure top performance at all times. Contact us today for additional information.

INNOVATIVE DATA TECHNOLOGY

5340 Eastgate Mall • San Diego, CA 92121
(619) 587-0555 • TWX: (910) 335-1610

Western Regional Office:
10061 Talbert Ave., Suite 202
Fountain Valley, CA 92078 • (714) 968-8082

Eastern Regional Office:
One Greentree Center, Suite 201
Marlton, NJ 08053
(609) 596-4538 • TWX: (710) 833-9888

CIRCLE NO. 108 ON READER SERVICE CARD

A CADD Workstation

Computervision's Personal Designer is an adaptation for the IBM PC of the company's minicomputer-based CADD system.

VICTOR E. WRIGHT

The rapid growth of microcomputer-based CAD has affected the traditional minicomputer workstation market more than other micro applications have upset their mainframe and minicomputer counterparts. Before the advent of microcomputer CAD, and for a long time after, CADD (computer-aided design and drafting) vendors enjoyed a comfortable market for their workstations. CADD was a high-profit industry, with room for new entrants.

Without a doubt, microcomputer CAD has affected the sales of the large systems. Some of those large vendors have witnessed dwindling profits; others have all but disappeared. Many large vendors are just beginning to realize the potential of the personal computer and the reality of the demand for microcomputer-based CADD systems.

Computervision is one such CADD powerhouse that has entered the microcomputer market: the Personal Designer package (a subset of its Computer Automated Design and Drafting System, or CADDS) is available through the firm's Personal Systems Business Unit division. CADDS, developed over a period of 15 years, has some 2,000 installations. Computervision targets both existing installations, and new users for sales of Personal Designer systems. Typically, Personal Designer is sold as a turnkey system, which includes the host PC/AT, Computervision's version of a Vermont Microsystem, Inc. 8820 graphics controller (compatible with an IBM Professional Graphics Controller), a monitor, a Kurta series 1 or 2 digitizer, and software. However, the software can be purchased separately. For this review, the Personal Designer elements were tested on a 6-MHz AT, and on a Heathkit H-248 (an 8-MHz AT compatible), using Computervision's Advanced Graphics Board (a VMI 8820 with custom firmware) and an NEC Multisync monitor as the graphics display system.

Personal Designer is a system of programs. The basic package is the microCADDS Geometric Construction and Detailing program—GCD. The basic program can be extended with a number of options. Surface modeling is provided with the addition of the Surfaces program, finite element modeling with the Personal Designer Finite Element Modeler package, finite element analysis with the MSC/pal 2 package. Macro extensions can be added with the User Programming Language (UPL) module, discussed later. Other similar systems available from Personal Systems Business Unit include Personal Machinist and Personal Architect.

This is a true three-dimensional production drafting system, with a full set of design extensions. Models are wire-frame models, but the program generates surfaces, if the Surfaces module is installed. The generated surfaces can be shaded to produce highlighted three-dimensional models of the quality associated with much larger systems.

The Personal Designer workstation can operate as a stand-alone unit, or it can be networked with a larger Computervision system for file exchange, or it can be connected directly to a Computervision host machine.

As configured on the distribution disks, the Personal Designer display consists of a graphics window, a com-

COMPUTER GRAPHIC • COMPUTERVISION

PHOTO 1: *Sample Screen with Menu*



A Personal Designer wire-frame model is displayed with one of the menus. The model consists of curves and surfaces.

PHOTO 2: *Alternative Screen Menu*



The dimensioning facility is not associative. As the part is altered, the dimensions are not updated automatically.

mand/prompt area across the top of the screen called the scrolling region, and a menu area on the right side (see photo 1). The program can be configured to add a coordinate display area that tracks the cursor and a message area along the bottom of the display.

The entire screen has a "graphics" look; that is, the hardware text font seen in the text windows of some CAD programs is not used here. The text used for command prompts and echoes is the same block font used when text is inserted in a drawing using the default font. Similarly, the screen menu consists of icons, rather than a list of commands. In fact, the screen menu is a drawing that can be edited.

The command area can be resized at any time, by dragging a window or by specifying the number of lines of text to be displayed. The command window can be sized to fill the screen or to display only a single line of text.

The menu can be turned off and on with the pointing device. The menu includes an icon for turning itself off. When the menu is off, a single icon appears in the scrolling region; selecting it turns the menu back on. The coordinate display is set to off by a flag in the configuration file. No command is provided to toggle it off and on.

Personal Designer is typical of CAD systems in that it operates in a loop. A command prompt, >>, is displayed in the scrolling region. The user enters a command that specifies what action is to occur, and where or how it is to occur. Commands to be entered can be typed in from the keyboard, selected from the screen menu, or selected from a digitizer overlay.

Most microcomputer-based CAD systems accept a command, then prompt the user for the parameters that are required to execute the command. A Personal Designer command is divided into two sections, the command section and the **getdata** section, separated by a delimiter, which is a colon(:). These two sections correspond to the commands and parameters of other systems, but are somewhat more complex. A command typically consists of a verb and a noun; optional modifiers can be used to select variations of a command, to control the display of the entity named, or to specify data that otherwise would have to be entered graphically. The **getdata** section consists of the prompts by the program, the graphic input, and optional references and masks. In addition, several **getdata** commands can be entered while another command is in progress. These **getdata** commands typically duplicate commands that can be entered directly at the command prompt, providing a method for nesting commands.

If commands are typed in from the keyboard, the complex syntax requires more typing than is necessary with some other systems. By the same token, the complex syntax allows the entry of more precise commands. The use of verbs, nouns, and references often provides several ways to construct or modify a given entity. (References correspond to object snap modes in other systems of this type, and are discussed later in the article.) Masks provide a means of restricting the type of entities to which a command is applied.

Entity masks are not used as commonly in micro CAD systems as object snap modes are. As implemented in Personal Designer, they allow the user to specify the types of entities to be included in or excluded from a selection group. For example, the user can move all of the text in an area without disturbing the surrounding lines, circles, arcs, and surfaces simply by including the TEXT mask in the **getdata** portion of a MOV ENT command, and then windowing the entire area. Entity masks can be inclusive or exclusive. Continuing with the example, everything but the text in the same area can be moved by including the XTEXT mask in the **getdata** portion of the command.

The entity masks are included to mask all entities, angular dimensions, arcs and circles, entities of specified colors, figures, labels, linear dimensions, lines, points, radial dimensions, line strings, text, and cross-hatching in the basic version. If the Surfaces module is included in the system, additional entity masks are provided for the various types of surfaces.

The icons in the screen menu and the digitizer menu invoke commands complete with verbs, nouns, delimiters, references, and in some cases, masks. The menus are more easily learned than is the complete command syntax, but to realize the full potential of the program, a user really must learn the syntax. (See photo 2 for an example of an alternative menu.) In many cases, the order in which command elements are entered is not critical—the user is learning concepts, not rigid sequences. Once learned, this command syntax provides a more concise method of specifying complex actions than a simpler syntax can offer.

THE DRAWING SPACE

Personal Designer's drawing world is on the order of 7.0 by 10^8 units along each of the three axes. This generous size drawing world certainly will be adequate for most drafting assignments. This limit is imposed intentionally to prevent problems associated with attempting to process zoom commands with out-of-range parameters. The limit was chosen to accommodate the type of design for which the program is used. (The author of the program is an aircraft designer.) The Personal Designer's drawing world is truly three dimensional. Any entity can be positioned arbitrarily within the drawing space.

The screen is a window into the system's drawing world (see figure 1). This window initially is positioned so that the *X* and *Y* axes are in the plane of the screen, and the *Z* axis is normal to the screen. Entities entered graphically are placed in the *X–Y* plane, with an elevation of 0. Entities can be entered at other locations by specifying the three coordinates on the command line instead of entering them graphically, or by repositioning the coordinate system relative to the screen.

Changing the current view repositions the coordinate system. Six predefined views are available, which are numbered 1 through 6, and correspond to the top, front, right, bottom, left, and rear views of traditional orthographic drawings. Changing the view does not alter the current elevation, only the orientation of the coordinate system. The current elevation can be changed using the SELECT DEPTH command, which determines the distance of the current viewing plane from the origin of the coordinate system. The depth that is set with the SELECT command applies to all views, but both positive and negative depths can be set. Thus, two opposite faces of a cube centered on the origin can be drawn in the same view by selecting a positive and then a negative depth, or by selecting a positive or a negative depth, and then selecting two opposite views in turn.

With the use of references, entities can be entered with little attention to the current depth. For example, a line can be drawn between the ends of two other lines by using the END reference, regardless of view or current depth.

When attaching new entities to entities that were constructed in the orthographic views, it is often advisable to work in an inclined view, to insure that the correct entity or reference is selected. In the orthographic views, one entity is likely to be masked by another.

FIGURE 1: *Personal Designer Drawing World*



The Personal Designer drawing world is a true three-dimensional space. As many as 256 different layers can be specified; these can be views or construction planes.

As many as 32,000 views can be defined, including the six predefined views that were listed above. Defining a new view is interactive; the model space is rotated about the three axes until the view is suitable, and then a view number is assigned. After that the view can be recalled by number.

A second method of defining views is useful when a model has been partially constructed. A view can be defined by selecting three entity references, such as the ends of the edges of a surface that is inclined in the current view. Personal Designer then rotates the drawing space so that the selected plane is parallel to the screen. Defining a view in this manner leaves the current elevation unchanged; the plane that is used to define the view may or may not lie at the current elevation.

The user can define a construction plane, which provides a local coordinate system. A construction plane, called CPLANE by Computervision, is defined by digitizing entity references, such as intersections, origins, and ends. The first point selected is the construction plane's origin; the second defines the *X* axis; and the third defines the *Y* axis. A construction plane has an associated view, although not every view need have an associated construction plane. Up to 32,000 construction planes can be defined, but the numbers assigned are in the same series as the views. The allowed views include those associated with construction planes.

Once defined, a construction plane can be activated with the SELECT command, and geometry can be entered directly on the plane, regardless of the current elevation. A construction plane can be activated without restoring the associated view, which can lead to unexpected results while learning to use the system. If a plane is activated, and the user wishes to draw in a true view, the associated view should be restored as well. However, the ability to activate a construction plane without restoring the associated view allows the user to place geometry on an inclined plane while referring to another plane in true view. This facility proves to be an extremely useful one. Because Personal Designer models are wire-frame models, it is easy to become disoriented and construction planes help ensure that geometry is placed as intended.

In Computervision terminology, a graphic entity is anything that can be inserted into a drawing. The most fundamental entities are simple entities—lines, circles, arcs, and points. A string is a compound entity, consisting of several simple entities that are connected end to end. As far as the user is con-

DAN BRICKLIN'S DEMO PROGRAM

Read what they're saying about this new concept in prototyping and demo-making:

"A winner right out of the starting gate. After you use DEMO once, you'll wonder how you got along without it."
— PC Magazine, 4/29/86

"Everybody who writes software, either commercially or for in-house applications, should immediately order a copy. Period. No exceptions."
— Soft•letter, 4/20/86

"Its low price, superb performance, and range of applications practically guarantee that it will be widely used. Four Floppy Rating (8.0)"
— InfoWorld, 3/31/86

"Apparently has a hit on its hands with . . . a development tool for personal computer software that has won rave reviews from early users."
— Computerworld, 4/7/86

"A gem."
— PC Week, 3/18/86

Product of the Month
— PC Tech Journal, 3/86

ORDER NOW!

Thousands of developers are designing better products faster and producing more effective demonstrations using Dan Bricklin's Demo Program. You can, too. Act now!

MasterCard VISA **ONLY $74.95**
617-332-2240

Massachusetts residents add $3.75. Outside of the U.S.A. add $15.00.

Requires 256k IBM PC/compatible, DOS 2.0 or later. Supports Monochrome, Color/graphics, and EGA Adaptors (text mode only).



SOFTWARE GARDEN

Dept. T-2
P.O. Box 373, Newton Highlands, MA 02161

CIRCLE NO. 142 ON READER SERVICE CARD

cerned, however, a compound entity is still a single graphic entity.

Text, or lettering, is a graphics entity. Two text fonts are included with the system, but instructions for creating and compiling additional fonts are included in the manuals. Dimensions are also graphic entities. The system calculates dimensions and inserts them as entities, but they are not associative dimensions in the current version. If a dimensioned line is trimmed, or stretched, the dimension is not changed automatically. Dimensions can be exploded or inserted as components if desired.

The Surfaces package adds three additional entities for surface modeling: C-poles, S-poles, and planes. C-poles define the edges of complex or simple surfaces, while S-poles are the actual surface entities. Planes are not actually drawing entities, but construction aids.

A C-pole is a form of curve; curves also include lines, circles, and arcs, but not strings. In other packages, C-poles are called Bezier curves, after P. Bezier who developed this method of representing curves. A C-pole is defined graphically by the position of control points called poles, which also form the vertices of the controlling polygon. The position of each pole is represented in the drawing database as a coefficient in a polynomial equation, but C-poles are entered graphically by picking the locations of the control points. The program displays the controlling polygon as the C-pole is entered. The controlling polygon usually disappears after the next screen repaint, but it can be redisplayed if desired.

Personal Designer's one surface entity, an S-pole, is similar to a C-pole, in that its shape is controlled by poles and a controlling polygon. The S-Pole can be created by digitizing the poles directly; it also can be created by digitizing four curves bounding a region. An S-pole can be flat, curved in one direction only, or arbitrarily curved.

In Computervision terminology, a drawing is a part. One part can be inserted into another part; that is, a drawing can be inserted into another drawing. A part can be inserted either as a part or as a figure. These two terms correspond to block or symbol definitions and block or symbol references. These features allow the user to create a comprehensive symbol library.

DRAWING AIDS

Personal Designer provides most of the expected drawing aids, a few not commonly found in microcomputer systems and a few with obvious weaknesses.

The coordinate display tracks the cursor location and is one of Personal Designer's weaker features. The first drawback is that the coordinate display must be enabled or disabled by changing a flag in the configuration file.

The second is that the coordinate display reflects the actual location of the cursor, regardless of whether or not the program is set to snap to a grid. The grid, a grid of dots, indicates the locations to which picks will snap. A separate command to set an invisible snap grid is not available.

The grid can be turned on and off with a command verb, noun, and modifier, or with a **getdata** command. In other words, it can be disabled and enabled within other commands by typing the **getdata** commands, GOFF and GON. Turning the grid off does not remove it from the screen, so its presence does not indicate whether or not the next pick will snap to the grid. A screen repaint must be executed to remove the grid once it is turned off.

An undesirable feature of Personal Designer is that the grid does not rotate with the coordinate system. If the view is changed to an isometric view, the grid does not become an isometric grid. It remains a rectangular grid, and does not line up with the model.

When the grid is on, it is displayed, regardless of the current zoom ratio. To avoid obscuring the drawing with a too-closely spaced grid, the program scales the grid when the zoom ratio is too high. Each time the screen is repainted, the scaling factor is displayed, if it is greater than 1, with an annoying beep. Iterating toward a new view is a noisy process if the grid is on. The grid can be easily repositioned and it can be set to arbitrary aspect ratios.

Instead of an ORTHO mode that can be turned on and off, Personal Designer provides VER and HOR **getdata** commands. Both the screen and digitizer menus provide icons for vertical and horizontal lines; the icons include VER and HOR modifiers in the command, before the delimiter.

In fact, the command format is a drawing aid. The **command : getdata** format allows commands to be tailored to the task at hand (see figure 2). The ability to enter **getdata** commands allows commands to be nested, in effect. The active command can be repeated by signalling the program to restart the **getdata** portion of the command without terminating and reentering the command portion.

The manual describes the use of construction lines in the context of

Is Your Modem Holding You Up?

Face it, if your modem is too slow you're spending too much time waiting and too much money on telephone charges. If your modem is faster than you need, you bought too much modem.

In either case, you're being held up!



AST Offers A Variety Of Hayes™-Compatible Modems With Speeds From 1200 to 19,200 bps. Select an AST modem whose speed matches the way you work. You'll save on the price of the modem and you'll save on your phone bill every month.

The cost of sending 200 pages (approximately 360 kb or 1 floppy diskette) over telephone lines at $20/hour. Imagine the savings over a year!



Don't Buy More Modem Than You Need. If you only use a modem for interactive services, like OAG and CompuServe, a 1200 bps modem is fine. The AST-1200™ is for you. It's a reliable, low-cost, full-featured modem.

But, if you use a modem to transfer files, in addition to using interactive services, you want more speed. File transfers take time. And the more data you transfer the faster your modem should be.

Time Is Money. Especially when you're using telephone lines. And there comes a point when the added cost of a faster modem is less than the added cost on your monthly phone bill.

How Much Modem Should You Buy? It depends on your needs. The AST-2400™ is a good choice for occasional file transfers. And it's price competitive with many popular 1200 bps modems.

Fast, Faster... Fastest. If you regularly transfer files you need an even faster modem.

And for downloading software, transferring graphics files or sending financial transactions, insurance claims or electronic orders; you need guaranteed error-free throughput.

You need the AST-2X2400™ or the AST-2X9600™

The AST-2X2400 is a 2400 bps modem that achieves throughput speeds of up to 4800 bps with advanced data compression techniques. While the AST-2X9600 sizzles with speed at a throughput level of 19,200 bps with data compression. And each employs error correction, ensuring data integrity over dial-up, as well as leased lines.

Internal PC Modems. *AST modems are also available as PC boards.*



Get AST's FREE Modem Selection Guide. Just send the coupon to AST Research, Inc., 2121 Alton Ave., Irvine, CA 92714-4992. Or call **(714) 863-1480.**

Yes, Send Me AST's FREE Modem Selection Guide, Today!

Name_____

Title_____

Company_____

Address_____

City/State/Zip_____

Telephone_____

PCTJ 4/87 01PCTE086A02MD

AST products are marketed worldwide—in Europe call: 44 1 568 4350; in the Far East call: 852 0499 9113; in Canada call: 416 826 7514. AST registered and AST-1200, AST-2400, AST-2X2400 and AST-2X9600 trademarks of AST Research, Inc. Hayes trademark of Hayes Microcomputer Products,

AST® RESEARCH INC.

Copyright © 1987 AST Research, Inc. All rights reserved.

BASIC Programmers

Memory—Resident BASIC

Stay-Res lets you pop up compiled BASIC programs. Select your hot key or pop them up with a POKE. Automatic screen save/restore. Add our EMS/disk module (for DOS 3 +) and programs use only 7K of DOS memory - the rest is stored in Expanded Memory or disk. Stay-Res includes a true SHELL facility allowing you to SHELL ANY PROGRAM, even other BASIC programs, before or instead of becoming memory-resident. Requires IBM or Microsoft compiler (QB2 needs DOS 3+). Only $95. Add $50 for EMS/disk module.

MACH 2 Turbocharges BASIC

Use our assembler subroutines to boost program speed many times. Instant screen displays and pop-up windows when compiled. No 64K limit - use all avail. DOS memory for strings/numbers. Store, search, sort strings at assembler speed. Controlled input routine uses standard edit keys & ignores^C &^Brk. Print using for numbers up to 6 times faster than BASIC. Read & write files fast as DOS. Much, much more. Assembler source code available. Only $75.

Know Thy PC

With Peeks 'n Pokes you can read & change system configuration from your program. Read CMOS chip on AT. Unprotect IBM/GW-BASIC pgms saved with "p" option. Plug characters into k'board buffer. Read/change k'board status. Read printer status - no more timeouts. Use 4 printers as LPT1. Swap printers, monitors, COM ports. Read monitor/COM status. Boot system 3 ways from BASIC. Disable^C &^Brk. Find more Peeks & Pokes. Much, much more. All BASIC & most assembler source code included. Only $45.

Indispensable Utilities

The Inside Track lets you load and execute large EXE files faster than DOS. DOS/BIOS calls & interrupts from BASIC. Limit memory used by compiled programs to eliminate Command.com reload. Copy protect a diskette. Boot system 3 ways from DOS. Memory map +summary of most common BIOS calls, including EGA. Control k'board state - force Caps Lock, Num Lock - disable ^C,^Brk and Ctrl-Alt-Del. Program tips. Much, much more. All source code included. Only $65.

Money-Back Guarantee

Call for details on 30-day money-back performance guarantee. Our software is not copy protected. No royalties when you use our subroutines in compiled programs. Compatible with IBM/GW-BASIC, QuickBASIC 1 & 2, BASCOM 1 & 2, MS 5.36. System Requirements:

- IBM PC, XT, AT or compatible
- DOS 2+ (Stay-Res EMS/disk requires 3+).
- Stay-Res with QuickBASIC 2 needs DOS 3+.

Order Now 800-922-3383

We welcome VISA/MC. COD in US only - add $3. Shipping: US $3/order. Canada - $5 for 1 or 2 pkgs. Add $2 each addt'l. Elsewhere - $18 for 1 or 2 pkgs. Add $7 each addt'l. In Georgia add tax and call 404-973-9272. Stay-Res/Mach 2 demo available - send $5 check. Refunded on direct purchase.

MicroHelp, Inc.
2220 Carlyle Drive
Marietta GA 30062

CIRCLE NO. 257 ON READER SERVICE CARD

FIGURE 2: *Diagram of Command Structure*



The syntax consists of a command section and a getdata section, separated by a colon. A command typically consists of a verb and a noun, with optional modifiers.

drawing aids. Personal Designer, however, does not provide a distinct entity type for construction lines. Instead, the manual advises the user to set up a layer for construction lines and then to use a different line font.

Personal Designer includes the expected display controls for changing the scale of the display, panning the display, and controlling the visibility of groups of entities. The ZOOM command allows the display to be enlarged or reduced, relative to the current display or to the original drawing display. A command modifier fills the screen with the current drawing extents, and another modifier allows specification of the display with a zoom window. The previous display cannot be recalled, but the modifiers UP and DOWN allow enlarging and reducing the display by the same factor: ZOOM UP 2 and ZOOM DOWN 2 produce complementary effects.

All of the commands can be nested in other ones by entering their corresponding **getdata** commands; for example, ZWIN executes a zoom window and ZALL executes zoom all. The operation of **getdata** zoom commands is unnerving at first; if the end of a line is picked while zoomed in, and ZALL is entered, the rubberband cursor does not remain attached to the original pick. However, the line appears correctly when the second point is picked.

The drawing is panned (or scrolled in Computervision terminology) using the SCROLL command. The viewing window can be moved a half-screen at a time with the modifiers, DOWN, LEFT, RIGHT, and UP, or the pointing device can be used to digitize a new view center or a scroll vector.

Personal Designer provides 256 numbered layers for visibility control. English names or aliases are not supported, so that a standard layering scheme is advisable, as pointed out in the manual. Layers are controlled using the ECHO command, which turns layers on and off, and displays which layers contain entities. A new active, or current, layer is designated using the SELECT command verb.

Colors and line fonts are not tied to layers. Any entity can be assigned a color and line font independently of the layer to which it is assigned.

The ability to display three-dimensional drawings in perspective views is missing from most micro CAD systems. Personal Designer can create a perspective view of a model in any defined view. The program produces a reasonable perspective automatically, yet allows the user to control the perspective view parameters if desired.

The perspective feature can produce some surprising results, but they are usually due to losing track of the orientation of the model in the current view, which is easy to do with wireframe models. However, when properly used, the perspective feature produces pleasing perspective views as quickly as the screen is repainted.

THE CREATIVE PROCESS

Drawings and models are created by inserting entities, which are named with the noun in the command; for example, the sequence **INS LIN:getdata** inserts a line, or a series of line segments. Modifiers then can be entered following the noun to specify the entity more precisely; the sequence **INS LIN VER:getdata** inserts a vertical line (vertical in the current view, not necessarily in the model space). Figure 2 gives an example of the command structure.

What to use with PCs that don't use our new VEGA Deluxe™ EGA card.



Pretty soon, this might become standard computer equipment. Unless, of course, our VEGA Deluxe card does first.

And that's a distinct possibility. After all, this short-card video adapter offers 37% higher screen resolution than standard EGA cards.

Visualize it: your existing software sharper and clearer by more than a third. Programs like Lotus 1-2-3 and Symphony, with 132 columns and 43 lines. Microsoft Windows in 640 x 480, too. And AutoCAD. As well as EASYCAD, EGA Paint, GEM, Dr. Halo II, In·A·Vision, Windows Draw, Windows Graph, and much more.

In fact, with all this information on the screen, there's only one thing there's less of. Strain on your eyes.

That's because the VEGA Deluxe gives you both 640 x 480 *and* 752 x 410 resolution. (Of course, for more than 640 x 350, the VEGA Deluxe requires a Multisync® or equivalent.)



The VEGA Deluxe is also compatible with every other video standard: EGA, CGA, Hercules and MDA. And when used with a compatible monitor, it automatically selects which mode is right for your software's needs.

At Video Seven, we've sold over 200,000 EGA cards to people who've seen the difference. If you'd like to see the difference for yourself, just call 1-800-238-0101 for the name of the Video Seven dealer nearest you. (In California, call 1-800-962-5700.)

The VEGA Deluxe. It puts everything in proper focus.

Video Seven Inc., 46335 Landing Parkway, Fremont, CA 94538.

VIDEO SEVEN

We make a clear difference.

High resolution modes require TTL color monitors capable of 25 KHZ and 29.4 KHZ. Trademarks: VEGA Deluxe—Video Seven Inc., Hercules—Hercules Computer Technology, MultiSync—NEC Home Electronics (USA) Inc., EASYCAD—Evolution Computing, EGA Paint—Rix SoftWorks Inc., GEM—Digital Research Corp., Dr. Halo—Media Cybernetics, In·A·Vision, Windows Draw, Windows Graph—Micrografx Inc.; Registered trademarks: Video Seven—Video Seven Inc., Lotus 1-2-3, Symphony—Lotus Development Corp., Microsoft—Microsoft Corp. Video Seven reserves the right to change specifications without notice.

CIRCLE NO. 204 ON READER SERVICE CARD

A series of similar entities can be inserted by repeating only the **getdata** section of the command. This is accomplished by entering a colon, an optional modifier, and another colon.

It should be noted that, although Personal Designer is a full three-dimensional system, no three-dimensional primitive objects are available. The set of entities created with the INSERT command does not include cubes and spheres. Three-dimensional models are created with curves (including lines) and/or surfaces. Although it would be a waste of the program, Personal Designer can be used strictly as a two-dimensional drafting package.

Creating a three-dimensional model from two-dimensional primitives requires a fair amount of navigation of the drawing space, by changing views, the current elevation, and the current construction plane. Personal Designer provides only minimal information on the screen, aside from the model itself. The coordinate display is available, and the construction plane coordinate system axes can be echoed if desired. Additional information is available from the system via the LIST command, however, the designer must learn to keep track of the orientation of the model views in the drawing space.

The references points available when drawing (see figure 3) correspond to object snap modes of other systems. Personal Designer's references include chains of entities connected end to end, temporary origins, digitized points, ends of entities, groups of entities, intersections of entities, apparent intersections, the last coordinate entered, index pointers, the axes of the model, origins of entities (centers and midpoints), points, the axes of the screen coordinate system, and windows.

Construction lines are also essential to the creation of complex models. Although a model can be constructed simply by entering coordinate data from the keyboard, this requires that a substantial amount of work be done before sitting down at the terminal. It is easier to rough out an object with construction lines, then use the construction line references for the creation of the model. Often it is easier to insert an entity into an easily established location, and then move it, than to create it in the desired location.

Many model components can be created by first drawing a cross section, then projecting the cross section along an axis, using the PROJ command. One or more entities are selected, then the axis of projection is entered. The axis can be entered by typing the coordinates in at the keyboard, by picking two points graphically, or by picking references in the existing geometry.

Personal Designer also includes a complete selection of editing commands. Entities can be deleted, moved, trimmed, stretched, mirrored, and rotated. A CHANGE verb is provided to change colors, fonts, text attributes, string attributes, and entity groups.

If symbol libraries are considered *useful* in two-dimensional drafting programs, they are *essential* to Personal Designer. Creating three-dimensional models is much more complicated and time-consuming than creating two-dimensional drawings. Thus, it is necessary to maintain libraries of parts for use in assembly drawings.

A part is created with the use of the CONSTRUCT command verb, which requests a filing name, selection of the component entities, and an origin. Parts are automatically written to disk files, and the original components are not erased from the drawing.

Inserting a part into a Personal Designer model is accomplished using the INSERT command verb. This operation can be as simple as in a typical two-dimensional part or considerably more involved. If the correct view and elevation is selected before the part is inserted, and the scale of the part is correct, it may be sufficient to specify the insertion point. If not, Personal Designer permits the user to specify the orientation of the part: the view of the part being inserted and the view of the model into which it is inserted, the angle of the inserted part's *X* axis to the *X* axis of the current view or construction plane, a new *X* axis for the inserted part, layering specifications, grouping specifications, and scale along each of the three axes, *X*, *Y*, and *Z*.

Parts can be inserted as parts or as figures. If a part is inserted as a part, its elements can be edited; once inserted, the part is no longer a single entity.

If inserted as a figure, a part remains a single entity and cannot be edited. An additional feature is that figures are updated in all drawings when the original is modified. If a part is inserted as a figure, it can still be reduced to simpler components, which can then be edited. The EXPLODE command works on figures, strings, arcs, crosshatching, and dimensions.

FITTING IN THE DETAIL

Detailing is the process of turning the design drawing or model into a document that others can use. Many design-

DOUBLE
YOUR STORAGE CAPACITY

The new PERSTOR 200 Series Double Capacity Controllers increase the storage capacity of your ST506/412 Winchester hard disks by 90% or more. Advanced RLL encoding technology is used to increase data transfer rate to 9 and 10 megabits per second, and a 56 bit error correction code is used to assure data integrity. What's more, it works with both RLL and MFM drives with plated or oxide media.*

To place an order or become a dealer call (602) 948-7313.

PERSTOR

Sensible solutions for your hard disk problems.

Systems and Software, Inc.
7825 East Redfield Road
Scottsdale, Arizona 85260

*call for specific drives.

CIRCLE NO. 231 ON READER SERVICE CARD

KNOWLEDGEMAN/2 LETS YOU GET TODAY'S WORK DONE AND PLAN FOR TOMORROW.

KnowledgeMan/2,® the most advanced business software available, lets you be more productive than ever before and in less time.

These powerful business capabilities, tightly fused into a single program, work together for you:

☐ Relational data management ☐ Spur-of-the-moment inquiry ☐ Spreadsheets ☐ Statistical analysis ☐ Forms management ☐ Programming language

☐ Options for creating graphs, processing text, generating reports, painting forms, mouse processing and remote communications.

KnowledgeMan/2's four user interfaces make it easy for you…and all your business people…to work with KnowledgeMan/2:

☐ Menus, help screens and easy-to-use documentation guide your every step, if you're just beginning.

☐ Direct commands for the power user, with help available when you want it.

☐ K-Chat, the optional natural language interface, for asking for information in plain English.

☐ Procedural programming for the advanced user.

Get KnowledgeMan/2 working for you today. And start planning for tomorrow.

KnowledgeMan/2 is available for the IBM PC, PC/XT, PC/AT and compatibles. Multi-user versions are offered for the DEC VAX system and 3Com, Novell and IBM PC local area networks.

Your local **mdbs** sales representative can provide additional information. For the location of the sales office nearest you, call or write **mdbs.**

mdbs and KnowledgeMan/2 are registered trademarks and K-Chat a trademark of **mdbs**, Inc. "VAX" is a registered trademark of Digital Equipment; "PC/XT" and "PC/AT" of IBM Corp.; 3Com of 3Com Corp.; Novell of Novell, Inc.

KNOWLEDGE man/2®
THE UNIVERSAL KNOWLEDGE MANAGEMENT SYSTEM

mdbs/Marketing and Sales · P.O. Box 248 · Lafayette, IN 47902 · 800/344-5832 · 317/463-2581 (Indiana, Canada)

mdbs®

CIRCLE NO. 211 ON READER SERVICE CARD

FIGURE 3: *Sample References*



References correspond to object snap modes. An apparent intersection moves depending on the current angle of view; the actual intersection remains constant.

ers feel that the design work is done when the first sketch is complete, and, indeed, many engineering departments rely upon detailers to turn the sketch into working drawings.

Personal Designer provides an excellent automatic dimensioning facility to handle detailing. The program requests the two entities or references that will be dimensioned, and the location of the dimension line. It then calculates the dimension value and inserts a dimension entity, which includes the dimension text, the witness lines, the dimension line, and the arrowheads. As with the other commands, modifiers are used to specify the appearance of dimensions. The user has control over the alignment of the dimension line; text angle, height, and width; size and orientation of arrowheads; precision of dimension values; display of witness lines; and visibility of dimensions. Similar control is available over both linear, angular, radial, and point (*X*, *Y*, *Z* coordinate) dimensions.

By default, dimensions are displayed only in the view in which they are inserted. Modifiers are provided to toggle this feature. Visibility is tied to individual dimensions. Thus, some dimensions can be displayed in all views and others in specific views as desired.

Soft*Rite ⟩⟩ LANbasic!

Soft*Rite announces a *Superior* three-part programmer's tool. MicroSoft BASIC™ compatible in every place that counts. *

LANscreen	LANbasic	LANdbase
LANscreen makes the burden of defining your database record structures one that you will look forward to instead of dread. Standard fields and types such as "Money", "Telephone" and "Date" are one keystroke to generate. As many as 255 database structures can be related to a single screen! Segmented data input can be done automatically by editing the field display. Part numbers with spaces or dashes and slashes are automatically parsed down to the essential raw data. Definable Upper and Lower limits for numeric inputs along with ACCEPT/EXCEPT input filters are standard features. Screen Mask generation is done with a "freestroke" approach. You may put mask elements and data input/output cells wherever you wish. COLOR them too! EGA support too! *Drivers Installed for IBM PC-NET/MS-NET	LANbasic is your own personal solution to powerfull data manipulation. How many times have you got excited over some new "total" database package only to find out (after spending a fair amount of time and money) that you were stuck in some corner, unable to do some function that has become standard in "**I**n **B**usiness for **M**oney's" Basic? The manual is 400 pages long, so we cannot fully describe all the features, but here are a few in ADDITION to the ones you are now used to: ★ COMDATA$ 14 common areas ALWAYS available to inside or outside, chained or linked programs ★ Re-assignable printer ports LPT1 -LPT4 ★ Generic filename use that allows file and database locations to be redefined outside of basic in a user-created REDIRECTOR file, to ease multi-user system configuation ★ USESCREEN,<1-16> ★ SCREENINPUT,<anyfield> ★ SCREENOUTPUT,<anyfield> ★ OPENDB,<remote or local database manager> ★ DBGET,<variable from DBM, automatically defines and dimensions in LAN basic> ★ DBPUT,<same>	LANdbase is the home for your data. LANbasic calls are coupled to LANdbase via network comunications (PCnet or ?). A single keyvalue and function number will return a record. Multiuser record locking is handled by simply putting an 'X' after the read call. (i.e. RDDBEQUX,<argument>. Automatic "health checking" to warn you of poor hardware performance and lost or fragmented data. "Paranoid" mode of operation where files not accessed for some time will be closed and reopened to flush buffers and insure integrity. Password, Userlevel and Data encryption functions. Several DBM's can be installed in the network system to improve performance and reliability. Toggle mode screen (printer) reporting to record log-on or other access activites. Bill Fairman's tried and proven true C-Tree(c) data management product.

Soft*Rite Multi-User Programming Tools
15381 Chemical Lane, Huntington Beach, CA. 92649
(714) 898-0525

CIRCLE NO. 186 ON READER SERVICE CARD

PC Magazine Puts It All Together For You!

Yes! Send me PC Magazine for:

☐ One year (22 issues) for $27.97. SAVE 57%!
☐ Two years (44 issues) for $49.97. SAVE 62%!
Savings based on annual single-copy price of $64.90

PC Magazine
P.O. Box 2443
Boulder, Colorado 80321

Mr./Mrs./Ms. _____
please print all information 8HU35

Company _____

Address _____

City _____ State _____ Zip _____

Please add $22 per year in Canada and all other foreign countries, U.S. currency only. Basic annual subscription price is $64.90. Please allow up to 60 days for delivery of first issue.

NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY MAIL

FIRST CLASS PERMIT NO. 66 BOULDER, COLORADO

POSTAGE WILL BE PAID BY ADDRESSEE

PC MAGAZINE

P.O. BOX 2443
BOULDER, COLORADO 80321

NO ONE PUTS IT ALL TOGETHER LIKE PC MAGAZINE

At PC Magazine, we know how tough it is for you to sort out product claims, specifications and performance questions. It's not easy finding out what's new, better, faster, quieter, cheaper, more compatible or more expandable.

That's why we're here. And why your subscription to PC Magazine is the best way to stay on top of it all. Twenty-two times a year, our editors and columnists keep you fully informed about what you can expect from PC products—and which are best for the business tasks you have to accomplish. And every time you need help solving applications problems, we're there to back you up.

The most experienced and sought-after editorial staff in the industry. Their credentials, plus the results of rigorous product testing that takes place in PC Labs—the only independent state-of-the-art testing facility in computer publishing—are your assurance that PC Magazine gives you all the facts.

Issue after issue is devoted to helping you buy PC products for your business with confidence and to making sure that maximum benefits are derived from that investment.

Whether you need to link your micro to a mainframe, evaluate graphics packages or upgrade your printers, we're here to help you do it all.

Subscribe today. Save up to 62% off the annual single-copy price of PC Magazine during our special introductory offer!

One year (22 issues) only $27.97 — Save 57%
Two years (44 issues) only $49.97 — Save 62%

Savings based on annual single-copy price of $64.90. For fast service call 1-800-852-5200 Toll Free.

8ZG14

Personal Designer's cross-hatching feature is simplistic. Cross-hatching patterns consist of parallel lines; the user can specify the line spacing and the angle. Unlike most CAD packages, cross-hatching can be inserted in areas bounded by entities that do not meet precisely; a tolerance for the gap can be specified in the command. Hatching is visible in all views, a feature that can be used to aid in maintaining orientation. The ability to cross-hatch in areas that are not completely bounded is convenient, but the lack of variation in cross-hatching is especially limiting for mechanical designers and is a design restriction that should not be present in a package of this complexity.

The text handling available in Personal Designer is as powerful as cross-hatching is weak. Several commands are devoted to text. Labels are text entities with leaders. The text entry can consist of as many as 1,000 characters, and it can contain embedded control characters. The angle, height, width, and line spacing of the text can be specified. The leader of a label must begin on an entity, as the label is attached to the entity. However, the entity can be deleted without deleting the attached labels.

Notes or other text that are not attached to specific entities are entered as TEXT. Using control characters, text strings can be split into lines, displayed in an alternate font, boxed, changed in height, superscripted, and subscripted.

For standard notes, specifications on drawings, or simply convenience, the INS TFILE command is an invaluable tool. This command reads into the drawing a text file that has been created with a text editor or word processor in a nondocument mode. Each line in the disk file is inserted as a single text string, as would be entered otherwise with the INSERT TEXT command. Therefore, each line in the file becomes a separate entity in the drawing.

The INS TFILE command does not allow the use of modifiers as does the INSERT TEXT command. Instead, the SELECT TEXT command must be used to predetermine the text characteristics, if they are to differ from the defaults. SELECT TEXT can also be used to define text characteristics before using INSERT TEXT. All text characteristics and the text itself can be edited using the CHANGE TEXT command.

The property feature provides the user with a mechanism for producing documents such as bills of materials from drawings, more or less automatically, and for producing schedules on drawings. Properties (nongraphic attributes) can be attached to entities, both figures and primitives.

Properties are not defined as part of the entity definition, as are attributes in some systems, but they are attached to entities on an individual basis. Since properties can be attached to primitives, one-of-a-kind objects can be placed in a bill of materials without having to first turn them into symbols.

A property has a name and a value. The value can be text or numeric with text as the default. A single invocation of the INS PROP command inserts one name value pair, one or more times. An arbitrary number of properties can be attached to an entity.

An external utility, EXTRACT, extracts properties from a drawing file. This utility scans the drawing database and creates a text file with entry for each property extracted. If the property value contains more than one line, the entry in the text file will contain a corresponding number of lines.

The property feature is intended for use with a text editor or database management program. However, if a property value contains more than one field in terms of content, it is still treated as a single field by the EXTRACT utility. Using a text editor to transform the extract file into a document is a relatively straightforward procedure. Importing the same file into a database management system will require more effort, unless each name value pair contains only a single field.

SURFACE MODELING

As mentioned previously, the Surfaces module is an optional addition to the GCD package that includes both entities and commands. GCD supports the creation of wire-frame models; the drawing database contains entities that represent the edges of surfaces. In GCD, no information about the surfaces themselves is recorded if only the basic features are used. Thus, wire frame models are inherently transparent.

The Surfaces package thus adds the capability of recording information about the surfaces themselves. With this program option installed, a Personal Designer drawing database can contain information about the boundaries of a surface and the shape of the surface between those boundaries.

Surfaces adds only a single surface entity, the S-pole; however, it adds a number of commands for the creation and manipulation of S-poles. Two basic methods of creating surfaces are provided—inserting and smoothing. To INSERT a surface requires direct input

dBASE Power without dPAIN

Why is dBASE so popular? The answer is simple. Power. The power to manage your data, users, and applications the way you want. But power has a price. To fully harness dBASE you must learn the programming language. dBASE users call this "Climbing the Wall."



If you're up against the Wall, take the express route, via an Adam Green dBASE Seminar.

FREE BOOKLET

dBASE PERFORMANCE GUIDE Spring '87

A detailed comparison of: dBASE III, dBASE III PLUS, CLIPPER, QUICKSILVER, and FOXBASE+. Call or write for your FREE copy today.

FOUR INTENSIVE dBASE SEMINARS

Call or write now for a FREE brochure.

Day 1 - dBASE Without Programming
Day 2 - Introduction to Programming
Day 3 - Advanced Programming
Day 4 - dBASE Compatible Languages

TAUGHT BY ADAM GREEN

A day with adam Green is like a month with dBASE.

Join the noted author and columnist in his seventh year of dBASE seminars.

COMING TO A CITY NEAR YOU

Washington May 4-7	**Los Angeles** May 18-21	**Boston** June 8-11
Toronto June 22-25	**New York** July 13-16	**San Francisco** August 17-20

Digital Consulting, Inc.
8 Windsor St.
Andover, MA 01810
(617) 470-3880

REGISTER NOW! ENROLLMENT LIMITED

A37PJ

CIRCLE NO. 154 ON READER SERVICE CARD

of the controlling polygon; to SMOOTH a surface means that the system infers the controlling polygon from existing contiguous boundary curves.

Several methods are available for generating surfaces. Using a circle as an example, a sphere can be generated by rotating the circle around an axis. Alternatively, a cylinder can be generated by projecting the circle along a vector. Drawing straight lines between corresponding points of two curves is yet another way to generate a surface.

The general surface is bounded by curves on four sides and is curved in both directions. It can be created directly or inferred from existing curves. Although the shape of single surface patches is limited, an arbitrary number of them can be connected to create arbitrarily complex surfaces.

Surface models can be created without first creating a wire-frame model—but it requires a great deal of planning and thought. Most designers are well-advised to build a wire-frame model and then add the skin. A workable approach for most models is to create a wire-frame model, add C-poles for contour lines, smooth or insert S-poles between the C-poles, and finally tune the surfaces by repositioning the poles of the surfaces.

Although the basic GCD package does not include construction lines explicitly, Surfaces includes a useful construction tool—planes. Planes are infinite flat surfaces in the drawing database. They are displayed as small squares and should be placed on special layers, because they are not really intended for display in a final drawing.

Planes are used to control the construction of other entities. A plane can terminate the projection of a tabulated cylinder or construct a tabulated cylinder between two planes. Similarly, planes can trim curves or establish the plane of a fillet between two nonintersecting curves. Planes can also be used to display cross sections of a surface, or surface contours at specified intervals. Planes can be inserted for this purpose or generated along the primary axes or along a curve.

If only the intersection of two surfaces is required, it can be displayed and placed in the database as a string. The intersection can be placed on the current layer, or on a specified layer.

While in the GCD program, surface models are displayed as wire-frame models. By default, only the surface boundaries are displayed, but intermediate curves can be specified. These curves are not part of the surface model, but are provided to assist in visualization. The drawing database does contain the mathematical description of each surface in the model.

In most cases, the objective of creating a surface model—and the justification for the time that such an operation requires—is the display of a shaded picture. This process is the least interactive of all that can be done with Personal Designer. The first step in creating a shaded picture is to create a complete surface model. Only surfaces will appear in the final shaded picture; the wire-frame geometry will not appear. In addition, the colors in the shaded picture are determined by the colors in the surface model.

The surface model then must be displayed in the desired view, while it is in GCD. An arbitrary number of pictures can be created from one model by selecting various views, turning layers on and off, and changing colors. Each view that is to become a shaded picture must be saved in a surface model data file, using PUT SHADE. This command allows several data files to be created within a single session.

The actual shaded pictures are created using an external program, SHADE. This program processes the data file and produces a picture file, which is in turn displayed using the DISPLAY program. The SHADE program enables fine tuning; it allows for the specification of the quality of the shaded picture, the direction of the light source used to determine shading, the background color, and the type of picture, either faceted or smooth.

The surfaces of a faceted display are composed of flat tiles, while the surfaces of a smooth display appear to be continuous. If the smooth display is selected, transparency and reflection also can be controlled. Smooth displays take longer to produce than do faceted displays—sufficiently longer that it is often worth checking a picture by first producing a faceted display as a preview of the final smooth display.

The manual does not point out that surfaces in parts inserted as figures are not displayed in the shaded picture. Surfaces in parts inserted as parts, however, are displayed in the shaded picture. Displaying surfaces in figures would have added considerable complexity to the Surfaces program. The figures facility is not likely to be used in surface modeling and can be accommodated by the use of parts instead of figures; therefore, it can be argued that displaying figures with surfaces would not be worthwhile.

HELP

is at hand

HELP/Control™ — an on-line help system for the IBM-PC. **HELP/Control** includes **HELP/Runtime, HELP/Popup** and our help screen compiler.

With **HELP/Runtime**, a few simple subroutine calls add context sensitive on-line help to your application. **HELP/Runtime** includes tested interfaces for C (Microsoft and Lattice), Pascal (Microsoft and Turbo), IBM BASIC (Interpreter and Compiler), Microsoft FORTRAN, COBOL (IBM and Realia) and assembler.

Use our concise screen definition language to build your help files. You define the bold captions on your help screens and specify the links to other screens. If you have existing documentation files, we supply a program which automatically marks them up to get on-line quickly. You can put an entire user or reference manual on-line, completely accessible to the user at all times.

HELP/Control also includes **HELP/Popup**, which provides memory resident access to your custom help screens. Use it to document dBase and 123 applications. **HELP/Popup** uses the same help files as **HELP/Runtime** and operates the same from the user's point of view, allowing you to provide a consistent on-line environment across diverse applications.

The complete package (software, on-line manual, printed manual, and demo programs) costs $125.00 and includes a royalty-free license to add **HELP/Runtime** to your applications and a license to make 25 copies of **HELP/Popup.** A demonstration diskette, including the on-line manual, costs $15.00. To order, or for more information (including dealer, multiple-copy and site-license pricing) call MDS at 207/772-5436. We accept MasterCard and VISA.

New with release 1.20! Use Dan Bricklin's Demo Program to build your help system. Our translator turns it into a HELP/Control source file.

MDS

MDS, INC., P.O. BOX 1237, PORTLAND, MAINE 04104

CIRCLE NO. 146 ON READER SERVICE CARD

SPEAKING THE LANGUAGE

A user programming language is a prerequisite to using CADD in referring to an interactive graphics program. It is the user programming language, such as UPL (which is included with Personal Designer) that allows users and third-party developers to customize a package so that designers can use it in the language of their discipline.

Computervision's UPL is a block structured language that resembles Pascal somewhat. A UPL program consists of a group section, in which global variables and constants are declared; optional procedure and function definitions, which may contain local variable declarations; and a main procedure.

The UPL repertoire of statements is limited in comparison to general-purpose programming languages, but it includes the essential programming constructs, IF. . .THEN. . .ELSE. . .ENDIF, and LOOP. . .END LOOP, as well as the expected assignment, input, and output statements, and a GOTO statement. This last inclusion reveals the program's FORTRAN heritage.

This language includes statements and functions that are tailored to interact with Personal Designer's GCD screen. Input can be accepted by a UPL program from the keyboard and the pointing device. Windows can be defined and sized dynamically, and alphanumeric output can be written to windows. A full complement of file-handling functions is provided as well.

The primary interface the user has with GCD is the SEND statement, which invokes GCD commands as if they have been typed at the keyboard or picked from a menu. Commands invoked with SEND can be echoed in a window, or executed silently, depending upon the setting of a toggle.

The key feature in a CAD user programming language is its ability to access the drawing database directly. UPL provides four basic, essential statements that add entities to the database, retrieve information about an entity in the database, remove an entity from the database, and modify the graphic attributes of an entity in the database. Of course, the variety of entities to which these statements can be applied requires the use of key words and parameters in order to specify the exact action desired. The number of possible combinations is large and provides total access to the database.

UPL programs must be written outside of GCD and compiled before use. The compiler produces an intermediate code file and an optional list file. Once a program compiles successfully, it is ready for execution under GCD. A UPL program is normally invoked with the **RUN <file name>** statement, typed at the GCD command prompt. In some Personal Designer configurations, a command can be added to the verb/noun table, which allows the UPL program to be invoked directly without the use of the RUN verb.

Two menu systems are furnished with the Personal Designer system: a screen menu and a tablet menu. Both menu systems provide access to essentially all of the basic commands, but not to some of the advanced functions or to seldom-used command sequences. Thus, a designer can use either menu exclusively, or both in concert. Sooner or later, however, keyboard input will be required to proceed.

The tablet menu overlay provided with the system is divided into a screen pointing area that is 7 inches wide by 5 inches high, and an L-shaped menu key area. Moving the tablet cursor inside the screen pointing area provides access to the graphics window and the on-screen menu; moving it outside the area provides access to the menu key commands. The description of the overlay and the meanings that are assigned to the keys are recorded in a separate file that can be edited to change the layout and key meanings.

The configuration file stores the name of the default tablet menu file, which is the tablet menu that is active at the beginning of a new drawing session. A different menu file can be activated during a drawing session using the RESTORE TABLET command entered at the command line.

Whereas the tablet menu is a flat menu, the on-screen menu has a hierarchical structure. Selecting a menu key can invoke a command or portion of a command, or activate a submenu. The standard screen menu is structured to display submenus according to the options that are available at each stage of the command entry.

Screen menus are stored as binary files that are created from screen layout parts, drawings of the screen. Creating a menu consists of creating the screen layout part, and then compiling the part to produce the menu file. A screen layout part defines both the appearance of the screen and the functions of the various areas of the screen. The screen layout can contain 20 alphanumeric windows, 1 graphics window, and an arbitrary number of menu windows.

The keys in a menu are closed strings. A key can contain an icon—text,

Tom Rettig's Library™

Prewritten Solutions to Programming Problems

Clipper Edition

Advanced Extended Library

- Convenient .LIB library file to link
- Separate object files so only the code actually used is added to your program
- Optimized for speed and code size
- Requires Clipper, Winter '85 or later

dBASE III PLUS Edition

Advanced Programmer's Library

- Interface to C/assembler is fully compatible with Clipper's Extend system
- Functions are CALL procedures
- Requires dBASE III PLUS, any version, and 128K of additional memory

Each edition comes complete with...

- Entire source code, nothing withheld. Cleanly written, liberally commented, easy to modify, helpful for learning.
- Support by phone and electronic mail
- No royalties or copy protection
- Documentation inserts for dBASE or Clipper manual. Accurate, complete, easy to use, page-per-command.
- Handy plastic reference card
- Full money-back guarantee

Over 175 functions; 55% written in C, 35% in Assembler, 10% in dBASE

$99.95 per edition at dBASE/Clipper dealers or direct

II/III Tom Rettig Associates
Excellence in dBASE since 1982

9300 Wilshire Boulevard, Suite 470
Beverly Hills, CA 90212-3237, U.S.A.
(213) 272-3784 ▪ Telex: 4996426 RETTIG
Source: BCR480 ▪ CompuServe: 75066,352

dBASE and dBASE III PLUS are Ashton-Tate trademarks, Clipper is a Nantucket trademark

Call or write for free product information



EE DESIGNER™

PROFESSIONAL CAE/CAD SOFTWARE STARTING AT $975.

A clear path through the CAE/CAD software maze. There are many CAE/CAD systems on the market today, but most are unproven in the work environment. With over 2,000 packages sold, the one system that has been getting the job done where it counts is EE Designer!

This is the IBM PC-based end-to-end CAE/CAD system that performs. Professionally. And affordably. That's why it's quickly become first choice of small and large companies alike. And the latter category includes companies like ***AT&T, Eastman Kodak, General Electric, IBM, Motorola, Sony, Texas Instruments, Westinghouse,*** and ***Xerox,*** to name just a few.

Join them and more than a thousand other companies in making the smart move—risk free. Order EE Designer or the advanced EE Designer II, try it for 30 days and be fully satisfied or your money back.

EE Designer. Schematic capture, digital logic simulation, manual interactive layout, limited multilayer capability. **$975.**

AutoRouter. Two layer AutoRouter for EE Designer. Uses vias and orthogonal routing style. **$975.**



Plug-In graphics card for IBM PC generated by EE Designer

EE Designer II. Schematic capture, digital logic simulation, manual interactive layout, extended multilayer and surface mount (SMD) capability, enhanced graphics for symbol creation, dimensioning capabilities.

Improved facilities for analog board design (improved ground planes, user definable trace widths.) **$1,875.**

AutoRouter II. Multilayer AutoRouter for EE Designer II. Supports routing with or without vias using orthogonal routing style. **$1,475.**

EE Designer II and AutoRouter II may be purchased together for **$2,975.**

System requirements: IBM PC/XT/AT or compatible with 640K memory.

To order, call toll-free

1-800-553-1177

VISA MasterCard

VISIONICS®
CORPORATION

343 Gibraltar Drive
Sunnyvale, CA 94089
(408) 745-1551

IBM PC, XT and AT are trademarks of International Business Machines Corp.

CIRCLE NO. 173 ON READER SERVICE CARD

graphics, or both—and an icon graphic can span several keys. A command is associated with a key by attaching one or more properties to the string that defines the particular key.

The hierarchical menu structure is implemented via layers. A group of menu icons on a layer constitutes an icon set. Icon sets also can be assigned specific properties of their own.

Once a screen layout part is defined or edited, a binary menu file is created using the BUILD MENU command. This command examines a screen layout drawing displayed on the screen, and creates the file necessary to implement the menu. The new menu can be set up as the default menu file, or it can be loaded with RESTORE MENU during a drawing session.

Creating a new working menu is not an exercise for the novice, although the manual includes a step-by-step tutorial in creating menus. The process requires considerable knowledge of the system's command structure, both for creating the layout part and for the assignment of commands to the keys. However, creating a Personal Designer menu is not much more difficult than creating menus for most other micro CAD programs; all require thorough knowledge of the command structure.

The effort of creating Personal Designer menus is certainly justifiable. The system offers total flexibility, not only in the creation of menus, but in general screen layout. The screen layout can range from one large graphics window and a minimal command window, to a small graphics window, a large screen menu, and several text windows. Nine windows are predefined for UPL use.

INSTALLING THE SYSTEM

Personal Designer is installed with the use of a batch program that creates subdirectories and copies files into the subdirectories. The installation program installs the CADD package on drive C:, and expects the high-density diskette drive to (absolutely) be drive A:. (Computervision indicates that it intends to improve this installation process in an upcoming version of Personal Designer.) The installation program also creates a configuration file.

The version reviewed here could only be reconfigured by editing the configuration file, a text file. The configuration file is fully documented in the installation notes, but reconfiguration is not a task for the novice. It requires a thorough knowledge of the hardware and of the operation of the CAD program. If the configuration is altered beyond recognition, however, it always can be restored to the distribution version by rerunning an install program—not the batch file that copies all the files—but a program that only rebuilds the configuration files.

Installation of the program includes installation of a security device. At the time of the review, two different types were available—one for installation on the parallel port and one for installation between the keyboard and system unit. The program must be informed of the type of device installed. No problems were encountered with the device; however, the never-ending string of numbers that were needed to install the security device and allow the software to run at *PC Tech Journal*'s editorial office, in addition to the indiscriminate renaming of the CONFIG.SYS and AUTOEXEC.BAT files, seem unreasonable. If the machine that is being used requires a device driver to recognize the hard disk this is deleted. It is a simple matter to design installation software to append to existing files and not to replace them. Not all users of CADD systems will be buying the software exclusively as a turnkey system.

It should be noted that Personal Designer is not generally sold through computer dealers, even dealers specializing in CAD. It is usually sold through Computervision representatives or sales offices, and often as a turnkey system including a substantial amount of on-site training. Thus, installation will not be of concern to many users.

Personal Designer GCD is contained in four diskettes, Surfaces, UPL, and PDFEM each on a single diskette. An additional utility program disk and a demo disk are included.

The manuals are IBM-size and typeset. Each module typically includes a user's guide and a reference manual. The user's guides are tutorial in nature, and the reference manuals are organized by commands, arranged alphabetically by command verb, then command noun. The indexes included in each of the manuals are inadequate. All of the manuals include examples, most of which worked. The program is designed to be purchased with training. However, a few glitches notwithstanding, a user can learn the system effectively just by working through the examples in the manuals. Once learned, the program is easy to use.

The distribution disks also include a tutorial, written in UPL. Although some of the screens in the tutorial are of the "Read this, press C to continue" design, most require user input to

Personalize your computing environment.

The MKS Toolkit now contains the Korn shell command interpreter.

The MKS version of Bell Labs' Korn shell has this and more:

- the full power of the UNIX System V.2 Bourne shell
- the most requested features of Berkeley's C shell
- the full-UNIX utility of executable shell files
- command aliases
- interactive command-line facilities
- previous command history and editing
- a powerful programming language
- shell variable expansion
- arithmetic evaluation

All this has been fine-tuned to create the optimum environment under DOS. The Korn shell is just one of over 100 commands — fully compatible with UNIX System V.2 — now contained in the MKS Toolkit, including the following:

awk	cat	chmod	cmp	cp	cpio	ctags	cut	date
dd	df	diff	du	echo	ed	egrep	ex	fgrep
file	find	head	help	join	lc	ls	more	mv
nm	od	paste	pg	prof	rm	sed	size	sort
split	strings	tail	time	touch	tr	uniq	vi	wc

and much, much more . . .

These programs run from the shell or command.com under DOS on machines such as the IBM PC, XT, and AT, the AT&T 6300, and most PC compatibles. Full documentation is included. Phone support is available 9-6 EST. Not copy protected.

Everything for only $139.

Mortice Kern Systems Inc.

43 Bridgeport Road East, Waterloo, Ontario, Canada N2J 2J4

For information or ordering call collect: **(519) 884-2251**

Prices quoted in U.S. funds. MasterCard and VISA orders accepted. OEM and dealer inquiries invited. UNIX is a trademark of Bell Labs. MS-DOS is a trademark of Microsoft Corp.

CIRCLE NO. 174 ON READER SERVICE CARD

GCD. The UPL program checks the input, passes the correct input through to GCD, and rejects the incorrect input. Although the tutorial does not include coverage of surface modeling, it covers three-dimensional wire-frame modeling and detailing very well.

DOES IT STACK UP?

How does Personal Designer stack up against AutoCAD, VersaCAD, CADvance, Cadkey, and other microcomputer-based CAD systems? The answer is that Personal Designer is a more capable system than any of those named.

Personal Designer provides an almost ideal mix of modeling and production drafting capabilities. For pure conceptual design modeling, some may prefer a package that offers solids as primitives, rather than Personal Designer's wire-frame facility. But, UPL provides a way to implement three-dimensional, wire-frame objects, with or without surfaces—not solid modeling, but close enough for most purposes.

Computervision is to be commended for supporting such a substantial subset of their full system in the microcomputer environment. If they, or any major CADD vendor, had placed such a powerful program on the market concurrently with the advent of the IBM PC, the CAD market would be much different than it is today.

Personal Designer appears to be as responsive as most moderately loaded minicomputer-based systems, although the two types of systems were not compared directly. With the 6-MHz AT and the Heathkit H-248 systems, Personal Designer is as responsive as any of the microcomputer-based CAD systems listed above, with few exceptions.

However, the manner in which Personal Designer handles parts inserted as figures can lead to a substantial number of disk accesses during drawing regeneration, even of small drawings. In fact, screen repaints generally require disk access, which imposes a speed penalty in comparison to programs that redraw the screen from a display list in memory. Finally, selecting commands from the screen menu also requires disk access, as the screen menu must be redrawn to display submenus. All of that notwithstanding, Personal Designer is reasonably fast.

It should be noted here that speed of redraws, of loading drawings initially, and of executing commands, should not be the principal criteria for selecting a CAD system. More important criteria include the number and types of automated tasks; the degree to which the system's operation resembles the way designers work; and the facilities for customizing the system. In terms of capabilities, this product is outstanding.

Personal Designer is a high-performance, three-dimensional design and detailing system. It provides a substantial subset of a minicomputer CADD system's capabilities, in a microcomputer environment. It also maintains compatibility with the larger system, providing a smooth upgrade path. A Personal Designer system can operate as part of a larger Computervision system, or stand-alone. It may not be the ideal program for all micro CAD users—cost is one factor, the learning curve another. But, if performance and capability are the main criteria, it is a strong contender. Personal Designer is highly recommended.

Computervision Corporation
15 Crosby Drive
Bedford, MA 01730
617/275-1800
GCD, $5,800; Surfaces, $2,800; FEM, $1,500; UPL, $500

CIRCLE 350 ON READER SERVICE CARD

Victor E. Wright is the manager of process engineering at Luckett & Farley, a firm located in Louisville, Kentucky.

FREE SOURCE CODE!

VITAMIN C
It's good for your system!

FREE SOURCE CODE!

Vitamin C Difference

With **Vitamin C,** your applications come alive with windows that explode into view! Data entry windows and menus become a snap. Vitamin C's **open ended design** is full of "hooks" so you can "plug in" special handlers to customize most routines. Of course, Vitamin C **includes all source code FREE,** with no hidden charges. *It always has.*

Windows

Create windows with one easy function. Vitamin C automatically takes care of complicated tasks like saving and restoring the area under a window.

Options include titles, borders, colors, pop-up, pull-down, zoom-in, scroll bars, sizes to 32k, and more. Unique built-in feature lets users move and resize windows at run-time!

Data Entry

Flexible dBase-like data entry and display routines feature protected, invisible, required, and scrolling fields, picture clause formatting, full color/attribute control, selection sets, single field and full screen input, and unlimited validation via standard and user definable routines.

High Level Functions

Standard help handler provides context sensitive pop-up help messages any time the program awaits key strokes. So easy to use that a single function initializes and services requests by opening a window, locating, formatting, displaying and paging through the message.

Multi-level MacIntosh & Lotus style menus make user interfaces and front ends a snap. Menus can call other menus, functions, even data entry screens quickly and easily.

Text editor windows can be opened for pop-up note pads and general purpose editing. Features include insert, delete, word wrap, justify, cut, paste, search, and more!

VCScreen

With VCScreen and Vitamin C working together, you'll reach a new level or productivity you can't reach with a function library alone!

VCScreen speeds development even more! The interactive screen editor actually lets you draw input, output and constant fields, headings, boxes, lines, even a window for your froms to run in.

VCScreen generates readable C source code ready to "plug in" to your application and link with Vitamin C.

Guarantee

Better than a brochure. More than a demo disk. If you're not satisfied, simply return the package within 30 days and receive a full refund of the purchase price.

Vitamin C $225.00
Includes ready to use libraries, tutorial, reference manual, demo, sample and example programs, and quick reference card; for IBM PC and compatibles. Specify compiler and version when ordering.

Vitamin C Source . . . . . FREE*
**Free with purchase of Vitamin C.*

VCScreen $99.95
Requires Vitamin C and IBM PC/XT/AT or true compatible.

Shipping $3 ground, $6 2-day air, $20 overnight, $30 overseas. Visa and Master Card accepted. All funds must be U.S. dollars drawn on U.S. bank. Texas residents add 7¼% sales tax.

(214) 245-6090

Creative PROGRAMMING
Creative Programming Consultants, Inc.
Box 112097 Carrollton, Texas 75011

THE MIGENT POCKET MODEM™ A STATE-OF-THE-

It's ironic. These days, modems bring the world to you at the speed of light. But for all their awesome speed and power, these high-performance machines just sit there on your desk like a low-tech toaster.

But now, we're introducing the Migent Pocket Modem. It's 100% Hayes-compatible, so it works with virtually any PC: IBM, Apple, or whatever. It runs at both 300 and 1200 bps. It has a full set of Hayes AT commands. A 28-character non-volatile memory. Remote ring and tone sensing. Busy and dial tone monitoring. And even dual phone jacks.

But that's where all similarities end. The whole modem is smaller than a 3" x 5" card and works on a 9 volt battery or AC power. So you can put it in your shirt pocket or briefcase, and take it home, on the road, or anywhere else you need your PC.

The Migent Pocket Modem. If you'd like to know more, send in this coupon or call **800-633-3444,** Dept. 609, and ask for Alexis. We'll send you full information and the name of your nearest dealer. But in the meantime, you may be wondering why this modem isn't beige like the rest. Because we think it's about time a high-powered information machine looked like one.

☐ Please send me more information about the Migent Pocket Modem. And send me the name of the dealer in my area.

NAME

ADDRESS

CITY STATE ZIP

PHONE

MIGENT™

Send to: Migent, Inc., 865 Tahoe Blvd., Call Box 6, Dept. 609, Incline Village, Nevada 89450-6062, Attn: Alexis

Registered trademarks: Apple, Apple Computer; Hayes, Hayes Microcomputer Products; IBM, International Business Machines. Trademark: Pocket Modem, Migent.

ART INFORMATION MACHINE THAT LOOKS LIKE ONE.

CIRCLE NO. 163 ON READER SERVICE CARD

A Resident Exception Manager

An interrupt handler can be installed to allow resident Ctrl-Break or critical error handling routines to take control during the execution of a program.

TED MIRECKI

Many services provided by DOS are available through interrupt handlers. In practice, the address of the code providing a particular service, such as sending data to (or receiving it from) peripherals, is available in a location in memory accessible to any program: the interrupt vector table that is in the lowest 1KB of system memory. System programmers who are not satisfied with the way DOS handles those functions can write their own routines and point the appropriate interrupt vectors to them, effectively replacing the standard code with customized interrupt handlers. DOS provides several functions to support the replacement of interrupt handlers: functions 35H and 25H of interrupt 21H read and set a given interrupt address, and function 31H and interrupt 27H can be used to install resident interrupt handling routines.

But three interrupts—22H, 23H and 24H—are not amenable to replacement in this fashion. These perform some very important functions: interrupt 22H points to the return point after a program terminates; interrupt 23H to the code that handles a Ctrl-Break; and interrupt 24H to the critical error handler that is invoked on device errors. (The standard DOS error handler issues the infamous "Abort, Retry, Ignore" message.) Those not satisfied with the way DOS handles these functions might try to replace them with customized interrupt handlers in the usual fashion, but to no avail. The DOS documentation for interrupt 27H states: "This interrupt restores the interrupt 22H, 23H, and 24H vectors to the values they had on entry to the program. Therefore, it cannot be used to install permanently resident Ctrl-Break or critical error handling routines."

This statement sounds like a definite challenge. Notice that the DOS manual does not claim that replacing these interrupt handlers is impossible, just that such replacement cannot be done with interrupt 27H. Although no such caveat appears in the documentation for function 31H of interrupt 21H (which also performs an "exit and remain resident" operation), that function operates in the same manner. How, then, is one to install such interrupt handlers? If they are not to be replaced, why are they provided as interrupts?

To answer the second question first, the interrupt addresses are available to be replaced only during the execution of a program. While a program is running, it may repoint the interrupts to its own routines (see "DOS Exception Handling," Dan Rollins, this issue, p. 130). Upon termination, however, DOS restores the original interrupt addresses. A program, therefore, can be written to provide its own Ctrl-Break and error handling during its own execution, but the program cannot leave these routines behind to service programs executed subsequently.

Because a program cannot leave behind an active break or error handler once it terminates, the trick is not to terminate the program that provides these interrupt services, but to suspend it during the execution of a subsequent program. This is exactly the operation performed by the EXEC function (4BH) of DOS. The way to customize these stubborn interrupts, then, is to install a



handler for interrupt 21H, function 4BH. As it happens, COMMAND.COM also uses the EXEC function when it executes programs with names that are typed at the DOS prompt, so a resident EXEC handler can provide customized interrupt 22H, 23H, and 24H services for any program run under DOS.

Fortunately, it is not necessary to duplicate everything that the EXEC function does in order to load and execute a program. Most details can be left to the original EXEC code in DOS. The interrupt handler need only repoint interrupt 23H to the desired Ctrl-Break handling, arrange for the child process to return to it instead of to DOS for post-termination processing, and then let DOS perform the actual EXEC call.

The program RES22-23.ASM (listing 1) demonstrates the means of installing a resident interrupt handler for interrupts 22H and 23H. (Interrupt 24H error handlers are beyond the scope of this article, but the same principles apply for installing them.) The installation method, not a specific interrupt service, is illustrated, so the following description concentrates initially on the means of transferring control into and out of the routines. The break-handling and post-processing routines in RES22-23 are merely suggestions. Using this method, customized services may be provided for any particular purpose.

RES22-23 is installed in the normal fashion as a resident program to service interrupt 21H. The initialization code at label INIT saves the original interrupt 21H address, resets this interrupt to the address of the new EXEC handler, and fixes the program in memory with interrupt 27H. When an interrupt 21H occurs, the code at label EXEC checks to see if the function code in register AH is 4BH (EXEC). If not, a long jump is taken to the saved original interrupt 21H address, and RES22-23 is no longer involved. DOS handles the function normally, returning to the program that issued the call to DOS.

When the function code is 4BH, however, RES22-23 springs into action. It repoints interrupt 23H to its own Ctrl-Break handler at label INT23 in the program, saves the return point (the address of the instruction following the interrupt 21H that caused the entry into the program), and performs a far CALL to the original interrupt 21H address within DOS. At entry to DOS, the stack is in a proper state for an interrupt: a far address is at the top, followed by the flags. It does not matter to DOS that the address points to a resident routine instead of the location where the original interrupt 21H occurred.

DOS now performs the EXEC function, loads the requested program, and then runs it. If a Ctrl-Break is detected during execution, DOS executes an interrupt 23H, returning control to the resident program, which performs any desired processing and either terminates or returns to continue with the interrupted child program's process.

When the child program terminates, it returns to DOS. After termination processing, DOS returns to RES22-23 at the instruction following the far call. There, the flags and register AX are saved in case DOS is returning an error code (such as file not found or insufficient memory), then the desired post-

ILLUSTRATION • MACIEK ALBRECHT

Think of us as the Book of the Mind Club.

processing (proc POSTPR) is performed. If desired, the post-processing may be skipped in case of error.

The exit sequence from RES22-23 consists of restoring the error status (flags and AX) that was saved on return from DOS, followed by a long jump to the return address that was saved on entry. This returns control to the program that issued the original EXEC call (perhaps COMMAND.COM), which is none the wiser that the call was intercepted by a resident program.

The desired effect—a terminated program returning to a resident post-processor—is achieved without directly changing the address in the interrupt 22H vector. Actually, the vector is changed to point to the resident program, but this is done by DOS as part of the EXEC function processing. At the end of its termination process, DOS places the address from the top of the stack into interrupt 22H and executes that interrupt. This scheme merely arranges for the proper address to be on top of the stack at the proper time.

One major detail needs to be taken care of: a program invoked by an EXEC call may in turn issue another EXEC to run another child process. This means that RES22-23 must be reentrant. To illustrate, suppose COMMAND.COM issues an EXEC for the program ABC. RES22-23 is entered, the return point in COMMAND.COM is saved, and program ABC is started. If ABC in turn issues an EXEC for program XYZ, RES22-23 is again entered and now saves a return point within ABC. When XYZ terminates, RES22-23 regains control and returns to the last saved address, the one in ABC. But when ABC terminates, RES22-23 returns to COMMAND.COM only if the first return address has not been overwritten by the second one.

Normally, reentrance is handled by a stack structure, and the 8086/88 microprocessors implement a stack automatically. In most cases, it would be sufficient to save the return value on the stack because each entry would provide a pointer to a new stack location. But the EXEC function is a special case because it does not guarantee preservation of the stack—that is, the Stack Segment (SS) and Stack Pointer (SP) registers may not have the same values after return from an EXEC as they had before. In personal practice, the stack registers have yet to be disturbed after return from an EXEC, but DOS documentation claims it is possible, so it is best to allow for it. Therefore, RES22-23 implements its own stack structure for saving each return address. This customized stack is implemented in the Program Segment Prefix at CS:0. This area is used only during the installation process, and, thereafter, becomes dead storage available for writing by the program after it becomes resident. For a .COM program, this area is in the same segment as the code, so the role of the SS register is played by the CS register, and the SP register is simulated by a data word that is stored in memory at label RETPTR in the program.

At initialization, the stack pointer is set to point to the end of the PSP, and it is decreased by 4 bytes (because each far return address is a double word) before each push to the stack and incremented by 4 after each pop. That way, RETPTR points to the last return address saved, just as SP points to the last word pushed onto the real stack, and the custom stack grows downward in memory. The 256-byte length of the PSP allows for saving 62 levels of return addresses (6 bytes of the PSP are used to save the original interrupt 21H address and the RETPTR value); in the unlikely event that EXEC calls are nested deeper than this, a system crash will result.

Now that the method of installing resident interrupt handlers 22H and 23H is available, what useful work can such handlers perform? Why would it be necessary to replace the standard Ctrl-Break handling of an existing program? The answer lies in the fact that the manner in which DOS handles the Break key was significantly changed in version 2.0. However, some programs have not been updated since DOS version 1.x; they do not, for example, support path names and mishandle Ctrl-Break, sometimes with disastrous results. Specifically, MicroPro's WordStar and the IBM Professional Editor are two such programs, and both are used often in a programming environment for source code maintenance.

These early programs make no provision for handling Ctrl-Break because they were written under the assumption that DOS can only recognize the Break key during character I/O. Under DOS 1.x, as long as no DOS functions are called to perform character I/O, the Break key cannot be recognized and the break-handler interrupt cannot be invoked.

In DOS 2.0 and later, however, the operating system may be directed (by means of the BREAK ON command) to check for the Break key at every DOS function. This is especially useful to programmers who might want to interrupt a long compilation. When a compiler is running, pressing Ctrl-Break will

Want to turn programming time into prime time? Want to put some topspin on your techniques? Want to develop invaluable new resources?

Time to hit the books. From Microsoft® Press. The best and brightest books in the business.

Our parent company is Microsoft, the folks who taught the PC how to think. Our authors read like a Who's Who of What's What.

Here are four ways to boost your computer's I.Q.:

Advanced MS-DOS® by Ray Duncan. From C programmer to A player—fast. With Ray Duncan's MS-DOS information bonanza: Disk files, records, directories, volume labels, internals, memory management, EXEC functions, installable device drivers. More. The featured columnist for *Dr. Dobb's Journal* has it down. You can, too. $22.95. 468 pages. Softcover.



The Peter Norton Programmer's Guide to the IBM® PC by Peter Norton. Want to develop intermediate and advanced programs you can port from one branch of the PC tree to another? Want to understand the hardware? Software? The differences between PC, XT, AT and Jr.? Get the latest tech talk? Relax. The leading authority in the field leads you out of the bog. $19.95. 448 pages. Softcover.

Microsoft QuickBASIC by Douglas Hergert. Here's the perfect way to get up to speed with QuickBASIC. Plus five, smart, sample programs that'll tweek your QuickBASIC skills: MORTGAGE, for data types; QUICKCHART, for graphics; SURVEY, for data-file techniques; EMPLOYEE, for random-access files; TWENTY-ONE, for IF...THEN...ELSE games. $18.95. 384 pages. Softcover.

Proficient C by Augie Hansen. Cross DOS and C and what do you get? Powerful programs that run at warp speed. Use the ANSI SYS device drive and the MAKE and LIB utilities to learn valuable, reuseable methods of structured program development. From the man whose proficiency at Bell Labs, General Dynamics and Rayethon was the springboard to this expert guide for intermediates—and experts. $22.95. 512 pages. Softcover.

Don't fumble for answers. Turn to Microsoft Press. Remember: What you get out of your PC depends on what you read into it.

Available wherever books and software are sold. Credit card orders call 1-800-638-3030. In Maryland call collect, 824-7300.

Microsoft PRESS

Microsoft and MS-DOS are registered trademarks of Microsoft Corporation. IBM is a registered trademark of International Business Machines Corporation.

CIRCLE NO. 226 ON READER SERVICE CARD

have no effect until the compiler next writes to the screen, but if the next message is "Compilation complete," it might be a long wait. Running the compiler with BREAK ON solves this problem because the Break key is recognized at the next DOS call of any type, and a compiler makes frequent calls for disk I/O when reading the source and writing the object file. On the other hand, leaving the BREAK switch on can cause other problems with programs that do not make provisions for such comprehensive break checking.

Once the compilation is interrupted, the programmer will typically call up an editor to work on the source program. For example, suppose that during the edit session, the Ctrl-Break key is pressed by mistake instead of the Ctrl-NumLock or Scroll Lock. The editor is smart enough to ignore this, but the BIOS keyboard routine records the break in the DOS break flag. Now, at the next DOS function, which is typically a save to disk, DOS recognizes the break and invokes the break handler. If the default handler is in effect, it immediately exits the editor, dumping the newly updated file into the bit bucket. This situation would be avoided if the editor could be provided with a customized break handler.

Within an editor, the preferred response to the Break key is simply to ignore it. But once outside the editor and back inside the compiler, the default action of exiting to the operating system is desired. It is possible, however, to write one resident handler that can accommodate both needs.

In the program given here, the interrupt 23H (Ctrl-Break) handler does two things. First, it issues a more informative message than ^C (in the example, it is *BREAK*, but it may be anything the programmer desires). Despite what DOS documentation implies, the ^C is output before, not after, the call to interrupt 23H, so the output of the resident break handler will be in addition to, not instead of, the standard ^C. Second, it terminates the program with an error level of 8. This is especially useful for programs invoked from a batch file.

When a batch file is interrupted with Break, the default break handler queries the user whether to terminate the batch stream or to continue with the next command. The customized handler illustrated below returns to the batch file, allowing a subsequent IF ERRORLEVEL statement to make the decision without user intervention. The batch file could be written to perform a cleanup sequence if a program is interrupted with Ctrl-Break. The problem with the Break mishandling in the editor could be handled by the following batch file for compilation:

```
BREAK ON
COMPILE %1
IF ERRORLEVEL 8 GOTO :CLEANUP
LINK %1
:CLEANUP
BREAK OFF
```

The BREAK switch is turned off after the compilation, even if the compiler is interrupted with the Break key. Therefore, a subsequent editing session cannot be aborted by the mishandling of the Break interrupt.

The post-processing performed by the example program is for data security—it clears all memory after each program terminates. This prevents snooping with DEBUG to discover possibly sensitive data left in memory by a word processor or database manager. The clearing of memory occurs unconditionally after every program without any effort by the user, so it is safer than writing a batch file to run a memory clearing utility after each application, and infinitely more convenient than requiring a system reset after terminating a session with sensitive data.

The clearing process works by tracing the DOS memory allocation blocks and writing zeroes to all blocks that do not belong to an active process. The format of memory allocation blocks, and how to determine if they are unowned, was previously described in some detail in "Managing Memory," (William Redmond, August 1984, p. 43). There are two minor inconveniences: a slight delay between program termination and the next system response, and the fact that COMMAND.COM must be reloaded after each program. The latter occurs because the transient portion of COMMAND.COM resides in memory that is not allocated, so this memory is wiped out. No easy method exists to determine where COMMAND.COM begins in high memory.

Critical error handlers are not limited, therefore, to functions determined solely by DOS. Interrupt-handling routines can be used to improve the Break key and error-handling ability of any program. Also, data security can be increased by using of post-processing techniques, even when a program is terminated unexpectedly.

Ted Mirecki has been a contributing editor to this magazine for three years. He recently joined the editorial staff at its location in Columbia, Maryland, as a technical editor.

Attention **Realia COBOL** Users:

SCREENIO 2.0

Screen Manager for COBOL Professionals.

A strictly COBOL approach to screen management, written by and for COBOL professionals. Screen Design is easy with SCREENIO. You take care of your application. We take care of the screens! Fully compatible with Realia COBOL.

What does it do?

Interactive Screen Design, Full Feature Screen Painter, COBOL Data Field Specifications, Edit Masks, Automatic Error Detection, Data Validation, High Speed Video, Full Compatibility, Window Panels, Hot-Fields, Key Redefinition, Foreign Language Capability, Full Color Support, Cursor Management, PC Speaker Control, Screen Libraries, and Very User Friendly. We've thought of everything!

And Best of all:

No Runtime Facility, No Runtime Fees, Superb Support. Only $400 Plus Shipping.
Ask about our FREE demo pack and SCREENIO+Realia Package Deal!

NORCOM
NORTHERN COMPUTING CONSULTANTS

Post Office Box 020897
Juneau, AK 99802-0897
(907) 780-6464
Telex: 5106014951 (NORCOM)
- Amex MC Visa Check -

CIRCLE NO. 191 ON READER SERVICE CARD

Why this publication and more than 1,200 others let us go over their books

---

once a year.

Some publications, we're sorry to say, keep their readers undercover. They steadfastly refuse to let BPA (Business Publications Audit of Circulation, Inc.) or any other independent, not-for-profit organization audit their circulation records.

On the other hand, over 1,200 publications (like this one) belong to BPA. Once a year, BPA auditors examine and verify the accuracy of our circulation records.

The audit makes sure you are who we say you are. The information helps advertisers to determine if they are saying the right thing to the right people in the right place.

It also helps somebody else important: you. Because the more a publication and its advertisers know about you, the better they can provide you with articles and advertisements that meet your information needs.

BPA. For readers it stands for meaningful information. For advertisers it stands for meaningful readers. Business Publications Audit of Circulation, Inc. 360 Park Ave. So., New York, NY 10010.

MEDIA
INTELLIGENCE

BPA

TASKVIEW™

EASY TO USE
OPTIONAL MENUS
TIME SLICING
VIRTUAL MEMORY
EMS SUPPORT
EGA SUPPORT
PRIORITY DRIVEN
CUT AND PASTE

Compatible, efficient DOS multi-tasking.

We designed Taskview with efficiency in mind. During normal operation, TASKVIEW hides behind DOS, providing you with control of up to 10 concurrent or non-concurrent programs. Just the touch of a key instantly switches a program to the foreground. Included desktop utilities let you cut and paste from program to program. Simple to use and reasonably priced, no well equipped PC user should be without it.

Requires: PC/AT/Jr compatible, DOS 2.0-3.1, 256K RAM, 1 Floppy drive.

Sunnyhill Software not affiliated with Borland International
Taskview trademark of Sunnyhill Software
Sidekick registered trademark of Borland International

Dealer Inquiries Invited.

$79.95 plus $3.00 S&H

Washington residents add 7.9%
International orders add $5.00
VISA and Mastercard accepted.

To order Toll-Free
call 1-800-367-0651

Sunny Hill Software
P.O. Box 55278
Seattle, WA 98155
(206) 367-0650 M-F, 8-6 PDT

CIRCLE NO. 158 ON READER SERVICE CARD

TURBO PROFESSIONAL™

SERVICE INTERRUPTS
No assembly required
RESIDENT PROGRAMS
Easy, pop-up routines
EXECUTIVE PROGRAMS
Run ANY DOS program
DISK SECTOR I/O
Lowest level access
FAST TEXT WINDOWS
Virtual windowing system
KEYBOARD MACROS
Simple, powerful
LOTS OF EXAMPLES
21+ full example programs
MUCH MORE...
Over 140 routines in all

"If you never thought Turbo Pascal was a systems programming language, you've never seen Turbo Professional."
Darryl Rubin
Computer Language

For programs that move with technology—Turbo Professional—a truly professional library of subroutines.

150 page reference manual.
Full source—many example programs.
No royalties charged for applications.

Requires IBM compatible, DOS version 2.0 or greater, Turbo Pascal 2.0 or greater.

Sunnyhill Software not affiliated with Borland International.
Turbo Professional, trademark of Sunnyhill Software
Turbo Pascal, registered trademark of Borland International

Dealer Inquiries Invited.

$69.95 plus $5.00 S&H

Washington residents add 7.9%
International orders add $5.00
VISA and Mastercard accepted.

To order Toll-Free
call 1-800-367-0651

Sunny Hill Software
P.O. Box 55278
Seattle, WA 98155
(206) 367-0650 M-F, 8-6 PDT

CIRCLE NO. 152 ON READER SERVICE CARD

LISTING 1: RES22-23.ASM

```
COMMENT "       PROGRAM RES22-23  by Ted Mirecki.

Demonstrates installable resident interrupt handlers for Terminate
Address (INT 22H) and Ctrl-Break (INT 23H).  After installation,
these routines will be used by all programs in lieu of standard
DOS handlers for these services.

The INT 22H handler clears memory after each program to prevent
snooping with DEBUG.

The INT 23H handler displays *BREAK* along with standard ^C, and
ends any program with errorlevel 8 for subsequent testing in a
batch file.

This program is meant to be converted to a COM file.  "


CODE    SEGMENT 'CODE'
        ASSUME  CS:CODE, DS:NOTHING, ES:NOTHING, SS:NOTHING

        ORG     0FAH            ;Use PSP for data area
RETPTR  DW      ?               ;Ptr to last save address
INT21   LABEL   DWORD           ;Original INT 21H vector
OFF21   DW      ?
SEG21   DW      ?

        ORG     100H
ENTRY:  JMP     INIT


; EXEC Proc replaces DOS EXEC function.  Any program executed
; from DOS (by COMMAND.COM or by another process) returns here
; for post-termination processing.


EXEC    PROC
        CMP     AH,4BH          ;Is it EXEC call?
        JE      X1              ;Yes: handle it here
        JMP     CS:INT21        ;No:  let DOS handle it

X1:     PUSH    AX              ;Save registers
        PUSH    DX
        PUSH    DS
        MOV     AX,CS
        MOV     DS,AX           ;Point DS:DX to CS:INT23
        LEA     DX,INT23
        MOV     AX,2523H        ;Point INT23 vector there
        INT     21H
        POP     DS
        POP     DX
        POP     AX

        SUB     CS:RETPTR,4     ;Update save area pointer
        MOV     SI,CS:RETPTR    ;SI -> Current save address
        POP     CS:[SI]         ;Save return address
        POP     CS:[SI+2]
        CALL    CS:INT21        ;Perform EXEC function


; Any program executed from DOS (by COMMAND.COM or by another
; process) returns here for post-termination processing.


        PUSHF                   ;Save error status
        PUSH    AX
        CALL    POSTPR          ;Perform post-process
                                ;Exit sequence
        MOV     SI,CS:RETPTR    ;Get return address
        ADD     CS:RETPTR,4     ;"Pop" the custom "stack"
        POP     AX              ;Restore & return
        POPF
        JMP     DWORD PTR CS:[SI]
EXEC    ENDP

POSTPR  PROC    NEAR            ;Clear memory
        MOV     AX,CS           ;Get current segment
        DEC     AX
        MOV     DS,AX           ;Point DS to memory control block
```

SAVE UP TO $53.35 WHEN YOU SUBSCRIBE

GET YOUR FREE COPY OF PC TECH JOURNAL'S DATA MANAGER REVIEW

If you're a systems integrator, designer, consultant, or DP/MIS pro involved in technologically advanced applications, you need **PC Tech Journal**. You'll receive 13 issues a year—including **The PC Tech Journal Directory Issue**, a complete, indexed reference to the products, applications and innovations covered in **PC Tech Journal**! *Special Offer*—Act today and you'll also receive the PC Tech Journal Data Manager Review, a comprehensive report covering 7 leading data managers—with benchmark tests!

Your PC Tech Journal Data Manager Review will be shipped upon payment.

Please begin my subscription to PC Tech Journal for:

☐ One year (13 issues) for **26.70**—I'll save over $26!
☐ Two years (26 issues) for **$53.35**—I'll save over $53!

SAVINGS BASED ON ANNUAL SINGLE-COPY PRICE OF $53.35

Mr./Mrs./Ms. _____
Please Print Full Name 4S747

Company _____

Address _____

City _____ State _____ Zip _____

ADD $8 per year for postage outside USA. US currency only. Please allow up to 60 days for delivery of first issue. Basic annual subscription price is $34.97.

☐ Bill me later ☐ Payment enclosed

Please complete the following questions:

1. Is above address:
A. ☐ Business B. ☐ Home C. ☐ If home and business are the same.
(If home address, please provide your business information.)

Company Name
Division
Company Street Address
Company City State Zip Code
Telephone

2. How would you describe your company or organization. (Check one only):
A. ☐ Value-Added Reseller, Value-Added Dealer or Systems House
B. ☐ Computer Consultant
C. ☐ Computer Retailer
D. ☐ Distributor of Computer Products
E. ☐ Manufacturer/Publisher of Computer Hardware or Software
F. ☐ End-User Company or Organization that does not manufacture, distribute or resell computer products.
G. ☐ Other _____.
please specify

3. What is your primary job function as it relates to computer activities within your own organization? (Check one only):
A. ☐ Systems Design/Integration/ Analysis
B. ☐ Data Communications
C. ☐ DP/MIS Management/Operations
D. ☐ Inside Consulting
E. ☐ Outside Consulting
F. ☐ Software Engineering
G. ☐ Hardware Engineering
H. ☐ Programming
I. ☐ Research and Development
J. ☐ General Management/ Administration
K. ☐ None of the Above

4. Which of the following systems activities takes place in your department. (Check all that apply):
A. ☐ Application Development
B. ☐ Programming
C. ☐ Systems Integration/Development
D. ☐ Networking of PC to PC or PC to Mini/Mainframe
E. ☐ None of the Above

5. Check the products that you personally evaluate, recommend or select. (Check all that apply):
A. ☐ IBM or Compatible Microcomputers
B. ☐ Peripherals
C. ☐ Software
D. ☐ Communications Products
E. ☐ None of the Above

Date _____ Signature _____

Z015

Please begin my subscription to PC Tech Journal for:

☐ One year (13 issues) for **$26.70**—I'll save over $26!
☐ Two years (26 issues) for **$53.35**—I'll save over $53!

SAVINGS BASED ON ANNUAL SINGLE-COPY PRICE OF $53.35

Mr./Mrs./Ms. _____
Please Print Full Name 4S747

Company _____

Address _____

City _____ State _____ Zip _____

ADD $8 per year for postage outside USA. US currency only. Please allow up to 60 days for delivery of first issue. Basic annual subscription price is $34.97

☐ Bill me later ☐ Payment enclosed

Please complete the following questions:

1. Is above address:
A. ☐ Business B. ☐ Home C. ☐ If home and business are the same.
(If home address, please provide your business information.)

Company Name
Division
Company Street Address
Company City State Zip Code
Telephone

2. How would you describe your company or organization. (Check one only):
A. ☐ Value-Added Reseller, Value-Added Dealer or Systems House
B. ☐ Computer Consultant
C. ☐ Computer Retailer
D. ☐ Distributor of Computer Products
E. ☐ Manufacturer/Publisher of Computer Hardware or Software
F. ☐ End-User Company or Organization that does not manufacture, distribute or resell computer products.
G. ☐ Other _____.
please specify

3. What is your primary job function as it relates to computer activities within your own organization? (Check one only):
A. ☐ Systems Design/Integration/ Analysis
B. ☐ Data Communications
C. ☐ DP/MIS Management/Operations
D. ☐ Inside Consulting
E. ☐ Outside Consulting
F. ☐ Software Engineering
G. ☐ Hardware Engineering
H. ☐ Programming
I. ☐ Research and Development
J. ☐ General Management/ Administration
K. ☐ None of the Above

4. Which of the following systems activities takes place in your department. (Check all that apply):
A. ☐ Application Development
B. ☐ Programming
C. ☐ Systems Integration/Development
D. ☐ Networking of PC to PC or PC to Mini/Mainframe
E. ☐ None of the Above

5. Check the products that you personally evaluate, recommend or select. (Check all that apply):
A. ☐ IBM or Compatible Microcomputers
B. ☐ Peripherals
C. ☐ Software
D. ☐ Communications Products
E. ☐ None of the Above

Date _____ Signature _____

Z015

NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY MAIL

FIRST CLASS PERMIT #66 BOULDER, COLORADO

POSTAGE WILL BE PAID BY ADDRESSEE

TECH JOURNAL

P.O. Box 52079
Boulder, Colorado 80321-2079

NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY MAIL

FIRST CLASS PERMIT #66 BOULDER, COLORADO

POSTAGE WILL BE PAID BY ADDRESSEE

TECH JOURNAL

P.O. Box 52079
Boulder, Colorado 80321-2079

```
X2:     ADD     AX,DS:[3]       ;Point to end of block
        INC     AX              ;Point to next ctrl block
        MOV     DS,AX
        CMP     WORD PTR DS:[1],0       ;Is block in use?
        JNZ     X5              ;Yes: skip the fill
        INC     AX              ;No:  point to its start
        MOV     ES,AX
        MOV     DX,DS:[3]       ;Get length of block
        MOV     CL,4
        ROL     DX,CL           ;Convert to bytes
        MOV     BL,DL           ;Get full segments in BL
        AND     BL,0FH          ;Any full segments?
        JZ      X4              ;No:  go do partial segment

X3:     XOR     AX,AX           ;Yes: fill it with zeroes
        MOV     DI,AX           ;Start at offset zero
        MOV     CX,8000H        ;Words in full segment
        REP     STOSW           ;Fill the segment
        MOV     AX,ES           ;Point to next segment
        ADD     AX,1000H
        MOV     ES,AX
        DEC     BL              ;Any more full segments?
        JNZ     X3              ;Yes: repeat

X4:     AND     DX,0FFF0H       ;Any partial segment?
        JZ      X5              ;No:  done with this block
        SHR     DX,1            ;Yes: convert to word count
        MOV     CX,DX
        XOR     AX,AX           ;Clear partial segment
        MOV     DI,AX
        REP     STOSW
        MOV     AX,DS           ;Restore AX to block addr
X5:     CMP     BYTE PTR DS:[0],'Z'     ;Is this last block?
        JNE     X2              ;No:  loop for next block
        RET
POSTPR  ENDP

; Data for INT23 Proc.

CTRLBRK$        DB      0DH, 0AH, '*BREAK*', 0DH, 0AH
MSGLEN  EQU     $-CTRLBRK$

; INT23 Proc is executed whenever Ctrl-Break is recognized.

INT23   PROC
        LEA     BX,CTRLBRK$     ;Point to message
        MOV     CX,MSGLEN       ;Get message length

Y1:     MOV     DL,CS:[BX]      ;Get next character
        MOV     AH,6            ;Console output function
        INT     21H             ;Send to standard output
        INC     BX
        LOOP    Y1

        MOV     AX,4CD8H        ;Set return code 0 & terminate
        INT     21H
INT23   ENDP

INIT    PROC
        ASSUME  DS:CODE
        MOV     AX,3521H        ;Get current INT 21H address
        INT     21H
        MOV     OFF21,BX        ;Save it in data area
        MOV     SEG21,ES
        LEA     DX,EXEC         ;Replace with new address
        MOV     AX,2521H
        INT     21H
        LEA     AX,RETPTR       ;Initialize addr pointer
        MOV     RETPTR,AX
        LEA     DX,INIT         ;End of resident code
        INT     27H             ;Terminate & stay resident
INIT    ENDP
CODE    ENDS
        END     ENTRY
```


REQUIRED READING FOR ALL IBM PC SYSTEMS EXPERTS

If you're a systems expert, microcomputer specialist, or MIS/DP professional working with IBM PCs, you need the comprehensive information PC TECH JOURNAL provides 13 times a year!

It's the only magazine that provides you with the technical information to help you increase the performance of your multi-component system. It talks to systems experts and systems designers in the language you understand—about the applications and products you have to know about!

As part of your annual subscription to PC TECH JOURNAL, you'll receive the special PC TECH JOURNAL Directory issue published in November, the most comprehensive guide and index to the products in the PC marketplace and PC TECH JOURNAL's coverage!

Don't leave a gap in your required reading, subscribe to PC TECH JOURNAL now and *save 50%!*

For faster service call Toll-Free 1-800-852-5200

PC TECH JOURNAL
P.O. Box 2966
Boulder, CO 80322

SAVE 50%!

Send me PC TECH JOURNAL for:

☐ One year (13 issues) for $26.70.
☐ Two years for $53.35.

Savings based on annual single-copy price of $53.35.

Mr./Mrs./Ms. _____
(please print full name)
Company _____
Address _____
City _____ State _____ Zip _____

☐ Bill me ☐ Payment enclosed

Add $6 per year for postage outside USA, US currency only. Please allow up to 60 days for delivery of first issue. Annual Basic subscription price is $34.97.

4Z692

AW . . .

WHAT THE HECK!

ProDesign II — Still $299!

ProDesign II — the Easy-to-Use CAD System. .The CAD system that was introduced two years ago for the amazingly low price of $299. The CAD system that has undergone four major revisions with more than 400 enhancements. The CAD system that still costs only $299!

How do we do it? Our accountants said to raise the price to cover research and development costs. Our business advisors said to charge more for the additional features. Our competitors said it's impossible to stay in business selling a comprehensive CAD package such as ProDesign II for only $299.

And our customers said $299 is great. So, we said:

"Aw . . . What the Heck! $299 it is!"

Now, two years after its introduction, ProDesign II is one of the world's leading CAD packages. It has features previously found only on CAD systems costing thousands of dollars. For the single price of $299, you get these features and more:

- Support for more than 180 printers (including color printers)
- Support for more than 80 plotters, with plotter optimization.
- Easy-to-Use single keystroke commands.
- On-screen menus accessible with a mouse.
- Comprehensive drawing commands, including the finest curve fitting in the industry.
- Editing features unsurpassed by ANY other CAD package.
- Extensive snap features, including snap to point, endpoint, midpoint, line, circle, ellipse, arc, intersection, and perpendicular.
- True Auto Dimensioning with several formats.
- Extensive Layering features.
- Full Macro capabilities.
- Specialized drawing aids, such as tangents to circles and ellipses, parallel lines, parallel curves, wide lines, and more.
- Complete hatching with up to 40 different patterns.
- Area and length calculation for line curves, circles, etc.
- Full Zoom, Pan, and Rotate capabilities.
- Capability to transfer drawings to and from other programs.
- Capability to Break/Trim Lines, Curves, Circles, Arcs, and Ellipses.
- Many more features — *All for only $299!*

Where do you get ProDesign II? See your local computer dealer, or contact:

American Small Business Computers, Inc.
118 South Mill Street
Pryor, OK 74361
(918) 825-4844
Telex 9102400302

Want more information? Call or write for a detailed brochure and a free demo disk!

PRODESIGN II STILL ONLY $299!

CIRCLE NO. 115 ON READER SERVICE CARD

Reviews and Updates

TOM RETTIG'S LIBRARY, CLIPPER EDITION
Tom Rettig Associates

R-CARD
Rodime, Inc.



MEGA
Mylex Corporation

TOM RETTIG'S LIBRARY, CLIPPER EDITION
Tom Rettig Associates
9300 Wilshire Blvd., Suite 470
Beverly Hills, CA 90212
213/272-3784

PRICE: $99.95



CIRCLE 349 ON READER SERVICE CARD

Tools of variety and quality distinguish a professional toolkit; for programmers working in a compiled language, one useful tool is a library of routines that link with programs for integration into applications. Tom Rettig's Library, Clipper Edition, Advanced Extended Library, by Tom Rettig Associates, is a professional, easy-to-use tool for the programmer working in the dBASE language using the Clipper compiler by Nantucket, Inc. (see "Dialects of dBASE," Ted Mireki, this issue, p. 46).

The Clipper compiler allows programmers to write user-defined functions (UDFs), link them with a compiled dBASE program, and execute them from within the program. The Clipper Edition of Tom Rettig's Library provides more than 150 prewritten functions and procedures for use in developing Clipper-compiled programs. Only representative examples in each category follow.

Arrays. Clipper's array-handling capabilities are enhanced with 15 functions and procedures, such as READARRC, which reads a character array from disk.
Business. Eight functions provide various business aids, such as DEPDB(), which calculates depreciation by declining balance, and TOMONEY(), which expresses numbers in dollars and cents for applications such as check writing.
Character. Nineteen functions process text and characters, such as CENTER(), which automatically creates a string of a given length with the specified text centered within the string.
Database. Eight functions help manage database files, such as FLDCOUNT(), which returns the number of fields in the file structure.
Date. Eighteen functions process dates, such as BOW(), which returns the date of the previous Monday (that is, the beginning of the week).
Debugging. Two procedures help to debug programs; one is MEMDUMP, which produces a hexadecimal dump of variable storage.
Disk. Five functions provide disk management. One is CURDRIVE(), which returns the current default drive to help the program manage the disk interface.
Memo. Three functions are useful in the processing of memo fields, such as LINES(), which calculates the number of lines required to output the memo field at a specified line width.
Miscellaneous. Three other uncategorized functions are included, such as STATUS(), which returns the current value of a specified SET switch.
Numeric. Twenty-one functions provide number-processing conversion, such as LOGNBASX(), which checks general logarithmic calculations.
Printer. Five print functions are provided, such as ISPRINTER(), which checks status and manipulates printers.
Screen. Six functions provide screen management, such as CURSOR, which turns the cursor display on and off.
System. Twenty-one advanced functions and procedures direct interface with the computer system, such as REG(), which reads the contents of a CPU register.
Time. Twelve functions manipulate time, such as TIMESTR(), which creates a time string from a number of seconds.
Stand-alone utilities. Five stand-alone programs are provided, such as FATTRIB, which modifies file attributes.

No advanced programming skills beyond those needed to create programs with Clipper are needed to use the functions and procedures in Tom Rettig's Library. The programmer simply refers to the desired function or procedure as if it were an existing dBASE III or Clipper function or procedure, compiles the program, and names the library (along with the standard Clipper library) at the link step. If the compiler cannot recognize the name of the function (for example, if the function is generated through macro substitution), it must be named in an EXTERNAL statement in the calling program. Procedures are executed with either the CALL or the DO statement. Minimal error trapping in the library's routines provide maximum performance—the documentation wisely cautions careful and proper use of the routines.

The routines are written in dBASE, assembly language, and C, as appropriate. In addition to the object files used for linking, all source code is included. Thus, experienced programmers can tailor routines to specific needs; the beginner can learn more about interfacing with C and assembly language using Clipper-compiled programs. Besides the functions called from dBASE programs, the library has a number of low-level, internal routines called by these functions. For advanced programming applications, these routines may be called from the programmer's C or assembly UDFs, but the documentation for these functions is mainly commented source code.

Tom Rettig's Library, Clipper Edition, is provided on three diskettes. Two versions of the library are available: 1.02 is for use with the winter 1985 version of Clipper, and 1.03, for the autumn 1986 version. The documentation consists of 170 loose-leaf pages that are hole-punched for insertion into the Clipper documentation binder. Function and procedure documentation is in a page-per-command format. A plastic reference card also is included. The contents of the user manual are generally clear and complete. An understandable explanation of the license agreement describes how the license grants the right for the programmer to incorporate code from the library into a software application, place the programmer's copyright notices into the application, and distribute copies of the incorporated library code as a part of the application without additional fee. A 30-day satisfaction guarantee and a one-year warranty against significant bugs also are provided; the programs are not copy protected.

Tom Rettig's Library, Clipper Edition, is a valuable set of tools that should be a part of every programmer's Clipper toolkit.

—DAVE BROWNING

R-CARD

Rodime, Inc.
29525 Chagrin Blvd., Suite 214
Pepper Pike, OH 44122
216/765-8414

PRICE: 37MB, $1,295; 45MB, $1,495



CIRCLE 348 ON READER SERVICE CARD

Rodime R-Cards bring both high performance and high capacity to the world of hard-disk cards. They are available with either a 37MB or 45MB capacity. The test unit was the 45MB model; the 37MB model has the same specifications, but it has one less disk surface.

Each R-Card consists of a Rodime hard disk and a Western Digital controller mounted on a black-anodized metal bracket. The construction quality is excellent; the fit and finish of all parts indicate a high degree of care in design and assembly. The read/write heads are voice-coil activated and, as befits a high-performance disk, they automatically park and lock when power is removed, minimizing the chance of a head crash.

The R-Card can be installed as the first or second hard disk in a system. It consumes 17.1 watts of power while running and even more at start-up, so a 135-watt power supply is needed. The R-Card uses one full slot if installed in the far left slot (with the speaker moved); otherwise, the slot next to it is limited to short cards only. While the controller receives all its power from the computer's bus, the disk requires a separate connection to the power supply. A Y-connector is provided for power supplies that lack an extra lead. Although quiet when running, the unit emits a loud click when power is either applied or removed.

The manual is clear and complete. Low-level formatting, partitioning, logical formatting, and copying of system files are all carried out smoothly by a menu-driven utility program. The interleave factor, which cannot be changed with the supplied software, is 3.

Rodime does not provide a utility to overcome the DOS-imposed limit of 32MB per volume, but some readily available products do perform this function (such as Golden Bow Systems' VFeature Deluxe). The R-Card can be divided into as many as eight logical disks with a total capacity of 45MB. No problems occurred when using various hard-disk utilities (such as Fifth Generation Systems' Fastback, Executive Systems' Xtree, and The Norton Utilities) on these configured disks.

To take advantage of this partitioning scheme, logical formatting must be performed using Rodime's software, not the DOS FORMAT program. However, Rodime's formatter establishes wastefully large cluster sizes (as in DOS 2.x). In the unit tested, for example, a 13MB partition was formatted with clusters of 4KB, and a 32MB partition with clusters of 8KB. Disks of this size, formatted using FORMAT from DOS 3.0 (or later), would have clusters of 2KB, allowing more economical use of disk space.

The R-Card is faster than any of the hard-disk cards reviewed in "Mass-Storage Mergers," (Peter G. Aitken, January 1987, p. 76). In fact, with an average ac-

THE COMMUNICATIONS PROGRAM THAT DOES ALL THIS ON DOS, UNIX, XENIX AND VMS:

TERM
COMMUNICATIONS SOFTWARE

TERM's built-in script language is so sophisticated that it allows exact solutions to be tailored to your specific needs. Over 25 pre-built scripts are provided for solving complex communication problems. **TERM** comes with nine protocols, six terminal emulations including DEC with full graphics character support even under UNIX.

TERM is available now on AT&T, DEC VAX, MICROVAX, IBM XT, AT, Sun, Altos, HP series 200, 300, Tandy,Fortune, Convergent, NCR, Sperry, Zilog, Plexus, Intel, Motorola and many others.

- State-of-the-art Lempel-Ziv-Welch data compression
- Exact VT102 Emulation on ALL systems
- Full numeric keypad support
- Full color support
- 19.2K file transfers
- KERMIT Protocol for mainframes
- XMODEM Protocol for bulletin boards
- Remote PC execution
- Powerful script language for customized applications
- Wildcard file send/receive capability
- Auto-login, dial/redial modem control
- Unlimited autodial directory
- Performs unattended file transfers
- Remote maintenance capability
- Online User's Manual for instant help
- Electronic mail/TELEX interface

PRICES FROM $195.
VISA/MC

CENTURY SOFTWARE
9558 South Pinedale
Salt Lake City, Utah 84092
(801) 531-8512

CIRCLE NO. 188 ON READER SERVICE CARD

TABLE 1: *Vital Statistics*

SPECIFICATIONS[a]	
Data encoding method	MFM
Interleave factor	3
Power consumption (watts)	17
Warranty (months)	12
Calculated MTBF (K hours)	18
DISK PARAMETERS[a,b]	
Surfaces	6
Tracks	865
Sectors per track	17
Bytes per sector	512
Sectors per cluster	8 or 16
Total space (bytes)	45,173,760
FEATURES[a]	
Activity Indicator	no
All power from bus	no
Runs in 63.5-watt PC	no
Automatic head locking	yes
Factory low-level format	no
Coexistence with 2nd drive	yes
Install program	yes
PERFORMANCE[a] **(ATDISK)**	
Track-to-track seek time (ms)	5.8
Average seek time (ms)	28.8
Effective transfer rate (KB/sec)	84.8
DOS file I/O (seconds)	10.8

[a] *The Rodime R-Card can be compared with other hard-disk cards reviewed in "Mass-Storage Mergers," Peter G. Aitken, January 1987, p. 76. For specifications and disk parameters, refer to table 2 (p. 82). For features, refer to table 1 (p. 80). For performance, refer to table 3 (p. 84).*

[b] *The 45MB R-Card's logical specifications were determined by the utility program INFO.EXE ("Finding Disk Parameters," Glenn F. Roberts, May 1986, p. 112). The R-Card was configured into a 32MB and 13MB drive, INFO run on both, and the results combined.*

The R-Card's performance is excellent. Its average access time is comparable to that of many disks intended for use with the PC/AT.

cess time of less than 30 milliseconds, its performance is in the same league with many disks used with the PC/AT. Like all other hard-disk cards, however, the R-Card will not work in the AT because of BIOS incompatibilities. The results of the ATDISK hard-disk benchmark program are shown in table 1.

Both R-Card models provide a level of disk performance unmatched by other hard-disk cards—indeed, their speed is matched by few PC disks of any kind. Such performance can make a big difference, particularly in disk-intensive applications such as large databases. In conjunction with an add-on accelerator board, an R-Card could considerably narrow the performance gap between the PC and the AT.

—PETER G. AITKEN

At last! - Fast, On-screen

FLOWCHARTS

Finally! An on-screen flowchart processor that knows about flowcharts - not just another "screen draw" program that makes you do most of the work.

Interactive EasyFlow is a powerful full-screen graphics program dedicated to flowcharts and organization charts. With this program you can quickly compose charts on the screen. More important, you can easily modify charts so they are always up to date.

Features: • Text is automatically centered, character by character, within shapes as you type it • Text formatting controls allow you to over-ride the automatic formating where desired • Lines are created by specifying the starting and ending points - the program automatically generates the route • Cut and paste facility allows arbitrary chart fragments to be moved, copied rotated, reflected or sent to/from disk • Shape insert-delete and row/column insert-delete • Charts can be up to 417 characters wide by 225 lines high. Charts too wide for the printer are automatically printed in strips. • Charts can be larger than the screen - the window into the chart scrolls both horizontally and vertically as necessary • Works with many popular matrix printers including Epson, IBM graphics printer and compatibles. Full support for HP LaserJet and LaserJet Plus. Works with HP 7475A (& compatible) plotters. Can be used with ANY printer when non-graphic (character) output is acceptable • All standard flowcharting shapes included • Most shapes supplied in large, medium and small sizes • Extensive manual (100+ pages) includes many examples • Context sensitive "help" facility provides immediate assistance at any time • Any number of titles can be placed on a chart • Commentary text blocks can be placed anywhere in the chart • Fast: written in assembly language • Plus many more features than we can mention here

Requires at least 320K memory, DOS-2 or higher and an IBM or Hercules compatible graphics card. On EGA, full 640x350 resolution is used.

Order direct for only **$149.95** + $2.00 S&H (USA/Canada), $10.00 (foreign). Payment by MO, check, VISA, MasterCard, COD or Company PO. Rush orders accepted ($15.00 S&H; USA/Canada only). Rush orders received by noon will be delivered the next business day (to most locations).

Order Desk: 1-800-267-0668

The sample screen display shown below is typical of what you see while editing a chart. Other screen displays are provided for entering titles, changing options, getting "help" and so on.

STATUS BAR (not to be confused with a wet bar) tells you what Interactive EasyFlow is doing at all times.

CHART WINDOW gives an overview of your chart; this example shows the "normal" view. "Close-up" view shows a smaller part of the chart in more detail. "Wide-angle" view shows a larger part of the chart at reduced size.

TEXT/MESSAGE WINDOW used to enter user text and to display messages from Interactive EasyFlow.

CURRENT SHAPE WINDOW - shows the content of the current flowchart shape (the one under the SHAPE CURSOR) in complete detail.



SHAPE CURSOR shows where you are in the chart. Cursor keys move it around; chart window scrolls if you run off the edge of the window.

HavenTree Software Limited
P.O. Box 1093-N
Thousand Island Park, NY 13692
Information: (613)544-6035 ext 48

CIRCLE NO. 113 ON READER SERVICE CARD

9-TRACK TAPE
OCR SCANNING
WP CONVERSION

For thousands of customers world wide, we supplied the connection to get information into their PC.

Our **"SCANNING CONNECTION"** system can scan images for use with desktop publishing systems, convert images to text using our OCR software and send images to facsimile machines.

Our **"TAPE CONNECTION"** system can read and write 1/2" 9-Track 800/1600/6250 GCR magnetic tapes from large computer systems. Our **"DISKETTE CONNECTION"** system can read and write most 3½", 5¼", and 8" diskettes.

For more information please call us at 602-779-3341.

FLAGSTAFF ENGINEERING
1120 Kaibab
Flagstaff, AZ 86001

Personal REXX
for the IBM PC

- ★ Interpreter for the full REXX language, including all of the standard REXX instructions, operators, and built-in functions
- ★ Sophisticated string manipulation capabilities
- ★ Unlimited precision arithmetic
- ★ Direct execution of DOS commands from REXX programs
- ★ Built-in functions for DOS file I/O, directory access, screen and keyboard communication, and many other PC services
- ★ Compatible with VM/CMS version of REXX
- ★ Uses include:
  - — Command programming language for DOS
  - — Macro language for the KEDIT text editor
  - — Can be interfaced by application developers with other DOS applications, written in almost any language

Mansfield Software Group, Inc.
P. O. Box 532
Storrs, CT 06268
(203) 429-8402

$125 plus $3 shipping
MC, VISA, AMEX, COD, PO, CHECK

CIRCLE NO. 263 ON READER SERVICE CARD

MEGA
Mylex Corporation
5217 N.W. 79th Avenue
Miami, FL 33166
305/592-9669

PRICE: $399



CIRCLE 347 ON READER SERVICE CARD

Since the IBM Enhanced Graphics Adapter (EGA) has now become entirely a commodity item, users may have a difficult time choosing from among the increasing number of EGA boards on the market. Thus, it is noteworthy when a new entry provides some added feature that differentiates it from other EGAs available.

This is the case with MEGA, a new EGA board from Mylex Corporation. MEGA is a full-length display board that uses Chips and Technologies (C&T) circuitry and the trapping-software technique for Hercules, IBM Color Graphics Adapter (CGA), and Monochrome Display and Printer Adapter emulation. Mylex configured the board with 256KB of video RAM; no parallel or serial port options are available with it.

What sets MEGA apart from other EGA boards is its font-editor utility. With this font editor, the user can design custom fonts, such as mathematical symbols, for use in specific applications. The MEGA font editor can create a font image in C source files, assembly source files, or in straight binary image, and also can load a font into the EGA's font plane. This utility could prove invaluable for redefining fonts and using alternative fonts in text modes.

Otherwise, MEGA's features are not remarkable. Its operation is controlled by eight mode switches that are accessible through the mounting bracket without opening up the system unit. These switches control the initial mode of the display adapter at boot-up, multiple-display-adapter emulation, and the monitor selection. A jumper changes the MEGA's I/O address base from 3xx to 2xx, following the IBM EGA standard.

MEGA supports only the standard EGA operating modes; it does not provide the higher vertical-resolution modes available with variable-scan-rate monitors. However, it does provide the trapping-software solution for CGA and Hercules emulation. The user installs the RAM-resident software that is provided for setting the emulation traps, and it places the board into an emulation mode. Then MEGA will issue a nonmaskable interrupt to the CPU when the software issues I/O instructions to CGA- or Hercules-specific I/O registers. (For further details of the trapping-software method of Hercules and CGA emulation, see "Evaluating the EGA: The EGA Spectrum, Part 2," John Cockerham, November 1986, p. 147.)

The MEGA board was tested using the *PC Tech Journal* EGA test suite described in the aforementioned article. Its C&T hardware passed all tests with ease because it is a replica of the IBM chip set. Like all other C&T boards (and the IBM EGA), MEGA duplicates the first scan line in EGA mode 16 (high-resolution graphics) when the split-screen mode is first entered.

The board could not pass all of the emulation tests; specifically, it could not emulate the CGA low-resolution games, in 160-by-100 mode because the hardware does not support this mode. However, MEGA did pass the FantasyLand test and EGATEST. Both Microsoft Windows and Graphics Software Systems' CGI operated flawlessly in native EGA, CGA, and Hercules modes.

The timing tests confirm the electronic similarity of MEGA to other C&T EGA implementations. The dot-plot benchmark times (65,000 iterations in graphics mode 16) were identical to the times for all other boards for subroutine calls (20.7 seconds) and in-line I/O (17.9 seconds). The BIOS dot-plot time, though, was one of the slowest—49.8 seconds. Examination of the BIOS reveals that function calls are dispatched through a test-and-branch sequence rather than through a transfer table.

Other BIOS errors are present as well. As with the IBM EGA, warm reboots of the CPU take a long time because the software writes over the reboot flag during EGA video RAM testing. Mode changes produce a fair amount of snow on the screen—presumably because video-driver output to the CRT is not disabled during a mode change. The cursor emulation routines are correct; however, the standard double-line cursor is reduced to a single line after additional fonts have been loaded into the font plane. Lastly, the graphics-mode character-painting routines do not paint the characters in user-designated colors.

The BIOS correctly implements the EGA BIOS save-area features, where a copy of the palette is stored, and the Alternate Print Screen routine runs correctly. The Mylex BIOS passes all unrecognized function calls to interrupt 42.

The installation and set-up of the adapter is adequately documented. However, a technical description of the EGA's function is not included.

Like most of the other EGA-compatible display boards, the Mylex MEGA has its share of correctable BIOS bugs. The C&T chip set guarantees compatibility with existing EGA software. Its distinguishing characteristic from the other boards, however, is its font editor; it is an excellent utility. Other font-editing utilities are available, but the bundling of this one with the MEGA may very well be the reason to choose this display board over another one.

—JOHN T. COCKERHAM

REQUIRED READING FOR ALL IBM PC SYSTEMS EXPERTS

If you're a systems expert, microcomputer specialist, or MIS/DP professional working with IBM PCs, you need the comprehensive information PC TECH JOURNAL provides 13 times a year!

It's the only magazine that provides you with the technical information to help you increase the performance of your multi-component system. It talks to systems experts and systems designers in the language you understand—about the applications and products you have to know about!

As part of your annual subscription to PC TECH JOURNAL, you'll receive the special PC TECH JOURNAL Directory issue published in November, the most comprehensive guide and index to the products in the PC marketplace and PC TECH JOURNAL's coverage!

Don't leave a gap in your required reading, subscribe to PC TECH JOURNAL now and *save 50%!*

For faster service call Toll-Free 1-800-852-5200 today!

PC TECH JOURNAL *P.O. Box 2966—Boulder, CO 80322*

Send me PC TECH JOURNAL for: **SAVE 50%!**

☐ One year (13 issues) for $26.70.

☐ Two years for $53.35.

Savings based on annual single-copy price of $53.35.

Mr./Mrs./Ms. _____
(please print full name)

Company _____

Address _____

City _____ State _____ Zip _____

☐ Bill me ☐ Payment enclosed

Add $6 per year for postage outside USA, US currency only. Please allow up to 60 days for delivery of first issue. Annual Basic subscription price is $34.97. 4Z684

PC ⇔ MAINFRAME
VIA 9-TRACK TAPE

For Information Interchange – Backup – Archival Storage

IBM format compatible 9-track, ½ inch magnetic tape is the universally accepted media for mainframes and minicomputers. Catamount offers *Low Cost, Lightweight* 9-track Tape Subsystems for the IBM-PC/XT/AT computers which allow:

- Reading tapes generated on mainframes and minicomputers.
- Writing tapes to be read on mainframes and minis.
- ASCII, EBCDIC and Binary tapes accommodated.
- 800 bpi NRZI, 1600/3200 bpi PE, and 6250 bpi GCR format systems available.
- Storage capacities up to 270 MB on a single reel.

Systems come complete with comprehensive DOS command syntax oriented software and an Installable Device Driver. For OEM applications, the tape controller is available separately.

CATAMOUNT CORPORATION

2243 Agate Court
Simi Valley, CA 93065-1898
(805) 584-2233
FAX: 805-584-0941

CIRCLE NO. 111 ON READER SERVICE CARD

Modula-2
IBM PC/DOS
Native Code Compiler

This is a full implementation of Niklaus Wirth's Modula-2 language. Our product is not an interpreter, but a true 8086 compiler, using state-of-the art techniques. A Unix-like "make" utility is included which provides automatic recompilation of modified source programs.

The code generator produces object module input for the DOS link utility. You may combine your Modula-2 programs with code from other languages such as Assembler. The software also operates on PC compatibles using MS/DOS. All the run time source code is included. None of the software is copy protected, and is fully supported and maintained by farbware. No royalties are charged for the use of the run time object. A complete and comprehensive reference manual is included in the purchase price. The manual is available separately for $25.00.

Site licenses and quantity discounts are available.

$89.95 Complete

farbware
1329 Gregory
Wilmette, IL 60091
(312) 251-5310

Master Card and Visa Accepted

CIRCLE NO. 117 ON READER SERVICE CARD

8080 Z80 6809 — AMX — 8086 8088 — Now 68000

Real-Time Multitasking Executive

- No royalties
- Source code included
- Fault free operation
- Ideal for process control
- Timing control provided
- Low interrupt overhead
- Inter-task messages



AMX is TM of KADAK Products Ltd.
CP/M-80 is TM of Digital Research Corp.
IBM, PC DOS are TM of IBM Corp.

Options:

- Resource Manager
- Buffer Manager
- Integer Math Library
- Language Interfaces : C, Pascal, PL/M, Fortran
- DOS File Access : CP/M-80, IBM PC DOS

AMX for 8080	$ 800 US
8086	950
6809	950
68000	1600
Manual (specify processor)	75

KADAK Products Ltd.
206–1847 W. Broadway, Vancouver, B.C., Canada V6J 1Y5
(604) 734-2796
Telex: 04-55670

CIRCLE NO. 258 ON READER SERVICE CARD

QuickBASIC just got quicker with QuickPak

QuickPak is a superb collection of enhancements, subroutines, and instructional material designed to help you get the most out of programming in BASIC.

- Powerful assembly language routines to give your programs more speed, more power, and full access to DOS and BIOS services. SORT all or part of a string array with one command! Complete windowing capability — display help screens instantly, overlay text. FIND any string or sub-string within an entire array *regardless of capitalization* — accepts wildcards. READ directories into your programs from any drive or path. READ/WRITE disk sectors — create your own DOS utilities! MANY, many more programs included.
- Professionally written QuickBASIC routines and functions. Powerful input routines for text, dates, and numbers. Menus, scroll bars, date/time functions, and much more.
- The Assembly Tutor — a complete guide to learning assembly language *from a BASIC perspective.* Learn how to create your own routines and extensions.
- Tips and Tricks book — packed with clever ideas and techniques to help *you* be a better programmer.



You get all this, all of the source code for *every program included,* and a thirty-day money back guarantee for only $69.00.

No royalties are required for using any of the QuickPak routines in your programs. Not copy protected, of course.

by
CRESCENT SOFTWARE
64 Fort Point Street, East Norwalk, CT 06855
(203) 846-2500

QuickPak requires Microsoft QuickBASIC or BASCOM, DOS 2.0 or higher. Visa, M/C, C.O.D., or checks accepted.

CIRCLE NO. 145 ON READER SERVICE CARD

Liability and Expert Systems

What are the legal ramifications of developing and marketing expert systems that may surpass their human counterparts in speed and accuracy?



ILLUSTRATION • MACIEK ALBRECHT

The time may be coming when expert systems will take over and then surpass some functions of their human counterparts in professions such as medicine, engineering, law, accounting, and computer science. Presumably, at least in its early stages, an expert system will suffer from many of the same frailties as its human counterpart: it will make mistakes. It has been years since an American court executed a horse as a witch, and it is doubtful that modern precedent exists for "punishing" an offending computer system. However, if a computerized expert system errs and an injury ensues, the fact that the injury was caused by a cold, dispassionate machine rather than a warm human will not likely deter the injured party from seeking compensation.

What are the risks in developing, marketing, and using expert systems? What standards of care are required? Will the day come when it will be malpractice for a professional *not* to use an expert system? (If that comes about, what a terrific marketing tool!)

These questions do not have definitive answers yet: the law is designed to respond to concrete issues rather than hypothetical situations. This article explores some considerations that should be given attention in developing and marketing expert systems. A subsequent article will consider some possible paths the law might take in responding to the emergence of expert systems for professional applications, with a view to developing a strategy for protecting oneself from liability.

For a system in a highly regulated field that poses most of the issues, consider a medical diagnostic system. Other professions are subject to similar types of regulation and accountability.

The developer of a diagnostic system must be aware that medicine is regulated in several areas: the federal Food and Drug Administration (FDA) reviews new drugs and medical devices before they can be introduced into the market; third-party insurers (such as Blue Cross) and federal and state departments of health and human services control the flow of significant funds to health care providers; states license individual physicians to practice medicine. The *malpractice* of medicine is dealt with civilly through lawsuits seeking compensation and in a regulatory framework by suspending or revoking licenses to practice. What are some of the regulatory hurdles that can be expected from these agencies?

One of the first questions to ask is: does the system require FDA approval? The FDA regulates not only drugs but also medical devices, which include "an instrument, apparatus, implement, machine, contrivance...or other similar or related article, any component, part, or accessory, which is ... intended for use in the diagnosis of disease or other conditions, or in the cure, mitigation, treatment, or prevention of disease, in man or other animals. . ." (21 United States Code Section 321).

If the system is within this definition, the developer must submit a premarket notification to the FDA at least 90 days before introducing the device into interstate commerce and again whenever significant modifications are made. All devices subject to FDA jurisdiction must meet general requirements including registration, quality control, and record keeping.

How would the developer go about demonstrating compliance with a performance standard? In the early stages of artificial intelligence, it might be possible to have a panel of experts give second opinions on a system's diagnoses. However, if expert systems advance beyond what humans can do, how would compliance be demonstrated once the system's "artificial" intelligence surpasses the natural intelligence of the evaluators? With luck, while the system is being developed the FDA will have been developing a system expert in evaluating expert systems.

Current payment mechanisms for medical services should be able to add expert systems as an insurable expense. Third-party payment plans typically pay not only the fees of treating physicians, but also the costs of laboratory and diagnostic tests. It should be a short step to the proposition that expert systems are like laboratory tests and therefore should be reimbursed similarly. However, most laboratory tests are not interactive with the treating physician: what if the expert system is used by a physician? (As will be shown, it is potentially beneficial to limit the use of expert systems to experts.)

Certain groups hold the view that many laboratory tests are unnecessary and are performed to protect the physician against malpractice claims rather than to protect the patient (the practice of defensive medicine). Will expert systems be perceived to be in the same category? Will health-care insurers be pressured to limit the use of expert systems as nonproductive?

Although a third-party payment plan cannot dictate how a physician practices medicine, more than half of all payments for medical care are made by third-party plans. The economic impact of the plans' decision on reimbursement will be significant. Can pressure be applied by liability insurers in favor of such expert systems for their potential to reduce malpractice claims?

Another question to consider is whether the system would be "practicing medicine" under state law. While the definition varies from state to state, a good working definition of "practicing medicine" is engaging, with or without compensation, in medical diagnosis, healing, treatment, or surgery. In general, an individual may not practice medicine without a license from the state, but an unlicensed individual may perform duties delegated by a licensed physician. As long as the system is being used solely by licensed physicians, the problem seems to be solved. The system could be designed to function as a laboratory test, and eliminate the physician's involvement.

When the number of people that can use the system is expanded, an organization may run into the thornier issue of how to get a computer program "licensed" to practice medicine. It obviously has not been done yet, and it is not likely to happen before computers get the right to vote, because typical licensing requirements include attaining a minimum age and holding a degree of doctor of medicine from an accredited medical school.

How far can a system go without requiring the unobtainable license? Clearly, it is not practicing medicine to write a textbook on diagnosis: the book can be sold to anyone, licensed or not. The line would be crossed, however, if the purchaser of the textbook began prescribing treatment for others. Still, it would be the reader and not the author of the textbook who would be engaged in the unlicensed activity. Is a computer program an interactive book or an inanimate reader? Should it be considered a source of information or a prescriber of treatment? These are good questions with, as yet, no definitive answers. The answers are extremely important, for they may determine whether developers of these systems (and lay users) would face criminal and civil liability.

Civil liability could arise in a number of contexts. Suppose, for example, that the expert system contains incorrect data. Under the usual nonprofessional contract theory, the parties can generally allocate risks as they choose: if a purchaser agrees to buy a system as is or without warranties, he is stuck with the system, bugs and all, so long as no fraud has been committed. Professionals, however, contractually cannot eliminate or reallocate their liability for prospective malpractice. A doctor cannot sell the patient an appendectomy, as is. As a general rule, a physician must show the degree of skill, care, and judgment ordinarily exhibited by practitioners in the same specialty under similar circumstances in the same locality. It may not be malpractice for a general practitioner in a rural area to be unaware of a recent development in treating an uncommon ailment; however, the same shortcoming might be considered malpractice for a specialist in a large urban teaching hospital.

FORTRAN PROGRAMMERS

Looking for the right PC FORTRAN language system? If you're serious about your FORTRAN programming then you should be using F77L - LAHEY FORTRAN.

"Lahey's F77L FORTRAN is the compiler of choice. It's definitely a 'Programmers FORTRAN,' with features to aid both the casual and the professional programmer. . . F77L compiled the five files in a total of 12 minutes, which was 4 times as fast as MS FORTRAN and an astounding 6 times as fast as Pro FORTRAN." - PC Magazine

Compare the features and performance of other PC FORTRANs with F77L and you will find that F77L is clearly the superior product.

- Full Fortran 77 Standard (F77L is not a subset)
- Popular Extensions for easy porting of mini and mainframe applications
- COMPLEX*16, LOGICAL*1 and INTEGER*2
- Recursion - allocates local variables on the stack
- IEEE - Standard Floating Point
- Long variable names - 31 characters
- IMPLICIT NONE
- Fast Compile - Increases productivity
- Source On Line Debugger (Advanced features without recompiling)
- Arrays and Commons greater than 64K
- Clear and Precise English Diagnostics
- Compatibility with Popular 3rd Party Software (i.e. Lattice C)
- Easy to use manual
- Technical Support from LCS

- *NEW FEATURE - NAMELIST*

F77L - THE PROGRAMMER'S FORTRAN

$477.00 U.S.

System Requirements: MS-DOS or PC-DOS, 256K, math coprocessor (8087/80287)

FOR MORE INFORMATION: (702) 831-2500

Lahey Computer Systems, Inc.
P.O.Box 6091
Incline Village, NV 89450
U.S.A.

International Dealers:
England: Grey Matter Ltd., Tel: (0364) 53499
Denmark: Ravenholm Computing, Tel: (02) 887249
Australia: Computer Transitions, Tel: (03) 537-2786
Japan: Microsoftware, Inc., Tel: (03) 813-8222

SERVING THE FORTRAN COMMUNITY SINCE 1967

MS-DOS & MS FORTRAN are trademarks of Microsoft Corporation.Pro FORTRAN refers to Professional FORTRAN a trademark of International Business Machines.

Editor's Choice
- PC Magazine

CIRCLE NO. 128 ON READER SERVICE CARD

Where will expert systems fit into this pattern? Will it be permissible to license systems as is? If not, will the systems be held to the same standards as human experts in the same fields? Should it make a difference if the error is not in factual content but rather in design logic? Will expert systems commit "malpractice" if their database is not kept up to date?

The user of an expert system could face similar exposures to liability. Who is responsible if an expert system is used and the system leads to a misdiagnosis? Again, two sets of analogous situations offer relatively clear answers. If a physician refers a case to a specialist and the specialist commits malpractice, that malpractice does not ordinarily make the referring physician liable. On the other hand, if a surgeon uses a scalpel where a catheter was called for, he can be held liable for his inappropriate choice of instruments.

Which is the expert system—a colleague or a tool? Superficially, it would appear that it is a tool. However, that answer may assume too much about how expert systems will develop. The proper distinction may not be between colleague and tool, but rather between tools that the community standard of care requires the physician to understand and discriminate between, and the tools it accepts as beyond the scope of proper medical practice.

People expect surgeons to distinguish between scalpels and catheters, but as technology becomes more complex, will they likewise require that the doctors understand the internal workings of microchips? To respond with the legal standard (that physicians must understand microchips if practitioners in the same specialty and locality under similar circumstances do) is not particularly helpful. If expert systems do progress to the point where they surpass the ability of even specialists in their field, then they will be operating in areas where even the specialist cannot determine whether the system is functioning properly or not. The decision whether or not to hold a physician responsible for errors in an expert system may determine whether or not expert systems come into use. If a physician can limit his malpractice exposure to his own mistakes by eschewing expert systems, but takes on additional exposure by employing them, what will motivate him to use the system (even if, statistically, his diagnoses are better using the system)?

One answer may be the threat of malpractice for *not* using an expert system. An expert, particularly a specialist in a field, is expected to use available, proven tools. The word *proven* brings us full circle to the issues of FDA approval. What standards are appropriate to prove expert systems? The question may be easy to answer as long as expert systems remain in the realm of automating and speeding the solution to problems that humans can solve through other, albeit tedious, methods. However, if the systems learn better than they are taught, the question becomes much more difficult.

The issue of proving a system is one of extreme economic importance. If a system, either through FDA or some other stamp of approval, is the first to be accepted as the norm for a particular purpose, it will offer a double benefit: protection (perhaps not complete) from malpractice claims and the threat of malpractice for failure to use, a combination that should guarantee substantial market penetration.

Max Stul Oppenheimer, PC, is a partner in the law firm of Venable, Baetjer & Howard with offices in Maryland, Virginia, and the District of Columbia.

GET PC/XT HEADACHE RELIEF.

Take one WELTEC floppy drive and upgrade your PC or XT to AT capacity - without changing your controller card.

Is your mix of IBM PC's and XT's giving you an MIS headache? Get rid of it fast with our versatile 5¼" half-height flexible disk drive.

- 1.2 Mb formatted capacity
- No additional controller card needed
- Brushless direct-drive motor with 30,000 MTBF



- Full interchange of diskettes between IBM AT and PC or XT as well as most IBM compatible systems
- Internal or external configurations
- ANSI and industry interface compatibility

Get relief now!
Call 714/250-1959

VAD and VAR inquiries invited

WELTEC digital, inc.

17875 Sky Park North, Suite P, Irvine, CA 92714

IBM™ PC, XT and AT are trademarks of International Business Machines Corp.

CIRCLE NO. 243 ON READER SERVICE CARD



Improved Serial Card ...EXTENDS SPEED AND FLEXIBILITY OF PC APPLICATIONS

New improved 8-channel ACL™ serial card now offers the option of RS422 and RS485 compatibility.

The new card provides all the standard ACL "smart card" features...flexible address decoding, programmable interrupts, expandable options via software, and the ability to download custom programs...now the ability to operate over greater distances and speeds of RS422 applications. In addition, the new card enables PCs to interface with industrial process controls via RS485 links.

Call for free literature that explains how the improved ACL Serial Card can expand your PC's multiuser options.

STAR GATE TECHNOLOGIES INC.
33800 Curtis Blvd.
Eastlake, OH 44094
(216) 951-5922

CIRCLE NO. 177 ON READER SERVICE CARD

SOFTWARE SENTINEL™

MUCH MORE THAN JUST PROTECTION



Stop unauthorized use of software...and keep your customers happy at the same time. The no-interference hardware keys from the industry's leading supplier put money in your pocket and save you from angry customer complaints. Our product line includes devices for either parallel or serial port. The latest addition allows you to **cover multiple programs with one device and/or customize as needed.** Call for new low prices.

SOFTWARE DEVELOPER BENEFITS

- Prohibits unauthorized use of software
- No need for copy protection
- Algorithm technique (never a fixed response)
- Virtually unbreakable
- Higher level language interfaces included
- 100 times faster (1ms) than fixed response devices
- Minimal implementation effort
- Runs under DOS and Xenix, on IBM PC, AT, XT & compatibles

SOFTWARE USER BENEFITS

- Unlimited backup copies
- No floppy required with hard disk
- Pocketsize
- Transparent
- Transportable

RAINBOW TECHNOLOGIES, INC

EVALUATION KIT AVAILABLE

Telex 386078

17971 SKYPARK CIRCLE SUITE E, IRVINE, CA 92714 (714)261-0228

CIRCLE NO. 157 ON READER SERVICE CARD

9-TRACK MAG. TAPE SUBSYSTEM FOR THE IBM PC/XT/AT AND...



For information interchange, backup and archival storage, IBEX offers a 9-track, IBM format-compatible ½" magnetic tape subsystem for the IBM PC, featuring:

- **IBM format 1600/3200 and 800 cpi.**
- **Software for PC-DOS, MS-DOS.**
- **Also for DEC, VAX, VME, S-100, RS-232, IEEE 488.**

Write, phone or TWX for information.

IBEX

IBEX COMPUTER CORP.
20741 Marilla St.
Chatsworth, CA 91311
(818) 709-8100
TWX: 910-493-2071

CIRCLE NO. 149 ON READER SERVICE CARD

IBM PC/XT/AT*

Repair Training

- 30 hr. hands on course
- Money back guarantee
- On site training available

Satisfied customers include such companies as:

— Southern California Edison
— GTE
— Shell Oil Company
— McDonnell Douglas
— U.S. Department of Commerce

National Advancement Corporation

Computer Hardware Training Specialists

3001 Redhill Ave. Costa Mesa, CA 92626
Building 5, Suite 108/113 (714) 540-5988

* IBM PC/XT/AT is a trademark of International Business Machines

CIRCLE NO. 192 ON READER SERVICE CARD

Clarifying MS-DOS

An "authorized biography" of MS-DOS enhances the Microsoft documentation and expands the programming possibilities for programmers.

Advanced MS-DOS
Ray Duncan (Redmond, WA: Microsoft Press, 1986) 468 pages; paper, $22.95; disk, $15.95



When a book and its subject share the same corporate parent, the situation is not unlike that of the "authorized biography." On the plus side, the author can count on the company's cooperation in supplying information and ensuring its accuracy. On the minus side, the information may be limited to the official line and provide little beyond the company's documentation that is already in the public record. Happily, in *Advanced MS-DOS*, the positive outweighs the negative.

According to the author's introduction, the book is written for the experienced assembly language or C programmer who is familiar with the architecture of Intel's 8088/8086/80286 microprocessors. It is meant to provide the information necessary to create robust, high-performance application programs using the services of the operating system. The book succeeds because it augments this information with lucid explanations and many examples.

The primary focus of *Advanced MS-DOS*, despite its title, is not on the generic MS-DOS machine, but on the IBM PC family. The IBM PC BIOS services and the Lotus/Intel/Microsoft Expanded Memory Specification (LIM EMS) are covered in the book even though they are not part of DOS.

Other topics include: character I/O devices (keyboard video, printer, serial port); "well-behaved" versus high-performance but nonportable programming; record and file I/O; logical and physical disk organization; memory allocation; the EXEC function; interrupt handlers; device drivers; and filters.

The first 13 chapters describe the structure and functioning of the operating system. A brief history of DOS is followed by excellent descriptions of its component parts, how they are loaded and initialized, and how user programs are loaded. The explanation of .COM and .EXE files, and the differences between them are the most comprehensive and informative given in any source to date.

The descriptions of the DOS services are organized functionally rather than numerically. Similar functions are compared and contrasted, and the pros and cons of using one over another are discussed. Most valuable of all are the many examples in assembly language and C code. Some of these are complete and functional programs; others are code fragments for incorporation into the reader's programs; and still others are templates that need to be fleshed out for particular applications. A disk containing these examples in source code is available separately.

In many cases, the information presented in the book is not readily available in system documentation or from other sources. For example, the console I/O functions are tabulated to clarify the characteristics of each one and the differences between them. Device drivers and filters are explained in detail with comprehensive example programs. The chapter on memory allocation gives more information than any of the official sources. It still does not do full justice to the subject, but the author implies (as he does in several other places) that he is limited to presenting what Microsoft wants to make public.

The last third of the book is a reference manual for DOS interrupts and functions, the services provided by the PC's ROM BIOS, and the interface between the expanded memory manager and application programs. This section is organized in numerical sequence and, at least for the DOS and expanded memory functions, it presents basically the same information as the documentation that comes with MS-DOS. The one improvement is that the use of each function is illustrated by a fragment of assembly language code. For the BIOS functions, which are formally documented only in commented assembly language listings, the presentation in the same format as the DOS functions is a major convenience.

Only a few minor errors were found in the text. The most serious is in the description of buffered keyboard input (interrupt 21H, function 0AH), where it is stated that non-ASCII keys insert a two-byte scan code into the input buffer. In fact, such keys (except for the few function keys that perform the limited editing functions during input) are ignored by MS-DOS.

No document is perfect, and this book has several failings. The first is typical of most books in this fast-moving field: a measure of obsolescence. Although DOS 3.2 is mentioned as the latest version, its new functions are not covered. More significantly, the section on video output treats only the IBM Color Graphics Adapter and the monochrome adapter; it mentions the IBM Enhanced Graphics Adapter (EGA) only in passing. The EGA BIOS functions are not described or documented at all.

The book has two significant omissions. First, a substantive discussion of the environment block that is allocated for each program and of the potential uses of environment strings and other information in the block is not given. Second, the capabilities and uses of the ANSI.SYS driver, an integral part of DOS, are not covered. These omissions preclude using this book as a total replacement for the *DOS Technical Reference* manual. This is unfortunate because for the subjects it does cover, it is so much better than that volume, and at one-fifth the price.

—TED MIRECKI

FREE!
DATA ACQUISITION • GRAPHICS • DATA ANALYSIS
PRODUCT CATALOGS FOR YOUR
IBM or Apple PC

Interactive Microware offers a complete, low cost family of high quality hardware and software for **Chromatography • Process Control • Spectrophotometry • Temperature Monitoring • Electrochemical Analysis • Atomic Absorption • Instrument Monitoring • Data Plotting • Curve Fitting • IR and UV/VIS Spectroscopy • Computer Assisted Design** and Much More!

Thousands of clients worldwide use IMI products for Science, Engineering and Business Applications.

CALL (814) 238-8294 FOR IMMEDIATE ACTION!



featuring

COMPLETE APPLE II WORKSTATIONS STARTING AT $ **2239**

COMPLETE IBM PC WORKSTATIONS STARTING AT $ **2998**

IBM is a registered trademark of International Business Machines Corp; Apple is a registered trademark of Apple Computer, Inc.

IBM 48 PAGES 94 PRODUCTS **APPLE 64 PAGES 264 PRODUCTS**

imi™ **INTERACTIVE MICROWARE, INC.**
POB 139, Dept. 237, State College, PA 16804
Phone: (814) 238-8294 • Telex 705250

CIRCLE NO. 208 FOR APPLE NO. 209 FOR IBM

PMI FASTCARD®
INTRODUCES **with 2 MBYTES**

10 DAY FREE TRIAL ONE YEAR WARRANTY

ONLY $295*

The Only Expanded Memory Card Which Can Save A Day Each Week.

A major independent testing laboratory benchmarked a PC-XT equipped with *FASTCARD* and demonstrated a tenfold improvement over a PC-AT on typical Disk I/O operations.

- Portable between IBM PC, XT, AT and compatibles.
- Up to 2MB with Split Memory Mapping to
  - Fill memory to 640K
  - Provide Expanded memory over 640K
- Unique Disk Caching
- Ram Disks (up to 8MB)
- Custom Password Security
- Print Buffering
- Built-in Diagnosis and Automatic Fault Tolerance
- Factory Installed and Tested DRAM's
- Lotus/Intel/Microsoft compatible

*Each *FASTCARD III* comes with 2 MBytes of Memory. *FASTCARD IV*, available with 2 MBytes, includes serial/parallel ports, game port and a clock calendar for $295. Dealer inquiries invited.

LOTUS EMS COMPATIBLE

For additional information, contact PMI at

PERIPHERAL MARKETING INC. **602-483-7983**
7825 E. EVANS RD., #500, SCOTTSDALE, AZ 85260

CIRCLE NO. 202 ON READER SERVICE CARD

VT100/VT52 & Tektronix™ 4010/4014 Terminal Emulator

Excellent emulation and the features you want:

VTEK™ 3.1

- → use 4096 x 3120 resolution
- → zoom, pan, and window plots
- → high resolution printer dumps
- → choose text and plot color
- → transfer files with XMODEM and Kermit protocols
- → scroll last 4 pages of text
- → 132 column VT100 capability
- → 18 User-definable keys
- → capture plots and text on disk
- → full or half duplex
- → access to DOS commands
- → all VT100 keypad commands
- → command line editing
- → fast direct screen access
- → password security

VTEK makes your PC better than a terminal

$150 from Scientific Endeavors

Publication Quality Graphics for Scientific and Technical Applications

GraphiC™ 3.0 in *Color*

- → linear, log, & polar plots
- → bar charts & Smith charts
- → contour plots with labels
- → 3-D curves, 3-D surfaces with hidden line removal
- → 4 curve types, 8 markers
- → 14 fonts, font editor
- → multiple levels of super/sub scripts
- → 4096 x 3120 resolution
- → zoom, pan, window plots
- → multiple plots on a page
- → high resolution printer dumps, full or half page
- → plotter support in COLOR

16 color plots on EGA, Sigma, TeleVideo & Tecmar boards

Over 100 routines can be called by your C program. $350. Demo $8.

SOURCE INCLUDED for private use only.

For DeSmet, C-86, Aztec, Lattice, and Microsoft C compilers.



Scientific Endeavors
Route 4, Box 79; Kingston, TN 37763
(615) 376-4146

For 256k IBM and Corona PCs, DOS 2.xx,3.xx. Epson, Okidata, Toshiba, C. Itoh printers. Hewlett Packard, Houston, Sweet-P plotters. Corona Laser printer. IBM, IBM EGA, Sigma, TeleVideo, Tecmar, Hercules, Corona graphics. A compatible assembler is required.

THIS AD WAS MADE USING GraphiC™

CIRCLE NO. 107 ON READER SERVICE CARD

Release the Power
of Fortran, C and Pascal

A library of over 120 Assembler routines transforms FORTRAN, Pascal and C language compilers into a flexible, responsive language for the microcomputer environment. Existing mainframe code may be converted with ease, saving time and money. With the powerful Assembler subroutines of *NO LIMIT*™, mainframe users can fully realize the advantages of microcomputer technology.

- Complete Communications
- File/Directory Management
- Full Screen/Keyboard Control
- Extensive Graphics Applications
- Character/String Manipulation
- System Information
- And much more!



NO LIMIT™ is available for $129, with no license fee, and supports MS/FORTRAN/Pascal/C, IBM Professional, Ryan-McFarland, and Lahey F77L compilers.

M·E·F Environmental, Inc.

P.O. Box 26537
Austin, Texas 78755
512/251-5543

©Trademark of Microsoft, Inc., IBM Corporation, Ryan-McFarland and Lahey, Inc., respectively.

CIRCLE NO. 133 ON READER SERVICE CARD

NEED IT FAST? WANT TO KNOW MORE? DON'T HAVE TIME TO SHOP AROUND?

INTRODUCING...

If you're like most system professionals you're up-to-date about the products in the PC marketplace. You're aware of brand and model differences, are informed about connectivity and compatibility problems, and you shop for competitive prices and fast service.

You're also probably among the many PC TECH JOURNAL readers who purchase by mail. That's why we're starting THE MART—PC TECH JOURNAL'S First Class Mail-Order Section.

Starting this month, and every month hereafter, you'll find the products you're looking for advertised in THE MART—and you'll benefit from the fast service and helpful support that identifies PC TECH JOURNAL advertisers.

If you're ready for First Class service, you're ready for THE MART.

PC XT/AT ADD-ON BOARDS

- MS DOS/GW Basic 3.2 ..... $80
- XT Mother Board/Bios $83
- XT Turbo Board/Bios $103
- Monochrome/Graphic/Printer Card ... $66
- Monochrome Graphic Card $60
- Color Graphic/Printer Card $60
- Color Graphic Card $50
- XT Multi I/O Card $73
- XT I/O Plus II $45
- Floppy Disk Controller
  - 1 port $25
  - 2 port $33
- RS232 Interface Card
  - 1 port $22
  - 2 port $27
- Parallel Printer Card $19
- Clock Card $25
- Game Card $18
- Hard Disk Controller Card $100
- Hard Disk/Floppy Disk Controller Card $123
- XT 2 MB RAM Card $195
- AT Mother Board/Bios $490
- AT 3 MB Multifunction Card $178
- AT 4 MB RAM Card $210
- AT 1.2M Floppy Disk Card $72
- EGA Card $245
- AT HDC/FDC Controller w/Cable $215

KEYBOARDS

- 5151 Style AT/XT Keyboard $68
- 747 AT Style AT/XT Keyboard $53

POWER SUPPLY

- 150 Watt XT Power Supply $53
- 200 Watt AT Power Supply $85

MONITORS

PARCO (Sony) Height Resolution 12" 90° Monitor 800 x 700 Lines With Non-Glare Screen/Swivels Base Amber. $115

- SAMSUNG — Amber $79
- TAXAN 620 Color $375
- TAXAN 630 Super Hi-Res. Color $445
- TAXAN 640 Super Hi-Res. Color $495
- TAXAN 760 EGA Monitor $499

PRINTERS

- RITEMAN PLUS (120 cps. 80 col.) $175
- RITEMAN - 15 (160 cps. 136 col.) $345
- BROTHER M1509 (180 cps. 136 col.) ... $395

DRIVES

- TEAC 360K Floppy Drive $90
- FUJISU 360K Floppy Drive $82
- CHINON 360K Floppy Drive $85
- 20MB Hard Disk/WD ..... $Call
- 30MB Hard Disk/WD ..... $Call
- 1.2MB TEAC AT Drive $135

CHASSIS

- Flip Top XT Case $29
- Slide Off XT Case $36
- AT Jr. Style XT Case $37
- AT Case $85

All Cases Include Speaker/Hardware

MODEMS

- Internal Modem-Everex $137

Select 300/1200 bps, powerful BitCom Communication Software Included. Auto answer/dial.

- External Modem-Smarteam $160

PC/AT 2000 SYSTEM

- 80286 Processor (6/8MHZ)
- 1024K RAM
- 1.2MB Floppy Disk Drive
- AT Hard Disk/Floppy Disk Controller Card
- Clock/Calendar with Batter Backup
- AT Style Keyboard
- 200W Power Supply/Case
- Runs All Major Software
- Six Month Warranty

$1249

PC/XT 2000 SYSTEM

- 640K RAM
- 360K Half Height Floppy Drive w/Controller
- AT Style Keyboard
- 150W Power Supply
- Slide Off Case
- Runs All Major Software
- Six Month Warranty

$495

(201) 944-5002
2142 N. Hudson St.
Fort Lee, NJ 07024

IBM PC, IBM XT and IBM AT are trademarks OF IBM corpration.
MS-DOS is a trademark of Microsoft Corporation.

Prices Subject to Change without Notice.

ORDER TOLL FREE:

1-800-367-1132

MONDAY — SATURDAY 9AM — 6PM EST.

Customer Service
(201) 944-5010
9AM — 5PM EST. M-F

ORDERS SHIPPED UPS COD WITHIN 24 HRS.

SUNNYTECH INC.

CIRCLE NO. 184 ON READER SERVICE CARD

GET 1 YEAR ON SITE SERVICE FREE

B.E.S.T. 286 AT™ Compatible

640 KB RAM Bare Bone System: only **$999** (Qty. 2)

★ FREE ★
- ☐ DOS 3.1 ($85 Value)
- ☐ 1 Year Nationwide on site service (Parts & Labor)

STANDARD FEATURES:

30 day money back guarantee

- Clock/calendar w/battery back-up
- *FCC and U.L. APPROVED*
- 6/8 MHz 80286 Microprocessor
- 80287 Math Co-processor Socket
- 8 Expansion Slots
- 640 KB RAM Expandable to 1024 KB on Mother Board
- 200 WATT U.L. Approved Power Supply
- AT case with Lock and LED indicators
- 5060 Compatible Keyboard
- MS DOS 3.1 ($85 value FREE)
- Full Documentation
- Complete technical support
- Fully compatible with IBM-AT



Evaluation Unit $1,095
We Welcome VAR and Dealer Inquiry (quantity discounts available)

All major credit cards accepted

SYSTEM CONFIGURATION B:
- AT 640 KB RAM Bare Bone System
- 1.2 MB Teac Floppy Disk Drive
- 30 MB Hard Disk (39MS)
- Western Digital WA-2 Floppy & Hard Disk Controller
- 1 Year Nationwide (50 States) ON-SITE Service (Includes Parts & Labor)
- MS DOS 3.1

only **$1,995**

GET OUT OF THE LOOP!

NO MORE RETURNS OR LONG WAITS FOR REPAIRS
WE WILL FIX YOUR COMPUTER ON SITE
FREE OF CHARGE FOR 1 YEAR

BUSINESS ENGINEERING SCIENTIFIC TECHNOLOGIES
1914 W. Farwell • Chicago, IL 60626
(312) 465-8886 or (312) 262-3480

Prices subject to change without notice
IBM AT is a trademark of International Business Machines Corporation

Turbo 286 - AT Compatible $1295

- 8 expansion slots
- 200 Watt Power Supply
- 640 K RAM
- 6/8 MHZ Switchable from keyboard
- 2 Floppy & Hard Disk Controller
- 1.2 MB Floppy Disk Drive
- Serial, Parallel Ports
- Color Graphics Card
- AT keyboard

MEDICAL & DENTAL
- Billing & Posting
- Faster Collection
- Improved Cash Flow
- Easy Insurance Procedure
- Appointment Scheduling
- Management Reports

LEGAL SOFTWARE
- Real-Time, Multi-User
- Time & Billing
- Client/Matter Reports
- Aged A/R Report
- Matter Account Inquire
- Transaction Entry & Editing

CONSTRUCTION
- Fully Integrated Construction Accounting System
- Job Costing
- Accounts Payable
- General Ledger
- Payroll
- Accounts Receivable
- And much much more

VIDEO STORE MANAGEMENT
- Full Rental Tracking
- Membership Control
- Employee Code System
- High/Low Rental Report
- Overdue Tape Report

POINT OF SALE
- For all Retail & Wholesale Businesses
- Cash Drawer & Bar Code Scanner Interface
- Complete Audit Trail of all P.O.S. Transactions
- Inventory Inquiry during sale, and much more. . .

MICROWAY ACCELERATES YOUR PC!

FastCACHE-286™

Runs your PC Faster than an AT!

Runs the 80286 at 9 or 12 MHz and the 80287 at 8, 9 or 12 MHz. Includes 8 kbytes of 55ns CACHE.



Compatible with Leading Edge Model D, Compaq, and Turbo motherboards. Includes 8088 Reboot Switch, DCache, Print Spooler and Diagnostics... **From $449**

LOTUS/INTEL EMS SPECIFICATION BOARDS

MegaPage™ The only EMS board which comes populated with two megabytes of cool-running, low power drain CMOS RAM installed. Includes RAM disk, print spooler, disk cache and EMS drivers. For the IBM PC, XT and compatibles...**$549**

MegaPage with ϕK..... **$149**

MegaPage AT/ECC™ EMS card for the PC AT and compatibles includes Error Correction Circuitry. With ECC, 11 RAM chips cover 256K so the user never encounters RAM errors. Sold populated with 1 megabyte CMOS . . . **$699** or with 3 megabytes CMOS cool running low power drain RAM . . . **$1295**. Optional serial/parallel daughterboard..... **$95**

INTEL, JRAM, or Maynard..... CALL

NUMBER SMASHER/ECM™

Triples the speed of CAE and all applications!

From $599



12 MHz 8086/8087 Accelerator Plus A Megabyte for DOS!

For the IBM PC, XT and compatibles

***PC Magazine* "Editor's Choice"**

8087 SOFTWARE

IBM BASIC COMPILER	$465
MICROSOFT QUICK BASIC	$79
87BASIC COMPILER PATCH	$150
87BASIC/INLINE	$200
IBM MACRO ASSEMBLER	$155
MS MACRO ASSEMBLER	$99
87MACRO/DEBUG	$199
MICROSOFT FORTRAN V4	$299
RM FORTRAN	$399
LAHEY FORTRAN F77L	$477
MS or LATTICE C	CALL
STSC APL★PLUS/PC	$450
STSC STATGRAPHICS	$675
SPSS/PC+	$695
87SFL Scientific Functions	$250
87FFT	$200
OBJ → ASM	$200
PHOENIX PRODUCTS	CALL

287 Turbo™-10/12



287 Turbo runs the 80287 at 10 or 12 MHz in the IBM PC AT, compatibles and the new Compaq 386 with 100% software compatibility.

10 MHz **$450**
12 MHz **$550**

***PC Magazine* "Editor's Choice"**

8087 UPGRADES

All MicroWay 8087s include a one year warranty, complete MicroWay Test Program and installation instructions.

8087 5 MHz..... **$114**
For the IBM PC, XT and compatibles

8087-2 8 MHz..... **$154**
For Wang, AT&T, DeskPro, NEC, Leading Edge

80287-3 5 MHz..... **$179**
For the IBM PC AT and 286 compatibles

80287-6 6 MHz..... **$229**
For 8 MHz AT and compatibles

80287-8 8 MHz..... **$259**
For the 8 MHz 80286 accelerator cards and Compaq 386

80287-10 10 MHz..... **$395**

PC-PAL™ Programmer..... **$395**

Call for great prices on V20, V30, 64K, 128K and 256K RAM

AT8™

Turns your AT into a high speed, multi-user Xenix business system!



8 port, intelligent serial controller with 3% response degradation. Includes 8 MHz 80186 with built in DMA **$1299**

MICROWAY SOFTWARE FOR LOTUS 1-2-3™

FASTBREAK™ employs the 8087 to increase the speed of Lotus 1-2-3™ Version 1A or 1A*. Users are reporting speed ups of between 3 and 36 to 1. When run with our NUMBER SMASHER accelerator card, recalculation speed ups of 10 to 30 are being reported..... **$79**

PowerDialer® Add-In for Lotus 1-2-3 Release 2. Automated telephone dialing from within 1-2-3. Adds least cost routing, automatic carrier selection and automated phone book worksheet. Builds customized dialing applications. Can be used with DesqView **$79**

HOTLINK™ adds easy linking of spreadsheets to Lotus 1-2-3 Version 1A... **$99**

287 TURBO-PLUS™

Speeds up your AT

Adjustable 80286 Clock 6-12 MHz
10 MHz 80287 Clock
Plus Full Hardware Reset..... **$149**
Optional 80286-10..... **$175**



287TURBO-PLUS
With 80287 10 MHz..... **$549**
With 80287 12 MHz..... **$629**

CALL (617) 746-7341 FOR OUR COMPLETE CATALOG

MicroWay P.O. Box 79 Kingston, Mass. 02364 USA (617) 746-7341

You Can Talk To Us!

MicroWay Europe
32 High Street
Kingston-Upon-Thames
Surrey England KT1 1HL
Telephone: 01-541-5466

TOOLS !

for Professional Programmers

asmTREE™

Database Development System

A database system is the heart of just about every successfull software package ! Accounting systems, Mailing programs, Analysis software, plus many other types of packages have reaped the benefits of a database.

NOW you too can utilize a sophisticated B+Tree database for your programming needs. Whether you program in Assembler, C, PASCAL, or FORTRAN, you can have all the advanced capabilities of asmTREE at your finger tips. asmTREE is written in assembly language for fast execution and small code size - for the DOS 2.xx or newer environment.

ISAM Functions - NO ROYALTIES - Full SOURCE CODE

asmTREE™ - The Programmer's Database

Only $395.00 - Complete

Other fine development tools -

- ASMLIB - The Programmer's Library - Over 210 functions for Assembler, C, PASCAL, and FORTRAN. NO ROYALTIES. With SOURCE CODE $149
- FPLIB - IEEE FLoating Point for REALIA™ COBOL $149
- Turbo.ASM - Assembly Langauge interfacing made easy for TURBO PASCAL ... $99.95

CALL TOLL FREE 1-800-262-8010
in Calif. CALL 1-714-526-5151

BC Associates
3261 N. Harbor Blvd - Suite B
Fullerton, CA 92635

VISA

MEGAMEMORY AND DESKTOP PUBLISHING

Lowest Prices In USA

Fully Populated 2MB Boards
Made by Tall Tree Systems
HIGHEST QUALITY RAM CHIPS

JRAM-2	$319
JRAM-3 LOTUS-INTEL	$389
JRAM-AT	$389
JLaser-Plus PCl	$675
1 MB DRAM (100 NS)	CALL

SUPER SPECIAL

QMS KISS/JLASER+ PC.	$2575
CANON IX-12 Scanner	$ 795
Dr. Halo DPE	$ 129
Ventura Publisher	CALL

THE RAM EXPLOSION
5119A Leesburg Pike, Suite 260
Falls Church, VA 22041

(703) 569-4471

Dealer Inquiries Invited
VISA/MASTERCARD
An Authorized TALL TREE DEALER

CIRCLE NO. 171 ON READER SERVICE CARD

Panasonic
TeleVideo®
TELECAT-286
SANYO
WYSE 286

MULTI USER SYSTEMS
ALTOS
SPERRY

MONITORS
TERMINALS
MODEMS

LASER PRINTERS

DIGITIZERS

Kurta	CALL
Hitachi	CALL
Houston Instruments	CALL
Cal Comp	CALL
Summagraphics	CALL

PLOTTERS

DMP-29	CALL
DMP-41/42	CALL
DMP-51/52	CALL
DMP-51/52 MP	CALL
DMP-40	CALL
DMP-56A	CALL
Roland DXY-101	599
Roland DXY-880	979
Roland DXY-980	1279
Calcomp 1043 GT	7500
Calcomp 1044 GT	11760
Plotter Software	CALL
Ioline	CALL

PRINTERS

CITIZEN

120-D	120 CPS	$180
MSP-10	160 CPS	280
MSP-15	160 CPS	379
MSP-20	200 CPS	311
MSP-25	200 CPS	461
Premier	35 CPS	450

PANASONIC

KXP 1080 I	120 CPS	$199
KXP 1091 I	160 CPS	260
KXP 1092 I	240 CPS	357
KXP 1592	180 CPS	402
KXP 1595	240 CPS	551
KXP 3131	17 CPS	250
KXP 3151	22 CPS	382

i·MEGA

Scottsdale Systems

602-941-5856 For Inquiries — Since 1980 — **1-800-367-2369** For Orders

CIRCLE NO. 127 ON READER SERVICE CARD

CANADA'S SOURCE FOR C

Compilers • Utilities & Aids • Editors
Interpreters • De-Bugging Tools
File Access Systems • Graphics

GREENLEAF SOFTWARE©
AZTEC
Phoenix
Lattice
LIFEBOAT

Complete Line of Programming Development Tools
Full Service and Support - Fast Delivery

VISA CORPORATE DISCOUNTS MasterCard

(416) 449-9252/5

SCANTEL SYSTEMS LTD.
801 YORK MILLS RD., 201, DON MILLS, ONT M3B 1X7



"Serving the Nation's Capitol and the World"

Technical Support and Shipping and Receiving
(703) 761-6177, 78
ITS TEK-NET-BBS (703) 690-7462

Visa, MC, CHOICE, AE
Leasing, Renting & Financing available

Open 7 days a week
(703) 847-4740 (800) 642-2395

Information and Technology Services, Inc.
Micro Systems Specialists
8478A Tyco Rd., Vienna, VA 22180

Software

SUPERCALC 4	$335
SUPERPROJECT +	$295
WORDPERFECT 4.2	$250
DBASE 3 +	$430
FOXBASE +	$335
FRAMEWORK II	$399
RBASE 5000	$320
RBASE SYSTEM V	$396
CROSSTALK XVI	$99
REFLEX	$96
TURBO PASCAL	$42
TURBO PROLOG	$60
TURBO LIGHTNING	$61
NORTON UTILITIES	$57
MS WINDOWS	$69
MS QUICKBASIC	$65
MS C-COMPILER	$298
MS WORD	$280
WORDSTAR 2000	$270
MULTIMATE	

Easy Business Accounting Systems

GENERAL LEDGER	$395
ACCOUNTS RECEIVABLI	$395
ACCOUNTS PAYABLE	$395
INV. CONTROL	$395
RETAIL INVOICING	$395
PAYROLL	$458
ORDER ENTRY	$395
TIME, BILLING & REC.	$635

Video Cards

QUAD EGA +	$379
PARADISE AUTO SWITCH	$419
STB EGA	$299
TECHMAR EGA	$299
VEGA DELUXE	399

NOVELL NETWORKING
DESIGN & INSTALLATION

Drives

20 MB SEAGATE 65MS	$399
30 MB SEAGATE RLL	$499
20 MB ST4026 AT	$573
30 MB ST4038 AT	$651
40 MB ST4051 AT	$792
80 MB ST4096 AT	$1273
40MB PRIAM XT	$1395
60MB PRIAM XT	$1450
40MB PRIAM AT	$1175
60MB PRIAM AT	$1350
BERNOULLI DUAL 10	$1939
BERNOULLI DUAL 20	$2594
20MB PLUS HARDCARD	$695
20MB MAYNARD HCARD	$759
ISI WORM 220MB INT.	$3295
TEAC 360K DRIVE	$89
60MB ARCHIVE TAPE	$740
60MB ARCH. EXT. TAPE	$740
60MB GENOA TAPE	$935
60MB SYSGEN	$1089
TOSHIBA 3.5 DRIVE	$150
TOSHIBA 10 MB DRIVE	$899
*TOSHIBA 5.25 EXT.	$349

Memory Boards

JRAM 2	$129
JRAM 3 ABOVEBOARD	$179
JRAM AT	$179
JRAM AT3 ABOVEBOARD	$239
JLASER MODULE	$265
JLASER +	AVAIL.
INTEL ABOVEBOARD	$438
AST RAMPAGE 512K	$485
ORCHID CRAMRAM	$291
ZUCKER BOARD	$68
AST 6 PAK + W/384	$199
QUADBOARD W/384	$189

Chips

64K 150ns set of 9	$8
64K 120ns set of 9	$9
256K/150ns set of 9	$23
256K/120ns set of 9	$25
64 x 4	$4
128K Piggyback	$5
8087-3	$119
8087-8	$169
80287 5MHz	$239
80287 6MHz	$245
80287 8MHz	$318

Printers

NEC P-6	$480
NEC P-7	$685
NEC P-5	$1122
NEC P-5XL	$1245
PANASONIC 1080 I	$235
PANASONIC 1091 I	$299
PANASONIC 1092	$360
PANASONIC 1592	$480
STAR LV1210	$189
STAR NX-15	$383
STAR ND-15	$445
STAR NR-15	$537
STAR NB 24-15	$699
STAR SD-10	$355
STAR NX-10	$255
BROTHER 1509	$440
CITIZEN MSP-10	$320
CITIZEN MSP-15	$435
CITIZEN PREMIER 35	$485
TOSHIBA P341	$835
TOSHIBA P351	$1227
FUJITSU DLP24	$1239
FUJITSU DM9I	$413
OKIDATA M182	$253
OKIDATA M192 +	$412
OKIDATA M193 +	$613
OKIDATA M84	$713
OKIDATA 2410	$1976
EPSON FX-286	$624
EPSON LX-80	$285
EPSON FX-85	$434
EPSON LQ-800	$631

Laser Printers

CANON A1	$2095
CANAON A2	$3085
HP LASERJET	$2295
QMS KISS	$1995
XEROX 4045	$CALL

Specials

Color RGB Mon.	$305
Amdek 310A	$150
TEAC 360 Drive	$89
Samsung Monitor	$89
Amdek 722	$549
NEC Multi-Sync	$631

***Other Systems*

Sharp PC 7000	$1095
IBM XT	$1798
IBM AT	$2789
BIOS AT 8MHZ	$1769

- Prices subject to change 12/18/86
- 10% re-stock fee on all items
- Software non-returnable if opened
- No surcharge on VISA, MC, CHOICE . . . AE, 3%

"Editor's Choice"

ITS Turbo XT

1 year warranty
30 day money back guarantee

The $895 ITS Turbo XT from Information and Technology Services is our "best buy" recommendation with 20MB $1224.00

PC MAGAZINE
OCT. 14, 1986
IBM® PC Compatible

$895.00 complete

SPERRY

PC/IT

Superior to the IBM AT
Rated 8.8 by InfoWorld
44MB, 28ms Access Hard Drive
3 Speed Processor
Free 8MHz Math Coprocessor
1.2MB Floppy , 640K Ram
2 Serial/1 Parallel Ports
Clock/Calendar, AT Keyboard
DOS 3.1, Basic, System Guide

$2,895.00 1 year warranty



ITS SYSTEM 386
BLACKHAWK

Features:
- INTEL 80386 CPU and support circuits
- INTEL designed motherboard
- Phoenix BIOS
- 18 Mhz clock speed
- PC/AT compatible 8 Mhz switchable from keyboard
- 512K RAM standard up to 14 megabytes
- Parallel/Serial/Clock
- 8 Slot Expansion bus interface
  2- PC Compatible 8 bit bus connectors
  2- 32 bit bus connectors
- Hard disk/Floppy disk controller
- 1.2 megabyte floppy

Available now

$4495.00

TOSHIBA Lap-Top
T-1100 Plus
(DUAL FLOPPY)

10 MB Disk Drive Now Avail.

$1695.00

$1995 with 640K

- 256K Ram Memory
- CMOS 80C86 Running at 7.1 MHz
- Two 720K 3.5" Floppy Drives
- One Expansion Slot
- TOSHIBA Keyboard
- LCD Display
- Color Graphics/Monochrome Composite Card
- One Parallel and Serial Port
- Clock Calendar
- External Floppy Drives Optional
- DOS 2.1

1800 +

80286 CPU



- IBM AT Compatible
- 512K of RAM expandable to 1MB
- 1.2MB Floppy
- AT Keyboard
- Documentation and Diagnostics
- Made in the USA

$1195.00

CIRCLE NO. 134 ON READER SERVICE CARD

THE COBOL SHOP

QUALITY PRODUCTS FROM TOP MANUFACTURERS

- The Latest in Compilers and Tools for DOS, Netware, Xenix, Unix and CICS.
- 4GL Applications Generators.
- Relational DBMS, SQL, etc.
- Forms, Maps, Editors, Debuggers, File Management Systems and more.

Low Price Example

	MFSR	COBOL SHOP
Level II COBOL™ from Micro Focus	**$1500.**	**$495.**

High performance ANSI 74 COBOL. GSA high level certified error free. Sort/Merge, Multi-Keyed ISAM, Communications and more. Subroutine Library for easy screen, keyboard and file I/O.

Best Products, **Best Prices,** Best Support

CALL
(713) 641-3440
Or Write
COBOL SHOP
P.O. BOX 672
RICHMOND, TX 77469

TM Level II COBOL and Animator Micro Focus Ltd.

CIRCLE NO. 223 ON READER SERVICE CARD

MOVING?

Please write to: PC TECH JOURNAL Magazine, P.O. Box 2968, Boulder, CO 80322.

Include your mailing label from a recent issue of PC TECH JOURNAL for faster service. Please allow up to 60 days for change of address to take place.

PROTECT YOUR COPIES OF TECH JOURNAL

Make your collection of PC TECH JOURNAL a handsome addition to your office or home—and protect and organize your copies for easy reference!

PC TECH JOURNAL Magazine Binders and cases are made of durable luxury-look leatherette over quality binder board. Custom designed for TECH JOURNAL every order receives FREE transfer foil to mark dates and volume numbers.

FOR FAST SERVICE CALL TOLL-FREE 1-800-972-5858

MAGAZINE BINDERS

Hold your issues on individual snap-on rods. $8.95 each; 3 for $25.75; 6 for $48.75.

OPEN BACK CASES

Store your copies for individual reference. $7.95 each; 3 for $22.95; 6 for $43.95.

TECH JOURNAL
P.O. Box 5120
Philadelphia, PA 19141

Please send ☐ Binders ☐ Cases Quantity _____

Payment enclosed $_____.* Add $1 per order for postage & handling. (Outside USA, add $2.50 per unit ordered, US currency only.)

Charge my:
☐ Amex ☐ Visa ☐ MC (Minimum order $10.)

Card No._____ Exp. Date_____

Mr./Mrs./Ms._____
please print full name

Address_____

City_____

State_____ Zip_____

*PA residents add 6% sales tax.

CUSTOM DESIGNED REPRINTS

When your product or company is covered by this magazine, you can order custom designed reprints* for use in promotional mailings, sales kits, press releases and point-of- purchase displays.

For more information on how you can take advantage of this wonderful promotional opportunity, call or write:
Jennifer Locke— Reprints Manager,
Ziff-Davis Publishing Company,
One Park Avenue, New York, NY 10016
212-503-5447.

*Minimum quantity—500 reprints.

TECH MARKETPLACE

THE COMPREHENSIVE GUIDE TO PRODUCTS AND SERVICES FOR THE MS DOS MARKET

PRODUCT CATEGORIES

HARDWARE 198-199

ACCESSORY CARDS 198
COOLING DEVICES .....
COMMUNICATIONS .....
COMPATIBLES .....
GENERAL 199
MASS STORAGE .....
PERIPHERALS 199
SECURITY DEVICES .....
USED EQUIPMENT .....

SOFTWARE 199-205

ACCESSORIES/SUPPLIES 199
ARTIFICIAL INTELLIGENCE 199
BUSINESS 199
COMMUNICATIONS 199
DATA BASE MANAGEMENT .....
EDUCATIONAL .....
ENGINEERING 199, 200
EXPERT SYSTEMS 200
GENERAL 200
GRAPHICS 200
LANGUAGES 200
MULTI/USER SYSTEMS .....
NETWORKING .....

SOFTWARE *continued*

OPERATING SYSTEMS 205
PROGRAMMERS TOOLS 200-202
PUBLIC DOMAIN 202
SCIENTIFIC 202
SECURITY DEVICES 202
STATISTICS 202, 203
TAXES .....
TERMINAL EMULATION 203
UTILITIES 203-205
WORD PROCESSING .....

MISCELLANEOUS 205

BAR CODING 205
PUBLICATIONS 205

Advertising Rates and Information: PC Tech Journal Marketplace

PC Tech Journal Marketplace is a special economical section for product and service listings.

Listings are grouped by category and sold by column inches. Second color option available.

Standard Directory Listings are also available for a minimum of 3 issues at $170 per issue ($510 total).

For additional information call 212-503-5115.

PC Tech Journal Classified Advertising Staff
One Park Avenue, New York, NY 10016
(212) 503-5115

Advertising Director
Kathryn J. Cumberlander
Sales Manager
Daniel L. Rosensweig
Sr. Advertising Coordinator
Monica Dixon
Advertising Coordinator
Angela Kiffin
Sales Assistant
Linda Annis
Production Manager
Anne R. Brockinton
(212) 503-5441
Production Coordinator
Elliot Appel
(212) 503-5470

Account Managers

Stanley H. Robinson (212) 503-5116
AL, AR, IA, IL, IN, KS, KY, AZ, CO, OR, NM, LA, MI, MN, MO, MS, NB, ND, OH, OK, SD, TN, TX, NV, AK, GA, UT, CA (ZIP 92999 & DOWN), CANADA (OTHER THAN BRITISH COL.) AND ALL OVERSEAS CALLS.

Lisa B. Stick (212) 503-5172
CT, MA, ME, NH, NJ, NY, RI, ID, MT, MD, VT, DC, DE, HI, NC, SC, FL, VA, WV, WI, PA, WA, WY, CA (ZIP 93000 & UP) BRITISH COL.

TECH MARKETPLACE

THE COMPREHENSIVE GUIDE TO PRODUCTS AND SERVICES FOR THE MS DOS MARKET

HARDWARE

ACCESSORY CARDS

I.C.s and Memory Boards

41256 150/ 120/ 100 ns	2.15/ 2.30/ 2.95
4128 150 ns (for IBM AT)	3.25
4164 150/ 120 ns	.75/ .85
41464 120ns (64K x 4 . . . 18 pins)	2.85
511000 120 ns (1 Meg)	35.00
51258 120/ 100 ns (for Compac 386)	4.20
6264 120ns Static (28 Pins)	2.75
43256/ 62256 100 ns Static	12.00
(Prices listed above are for 100 pcs.)	
2764/ 27128/ 27256 available	Call
8087-3 99.00/ 8087-2	145.00
80287-6 175.00/ 80287-8	239.00
V-20 5/ 8 MHz (9 pcs)	8.50
V-30 8 MHz (9 pcs)	11.50
JRAM-3 or JRAM AT w/ 2MB	329.00
JRAM AT-3 w/ 2MB	382.00
CLASSIC 286 SPEED PAK (8 MHz w/1 MB)	695.00

ADVANCED TECHNOLOGY PRODUCTS CORP.
11141 Georgia Ave., Silver Spring MD 20902
Phone: **301-933-3523** / FAX: **301-933-3643**

CIRCLE 376 ON READER SERVICE CARD

PC ANALYZER
Real-Time debugging package for your PC or XT. Complete with board and debugging software. Also allows you to use your own software debugger. Nonintrusive operation, simple to install. Operates with DOS & QNX. Price $995. Free shipping.
SOFPAK TECHNOLOGIES, INC.
215 Stafford Road, Unit 101
Ottawa, Canada K2H 9C1
(613) 726-1908

Truly Low Cost PC Imaging!



IMAGE ACE II
Video Capture System

- Digitize video from cameras, tuners, and VCRs directly to your IBM PC display
- 320 x 200 x 4 levels
- 1.3 sec. full screen capture
- Complete with hardware card, software, cable, and manual

Lodge Electronics
P.O. Box 338 • Streamwood, IL 60103
(312) 837-6553
CIRCLE 378 ON READER SERVICE CARD

DIGITAL SIGNAL PROCESSOR
The Model 10 coprocessor board is based on the 16/32 bit TI TMS 32010 and is designed for applications in communications, speech, instrumentation, and numeric processing. A 1K complex FFT takes 90ms. Offered with onboard 12 bit 80 Khz A/D and D/A. Includes all utility and applications software. $650-$850.
DALANCO SPRY
Suite 241 2900 Connecticut Ave. NW
Washington, DC 20008
(202) 232-7999

80386
INTEL MOTHERBOARD
WITH USERS MANUAL AWARD OR PHOENIX BIOS
32 BIT BUS • 18 MHZ
NORTON SI·23.0

1	$2800.
2	$2700.
3	$2600.

702·795·2853
CIRCLE 375 ON READER SERVICE CARD

PC-PROMPAK
ROM Expansion for PC!
Aldia systems introduces PC-PROMPAK, a "half-sized" PROM/ROM expansion board for IBM and IBM compatible PCs. PC-PROMPAK will support up to six 28-pin JEDEC compatible devices (ex: 2764, 27128, 27256, 27512, 6264, etc.) with individually selectable address ranges. Prices start at $125 for single units. Quantity discounts and OEM arrangements available. MC/VISA.
ALDIA SYSTEMS, Inc.
P.O. Box 37634
Phoenix, AZ 85069
(602) 866-1786

PC-SPRINT

One of the only slotless speedups chosen by PC Magazine.

- Run your PC, XT or clone at 7.38 mhz.
- 280% Speedup (Norton SI rating)
- Speeds up all software—you can see the difference
- External speed switch
- External reset button
- Change speed "on the fly"
- Compatible with 8087
- Works with all color or mono displays
- "Slotless" plug-in on most PCs
- Includes: Selectable top speed, instructions, warranty, tool, remote mount switch, free BBS subscription

$89.95 V20 add $10. Call for information on other products

Exec-PC, Inc.
P.O. Box 11268 Shorewood, WI 53211
(414) 242-2173
CIRCLE 377 ON READER SERVICE CARD

To place your ad in
Tech Marketplace
Call (212) 503-5115

IBM-AT SPEEDUP

The High-Performance SpeedInjector™ from Ariel

As the industry's recognized leader in high-performance speedup products, Ariel has performed extensive research and developed unmatched experience in this field. Our products offer the complete solution.

- **XCELX 286/287 XPRESS™**—A SpeedInjector for ALL IBM-ATs. Uses reliable frequency synthesis for full compatibility and high performance • 100% variable from 5-13 MHz CPU speed, while running • Mode switch defaults to standard 6 MHz or fast mode • Hardware reset switch • Speedup the 80287 independently. Choose from: Standard—⅓ CPU speed, 8, 10, 12, 14, or 16 MHz actual co-processor speed • Rear mounted • One-year warranty . . . . . $ 99.95
- **XCELX 286/287 XPRESS + The Speed Utilities**—The SpeedInjector with software that will display exact XCELX frequencies • speedup hard disk by 50% • speedup keyboard reaction time • correct floppy disk access $139.95
- **FAST 80286-10**—For CPU speeds of 10 + MHz $299.95
- **FAST 80287**—8, 10, 12, 14, 16 MHz . . . . . Call
- **FAST RAM**—100 & 120 NS, 128K & 256K . . . . . Call
- **Mil-Spec Crystals**—The famous Ariel Crystals. For early ROM ATs. Available: 16-17-18-19-20-22-24 MHz . . . . . $ 19.95

increase overall speed up to 300%



Ariel

ORDER HOTLINE: 201-788-9002
P.O. Box 866—Flemington, NJ 08822

CIRCLE 392 ON READER SERVICE CARD

TOTAL CONTROL OF ALL YOUR FILES
EASYPATH. The Cadillac of hard disk management systems.
—Especially for programmers and power users—

EasyPath fills the void in DOS by allowing complete access to all your hard disk files.

..... EasyPath Lets You .....

- Access and file from any subdirectory
- Redirect file retrieval or file storage
- Execute any program from any subdirectory
- Specify pathing for COM, EXE and all other files.
- Locate any file anywhere on your hard disk
- Find files by name or attribute
- Change attributes of files
- Pipe files to RAM disks
- Search for or redirect files by name, extension, attribute, subdirectory or other means.
- Use wildcards and global filenames.

EasyPath comes with pre-configured BAT files for most major programs, a complete user's guide, and online help.

"Great program!"—Woody Liswood, The source. Now at a new price of $59.95 directly from:

ISOGON CORPORATION

ISOGON CORPORATION
330 Seventh Avenue
New York, New York 10001
212-967-2424

Tech Marketplace . . . the comprehensive guide to products and services for the MS DOS market.

TECH MARKETPLACE

THE COMPREHENSIVE GUIDE TO PRODUCTS AND SERVICES FOR THE MS DOS MARKET

General

VIDEO LAN 'LINK SYSTEM'®

FOR IBM, PC, PC/XT, PC/AT labs. Instructor has complete control of all trainee computer monitors. Instructor can 1) transmit image, 2) receive trainee image or 3) transmit any trainee image to any/all trainees. Color or mono. Software independent. Increases instructor efficiency and trainee comprehension.
APPLIED COMPUTER SYSTEMS, INC.
3060 Johnstown-Utica Road
Johnstown, OH 43031
1-800-237-LINK

9 TRACK TAPE SUBSYSTEMS IBM FORMAT COMPATIBLE PC/XT/AT to MAINFRAME TAPE DATA EXCHANGE

- Read/Write data files to or from any computer on universally standard tape. Process archive files.
- Streaming and Start-Stop Systems.
- For all IBM compatibles.
- 800 NRZI, 1600/3200 PE, 6250 GCR.
- Fast, reliable read-after-write hard disk backup.
- Data Transfer Rate: 1 to 4 MByte/Minute.
- Record Translation. EBCDIC/ASCII Conversion.
- Total system, all software & hardware supplied.
- Best Installation and Software Support.

9 Track Magnetic Tape System experience since 1971. We have supported hundreds of satisfied customer installations.

Call for complete information
Contech Computer Corporation
P.O. Box 153, Tarzana, CA 91356
(818) 343-6505

CONTECH

21000 Devonshire Avenue Suite 110
Chatsworth, CA 91311
CIRCLE 380 ON READER SERVICE CARD

Peripherals

EPROM/EEPROM PROGRAMMER

Programs 2716-27512, 25xx, 68764/66 eproms via RS-232. Also 874x, micros, 28xxA & 52Bxx eeproms. Automatic Baud rate select, built in menus, no personality modules. Price: $250. Mention this ad for free terminal software. 16 BIT I/O MODULE $75
For control of input or output lines via RS-232. Use with modems for remote control.
INTELLITRONICS
P.O. Box 3263;
Tustin, CA 92680
(714) 669-0614

SPEECH SYNTHESIS

SynPhonix: TRUE Unlimited Speech Synthesizer for IBM-PC/XT/AT/jr & compatibles. This low power short card includes an SSi263 speech chip, amplifier and speaker. Software includes Text-to-Speech, Phonetic Editor, Talking Clock & demos. Can be programmed with BASIC and other languages. Prices start below $200.

SynPhonix™
Electronic Speech Articulator

Artic Technologies
1311 N. Main St.
Clawson, MI 48017
(313) 435-4222

CREATE A DISKLESS PC!

PC-ROMDRIVE allows users to create a "Diskless PC" capable of booting a ROM-resident copy of MS-DOS and/or user application programs. PC-ROMDRIVE consists of a PC-compatible ROM/PROM expansion board and the PC-ROMDRIVE software. PC-ROMDRIVE is priced at $195 for single units. Quantity discounts and OEM arrangements available. MC/VISA
ALDIA SYSTEMS, Inc.
P.O. Box 37634
Phoenix, Az. 85069
(602) 866-1786

CP/M & 1.2Mb AT ON PC

With MULTI-DISK card & UniForm-PC use 3.5, 5.25 & 8-inch single & double density CP/M format as DOS diskettes on your IBM PC or XT. Many MS-DOS formats supported including IBM AT 1.2 Mb. HP-150 & Data General 1. Over 200 formats. Both MULTI-DISK & Uniform-PC for $225. Disk drives & adapter cable available.
PS ENGINEERING
P.O. Box 51068
San Jose, CA 95151-5068
1-800-369-2398; 1-800-423-7171 in CA.

Software

Accessories/Supplies

DISK COPIER

Fast (one minute)
Simple (one button)
Reliable (one board)
$995 (one price)

RECORTEC
275 Santa Ana Ct., Sunnyvale, CA 94086
(408) 737-8441
CIRCLE 379 ON READER SERVICE CARD

Artificial Intelligence

TURBO EXPERT

Full Scale IBM-PC Expert Systems/Ready To Consult. $34.95. Runs on all compatibles.
#1. THE STOCK MARKET EXPERT
#2. THE EXECUTIVE HEALTH EXPERT
#3. THE PSYCHIATRY EXPERT
#4. THE TURBO EXPERT TOOLKIT III
Please specify # when ordering.
THINKING SOFTWARE, INC.
46-16 65 Place
Woodside, N.Y. 11377
(718) 429-4922

Tech Marketplace, the home of the power buyer.

Business

TRANSPORTATION RESEARCH

TSA88	Transportation Simplex Algorithm (up to 510 sources, sinks or transshipment points)
TNET88	Transportation Network System (networks up to 510 nodes & 16K links)
TPR088	Transportation Problem Solver (shortest path, tours up to 50 stops)

Req. 192K, color graphics adaptor. $99 each w/ 8087 support, User's guide. Write or call for our brochure.
EASTERN SOFTWARE PRODUCTS INC.
P.O. Box 15328,
Alexandria, VA 22309
(703) 549-5469

Auto-Pilot™

Put your responsibilities on Auto-Pilot: ToDo list, sophisticated Tickler file, appointment calendar. Tracks employee assignments/action items. Windows display future, present, and uncompleted past events. Multi-users, multi-files, periodic & one time events. DOS 2.0+ PC/XT/AT/ compatible $29.95 Check/Visa/MC
Advanced Concepts
P.O. Box 246
Ironia, N.J. 07845
1-800 235-6646 Ext 852 1-800-235-6647(CA)

Communications

PC SERIAL DATA ANALYZER

Use your IBM PC or compatible to analyze data streams between serial devices. Windows show each devices transmissions in ASCII or HEX. 64K buffer, Signal line monitoring, disk save, "Lotus" style interface, an invaluable tool for debugging serial interfaces. DISK and MANUAL $150.00
TRIPLE C SOFTWARE
1827 S.W. 24th Ave.
Fort Lauderdale, FL 33312
(305) 583-0687

Engineering

ENGINEER'S AIDE

- Pipeline/Ductwork Sizing
- Pump/Fan/Compressor Sizing
- Heat Exchanger Sizing
- Orifice/Control Valve Sizing
- Project Financial Analysis
- Conversion Calculator
- Specification Writer

Pull down menus, Pop-up help windows, Single Screen entry & results-ALL above for $395 (into price, $back guarantee). For IBM & MAC.
ENGINEERING PROGRAMMING CONCEPTS
P.O. Box 925
Camarillo, CA 93011
(805) 484-5381 In CA, 1(800) 367-3585

TECH MARKETPLACE

THE COMPREHENSIVE GUIDE TO PRODUCTS AND SERVICES FOR THE MS DOS MARKET

ENGINEERING

METAL FABRICATORS

PC/Cultist takes input from your bill of material—Detail drawing and calculates the best cutting combination for any length stock and prints a shop ready cutting list and scrap report. Also an optimization feature finds best multi length for mill orders. Price $300. Demo Disk $25.00
THE JOSEPH ALBERT CO.
P.O. Box 611
Blue Island, Illinois 60406
(312) 349-9032

FINITE ELEMENT ANALYSIS

MSC, the leader in FEA technology, markets a full line of FEA tools for personal computers. Starting at $45 for MSC/pal INTRO on either the IBM PC or the Apple Macintosh, our products are designed to be complete and easy to use. Interfaces for most CAD systems available.
The MacNeal-Schwendler Corporation
815 Colorado Blvd.
Los Angeles, California 90041
(213) 259-3888

EXPERT SYSTEMS

CxPERT for Expert Systems

C programmers interested in using expert systems technology will love CxPERT. AI features such as explanations, why, frames, av pairs, legal values and more are completely compatible with C. Create executable systems with no royalties. $165 + $5 s&h. MD add 5%. CK/MO/Visa/MC. Req. C compiler & DOS 2.0+.
SOFTWARE PLUS
1652 Albermarle Dr.
Crofton, MD 21114
(301) 261-0264

GENERAL

DOCUMENTATION BY MAIL™

When they ask about your manual...Do you politely change the subject? No more! Give them documentation you can be proud of, at a cost you can afford. Fixed price contract, professional quality, quick turnaround. User's guides, tutorials, reference manuals. Call for a no-obligation free estimate.
DOCUMENTATION-BY MAIL
20370 SW 84 Ave
Miami, FL 33189
(305) 253-2317

GREAT SOFTWARE, CHEAP!

Only $5.95 per disk for absolutely smashing Shareware and Public Domain programs! Money-back guarantee. PC-Outline, AutoMenu, PC-Key Draw, PC-DeskTeam, PC-Write 2.7, DOSamatic, Utilities Galore plus Databases, Arcade and Adventure Games. Lots more! IBM PC, PC jr, and compatibles. Send for free catalog.
SHAREWARE EXPRESS
31877 Del Obispo, Suite 102Q
San Juan Capistrano, CA 92675
(714) 240-1322

TAPE/DISK CONVERSIONS

Conversion services to or from over 500 computer systems:
- Magtapes
- Micro Computers
- Mini Computers
- Word Processors
- Typesetters

Our conversion capabilities surpass most in the industry.
PIVAR COMPUTING SERVICES, INC.
165 Arlington Hgts. Rd. #T
Buffalo Grove, IL 60089
(312) 459-6010

GRAPHICS

MetaWINDOW™/TurboWINDOW™
Advanced graphics toolkit provides Xerox Star/Apple Macintosh style graphics on your IBM PC. Supports most popular graphics cards. Allows you to create pop-up menus, windows & icons; use proportionally spaced fonts; rubberband & rag lines, text or bitmap images; supports mouse-cursor tracking. Tightly optimized for use with Turbo Pascal, IBM Pascal, C, Fortran.

METAGRAPHICS SOFTWARE CORPORATION

METAGRAPHICS SOFTWARE CORP.
4575 Scotts Valley Drive
Scotts Valley, CA 95066
(408) 438-1550
CIRCLE 399 ON READER SERVICE CARD

FORTRAN GRAPHICS LIBRARY

GRAFMATIC (screen graphics): 75 MS FORTRAN/Pascal, R-M/Profort, Lahey FORTRAN callable subroutines. Fully documented, prof. graphics capabilities, inc. general utility, 2-D interactive, total 2-D plots, 3-D plots and solid models. $135. H-P or H-I plotter? get PLOTMATIC, complete plotter graphics library. Interfaces w/GRAFMATIC. $135. Both $240.
MICROCOMPATIBLES, INC.
301 Prelude Drive Dept. J
Silver Spring, MD 20901
(301) 593-0683

SCIENTIFIC DATA PLOTTING

SCI-GRAF creates graphs up to 1680 X 1712 dots (over 3 million pixels!) on Epson or IBM graphics, printers. Supports log scaling, overlays, point-labeling, legend creation, batch mode, wide-carriage printers, and color graphs on a JX-80. Requires DOS 2 or 3, 256k. No credit cards. $99.95
Microcomputer Consultants (MSC)
32 W Anapamu Suite 190
Santa Barbara, CA 93101
(805) 963-3412

35mm SLIDE FROM YOUR PC

COMPUTER SLIDE EXPRESS converts graphic files produced on the IBM PC into brilliant 35mm color slides with color resolution 400% better than your monitor. Leave your printouts behind. Use high resolution color slides up to 4000 line. COMPUTER SLIDE EXPRESS $9/slide.
VISUAL HORIZONS
180 Metro Park
Rochester, NY 14623
(716) 424-5300

LANGUAGES

FINALLY! MODULES

Add class to your compiled BASIC programs with FINALLY ! MODULES. Use pull-down WINDOWS, horizontal menus, pop-up help screens, input screen and directory managers. For use with FINALLY! Library and Quick Basic 2.0 or IBM compiler 2.0. 30 day MoneyBack guar. Visa/MC/CK/MO. FINALLY! MODULES is $99+$4 s/h.
Komputerwerk Inc. Dept PCT
851 Parkview Blvd.
Pittsburgh, PA 15215
(412) 782-0384

FIRMWARE DEVELOPMENT IN C

REX-C/86 C package supports ROM code generation. Includes XC86 C compiler which implements draft ANSCI C standard, supports-in-line assembly, produces optimized 8086/87/186 reentrant code for real-time environment, generates separate segment for initialized data and string constants for ROM-based applications, produces object file in Intel OMF with debug information, global and local symbols with data type and line numbers for high-level debugging. Price is $750 which includes XC86, linker, locator, librarian, hex formatters, and run-time library source.



SYSTEMS & SOFTWARE, INC.
3303 Harbor Blvd., C11
Costa Mesa, CA 92626
(714) 241-8650

PROGRAMMERS TOOLS

ATTENTION TURBO PASCAL USERS!
Crash the 64K Barrier
Try **TURBO PACKAGE** now!
90 day money back guarantee!
Modular Programming!
Promotes **REUSE** of working **CODE**
CUTS development **TIME**
IMPROVES system **RELIABILITY**
SIMPLIFIES program **MAINTENANCE**
FILL 640KB with code/data any way you want
VERY FEW CODE CHANGES.
FASTER than chaining or overlaying
SUPERMATH, FREE!
With purchase of Turbo Package
40 plus LONG (**32-bit math**) routines
Faster than real - big enough for $.
ASM coding insures top performance
Just $49.95 (in TX add tax)
Visa/MC Outside USA add $5.00 shipping
IBM/PC, XT, AT or compatible MS/DOS machine and Z100
Write or call for more information
CONVERSATIONAL COMPUTER SYSTEMS
5371 Verbena Rd.
San Antonio, TX 78240
Phone: (512) 692-0353
CIRCLE 381 ON READER SERVICE CARD

ROMable CODE on PC!

PCLOCATE allows PC users to develop ROM-based software from MS-DOS "Exe" files. The user specifies the physical location of all segments. Output files are compatible with most PROM programmers. PCLOCATE supports the 8086, 8088, 80186, 80188, and 80286 processors. MC/VISA.
ALDIA SYSTEMS INCORPORATED
P.O. Box 37634
Phoenix, AZ 85069
(602) 866-1786

MODULA-2 TOOLS: $19

REPERTOIRE—the proven toolkit for Logitech, ITC and others: 250p manual (on disk); screen design/display system; DBMS with variable-length records, multi-window editor, natural-language analyzer; over 200 low level routines. Printed manual: $15. Source code (440K): $89. Call for free demo/doc. disk.

MODULA-2

PMI
4536 SE 50th
Portland, OR 97206 (503) 777-8844
BIX: pmi; Compuserve: 74706,262

Productivity Tools
Software Revision Management System™
SRMS is a full featured version control system featuring:
- 10 Integrated Utilities with user shell
- Capability for hundreds of versions/library
- Merge utility resolves parallel effort conflicts
- Report Generation Utilities
- Typeset documentation and much more!

Version 3.0 $185

QMAKE™
- Program generation utility patterned after UNIX make to aid in rebuilding sytems
- Recompiles only routines necessary
- Support for macros and multiple entry points
- Integrates fully with SRMS

Version 1.2 $99

TXTTOOLS
- QDIFF - Windowed File Difference Utility
- QSE - Quilt Stream Editor
- QSRCH - Like UNIX GREP

$85

Quilt Computing
7048 Stratford Road
Woodbury, MN 55125
(612) 739-4650
CIRCLE 396 ON READER SERVICE CARD

FORTRAN Developers

Essentials for documenting and debugging large FORTRAN programs. DOCUMENT'er: prepares x-references and symbol tables for an ENTIRE program with ALL routine, COMMON, ... definitions + ALL uses. DIAGRAM'er: draws clear diagram(s) of complex code and data structures of your code. Interactive + many display options. Needs only existing source, MAP, and library files. All compilers supported. Both $128.75

IMPULSE ENGINEERING

Ray Strong, (415) 788-4611
IMPULSE Engineering
P.O. Box 3540
San Francisco, CA 94119-3540

TECH MARKETPLACE

THE COMPREHENSIVE GUIDE TO PRODUCTS AND SERVICES FOR THE MS DOS MARKET

PROGRAMMERS TOOLS

VERSION CONTROL SYSTEM

TLIB™ stores ALL versions of your source in ONE compact library file, even with hundreds of revisions. Updates (deltas), 5-7 times faster than Unix SCCS. Date & comments for each version, easy retrieval. LAN-shared libraries. Free public domain MAKE (with source) by Landon Dyer. DOS 2.x/3.x $99.95 $3 s/h VISA/MC.
BURTON SYSTEMS SOFTWARE
P.O. Box 4156-TJ
Cary, NC 27511-4156
(919) 469-3068

END YOUR FRUSTRATIONS—

MASTER YOUR SCREENS WITH FORMIX™

Developing, testing & changing screens is tedious, frustrating, time-consuming work.

Until now.

With FORMIX, you can trouble-shoot before writing one line of code. You can even prototype the entire system with actual screens—complete with data entry. Little changes in screen design are little effort. So are major changes.

Our advance panel-oriented system allows you to quickly develop complex screens that integrate several panels or windows.

Plus, FORMIX has an on-line help system. You just write the application help text. FORMIX handles the rest.

In short, FORMIX simplifies screen design and slashes the cost of program development. Let FORMIX handle the tedious, error-prone programming aspects while you concentrate on solving today's application problems—and eliminating a lot of tomorrow's.

And there's more. Contact us for details. We're ready to prove the power, flexibility & simplicity of FORMIX.

MCSI
An Expression of Quality
Master Computer Systems, Inc.
FORMIX Division
9531 West 78 Street
Eden Prairie, Minnesota 55344
612/944-5220
FORMIX interfaces with ADA, Assembler, Basic, C Cobol, Fortran & Pascal

SCREEN MANAGER

SAVE TIME! Powerful Screen Designer and Memory Resident Screen Manager Increases Programmer Productivity! Interfaces to most languages. BASIC, FORTRAN, COBOL, C, PASCAL, PLM86, ASM. Not a Code Generator! No Royalties.

$125 VISA/MC

The West Chester Group
P.O. Box 1304
West Chester, Pa 19380
(215) 644-4206

FREE DEMO DISK
CIRCLE 383 ON READER SERVICE CARD

MS-COBOL SCREEN GENERATOR

MSCREEN generates Screen Section code for MICROSOFT/IBM COBOL. Paint, Edit Screen. Draw Boxes. Complete set of attributes for each field. No field terminators. Many other features! COBWORK generates Report Headers. $90+Shp.
TAJEVA SOFTWARE
6064 Belle Grove Cv.S.
Memphis, TN 38115
(901) 365-4692

ASSEMBLY LANGUAGE TOOL

VersiCERF™ creates a sorted Master Cross-Reference Listing of an entire application from the MASM CRF files. Pinpoints which source modules are affected by changes to common PROC's, variables, etc. Handles 100+ separate programs source files. Full X-Ref or just PUBLIC symbols. $55 MC/VISA/COD

SUMMIT INFORMATION SYSTEMS INC.
73 East Lane
Willingboro, NJ 08046
1-800-334-4096 (in NJ 609-871-0202)

PASCAL-to-C TRANSLATOR

Industrial strength conversion from Turbo, Microsoft, UCSD, MT+, Apollo, Macintosh, and other Pascals to K&R C. Handles nested procedures, intrinsic functions, separately compiled units and modules, all data types including long integers.
Requires 512K IBM PC/XT/AT. Send up to 500 lines of Pascal and we will convert it for FREE. Site licensing from $5,000. Conversions 50 cents/line.
TGL Inc.
27096 Forest Springs Ln.
Corvallis, OR 97330
(503) 745-7476

PC CROSS-ASSEMBLERS

Up to 10,000 lines per minute! Fast X-ref and Linker plus Macros and Librarian. Generates HEX, TEKHEK, S-records, and .OBJ output records. Over 40 micros and XENIX, MS DOS, CPM 80 and ISIS versions. Accepts MOTOROLA and INTEL directives and Mnemonics.
RELMS™
P.O. Box 6719
San Jose, CA 95150
(408) 265-5411

BOOSTERS V2.0 IS HERE!

Tools for Turbo Pascal programmers who need the speed and efficiency of inline code. 70+ string, video, and DOS routines—incl. Exec. V2.0 also incl. powerful new SCREEN GENERATOR, DOS SHELL, and many example programs. All Pascal and assembler source, manual, update notices. No Royalties. $40 + 4% GA tx. Visa/MC.
GEORGE F. SMITH & COMPANY
609 Candlewick Lane
Lilburn, GA 30247
(404) 923-6879

BASIC + StruBAS

Developing serious applications in compiled BASIC? It's easier with StruBAS v2.0 tools complementing QuickBASIC and IBM BASIC 2.0 with extended structured code, screens, menus, native ISAM, Btrieve interface, and subroutine object library. $495 single, $1495 site license. VISA/MC. Not copy protected.
LANEY SYSTEMS INC.
3 Office Park Dr., Suite 100
Little Rock, AR 72211
501-225-7755

True Shell for BASIC

SHELL any other program or batch file, including other compiled BASIC programs and the BASIC interpreter. Requires DOS 2+ and IBM (Ver 1 or 2) or Microsoft compiler (QB1, QB2 or 5.36). QB2 requires DOS 3+. Only $29.95 + $3 s/h. MC/VISA/COD OK. 30 day money-back performance guarantee.
MicroHelp, Inc.
2220 Carlyle Drive
Marietta, GA 30062
800-922-3383. In GA 404-973-9272

APL Programmers!

Interface C and APL*PLUS with APL2C™! Speed up your APL code. Link to C libraries. Includes K & R C compiler. $195 Complete. FULLSCREEN Panels™ is here! Screen Generator and full-screen processor for the APL environment. Pop-ups, panels, menus, scrolling fields NO ROYALTIES, $150.
Lauer Software
PO Box 728
Newtown, PA 18940-0728
(609) 921-6249

Tech Marketplace . . . the comprehensive guide to products and services for the MS DOS market.

Frustrated with Assembler?

Unique program adds structure to assembly language. IBM/MASM compatible. Develop and debug faster with structured concepts. IF-THEN-ELSE, SELECT-WHEN-OTHER, DO WHILE/UNTIL/INCREMENTAL and combinations. LEAVE/LEAVEALL loop exits, and file includes. Nest 16 deep. $50.
Michael T. Holland
8808 Boulder Lane
Little Rock, AR 72207
(501) 224-2749

P-tral
BASIC TO PASCAL TRANSLATOR

Translate your BASIC source programs to Pascal source. P-tral, now available for the IBM PC and compatibles, will translate MS–BASIC/BASICA to Turbo Pascal (Req Dos 2.0 or later w/ANSI.SYS).

P-tral supports the translation of business, scientific, graphics and game software. And when necessary, P-tral interacts with you to pick out subroutines, name subroutines and rename variables which don't fit Pascal criteria. It will also prompt for fixed dimensions for dynamic arrays.

LIST PRICE: $179.

(212) 206-6490/924-0576
WOODCHUCK INDUSTRIES
340 WEST 17TH STREET (#2B)
NEW YORK, NY 10011
CIRCLE 398 ON READER SERVICE CARD

LINK & LOCATE



LINK & LOCATE enables PC users to produce ROM-based firmware for 8086/87/186 from object files generated by popular C compilers, such as from Wizard, Microsoft and Lattice, and MASM assembler from Microsoft. Provides full control of segment placement anywhere in memory. Supports output of Intel HEX file for PROM programmers, Intel OMF absolute object file for symbolic debuggers and in-circuit emulators. Includes Intel compatible linker, locator, librarian and hex formatters. $350.

Systems & Software, Inc.
3303 Harbor Blvd., C11, Costa Mesa, CA 92626
Phone (714) 241-8650 FAX (714) 241-0377 TWX 910-695-0125
CIRCLE 384 ON READER SERVICE CARD

TECH MARKETPLACE

THE COMPREHENSIVE GUIDE TO PRODUCTS AND SERVICES FOR THE MS DOS MARKET

PROGRAMMERS TOOLS

BASIC Base 007

BASIC database library including menus, passwords, program generator, query, screen control, data record control, index commands for add, delete, find, find next, find last. $15 demo with disk manual and compiled database software. $99 development system with library source code and printed manual. $165 for compiled & all 4,000 + lines of BASIC code.
Application Micro Computers, Inc.
1663 Bachan Ct.
Reston, Va. 22090
(703) 471-1471 - 3:00 to 9:00 P.M.

Quelo® 68000

Software Development Tools

Quelo Assembler Packages are **Motorola compatible.** Each package includes a macro assembler, linker/locator, object librarian, utilities for producing **ROMable code,** extensive indexed typeset manuals and produces **S-records,** Intel hex, **extended TEK hex, UNIX COFF** and symbol cross references. **Portable source** written in "C" is available. It has been ported to a variety of mainframes and minis including **VAX.**

68020 Assembler Package
For CP/M-86,-68K and MS/PC-DOS . $ 750

68000/68010 Assembler Package
For CP/M-80,-86,-68K and MS/PC-DOS . $ 595

68000 **"C" Cross Compiler**
For MS/PC-DOS by Lattice, Inc.
With Quelo 68000/68010 Assembler Package $1095
With Quelo 68020 Assembler Package . $1250

Call **Patrick Adams** today:

Quelo, Inc.
2464 33rd W. Suite #173
Seattle, WA USA 98199
Phone 206/285-2528
Telex 910-333-8171

COD, Visa, MasterCard

Trademarks: CP/M, Digital Research; MS, Microsoft Corporation; Quelo, Quelo, Inc.

CIRCLE 382 ON READER SERVICE CARD

Tech Marketplace,
the home
of the
power buyer.

Turbo Pascal Programmers:
15 MINUTES = 200 HOURS!
with new *turboMAGIC*
code generator.

Input forms and help windows up to 66 lines long. Scrolling within framed windows. Pop-up menus. Pull-down menu systems. And **much** more!

Read what professionals say: "Fast automatic updating of dependent fields adds flair to your input screens...turboMAGIC will be a blessing for programmers who would rather not write the user interface for every program." Neil Rubenking, PC Magazine, 24 Feb. 87.

Order your magic today! Just $99. Call 800-225-3165. Money Back Guarantee. Requires 256K IBM PC compatible.

turbo magic™
Sophisticated Software Inc.
6586 Old Shell Road
Mobile, AL 36608
205-342-7026

CIRCLE 385 ON READER SERVICE CARD

PUBLIC DOMAIN

TURBO PASCAL™ SOFTWARE $6

Write or call for information about:
- Systems & applications development tools
- Programs for home and business
- Communication tools & applications
- Games in specialized applications
- Scientific/engineering programs & routines
- Graphics including animation tools

TURBO S.I.X.
P.O. Box 8373
Waco, TX 76714
(817) 753-2182

TURBO PASCAL $2/disk

TSS is a BBS-by-mail, no modem needed (long distance is more $$$ than mails)! 60+ disks of Pascal files. Most incl. source code. All files compressed. Membership fee ($25) incl. free starter pkg. and 2 FREE disks with 1st order. Non-members $7/disk. Cat. list $5. VISA/MC/COD (s/h extra) (data) 617-545-9131
TURBO SOURCE SEARCH
P.O. Box 876
Scituate, MA 02066
(voice) 617-545-6677

PUBLIC DOMAIN SOFTWARE IN C

Over 115 volumes of public domain software in CP/M and MSDOS format.
- editors, compilers, text formatters
- many UNIX-like tools & misc. utilities
- communications packages, etc.

Write or call for more details. Send $10 for comprehensive directory.

C Users' Group
THE C USERS' GROUP
P.O. Box 97
McPherson, KS 67460
(316) 241-1065

SCIENTIFIC

SCI/ENG GRAPHICS

OMNIPLOT [S] (screen graphics) & OMNIPLOT [P] (plotter driver) provide integrated engineering/scientific 2-D & 3-D graphics with NO PROGRAMMING! Menu-driven, flexible, professional. Choice of formats: tabular/line, contour, bar, pie, 3-D wire frame & much more! OMNIPLOT [S] $195. Add OMNIPLOT [P], both $295.
MICROCOMPATIBLES, INC.
301 Prelude Dr. Dept. J
Silver Spring, MD 20901
(301) 593-0683

8087 FFT/VECTOR PROCESSING

The VECTOR87 library is written in assembler, includes 60 routines to speed up your number-crunching programs. Uses 80(2) 87 extensively. PC 1K real FFT takes only 1.2 sec. Versions for Fortran (MS, RM, Lahey), C (MS, Lattice), Turbo Pascal -87. $150 per version with source, no royalties. Write for technical information.
VECTORPLEX Data Systems Ltd.
136-100 Maitland Place N.E.
Calgary, Alberta, Canada T2A 5V5
(403) 248-1250

DATA ACQUISITION & ANALYSIS

*MEASURE for data acquisition directly to Lotus 1-2-3*FOURIER PROSPECTIVE II advanced digital signal analysis *Lotus MANUSCRIPT & technical document preparation system*PRIME FACTOR FFT subroutine library. Call Turbo Pascal, C, Fortran, Basic. Up to 65,520 data-points. Mention this ad and get PF SST for $99. *TURBO PASCAL FROM BORLAND *TELEVISION for Image Communications *8087 Coprocessors, all varieties*Dash-16A/D converter board from MetraByte.
ALLIGATOR TECHNOLOGIES, INC.
P.O. Box 11386
Costa Mesa, CA 92627
(714) 662-0660

NUMERICAL C SOFTWARE

Computationally stable numerical routines for scientific C software developers. LINLIB contains all the basic vector and matrix routines solutions to equations, LU, QR, Cholesky factors of matrices, least squares solutions. LINLIB has splines, B-spline routines, spline interpolation, spline approximation of data. $150.
INFORMATION AND GRAPHIC SYSTEMS
15 Normandy Court
Atlanta, GA 30324
Call (404) 231-9582

SECURITY DEVICES

"NEW" BIT-LOCK® SECURITY

Pirace SURVIVAL ">4" YEARS proves effectiveness of powerful multilayered security. Uses rapid decryption algorithms and small reliable port for transparent security device. NOW AVAILABLE for PARALLEL or SERIAL port. NEW KEY-LOK™ security device available at HALF-PRICE.
MICROCOMPUTER APPLICATIONS
7805 S. Windermere Circle
Littleton, CO 80120
(303) 798-7683 or 922-6410

Multi-User Security

File access by user at the directory or sub-directory level. Protection from unauthorized formatting of specified drives by user. User transparent. Accounting reports by user and category.
PC-LOCK $90.
ONTAR Corporation
129 University Road
Brookline, MA 02146-4532
617-739-6607

EVERLOCK COPY PROTECTION

Designed for user-transparency, clone compatibility & strength. It features:
—no I/O plugs or special media
—FULL hard disk & cartridge support
—file-server network support
—variable number of installs (0-99)
—demo diskette option with unlock
—protected upgrades by modem/BBS
All this for $495 with no meter counts. Free info & demo disk.
(Duplication services also available.)

AZ
Az-Tech Software, Inc.
426 Grandview
Richmond, MO 64085
(816) 776-8153

STATISTICS

RATS! VERSION 2.0

RATS, the best selling Econometric software package now includes daily & weekly data, a new, easier to use 500-page manual, & many advanced features. Use RATS for time-series & cross-section regression, including OLS, ARIMA, VAR, logit, & probit. IBM PC or compatible. $200. VC/Visa. Call for brochure.
VAR Econometrics, Inc.
P.O. Box 1818
Evanston, IL 60204-1818
1(800) 822-8038

StatPac Gold™

Buy the best statistical and forecasting package available. Complete and easy to use.

Call for free descriptive brochure:
1-800-328-4907

WA
WALONICK ASSOCIATES, INC.
6500 Nicollet Avenue S. Minneapolis, MN 55423
(612) 866-9022

CIRCLE 393 ON READER SERVICE CARD

TECH MARKETPLACE

THE COMPREHENSIVE GUIDE TO PRODUCTS AND SERVICES FOR THE MS DOS MARKET

STATISTICS

P-STAT®

Full mainframe package for IBM PC/XT/AT & compatibles. Combines data & file management, data display, statistical analysis, report-writing & survey analysis in a single package. 4GL programming language, online HELP, menu or command driven with interactive EDITOR. $95 demo and Site License available.
P-STAT Inc.
471 Wall Street, P.O. Box AH
Princeton, N.J. 08542
Telephone: 609-924-9100 Telex: 466452

STATISTIX™—ONNLY $75!

STATISTIX is a powerful and very easy-to-use interactive statistical system for micros. Used by many major universities, businesses, state governments and research organizations. Please check us out before you buy a statistics program; you'll agree SX is a "best buy"! SATISFACTION GUARANTEED—For more info:
NH ANALYTICAL SOFTWARE
801 West Iowa Avenue
St. Paul, MN 55117
(612) 488-4436

TERMINAL EMULATION

MAI/BASIC FOUR TERMINAL PRINTER EMULATOR

The MAI Terminal Emulator allows your PC/XT/AT to be used as a MAI 7270 VDT terminal. Very easy to use. Menu driven. Includes Slave Printer emulation. Sends/receives files to/from the MAI computer. Available for several languages. Dealers/distributors wanted. $395+15(s&h).
ELEKTROKONSULT A/S
Austadg.4,pob 846
N-3000 DRAMMEN
NORWAY Tel.+473 831500

PCBTAM
Communications Access Method

General purpose binary synchronous access method for custom file transfer or terminal emulation on PC/XT/AT with IBM BSCA card.

- high performance, full featured
- object ($300.00) or source ($2,500.00) license
- link with ASM, Lattice or Microsoft programs
- Z-SIO version available

Symbiotic, Inc.
1035 Route 46 East
Clifton, NJ 07013
201-777-6454
CIRCLE 389 ON READER SERVICE CARD

Tech Marketplace...
Second Color Option Available
Call (212) 503-5115
For More Information

BARR/HASP INTELLIGENT RJE WORKSTATION

Hardware and software communications package for IBM PC, XT and AT. Simultaneously transmits data to host and receives output directly to MVS/JES2, MVS/JES3, VS/RSCS, and CDC/NOS, bypassing TSO and CMS. Emulates IBM 3777-2 and HASP on IBM 360/20. Line speed: 1,200 to 19,200 baud (56,000 bps on AT). Supports multiple high-speed printers beyond 2,400 lpm. (6,000 lpm on AT). Features: concurrent DOS, LAN support, printer forms control, plotter support, unattended operation, easy installation. $1,290 includes Hardware & Software.

BARR

BARR SYSTEMS, INC.
2830 NW 41st Street, Building M
Gainesville, FL 32606
(800)-BARR-SYS/(904) 371-3050

UTILITIES

QDEX YOUR DATA FILES!

No need for sentinels, hash routines, etc. QDEX Btree modules support find, first, last, next, and previous calls, plus partial key searches and multiple indexes to your data. QDEX is written in Microsoft C, and links with compatible .oBj modules. Manual with examples.
$59.00 + $2 COD
NORTH Computer Consulting
775 East 8230 South
Sandy, Utah 84070
(801) 566-1986

DISK ACCELERATOR V2.0

DiskCache speeds up your hard disk access. Disk caching and ram disk in one package. Ram disk shares cache space. Transparent, flexible, configurable, no h/w changes. RAM, EMS, and AT extended memory versions incl. Not copy protected. VISA, MC, volume discounts. No PO's w/o prior approval. $49.00
DATAMORPHICS LTD.,
P.O. Box 820
Stittsville, Ontario, Canada KOA 3G0
Or call (613) 836-2670

HARD DISK EXPANSION!

Disk Manager allows the installation of any ST506 hard disk on PC,XT,AT and compatibles. Volumes up to 256mb! Menu driven/auto install, compatible w/ all vers of MS/PC DOS (does not modify DOS), up to 16 volumes, easy to use! $125+ ship. Ask about Novell product! Dealer inquiries invited.

ONTRACK COMPUTER SYSTEMS INC.

ONTRACK COMPUTER SYSTEMS, INC.
6222 Bury Drive
Eden Prairie, MN 55344
(612) 937-1107

THE NEWMAN UTILITIES

45 Utilities including UNERASE and EMUCOLOR which will run most color software on monographics card -$19.95. EZRUN menu system: allows running 1-36 programs with a keystroke -$19.95. 15 day MB guar, $2 Ship
NEWMAN COMPUTER
2 Briar Mills Drive
Suite 2A
Bricktown, NJ 08724
(201) 458-5169

CHARACTER CUSTOMIZATION

CHARGENI 3.0 works with the IBM/EGA to let you modify the character set, allowing many wordprocessors to display technical material, equations or other special characters. Requires DOS 2 x or 3.x, IBM Standard or Enhanced Graphics Adapter. $35+ $2 s/h (MN add 6%).
DK MICRO CONSULTANTS
P.O. Box 6714
Minneapolis, MN 55406
(612) 722-0931

Quaid Analyzer
the tool that created CopyWrite

Now you can debug your own programs with a professional quality debugger - the one that unraveled every form of copy-protection used on the PC.

With the Quaid Analyzer, you can:

- ☐ See occurences of any interupt, with its meaning shown on the screen.
- ☐ View memory as text or instructions, scrolling as easily as you do with an editor.
- ☐ Run until a memory location or I/O port is changed.
- ☐ Protect your hard disk from accidental destruction.
- ☐ Analyze software without the source, even when it uses countermeasures to thwart tracing.
- ☐ See all stages of the boot load.

We kept the Quaid Analyzer off the market to avoid helping publishers with copy-protection. Now that copy-protection is gone, we can sell it to you.

The Quaid Analyzer is a software tool occupying 100K bytes. It runs on any IBM PC and most MS-DOS systems without hardware modification.

Quaid Software Limited

$99 U.S. To order Call **(416) 961-8243**
All orders shipped at our expense within a day. All major credit cards accepted.
or write to:
45 Charles St. East
Third Floor, Dept. 602
Toronto, Ontario. M4Y 1S2

Ask about Disk Explorer the program that takes over where Quaid Analyzer leaves off.
CIRCLE 387 ON READER SERVICE CARD

TECH MARKETPLACE

THE COMPREHENSIVE GUIDE TO PRODUCTS AND SERVICES FOR THE MS DOS MARKET

UTILITIES

THE COMPLETE DISK UTILITY

If it's on a disk or diskette, Disk Explorer will find and display it. Disk Explorer, the complete disk utility: Recovers files. Displays, changes, creates and compares sectors. Creates tracks that can't be duplicated by DOS, locates the precise end of a track, creates specialized track formats. Allows viewing and moving of clusters. Reports on disk drive speed, increases the speed of reading data and much more. IBM PC, XT or AT, 128kb and one diskette drive. $75.00 U.S. Check/Credit card welcome.

Quaid Software Limited

QUAID SOFTWARE LIMITED
45 Charles St. East, Third floor
Toronto, Ontario M4Y 1S2
(416) 961-8243

SPEED UP YOUR HARD DISK!

Vopt™ DISK ORGANIZER

For fast, efficient, time-saving use, organize your hard disk ***Vopt***!

Vopt consolidates the fragmented files that slow down and wear down your disk. Now your hard disk can find what it's looking for — all in one place!

Vopt is fast! Initial organization averages under 5 minutes! Daily runs from the AUTOEXEC file average under 1 minute!

Vopt includes — ***Vmap*** for graphic display of HD utilization, ***Vseek*** for HD seek times, ***Vmarkbad*** to flag bad clusters, plus much more!

Get ***Vopt*** and get going!

ONLY $49.95

Add $3 shipping & handling
CA residents add 6% sales tax

GOLDEN BOW SYSTEMS

2870 Fifth Avenue
Suite 201
San Diego, CA 92103
619/298-9349

Vopt is a trademark of Golden Bow Systems
CIRCLE 390 ON READER SERVICE CARD

AT's DON'T NEED 360KB DRIVES

The 1.2MB drive has long been known to **READ** but **NOT** reliably **WRITE** on 360KB floppies. With **"CPYAT2PC"** 1.2MB drives **CAN** reliably **WRITE** 360KB floppies saving a slot for a second hard disk or backup tape. **"CPYAT2PC"** (Not Copy Protected) offers the preferable **SOFTWARE SOLUTION.**

- **NO** software or hardware modification
- A 360K drive is **NOT** required
- **"CPYAT2PC"** program **MAY** reside on hard disk
- Runs on IBM PC/AT and COMPATIBLES
  i.e. Compaq Deskpro 286/386, AT&T 6300+, HP Vectra, Sperry PC/IT, Tandy 3000

Only $79.00 + $4.00 S/H VISA, MC, COD, UPS-B/R
ORDER TOLL FREE 1-800-621-0851 XT777
TELEX EZLINK 62873089
Dealer Inquiries Invited

VISA master card

MICROBRIDGE COMPUTERS
655 Skyway #125
San Carlos, CA
CA 415-593-8777
NY 212-334-1858

CIRCLE 386 ON READER SERVICE CARD

Compress your data into 1/10th the space!

Introducing ARC. It's used to create and maintain data file archives for computers operating under any DOS system.

But it does something that other archive and library utilities can't. It automatically squeezes the files being saved so they take up less space. Like a can of concentrated orange juice.

From 20% to 90% less, depending on the kind of data being saved!

So there's more room to store data, no matter what media it's stored on! And that's like giving a shot of vitamin C to your savings on equipment and supplies.

This compressed data can be transmitted over telephone lines in a lot less time than it takes to transmit uncompressed data. So you can beat the high cost of phone bills to a pulp, as well.

ARC has a full range of functions for archive creation and maintenance. Including password encryption to protect data from unauthorized use.



Typical Compression Rates

sea

System Enhancement Associates • 21 New Street, Wayne, NJ 07470 • (201) 473-5153

CIRCLE 400 ON READER SERVICE CARD

PC Tech Journal Marketplace:

Kathryn J. Cumberlander
Classified Advertising Director

Daniel L. Rosensweig
Classified Sales Manager

Lisa B. Stick
Account Manager

Stanley H. Robinson
Account Manager

Call: (212) 503-5115

TallScreen—DOS POWER

Natural extension of DOS. Scroll back through screen output, edit text on full screen, mark blocks to printer or file, recall commands & directories, enter multiple commands, capture screens from application programs, create user profiles. Solid tech support. PC MAG & PC WORLD calls TallScreens a Real bargain at $49.95. VISA/MC

QUALITAS™

QUALITAS, INC.
8314 Thoreau Drive
Bethesda, MD 20817
(301) 469-8848

MAKE YOUR PC SEEM LIKE AN AT!

MAKE YOUR AT SEEM LIKE A DREAM MACHINE!

ANSI-CONSOLE™

The Integrated Console Utility™
FAST, POWERFUL ANSI.SYS REPLACEMENT
For the IBM-PC, AT, and clones
New Version 2.00 is MUCH FASTER

Now blink free scrolling on CGA!
Now use EMS for scroll recall!
New option menu program!

- Speed up your screen writing
- Extend your ANSI.SYS to full VT100
- Scroll lines back onto screen
- Save scrolled lines into a file
- Add zip to your cursor keys
- Free your eyes from scroll blinking
- Easy installation
- Get 43 line EGA support
- Over 50 useful options

"The psychological difference is astonishing" -*Lotus* June 85 pg 8.

"So many handy functions rolled into one unobtrusive package" -*PC-World* Feb 86 pg 282.

"The support provided by the publishers is extraordinary." -*Capital PC Monitor* May 86 pg 25.

"...the best choice for improving your console..." -**Capital PC Monitor** June 86 pg 282.

460p Manual (w/slip case) and software diskettes $75.

Satisfaction Guaranteed!
Order Yours Today!

HERSEY MICRO CONSULTING
Box 8276, Ann Arbor, MI 48107
(313) 994-3259 Visa/MC/Amex
DEALER INQUIRIES INVITED

CIRCLE 388 ON READER SERVICE CARD

TECH MARKETPLACE

THE COMPREHENSIVE GUIDE TO PRODUCTS AND SERVICES FOR THE MS DOS MARKET

UTILITIES

XT/AT HARD DISK DIAGNOSTICS!

Disk Manager Diagnostics performs extensive tests on your ST412/506 hard disks. Areas tested are: Controller, data write/read, seek test, automatic error correction(ECC), random reads and media defects. Interactive help. Excellent error detection and isolation. $49.95 + ship. VISA/MC accepted.

ONTRACK COMPUTER SYSTEMS INC.

ONTRACK COMPUTER SYSTEMS, INC.
6222 Bury Drive
Eden Prairie, MN 55344
(612) 937-1107

LIMSIM

Expanded Memory Simulator for the PC/AT and compatible 286 machines. Use the extended memory you already have as Lotus style Expanded Memory. Fully supports EMS version 3.2. Requires 70k of conventional memory. $50 ($75 with assembler source) plus $5 s/h. 30 day money back guarantee. Visa/MC accepted.
Larson Computing
1556 Halford Ave. #142
Santa Clara, CA 95051
(408) 737-0627

DOCUMENTATION MANAGER

Create and maintain manuals - procedure manuals, program documentation / system user manuals, etc. * Edit files with the excellent Norton Editor (included) * Save User Defined configuration * Save screen dumps to files * Variety of Print Options *
$69.95 complete MasterCard/Visa

PHENIX

PHENIX HOSPITAL SYSTEMS
1616 Palm Avenue
Deland, FL 32724
(904) 736-1132

Tech Marketplace...
The comprehensive guide to products and services for the MS DOS market.
To place your ad Call
(212) 503-5115

MISCELLANEOUS

BAR CODING

BAR CODE READERS

- IBM, AT&T, Link, Kimtron, TeleVideo,
- Alloy, DEC keyboard interfaces or RS-232C
- Need others? Call.
- NO programming. Reads dot matrix
- Auto-recognition and single code decoding
- Reads Code 39, UPC A/E, Codabar & 1 2 of 5
- Units in stock, 2 year warranty
- Bar code printing software, call for info

PERCON®

PERCON, Inc.
2190 W. 11th
Eugene, OR 97402
(503) 344-1189

$99 BAR CODE READERS

We need Distributors & OEMs worldwide. Our readers are IBM PC/XT/AT & Tandy 1000/2000 keyboard compatible, convertible to RS232 Interface, have auto code distinction, need no additional software and are available from assembled board to fully packaged units. From US $99 plus wand in modest OEM quantities.
ASP MICROCOMPUTERS
P.O. Box 259, Caulfield East 3145
VICTORIA, AUSTRALIA
Phone 011 61 3 5000628 (note time difference)

PUBLICATIONS

AN INVITATION TO STEAL

Bad copyright—or none at all? Your software may be public domain. Protect your work before you show it. Learn how to copyright software inexpensively and effectively. Software Copyright Guide. $6 ppd.
INNOVATION PRESS
Dept. 112
Box 351
Highland, IL 62249

The BEST BAR CODE READER for the IBM PC & AT
$595
Simple & quick installation
No additional software or port
Metal wand & case
Also available:
Bar code printing software
Magnetic stripe readers
Units for other computers & terminals
TPS ELECTRONICS
4047 Transport Street
Palo Alto, CA 94303
Telephone: 415-856-6833
Telex: (Graphnet) 371-9097 TPS PLA
CIRCLE 394 ON READER SERVICE CARD

SOFTWARE/OPERATING SYSTEMS

Multitasking with MS-DOS is possible NOW!

A full multitasking extension for MS-DOS ver 2.10 (100% assembly & it's fast)

Easy command line or pgm interface to:
Exec another pgm concurrently
Make a program resident
Modify a program to be re-entrant
Exec a resident pgm as subroutine
Program and use all 40 func keys
Save screen & keyboard before exec
512 byte Keyboard buffer
Pgms can be grouped & exec as "applications"
Allocation of devices thru "logical devices"
Pgm interface MS,Lat "C" w/ "On Error branch"

"Extended DOS" $159 Distributed Software
3951 Emerson St.
404-977-0152 Marietta, Ga. 30062

MS-DOS is a trademark of Microsoft Corp.

CIRCLE 391 ON READER SERVICE CARD

ETHERNET FOR PCs.

PC/TCP is a complete ethernet package for PCs. Connects PCs to other PCs or UNIX hosts.

Runs on any PC or compatible and requires a 3COM, Interlan, Proteon, or BICC board.

Price: $400 per PC.

UniPress Software
Your Leading Source for UNIX Software

2025 Lincoln Hwy.
Edison, NJ 08817
800-222-0550 (Outside NJ)
201-985-8000
Telex: 709418

CIRCLE 397 ON READER SERVICE CARD

PC TECH JOURNAL
(212) 503-5115

Advertising Director
Kathryn J. Cumberlander

Sales Manager
Daniel L. Rosensweig

Account Manager
Lisa B. Stick

Account Manager
Stanley H. Robinson

Production Manager
Anne R. Brockinton

Advertising Rates and Information:
PC Tech Journal Marketplace

PC Tech Journal Marketplace is a special economical section for product and service listings.

Listings are grouped by category and sold by column inches. Second color option available.

Standard Directory Listings are also available for a minimum of 3 issues at $170 per issue ($510 total).

For additional information
call 212-503-5115.

READER SERVICE NUMBER	ADVERTISER	PAGE
116	Advanced Logic Research	Cover 3
153	Aker	119
106	Aldebaran	113
118	American Small Business	178
214	Answer Software	20
136	Arity Corporation	128
122	Arrix	110
*	AST Research, Inc.	155
207	ATI	14
206	ATI	15
203	Atron	8
249	Atron	22
165	Attachmate	35
221	Avocet	52
105	Barrington Systems	56
*	BC Associates	194
102	Blaise Computing	19
*	Borland Int'l.	Gatefold Cover
254	Borland Int'l.	1
178	Boston Business Computing	108
*	Business Engrg. Systems	192
111	Catamount Corp.	184
188	Century Software	180
223	Cobol Shop	196
213	Coefficient Systems	92
*	Creative Programming Consultants	167
145	Cresent Software	184
167	Crosstalk Communications	Back Cover
261	Custom Software Systems	123
110	Digiboard	142
123	Digi Data	89
131	Ecosoft	136
119	FairCom	85
117	Farbware	184
*	Flagstaff Engineering	182
180	Fox Software Inc	112
*	Gimpel Software	138
172	Giltronix	60
113	Haven Tree Software Limited	181
149	Ibex Computer Corp.	188
237	IDEAssociates	38 & 39
108	Innovative Data Tech	149
216	Intel Corp.	100 & 101
114	Intellisoft	11
209	Interactive Microware	190
134	ITS	195
258	KADAK Products	184
148	Kurtzberg Computer Systems	139
128	Lahey Computer Systems, Inc.	186
160	Lattice, Inc.	87
143	Lifeboat Assoc.	120
229	LOGITECH Inc.	58
125	Lugaru	91
263	Mansfield Software	182
225	mbp Software	125
146	MDS, Inc.	163
133	M.E.F. Environmental	190
211	Micro Data Base Systems	159
257	MicroHelp, Inc.	156
*	Microsoft Corp.	21
226	Microsoft Press	172 & 173
*	MicroTech	148
155	MicroWay	70
*	MicroWay	193
163	Migent	168 & 169
174	Mortice Kern	166
224	Nantucket Corp.	82
192	National Advancement	188
191	Norcom	174
222	Opt-Tech Data Processing	4
159	Orchid Technology	109
230	Paradise Systems	6 & 7
101	Paul Mace Software	18
*	PC Brand	42-45
150	PC's Limited	12 & 13
202	Peripheral Marketing	190
215	Perisope Company	5
164	Polytron	24
161	Princeton Graphics	99
252	Pro/Am Software	114
175	Programmer's Connection	25-27
175	Programmer's Connection	129
220	Programmer's Shop	40
162	Programmer's Shop	102 & 103
*	Raima Corp.	65
157	Rainbow Technology	188
171	Ram Explosion	194
137	Ryan-McFarland	121
*	Scantel Systems Ltd.	194
107	Scientific Endeavors	190
127	Scottsdale Systems	194
170	Seattle Telecom	72
227	Sigma Designs	143
201	SoftCraft Inc.	2
186	Soft*Rite	160
142	Software Garden	154
154	Software Institute	162
196	Software Link	111
120	Software Merchants	141
189	Software Security	86
130	Solution Systems	16
177	Stargate Technologies	188
198	Sterling Castle	122
176	Storage Dimensions	115
195	Summit Software	88
158	Sunny Hill Software	176
184	Sunny Tech Inc.	192
231	Systems & Software	158
194	Tall Tree Systems	37
200	Tektronix	32A-D
182	TeleVideo	76 & 77
*	Texas Instruments	117
193	Tom Rettig Assoc.	164
219	TurboPower Software	124
156	Unify Corp.	137
169	Upper Bound Micro Computer	118
115	Vermont Creative Software	23
204	Video 7	157
173	Visionics	165
124	Wells American	135
243	Weltec	187
236	Zanthe	28 & 29
212	Zylab	90

RS#	PRODUCT	ADVERTISER	PAGE
	IBM AND COMPATIBLE PC'S		
124	A * Star	Wells American	135
	MULTIFUNCTION/MEMORY CARDS		
155	Number Smasher/ECM	Microway	70
159	Tiny Turbo 286, PC Turbo 286e, Jet 386	Orchid Technology	109
202	Fastcard	Peripheral Marketing, Inc.	190
170	PC 386	Seattle Telecom & Data	72
	GRAPHICS CARDS		
207	Graphics Solution/EGA Wonder	ATI Technologies	14 & 15
230	Auto Switch EGA	Paradise Systems	6 & 7
204	Video Deluxe	Video Seven	157
	GRAPHICS SYSTEMS		
200	Graphic Systems	Tektronix Inc.	32A-D
	386 BOARDS		
216	386 Board	Intel	100 & 101
	MASS STORAGE HARDWARE		
111	9 Track Tape System	Catamount Corporation	184
123	9 Track Tape System	Digi Data	89
*	9 Track Tape System	Flagstaff Engineering	182
149	9 Track Tape System	Ibex Computer Systems	188
108	"Leo"	Innovative Data Technology	149
231	Perstor 200	Systems and Software	158
169	The Eagle Series	Upper Bound Micro Computer	118
243	Floppy Disk Drive	Weltec Digital Inc.	187
	PRINTERS-PLOTTERS		
194	J Laser Plus	Tall Tree Systems	37
	MODEMS		
163	Pocket Modem	Migent Software Inc.	168 & 169
	DATA ACQUISITION		
209	Catalogue	Interactive Microware	190
	MONITORS		
227	Laser View Display System	Sigma Designs	143
	MICRO-MINI MAINFRAME COMMUNICATIONS		
189	The Block	Software Security	86
	LOCAL AREA NETWORKS		
116	386 Network Tower	Advanced Logic Research	Cover 3
165	3-N-1	Attachmate Corporation	35
172	Easy Queue	Giltronix	60
186	Lanscreen, Lanbasic, Lanbase	Soft*Rite	160
182	PM 286 Network Server	Televideo Systems Inc.	76 & 77
	OTHER COMMUNICATION HARDWARE		
213	V-Term	Coefficient Systems	92
110	Digiboard COM/XI	Digiboard Inc.	142
237	5251 Communications	IDE Associates	38 & 39
177	Stargate OC8000	Stargate Technologies	188
	OTHER COMMUNICATION SOFTWARE		
188	Term	Century Software	180
167	Crosstalk	Crosstalk Communications	Back Cover
186	Lanscreen, Lanbasic, Lanbase	Soft*Rite	160
196	Multi Link Advanced	Software Link	111
	SCIENTIFIC/ENGINEERING SOFTWARE		
254	Eureka	Borland Intl.	Gatefold Cover & 1
	LANGUAGES		
136	Prolog Compiler	Arity, Inc.	128
105	Clarion	Barrington Systems, Inc.	56
254	Basic, Prolog, Pascal	Borland Intl.	Gatefold Cover & 1
223	Languages	Cobol Shop	196
131	ECO-C88-Microstat	Ecosoft Inc.	136
117	Modula-2	Farbware	184
*	PC Unit	Gimpel Software	138
128	F77L Lahey Fortran	Lahey Computer Systems	186
143	C++	Lifeboat Associates	120
229	Modula 2	Logitech Inc.	58
263	Personal Rexx	Mansfield Software	182
225	mbp Cobol	mbp Systems	125
*	Language Library	Microsoft Corporation	21
226	Language Newsletter	Microsoft Corporation	172 & 173
137	Cobol's Double Standard	Ryan McFarland	121
130	Brief	Solution Systems	16
195	Better Basic	Summit Software Technology	88
	PROGRAMMER'S TOOLS		
106	Source Print & Tree Diagrammer	Aldebaran	113
214	ICD 286	Answer Software	20
122	Micro DCF	Arrix Logic Systems	110
203	68020 Probe	Atron	8
249	Mini Probe	Atron	22
221	Assemblers, Simulators	Avocet Systems, Inc.	52
102	Power Tools Plus	Blaise Computing	19
254	Turbo C	Borland Intl.	Gatefold Cover & 1
178	PC/EDT	Boston Business Computing	108
*	Vitamin C	Creative Programming Cons.	167
145	Quick Pak	Crescent Software	184
261	PC/VI	Custom Software Systems	123
119	R-Tree/C-Tree	FairCom	85
113	Flowchart	HavenTree Software	181
148	C-Tree Query	Kurtzberg Computer System	139
160	Programming Tools	Lattice, Inc.	87
125	Epsilon	Lugaru Software	91
146	Help/Control	MDS, Inc.	163
*	C Cross Compiler	Micro Tech Research	148
257	2 New Programs	MicroHelp, Inc.	156
191	Screenio	Norcom	174
222	Opt-Tech Sort	Opt-Tech Data Processing	4
101	Mace Utilities	Paul Mace Software	18
*	Programmer's Tools	PC Brand	42-45
164	PolyShell	Polytron Corporation	24
252	Dis N Data	Pro/Am Software	114
201	Btrieve	Softcraft	2
142	Demo Program	Software Garden	154
198	Basic/C Tools	Sterling Castle	122
152	Turbo Professional	Sunnyhill Software	176
158	Taskview	Sunnyhill Software	176
219	Tdebug	Turbo Power Software	124
115	Windows for Data	Vermont Creative Software	23
212	Zy Index	Zylab	90
	SOFTWARE UTILITIES		
114	Bookmark	Intellisoft Intl.	11
133	No Limit	MEF Environmental Inc.	190
191	Screenio	Norcom	174
101	Mace Utilities	Paul Mace Software	18
215	Periscope	Periscope Company	5
176	Speedstar	Storage Dimensions	115
200	Graphic Systems	Tektronix Inc.	32A-D
219	Tdebug	Turbo Power Software	124
	EXPERT SYSTEMS/AI SOFTWARE		
*	Personal Consultant	Texas Instruments	117
	GRAPHIC SOFTWARE		
118	Pro Design II	American Small Business	178
107	Graph C	Scientific Endeavors	190
	DATA BASE MANAGEMENT SOFTWARE		
153	Magic PC	Aker Corporation	119
180	Fox Base	Fox Software Inc.	112
211	MDBS III	Micro Data Base Systems	159
224	Clipper	Nantucket Corporation	82
*	db Vista	Raima Corporation	65
120	Simple	Software Merchants Unltd.	141
193	Tom Rettig's Library	Tom Rettig Associates	164
156	Unify	Unify Corporation	137
236	ZIM	Zanthe	28 & 29
	OPERATING SYSTEMS		
258	AMX Multi Tasking Executive	Kadak Products Ltd.	184
174	MKS Tool Kit	Mortice Kern Systems Inc.	166
	OTHER SERVICES		
192	Computer Hardware Training	National Advancement Corp.	188
154	Adam Greene Seminar	Software Inst. of America	162
	SECURITY DEVICES		
157	Software Sentinel	Rainbow Technologies, Inc.	188
	MAIL ORDER		
*	Mail Order	BC Associates	194
*	Mail Order	Business Engrg. Syst.	192
134	Mail Order	ITS	195
*	Mail Order	Microway	193
*	Mail Order	PC's Limited	12 & 13
175	Mail Order	Programmer's Connection	25-27
175	Mail Order	Programmer's Connection	129
220	Mail Order	Programmer's Shop	40
162	Mail Order	Programmer's Shop	102 & 103
171	Mail Order	Ram Explosion	194
*	Mail Order	Scantel Systems	194
127	Mail Order	Scottsdale Systems	194
184	Mail Order	Sunnytech, Inc.	192



ILLUSTRATION • DAVID POVILAITIS

APRIL

April 1–3
Database Systems for Office Automation, Engineering, and Scientific Applications
Darmstadt, West Germany
Sponsor: Gesellschaft für Informatik
Contact: H.-J. Schek, Technische Hochschule Darmstadt, Fachgebiet Datenverwaltungs-systeme I, Fachbereich Informatik, Alexanderstrasse 24, D-6100 Darmstadt, Federal Republic of Germany

April 5–9
CHI + GI '87
Toronto, Ontario, Canada
Sponsor: ACM
Contact: Wendy Walker, CHI + GI '87, Computer Systems Research Institute, University of Toronto, 2002-10 Kings College Road, Toronto, Ontario, Canada M5S 1A4; 416/978-5184

April 8–10
Mathematical Foundations of Programming Semantics
New Orleans, LA
Sponsor: ACM
Contact: ACM, 11 W. 42nd Street, New York, NY 10036; 212/575-1520

April 9–10
Advanced SPSS/PC+
Austin, TX
Sponsor: SPSS Inc.
Contact: Training Department, 444 N. Michigan Avenue, Chicago, IL 60611; 312/329-3557

April 9–10
Decision Support and Expert Systems
Cambridge, MA
Sponsor: Decision Support Technology, Inc.
Contact: Conference Registration Office, 51 Church Street, Boston, MA 02116; 800/843-3263; in Massachusetts, 617/482-3596

April 20–24
Complexity of Approximately Solved Problems
New York, NY
Sponsor: Computer Sciences at Columbia University
Contact: Susan Maser, 450 Computer Science Building, Columbia University, New York, NY 10027; 212/280-8832

April 27–29
Symposium on Security and Privacy
Oakland, CA
Sponsors: IEEE-CS and IACR
Contact: Virgil D. Gligor, General Chairman, Department of Electrical Engineering, University of Maryland, College Park, MD 20742; 301/454-8846

MAY

May 4–6
Connectivity Symposium on LANs and Micro/mainframe Links
Boston, MA
Sponsors: Digital Consulting Associates, Inc.
Contact: Seminar Services Department, 8 Windsor Street, Andover, MA 01810; 617/470-3880

May 10–14
APL87
Dallas, Texas
Sponsors: Southwest APL Users Group (SWAPL)
Contact: APL87 Registrar, 440 Northlake Shopping Center, Suite 210, Dallas, Texas 75238; 214/539-9281

May 11–13
Application-Specific Integrated Circuits
Cherry Hill, NJ
Sponsor: IEEE
Contact: Workstation Technology and Systems Workshop, 12 Colburn Drive, Poughkeepsie, NY 12603; 914/435-8185

May 11–13
Desktop Publishing '87
San Francisco, CA
Sponsor: Online International
Contact: Carol Peters, Online International, 989 Avenue of the Americas, New York, NY 10018; 212/279-8890

May 11–15
CompEuro '87: VLSI and Computers
Hamburg, West Germany
Sponsors: IEEE, IEEE-CS, Gesellschaft für Informatik, and Verband Deutscher Elektrotechniker
Contact: CompEuro '87, Dr. W. E. Proebster, IBM P.B. 80 08 80, D-7000 Stuttgart 80, Federal Republic of Germany

May 13–15
History of Scientific and Numeric Computation
Princeton, NJ
Sponsors: ACM and Society for Industrial and Applied Mathematics
Contact: Hank Friedman, Department of Computer and Information Science, Room 303, Computer Center Building, Temple University, Philadelphia, PA 19122; 215/787-8450

May 13–16
Computer Applications in Medicine and Health Care
San Francisco, CA
Sponsor: AAMSI
Contact: American Association for Medical Systems and Informatics, Suite 700, 1101 Connecticut Avenue NW, Washington, DC 20036; 202/857-1189

May 20
Intelligent Infrastructure Technology
Chicago, IL
Sponsors: A-E-C and F-M Automation Newsletters
Contact: Jerry Robinson, Editor, F-M Automation Newsletter, 9501 W. Devon Avenue, Suite 203, Rosemont, IL 60019-4804; 312/823-0555

CALL FOR PAPERS

Deadline: April 1
Western Educational Computing Conference
San Francisco, CA
(November 19–20, 1987)
Sponsor: California Educational Computing Consortium
Submit papers to: Judah Rosenwald, Extended Education, San Francisco State University, 1600 Holloway, San Francisco, CA 94132

Use these reader service cards to get

FREE INFORMATION

about the products and services in this issue of TECH JOURNAL

Learning more about a product that's advertised or mentioned in an article in this month's issue is as simple as 1-2-3. And absolutely free.

1 Print or type your name and address on the attached card. Use only one card per person.

2 Circle the numbers on the card that correspond to the numbers at the bottom of the advertisements or articles for which you want more information.

(Key numbers for advertised products also appear in the Advertisers' index.)

3 Simply mail the card, and the literature will be mailed to you free of charge by the manufacturer.

FOR IBM COMPUTER EXPERTS
TECH PC JOURNAL.

Are you personally involved in the selection of microcomputers and related products for:

1 Your company or organization?
A☐ Yes B☐ No

2 Your client companies or organizations?
C☐ Yes D☐ No

3 Are you planning to purchase in the next 6 months:
E☐ PC Hardware?
F☐ PC Software?
G☐ PC Peripherals?

101	116	131	146	161	176	191	206	221	236	251	266	281	296	311	326	341	356	371	386
102	117	132	147	162	177	192	207	222	237	252	267	282	297	312	327	342	357	372	387
103	118	133	148	163	178	193	208	223	238	253	268	283	298	313	328	343	358	373	388
104	119	134	149	164	179	194	209	224	239	254	269	284	299	314	329	344	359	374	389
105	120	135	150	165	180	195	210	225	240	255	270	285	300	315	330	345	360	375	390
106	121	136	151	166	181	196	211	226	241	256	271	286	301	316	331	346	361	376	391
107	122	137	152	167	182	197	212	227	242	257	272	287	302	317	332	347	362	377	392
108	123	138	153	168	183	198	213	228	243	258	273	288	303	318	333	348	363	378	393
109	124	139	154	169	184	199	214	229	244	259	274	289	304	319	334	349	364	379	394
110	125	140	155	170	185	200	215	230	245	260	275	290	305	320	335	350	365	380	395
111	126	141	156	171	186	201	216	231	246	261	276	291	306	321	336	351	366	381	396
112	127	142	157	172	187	202	217	232	247	262	277	292	307	322	337	352	367	382	397
113	128	143	158	173	188	203	218	233	248	263	278	293	308	323	338	353	368	383	398
114	129	144	159	174	189	204	219	234	249	264	279	294	309	324	339	354	369	384	399
115	130	145	160	175	190	205	220	235	250	265	280	295	310	325	340	355	370	385	400

Please print clearly—Use only one card per person. Void after July 31, 1987

Name_____ Phone (_____)_____

Title_____

Company_____

Address_____ Apt._____

City_____ State_____ Zip_____

(Zip code must be included to insure delivery.)

4☐ **Please send me 1 year (13 issues) of *PC Tech Journal* for $26.70 and bill me. I'll save 50% off the cover price.**

TJ4872

FOR IBM COMPUTER EXPERTS
TECH PC JOURNAL.

Are you personally involved in the selection of microcomputers and related products for:

1 Your company or organization?
A☐ Yes B☐ No

2 Your client companies or organizations?
C☐ Yes D☐ No

3 Are you planning to purchase in the next 6 months:
E☐ PC Hardware?
F☐ PC Software?
G☐ PC Peripherals?

101	116	131	146	161	176	191	206	221	236	251	266	281	296	311	326	341	356	371	386
102	117	132	147	162	177	192	207	222	237	252	267	282	297	312	327	342	357	372	387
103	118	133	148	163	178	193	208	223	238	253	268	283	298	313	328	343	358	373	388
104	119	134	149	164	179	194	209	224	239	254	269	284	299	314	329	344	359	374	389
105	120	135	150	165	180	195	210	225	240	255	270	285	300	315	330	345	360	375	390
106	121	136	151	166	181	196	211	226	241	256	271	286	301	316	331	346	361	376	391
107	122	137	152	167	182	197	212	227	242	257	272	287	302	317	332	347	362	377	392
108	123	138	153	168	183	198	213	228	243	258	273	288	303	318	333	348	363	378	393
109	124	139	154	169	184	199	214	229	244	259	274	289	304	319	334	349	364	379	394
110	125	140	155	170	185	200	215	230	245	260	275	290	305	320	335	350	365	380	395
111	126	141	156	171	186	201	216	231	246	261	276	291	306	321	336	351	366	381	396
112	127	142	157	172	187	202	217	232	247	262	277	292	307	322	337	352	367	382	397
113	128	143	158	173	188	203	218	233	248	263	278	293	308	323	338	353	368	383	398
114	129	144	159	174	189	204	219	234	249	264	279	294	309	324	339	354	369	384	399
115	130	145	160	175	190	205	220	235	250	265	280	295	310	325	340	355	370	385	400

Please print clearly—Use only one card per person. Void after July 31, 1987

Name_____

Title_____ Phone (_____)_____

Company_____

Address_____ Apt._____

City_____ State_____ Zip_____

(Zip code must be included to insure delivery.)

4☐ **Please send me 1 year (13 issues) of *PC Tech Journal* for $26.70 and bill me.**

FREE INFORMATION

Follow the instructions on the reverse side of this card to receive advertisers' product information. FREE.

SUBSCRIBE NOW!

Now's an ideal time to consider having us start you as a PC Tech Journal subscriber.
13 issues cost you only $26.70...a savings of 50% off the cover price.
Special PC Tech Journal Directory published in November included with your subscription! Just check the box at the bottom of the reply card.



NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

BUSINESS REPLY MAIL

FIRST CLASS PERMIT NO. 27346 PHILADELPHIA, PA

Postage will be paid by addressee

FOR IBM COMPUTER EXPERTS
PC TECH JOURNAL.
P.O. Box 40086
Philadelphia, PA 19106-9931

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 27346 PHILADELPHIA, PA
Postage will be paid by addressee
FOR IBM COMPUTER EXPERTS
PC TECH JOURNAL.
P.O. Box 40086
Philadelphia, PA 19106-9931

If You Can Open A Box, You Can Install The Most Powerful Network Available.

Because they're built around the same 80386-based ALR computer *Byte* said offers "high-performance in nearly every sense of the word," you'd expect four or eight-user ALRnet networks to be fast. What you might not anticipate is how fast you can set one up.

ALRnet networks are completely preconfigured before we put them in the box. So setting them up is about as simple as taking them out of the box—you just have to hook up some coax connections and find a few power outlets. And that helps make the fastest network the fastest to set up.

Authorized NetWare Reseller

How ALRnet Works.

ALRnet takes full advantage of Novell's best-selling network operating system, Advanced NetWare 286,™ to run a powerful combination of AT™-compatible workstations and an ALR Network 386 fileserver.

The fileserver comes fully equipped for the most demanding network applications with plenty of I/O options and a choice of high-performance hard drives. All packaged in a rugged hirise design that improves cooling and accommodates as many as four additional full-height drives and a 200-watt power supply. The PC2/286 workstations are the same compact AT-compatibles *PC Magazine* made their editor's choice. They each have 512K, a 1.2-MB floppy and Hercules™-compatible graphics. One of them houses intelligent tape backup for the network hard disk.

ALRnet networks also come with everything you need, down to the last cable. And when it comes time to grow, as many as 250 additional users can be easily added using readily available hardware.

More Powerful PCs.

ALR got its start developing advanced performance systems for research, software development and business applications. Since then, we've introduced more high-performance PC systems than any other manufacturer, including the first Intel 80386-based family of computers. And because Advanced Logic Research designs, manufactures and distributes high-performance microcomputer systems worldwide, we can provide cost-effective PC alternatives through over 500 full-service dealers.

Systems backed by a one-year parts and labor warranty on everything ALR makes.

Please call today for more information or the location of your authorized ALR dealer.



Get everything you need for four or eight users now, easily expand to over 250 users later.

Advanced Logic Research, Inc.
10 Chrysler, Irvine, CA 92718
(714) 581-6770 Extension #N386
FAX: (714) 581-9240 TELEX: 5106014525,
Answer back Advanced Logic

CIRCLE NO. 116 FOR RE-SELLER,
NO. 121 FOR END-USER.

Hercules a trademark of Hercules Graphics Products, Inc. Advanced NetWare 286 a trademark of Novell, Inc. AT a trademark of IBM.


The Launch Of Our New Flagship:
Customizable, Expandable, and Responsive CROSSTALK® Mk.4.
It takes a powerful, flexible PC communications program to cut through the sea of incompatible systems you face today. CROSSTALK® Mk. 4 has what it takes. More protocols — X.PC, Xmodem, Kermit, and our own CROSSTALK. More terminal emulations, including complete IBM 3101, DEC VT-100, and TeleVideo 900 series. Concurrent communications capability — up to 15 sessions. Error checking at high speeds. Beginners can use the simple menus, a clear help system, and prepared script files that help extract data from many popular information utilities. Experts can use the powerful command programming language to create extensive, customized "scripts." A unique modular architecture means we can quickly add new capabilities by phone. So CROSSTALK Mk. 4 may be the launch of more than just today's standard in PC communications. It's probably tomorrow's as well.
CROSSTALK® COMMUNICATIONS
Digital Communications Associates, Inc.
1000 Holcomb Woods Parkway
Roswell, Georgia 30076
1-800-241-6393
CROSSTALK is a registered trademark of Digital Communications Associates, Inc.
DEC VT-100 is a registered trademark of Digital Equipment Corp.
IBM is a registered trademark of International Business Machines Corp.
TeleVideo is a registered trademark of TeleVideo Systems, Inc.
X.PC is a trademark of Tymshare, Inc.
CIRCLE NO. 167 ON READER SERVICE CARD
CROSSTALK® MK.4